

Class 620.6

Book No. 21290



Northeastern University
Library
Day Division

7-9

JOURNAL

OF THE

Association of Engineering Societies.

BOSTON.

CLEVELAND.

MINNEAPOLIS.

LOUISIANA.

MONTANA.

ST. PAUL.

BUFFALO.

CINCINNATI.

DETROIT.

PACIFIC COAST.

ST. LOUIS.

CONTENTS AND INDEX.

VOLUME XXVI.

January to June, 1901.

PUBLISHED BY

THE BOARD OF MANAGERS OF THE ASSOCIATION OF
ENGINEERING SOCIETIES.

CONTENTS.

VOL. XXVI, January-June, 1901.

For alphabetical index, see page v.

No. 1. JANUARY.

PAGE

Hydraulic Excavation. <i>Latham Anderson</i>	1
Street Lighting of Cities. <i>Henry H. Humphrey</i>	18
Water Power by Direct Air Compression. <i>William O. Webber</i>	35
A Modern American Blast Furnace—Its Construction and Equipment. <i>Arthur C. Johnston, M. E.</i>	47
Obituary.—George W. Percy	59
Association of Engineering Societies	62

Proceedings.

Lists of Members of the Associated Societies.

No. 2. FEBRUARY.

Brick and Concrete-Metal Construction. Economy and Strength of Brick and Concrete Arches for Floor Systems of Highway Bridges. <i>William D. Bullock</i>	73
A Test of the Strength of Rapp Floor Arches. <i>Frederic H. Fay</i>	79
Expanded Metal as Used in Fireproof Building Construction and Other Work. <i>William M. Bailey</i>	84
Description of Ransome System of Concrete Steel Floors. <i>M. C. Tuttle</i> . .	93
Tests of Roebling Fireproof Floors. <i>Andrew W. Woodman, C. E.</i> . .	100
A Review of Concrete-Metal Construction. <i>Chas. M. Kurtz</i>	108
The Steel Skeleton Construction of a Tall Office Building. <i>J. S. Branne</i> . .	125
The Engineering Society—Its Relations to the Engineer and to the Profession. <i>H. J. Maloché</i>	149

Proceedings.

No. 3. MARCH.

A Study in Hydraulics. <i>George H. Finkell</i>	155
Discussion. <i>Messrs. Thron, Hubbell, Williams, Trautwine and Finkell</i> . .	163
Submerged Pipe Crossings of the Metropolitan Water Board. <i>Caleb M. Saville</i>	193
Discussion. <i>Messrs. Herschel and M. Hines</i>	219

	PAGE
Extension of the Group Theory of Atoms and Molecules. <i>Arthur A. Skeels</i>	223
Engineering Explorations in Montana and Elsewhere in the Rocky Mountains. <i>Francis W. Blackford</i>	239
Obituary.—James S. B. Hollinshead	251
Henry M. Clatten	253
Proceedings.	

No. 4. APRIL.

Installation, Operation and Economy of Storage Batteries. <i>Ernest Lunn</i>	255
Concrete Construction. <i>C. R. Neher</i>	273
Discussion. <i>Messrs. Diehl, Neher, Knighton, Vander Hock, Tutton,</i> <i>Rockwood and Norton</i>	279
Obituary.—Sherman Emmett Burke	283
Proceedings.	

No. 5. MAY.

The Softening of Feed Water for Boilers. <i>Louis Bendit</i>	285
On the Engineering Difficulties Attending a Proper Inspection of Cement. <i>J. F. Coleman</i>	305
Discussion. <i>L. W. Brown</i>	311
Early Transportation Canals. <i>J. T. Fanning</i>	315
Proceedings.	

No. 6. JUNE.

Subaqueous Tunnels for Gas Conduits. <i>W. W. Cummings</i>	327
Discussion. <i>Messrs. Carson, Saville, Shailer and Cummings</i>	339
The Increasing Elevation of Floods in the Lower Mississippi River. <i>Linus W.</i> <i>Brown</i>	345
Discussion. <i>Messrs. Richardson, Harrod, Hardee, Lewis and Brown</i>	360
Obituary.—David Walker Hardenbrook	402
Proceedings.	

INDEX.

VOL. XXVI, January-June, 1901.

The six numbers were dated as follows :

No. 1, January.	No. 3, March.	No. 5, May
No. 2, February.	No. 4, April.	No. 6, June.

ABBREVIATIONS.—P = Paper ; D = Discussion ; I = Illustrated.

Names of authors of papers, etc., are printed in *italics*.

	PAGE
A ir Compression, Water Power by Direct —. <i>William O. Webber</i> .	
P, I, Jan.,	35
Arches, Rapp Floor—, A Test of the Strength of—. <i>Frederic H. Fay</i> .	
P, I, Feb.,	79
<i>Anderson, Latham</i> . Hydraulic Excavation	P, I, Jan., 1
Annual Report of the Chairman of the Board of Managers	Jan., 65
Annual Report of the Secretary of the Board of Managers	Jan., 65
Arches, Economy and Strength of Brick and Concrete—for Floor Systems of Highway Bridges. <i>Wm. D. Bullock</i>	P, I, Feb., 73
Articles of Association	Jan., 62
Atoms and Molecules, Extension of the Group Theory of—.	
<i>Arthur A. Skeels</i>	P, I, March, 223
<i>Bailey, William M.</i> Expanded Metal as Used in Fireproof Building Con- struction and Other Work	P, I, Feb., 84
B atteries, Storage —, Installation, Operation and Economy of —.	
<i>Ernest Lunn</i>	P, I, April, 255
<i>Bendit, Louis</i> . The Softening of Feed Water for Boilers	P, I, May, 285
<i>Blackford, Francis W.</i> Engineering Explorations in Montana and Else- where in the Rocky Mountains	P, March, 239
Blast Furnace, A Modern American —, Its Construction and Equipment.	
<i>Arthur C. Johnston</i>	P, I, Jan., 47
Boilers, The Softening of Feed Water for—. <i>Louis Bendit</i> . P, I, May,	285
<i>Branne, J. S.</i> The Steel Skeleton Construction of a Tall Office Building.	
P, I, Feb.,	125
BRICK AND CONCRETE-METAL CONSTRUCTION.	
Economy and Strength of Brick and Concrete Arches for Floor Systems of Highway Bridges. <i>Wm. D. Bullock</i>	P, I, Feb., 73
A Test of the Strength of Rapp Floor Arches. <i>F. H. Fay</i> . P, I, Feb.,	79
Expanded Metal as Used in Fireproof Building Construction and Other Work. <i>William M. Bailey</i>	P, I, Feb., 84
Description of Ransome System of Concrete Steel Floors. <i>M. C. Tuttle</i> .	
P, I, Feb.,	93
Tests of Roebling Fireproof Floors. <i>Andrew W. Woodman</i> .	
P, I, Feb.,	100
A Review of Concrete-Metal Construction. <i>C. M. Kutz</i> . P, I, Feb.,	108

Bridges, Floor Systems of Highway —, Economy and Strength of Brick and Concrete Arches for—.	<i>Wm. D. Bullock</i>	P., I., Feb.,	73
<i>Brown, Linus W.</i> The Increasing Elevation of Floods in the Lower Mississippi River		P., D., June,	345
Building, The Steel Skeleton Construction of a Tall Office—.			
<i>J. S. Branne</i>		P., I., Feb.,	125
<i>Bullock, William D.</i> Economy and Strength of Brick and Concrete Arches for Floor Systems of Highway Bridges		P., I., Feb.,	73
Burke, Sherman Emmett—.	Obituary. Engineers' Club of Cincinnati .	April,	283
Canals, Early Transportation—.	<i>J. T. Fanning</i>	May,	315
Cement, On the Engineering Difficulties Attending a Proper Inspection of—.			
<i>J. F. Coleman</i>		P., D., May,	305
Chairman of Board of Managers, Annual Report of—.		Jan.,	65
Claffen, Henry M.—.	Obituary. Civil Engineers' Club of Cleveland .	March,	253
<i>Coleman, J. F.</i> On the Engineering Difficulties Attending a Proper Inspection of Cement		P., D., May,	305
Compression, Water Power by Direct Air—.	<i>William O. Webber</i> .		
		P., I., Jan.,	35
Concrete Construction.	<i>C. R. Ncher</i>	P., D., I., April,	279
Concrete-Metal Construction, Brick and —.		P., D., I., Feb.,	73
Concrete-Metal Construction, A Review of—.	<i>Charles M. Kurtz</i> .		
		P., I., Feb.,	108
Conduits, Gas—Subaqueous Tunnels for—.	<i>W. W. Cummings</i> .		
		P., D., I., June,	327
<i>Cummings, W. W.</i> Subaqueous Tunnels for Gas Conduits.		P., D., I., June,	327
Early Transportation Canals.	<i>J. T. Fanning</i>	P., May,	315
Electric Lighting of City Streets.	<i>Henry H. Humphrey</i>	P., I., Jan.,	18
Engineering Explorations in Montana and Elsewhere in the Rocky Mountains.	<i>Francis W. Blackford</i>	P., March,	239
Engineering Society, The—Its Relations to the Engineer and to the Profession.	<i>H. J. Maloché</i>	P., Feb.,	149
Excavation, Hydraulic—.	<i>Latham Anderson</i>	P., I., Jan.,	1
Expanded Metal as Used in Fireproof Building Construction and Other Work.			
<i>William M. Bailey</i>		P., I., Feb.,	84
Extension of the Group Theory of Atoms and Molecules.	<i>Arthur A. Skeels</i> .		
		P., I., March,	223
<i>Fanning, J. T.</i> Early Transportation Canals		P., May,	315
<i>Fay, Frederic H.</i> A Test of the Strength of Rapp Floor Arches.		P., I., Feb.,	79
<i>Fenkell, George H.</i> A Study in Hydraulics		P., D., I., March,	155
Fireproof Building Construction and Other Work. Expanded Metal as Used in —.	<i>William M. Bailey</i>	P., I., Feb.,	84
Fireproof Floors. Roebbing, Test of—.	<i>Andrew W. Woodman</i> .	P., I., Feb.,	100
Floods, The Increasing Elevation of—in the Lower Mississippi River.			
<i>Linus W. Brown</i>		P., D., June,	345
Floor Arches, Rapp —A Test of the Strength of—.	<i>Frederic H. Fay</i> .		
		P., I., Feb.,	79
Floor Systems of Highway Bridges. Economy and Strength of Brick and Concrete Arches for —.	<i>Wm. D. Bullock</i>	P., I., Feb.,	73
Floors, Description of Ransome System of Concrete Steel—.	<i>M. C. Tuttle</i> .		
		P., I., Feb.,	93

Floors, Roebling Fireproof— Tests of—.	<i>Andrew W. Hood</i>	
	P., I., Feb.,	108
Furnace, Blast—A Modern American—, Its Construction and Equip- ment.	<i>Arthur C. Johnston</i>	P., I., Jan., 47
Gas Conduits, Subaqueous Tunnels for—.	<i>W. W. Cummins</i>	
	P., D., I., June,	327
Hardenbrook, David Walker—	Obituary. Montana Society of Engineers	
	June,	402
Hollinshead, James S. B.—.	Obituary. Montana Society of Engineers.	
	I., March,	251
<i>Humphrey, Henry H.</i> Street Lighting of Cities	P., I., Jan.,	18
Hydraulic Excavation.	<i>Latham Anderson</i>	P., I., Jan., 1
Hydraulics, A Study in—.	<i>George H. Finkell</i>	P., D., I., March, 155
Increasing Elevation of Floods in the Lower Mississippi River.	<i>Linus W. Brown</i>	P., D., June, 345
Installation, Operation and Economy of Storage Batteries.	<i>Ernest Lunn</i> .	
	P., I., April,	255
<i>Johnston, Arthur C.</i> A Modern American Blast Furnace—Its Construction and Equipment	P., I., Jan.,	47
<i>Kurtz, Charles M.</i> A Review of Concrete-Metal Construction.	P., I., Feb.,	108
Lighting, Street—of Cities.	<i>Henry H. Humphrey</i>	P., I., Jan., 18
<i>Lunn, Ernest.</i> Installation, Operation and Economy of Storage Batteries.		
	P., I., April,	255
<i>Malochée, H. J.</i> The Engineering Society—Its Relations to the Engineer and to the Profession	P., Feb.,	149
Metropolitan Water Board, Submerged Pipe Crossings of the—.	<i>Caleb Mills Saville</i>	P., D., I., March, 193
Mississippi River, The Increasing Elevation of Floods in the Lower—.	<i>Linus W. Brown</i>	P., D., June, 345
Modern American Blast Furnace, A—Its Construction and Equipment.	<i>Arthur C. Johnston</i>	P., I., Jan., 47
Molecules, Atoms and—, Extension of the Group Theory of—.	<i>Arthur A. Skeels</i>	P., I., March, 223
Montana, Engineering Explorations in—and Elsewhere in the Rocky Moun- tains.	<i>Francis W. Blackford</i>	P., March, 239
<i>Ncher, C. R.</i> Concrete Construction	P., D., I., April,	273
OBITUARY—		
Sherman Emmett Burke, Engineers' Club of Cincinnati	April,	283
Henry M. Claßen, Civil Engineers' Club of Cleveland	March,	253
David Walker Hardenbrook, Montana Society of Engineers	June,	402
James S. B. Hollinshead, Montana Society of Engineers	I., March,	251
George W. Percy, Technical Society of the Pacific Coast	I., Jan.,	59
Office Building, Steel Skeleton Construction of a Tall—.	<i>J. S. Brannan</i> .	
	P., I., Feb.,	125
On the Engineering Difficulties Attending a Proper Inspection of Cement.	<i>J. F. Coleman</i>	P., D., May, 305

	PAGE
Percy George W.—. Obituary. Technical Society of the Pacific Coast.	
I., Jan.,	59
Pipe Crossings, Submerged—of the Metropolitan Water Board.	
<i>Caleb Mills Saville</i> P., D., I., March,	193
Power, Water—by Direct Air Compression. <i>William O. Webber</i> . P., I., Jan.,	35
Ransome System of Concrete Steel Floors. Description of— <i>M. C. Tuttle</i> .	
P., I., Feb.,	93
Rapp Floor Arches. Test of the Strength of— <i>Frederic H. Fay</i> . P., I., Feb.,	79
Review of Concrete-Metal Construction. <i>Chas. M. Kurtz</i> . . . P., I., Feb.,	108
Rocky Mountains, Engineering Explorations in Montana and Elsewhere in the— <i>Francis W. Blackford</i> P., March,	239
Roebling Fireproof Floors, Tests of— <i>Andrew W. Woodman</i> . P., I., Feb.,	100
<i>Saville, Caleb Mills</i> . Submerged Pipe Crossings of the Metropolitan Water Board P., D., I., March,	193
Secretary of Board of Managers, Annual Report of— Jan.,	65
<i>Skeels, Arthur A.</i> Extension of the Group Theory of Atoms and Molecules. P., I., March,	223
Softening of Feed Water for Boilers, The— <i>Louis Bendit</i> . . P., I., May,	285
Steel Skeleton Construction of a Tall Office Building. <i>J. S. Branne</i> . P., I., Feb.,	125
Storage Batteries, Installation, Operation and Economy of— <i>Ernest Lunn</i> . P., I., April,	255
Street Lighting of Cities. <i>Henry H. Humphrey</i> P., I., Jan.,	18
Study in Hydraulics, A— <i>George H. Fenkell</i> P., D., I., March,	155
Subaqueous Tunnels for Gas Conduits. <i>W. W. Cummings</i> . . P., D., I., June,	327
Submerged Pipe Crossings of the Metropolitan Water Board.	
<i>Caleb Mills Saville</i> P., D., I., March,	193
Tunnels for Gas Conduits, Subaqueous— <i>W. W. Cummings</i> .	
P., D., I., June,	327
<i>Tuttle, M. C.</i> Description of Ransome System of Concrete Steel Floors.	
P., I., Feb.,	93
Water Power by Direct Air Compression. <i>William O. Webber</i> . P., I., Jan.,	35
Water, The Softening of Feed—for Boilers. <i>Louis Bendit</i> . . P., I., May,	285
<i>Webber, William O.</i> Water Power by Direct Air Compression . P., I., Jan.,	35
<i>Woodman, Andrew W.</i> Tests of Roebling Fireproof Floors . . P., I., Feb.,	100



GEORGE W. PERCY

President, Technical Society of the Pacific Coast.

ASSOCIATION OF ENGINEERING SOCIETIES.

Organized 1881

VOL. XXVI.

JANUARY, 1901.

No. 1.

This Association is not responsible for the subject-matter contributed by any Society or for the statements or opinions of members of the Societies.

HYDRAULIC EXCAVATION.

BY LATHAM ANDERSON, MEMBER ENGINEERS' CLUB OF CINCINNATI.

[Read before the Club, October 18, 1900.*]

THE origin of hydraulic mining is recorded as follows by an eminent authority, Mr. Charles Waldeyer, of California, and published in the report of Dr. Rossiter W. Raymond, United States Commissioner of Mining Statistics, 1873. Page 390 *et seq.*:

"The origin of hydraulic mining dates back as far as the spring of 1852, . . . when a miner, whose name is forgotten, put up a novel machine on his claim at Yankee Jim, in Placer county, Cal. This machine was very simple. From a small ditch on the hillside, a flume was built towards the ravine, where the mine was opened; the flume gained height above the ground as the ravine was approached, until finally a 'head' or vertical height of 40 feet was reached. At this point the water was discharged into a barrel, from the bottom of which depended a hose, about 6 inches in diameter, made of common cowhide, and ending in a tin tube about 4 feet long, the latter tapering down to a final opening or nozzle of 1 inch.

"This was the first hydraulic apparatus in California. Simple in design, dwarfish in size, yet destined to grow out of its insignificance into a giant powerful enough to remove mountains from their foundations."

Within three decades after the conception of that germ of the giant the topography of two antipodal continents has been profoundly modified, in large areas, by hydraulic mining. In California alone countless millions of cubic yards of detritus, torn from their primordial beds, have been transported from the mountains to the ocean, an average "haul" of more than 100 miles, or have been dropped on the way in the main river beds and the Bay of San Francisco. Many miles of the abyssmal canyons of

*Manuscript received December 31, 1900.—Secretary, Ass'n of Eng. Soc's.

the Sierras have been filled a hundred feet and more in depth by the heavier parts of the tailings.

When one is first brought to face these stupendous results, he finds it difficult to accept facts so at variance with previous human experience. But the main facts are incontrovertible, having been recorded in years of litigation and legislation concerning the struggle for existence between the farmers and the miners. For the filling of the river beds with tailings so increased the destructive effects of floods as to damage or ruin whole districts of farming country, and the shoaling up of large areas in the bay had so seriously affected navigation therein that these two interests combined and organized to demand the abolition of hydraulic mining. The outcome was a Waterloo to the great hydraulic mining companies. Nothing could more strongly emphasize the vastness of these deposits and their resulting damages than that verdict of the courts and legislature. It is still further accentuated by the fact that these findings and laws were possible in California,—the child of mining, and especially of gravel mining,—which has produced more than three-fourths of all the gold output of the State.

The extent of these mining operations may be further illustrated by a glance at two of the large hydraulic mines as types of the class,—viz, the North Bloomfield, in Nevada county, Cal., and the Spring Valley, at Cherokee, Butte county. The capital invested in the North Bloomfield was \$2,500,000. To gain outlet for the tailings into the nearest canyon, a tunnel 7 by 9 feet, 6900 feet long, had to be cut through solid rock. The sluice line was over 2 miles in length and 6 feet wide. The "bank" or auriferous gravel deposit was 400 feet deep and 600 feet wide, the company owning a mile and a half in length of this deposit. A 6-inch g'iant was used under a 500-foot head delivering 32.8 second feet of water and developing nearly 1690 horse power; and a 7-inch nozzle under a 250-foot head, delivering 31.54 second feet and developing about 1560 horse power. From 15,000 to 18,000 cubic yards of gravel were washed away each day of twenty-four hours.

The Spring Valley bank was about 400 feet in height. The bed rock tunnel was much shorter, but to obtain a dumping ground the company had to purchase over 700 acres of valuable farm land. At the time of the writer's visit in 1882, they had buried this land 12 feet deep with tailings, were expecting to add three feet to this depth, and still would be under the necessity of buying more land.

At the Dardenelles Mine 10-inch nozzles, under heavy pressure, are said to have been used.

All the data concerning the three above-named mines are given from memory, the writer not having any records at hand for verification.

It may seem superfluous to rehearse before an audience of engineers so many facts concerning hydraulic excavation, which have become stale history. The only purpose of the recital is to emphasize the strangeness of this strange freak in economic history, that in this century, pre-eminent for discoveries and appliances in the mechanical arts, so little has been done towards adopting, in general engineering practice, this most economical of all methods of earth removal. It is still more singular that it has not been generally adopted in the mining of other ores than gold, especially in winning limonite iron from its clay beds on the flanks of hills to which, in the writer's opinion, it is better adapted than even to gold mining.

But this is only in passing, as mining is not within the scope of this paper.

For the purposes of this discussion, there are three different processes employed in hydraulic excavation,—viz:

First. The sluice (sometimes called the "ground-sluice").

Second. The "giant."

Third. The "boom."

Under certain conditions all may be used to advantage by the general practitioner.

The second is, in the opinion of the writer, more generally applicable, and more powerful and economical in the class of works herein contemplated.

The sluice is best adapted to shallow deposits, where the banks would not be high enough to cause danger from caves. It consists simply of a line of boxes laid along the bottom of an open cut through the deposit to be moved. The material is loosened by the pick or plow, and shoveled by hand or dumped from wheelbarrows into the stream running through the boxes, at the lower end of which it is discharged upon the dump. Of course the more copious the supply of water, and the rate of fall in the boxes, the greater their carrying power and the economy of the process.

The boom consists of a temporary dam behind which the water supply is allowed to accumulate till a sufficient amount is stored, when the water is let out in a rush by suddenly opening large flood gates. The wave or torrent thus produced is directed against the foot of the bank to be removed. It is said that the boom has seldom been used outside of Colorado; but its advo-

cates there claim that it is one of the most economical methods of hydraulic excavation where the supply of water is either very abundant or very scarce.

The writer has had no experience with the hydraulic boom, and only quotes from other writers on the subject.

The following table is quoted from Van Wageningen's "Manual of Hydraulic Mining" (D. Van Nostrand Company), page 20, to illustrate the comparative efficiency of primitive hand work and the three types of hydraulic mining above enumerated.

The two materials assumed as a basis of comparison are ordinary loose and cemented gravels. Of course only an approximate and general average is attempted in such tables. According to the writer's experience, while very soft and friable clay will cut and wash away more rapidly than any gravel, the average compact clay bank will come between the two enumerated gravels in rate of working, being closer to the loose gravel.

TABLE.

	ORDINARY.	CEMENTED.
By the pan.	1 cu. yd.....	$\frac{3}{4}$ cu. yd.
" " rocker.	2 " yds.....	2 " yds.
" " long ton.	5 to 6 " ".....	3 to 5 " "
" " sluice.	10 to 20 " ".....	6 to 12 " "
" " hydraulic.	100 to 1000 " ".....	100 to 1000 " "
" " boom.	unlimited.....	unlimited.

The table shows the number of cubic yards of dirt which may be washed per day of ten hours per man, in the first two cases each man working alone, and in the last four in pairs or economically arranged gangs.


The likelihood that the boom will ever be indicated as a sole means of excavation in general practice is so remote that the device is not worthy of consideration here, but it may, in rare instances, be a useful auxiliary to the giant. It is also frequently beneficial to increase the carrying capacity of an hydraulic sluice line by turning into its head an auxiliary natural stream without head, or from a lower source than that supplying the giant.

Mr. Waldeyer's paper, above quoted, contains a lucid description of hydraulic mining, and, notwithstanding the fact that it was written more than a quarter of a century ago, the reader may gain a clear impression of all the essential features of the process which are germane to this discussion.

But a word of caution is demanded here to the reader who consults text-books on hydraulic gold mining for information as

to the serviceability of the hydraulic for general purposes. (It must keep in mind that the sole aim of the miner is to save gold, and as much gold as possible, consistent, of course, with economy.) To this end, it is always necessary to restrict the amount of gravel carried by the boxes in order to increase the yield of gold.

(It goes without saying that all the mere gold-saving improvements and appliances of the miner are foreign to the topic in hand.) The maximum discharge of the boxes occurs when the velocity of the current is greatest and the water is most charged with mud, but the clearer the water and the slower the current the more readily will the fine gold settle to the bottom of the boxes and be caught by the quicksilver. Hence the necessity of restricting the discharge, in order to increase the amount of gold




saved, and whence it follows that statistics from gold-mining practice must invariably underestimate the capacity of the giant as a labor-saving device.

To recapitulate the conditions essential to economical hydraulic excavation, they are: the greater the volume of water, the head and the fall in the sluice line, the higher the bank (*i.e.*, the deeper the cut), and the more available the dumping ground, the greater the economy.

As all of these must be self-evident to every engineer, except possibly that of the height of the bank, we will refer to that at length further on.

It is now in order to outline the process of opening and working an hydraulic mine. From the great storage reservoir in the Sierras, fifty or one hundred miles distant, a ditch conveys the water to the service or distributing reservoir, which is on the nearest hill to the "cut" which will give the required "head" or pressure. From the distributing reservoir the water is conveyed to the workings in a riveted sheet iron pipe, in 16-foot lengths, at 100

are jointed stovepipe fashion. To the lower end of the pipe line P, Fig. 1, is strongly attached the giant. A longitudinal section of one of the smaller sizes is shown in Fig. 1. This consists of a pipe about 9 feet long, attached at its lower end to a cast iron globular casing or jacket G¹, inclosing the minor globe G. Attached to the outer surface of G are the trunnions T, whose horizontal axis passes through the center of the spherical surfaces G and G¹. The trunnions pass outwardly through collars in the casing G¹. This arrangement permits ample upward and downward movement of the pipe. The outer end of the pipe is provided with a screw joint, so that nozzles N of different aperture may be attached. There is a horizontal joint J between the lower extension of the globe, called the "goose neck" (GN), and the heavy bedplate BP. Of course all joints and bolt holes




must be packed water-tight. (The joint J is tightened by the rod R passing down through the goose neck and bedplate.) Horizontal and vertical motion may be imparted to the pipe, simultaneously, if desired, by the lever L, a piece of scantling attached, at its front end E, to the pipe by the collar strap C, and to the fulcrum F by the collar C¹ and the pin P³.

The plan of the bed frame is shown in Fig. 2, in which S.S. are the bed sills and Sm, Sm are the mud sills. Nailed to the top of the lever is a shallow wooden box W, which is weighted down with loose stones so as just to counterbalance the downward reaction of the water upon the pipe. It is apparent that this machine is so simple as to be readily set up, managed and kept in order by any workman of average intelligence. But, like many other simple machines (billiard cues, for instance), there are widely differing degrees of skill displayed by different practitioners. This is so pre-eminently true with regard to the giant

as to make the pipeman the essential and most important employe on the works after the installation is complete. In fact, the degree of economical success or failure of the enterprise is gaged by his skill. It lies in him to make or mar the business. It is, therefore, a sheer waste of money to put such a plant in the hands of a novice or of an unskillful pipeman. Quick perception, nerve, intelligence and good judgment all go to make up the ideal pipeman or bank foreman. (In small plants the two offices are usually combined.)

THE NOZZLE.

The nozzle N requires further notice. Upon the perfection of its shape and condition the cutting efficiency of the stream mainly depends. The cutting power of a stream of given volume and nozzle velocity is in the ratio of its solidity at the point of impact. Strictly speaking, a column or shower of spray has no



cutting power; it merely washes. But a solid stream with a nozzle velocity of say 90 feet (due to a head of 150 feet) pierces a bank like a projectile or bores like an auger. It surprises the novice to see what refinements of precaution are requisite to insure such solidity of stream.

First. No entrained air should be permitted to pass the nozzle.

Second. The bore of the latter should be of correct shape ("ajutage"), and, in the cylindrical part, should be as true and smooth as a gun barrel. Because iron soon becomes roughened by rust, hard gun metal is a better material for nozzles.

Third. Rifles or radial plates *r, r*, Figs. 3 and 4, should be inserted in the pipe to prevent the rotary motion otherwise bound to occur, which whirling motion of the column would destroy its cylindrical shape and solidity.

THE SLUICE LINE.

In gold mining, the boxes, Figs. 5 and 6, must be of planed, tongued and grooved lumber, so as to be perfectly water-tight, since the smallest leak would cause the loss of fine gold and

amalgam, and they must have costly bottom paving. But, for our purposes, any tolerably tight boxes of cheap, undressed lumber will answer. And here is our first advantage in point of economy over the gold miner. A further gain is in avoiding (usually) the costly bottom paving of the gold miner, no lining being required for small operations, say of 20,000 or 30,000 yards, while for larger ones 1 or 1½-inch plank bottom linings would usually be sufficient on moderate grades. The upper end of the boxes should be provided with flaring wings of temporary sheet piling.

Near the head of the upper box is placed an inclined grating, with spaces of such size as to arrest all stones too large to be carried freely by the current in the boxes. The rejected stones are forked over in a pile to one side of the line of boxes by a man stationed at the grating for that purpose. If required, these piles of stones may be carried or run out of the cut on a tramway as




FIG. 5. ELEVATION OF UPPER END.

the work proceeds. The giant is set up a little to one side of the sluice head.

Everything is now in position to begin the cut. Fig. 7 shows in plan the relative positions of the sluice head S, the giant G and the initial point P. T.T. is the tramway for removing the piles of refuse R (including boulders, stumps, roots of trees, etc.). The stream from the giant is turned upon the point P. A cavity is rapidly formed in the base of the hill and a mixture of water, mud and stones pours down into the boxes. When the face of the cut approaches the limit of the giant's cutting efficiency, the work is stopped. The giant is taken up, a new joint or joints of pipe are added, and the giant set up in its new position. Especial care is demanded in securing the bed frame of the giant firmly in the ground. Small, sharp gravel or firm soil should be rammed hard around the mud sills, and the frame should be strongly braced against forward or lateral motion, because a very slight movement of the giant would loosen some of the joints in the pipe line.

The sluice head is carried forward at the same time with the giant, by adding boxes at the upper end.

When the bank attains a height of 15 or 20 feet, it is usually in a shape to begin the first cave. The foot of the bank is undercut several feet in height, forming a cave, or a series of caves, with intervening pillars. When the caves are knocked into one by cutting out the pillars, the overhanging mass trembles, splits off on the plane of the back of the cave, and plunges into the cut with a momentum that shatters the mass. Now, the higher the bank the larger will be the amount of overhanging earth brought down by a given amount of undercut, whence the economy of high banks becomes apparent. Take the case of a bank like that at North Bloomfield, 400 feet high. Suppose the cut is 40 yards long, 2 yards deep and 10 feet high. The amount of undercut would be about 260 yards, and the amount caved down




FIG. 6. SECTION OF ELEVATION ON LINE *a b*, FIG. 5.

would be over 10,000 tons. But such high banks are usually so dangerous that it is preferred to work them in two stages, as they were doing at North Bloomfield on the occasion of the writer's visit. But operations on such a scale would rarely, if ever, be demanded in engineering work. In railroad cuts of from 40 to 100 feet, for instance, it is not likely that more than from 2 to 4 second feet of water under 150 feet head (2 to 3-inch nozzles) would ever be required. In most cases, especially on high summits, the water would have to be delivered by steam power.

To recapitulate, in point of economy our practice is inferior to the great hydraulic mining plants in the following particulars: First. In volume of water.

Second. (Usually) in amount of head or pressure.

Third. (Probably in most localities) in not having a natural or gravity supply and pressure.

But, on the other hand, we have the following advantages over any and every mining plant:

First. We may use cheaper boxes and sluice line.

Second. We avoid the expense of all the costly gold-saving devices and appliances,—*e.g.*, costly bottom paving in the sluice line, undercurrents, box-riffles, retort house and the loss of at least four days' time each month in "cleaning up" (collecting amalgam) and in repairing sluice line.

Third. We save the interest and sinking fund on the capital invested in the huge dam and reservoir, and in the scores of miles of main ditch.




FIG. 7.

Fourth. The outlay, in railroad work especially, will be much smaller for giants, pipe line, tools and machinery for the cut than in mining.

As a deduction from the foregoing premises, we conclude that, under certain conditions, a great saving may be effected in the cost of the above indicated classes of engineering work by the use of hydraulic excavation, especially with the nozzle.

That this conclusion may not be relegated to the domain of abstract argument, your attention is called to the following recent

instances of the successful application of hydraulic cutting and filling in general engineering practice.

We will begin with extracts from "Reservoirs for Irrigation," by James D. Schuyler, Member American Society of Civil Engineers (United States Geological Survey Report, 1896-97, Part IV).

HYDRAULIC DAM CONSTRUCTION.

La Mesa Dam, San Diego, Flume county, Cal., for the purpose of storing the flood water of San Diego River, etc. "The dam was designed and constructed by J. M. Howells, C.E., President of the San Diego Flume Company. . . . It is an earth and rock-fill dam, 66 feet high and 20 feet wide on top, the materials for which were transported and deposited in place by flowing water, by the process known to miners as '*ground-sluicing*,' the surplus water from the flume being used for this purpose, and at the same time being stored in the reservoir as it was being formed back of the dam (page 649). The volume of material handled was 38,000 cubic yards, which had to be brought an extreme distance of 2200 feet, and stripped from an area of $11\frac{1}{2}$ acres to a mean depth of 2 feet. Had the material been favorable in depth and character, it is thought the entire dam could have been finished for 25 or 30 per cent. of its ultimate cost, which was about \$17,000. Instead of sluice boxes, the material was conveyed for the last 2000 feet in 24-inch wooden stave pipes lined with strips of steel to resist wear. Cost, 90 cents per foot. (Page 650.)

PROPOSED PINE VALLEY DAM, SAN DIEGO, FLUME COUNTY.

(Page 653.)

Dam to be 130 feet high, 30 feet wide on top. The water to be used for sluicing will have to be pumped to a height of 400 feet, in order to reach the deposits of material available for sluicing, but the engineer estimates that even this high lift is feasible and profitable, and he expects to increase the duty of water used from 5 per cent. of solids conveyed (the maximum accomplished at La Mesa Dam) to about 20 per cent. of solids, or 13 cubic yards per miner's inch of twenty-four hours (0.02 cubic foot per second). "If this duty can be maintained, and the cost of pumping be assumed at a maximum of 5 cents per 1000 gallons, the cost per yard for water will be about 5 cents, with but little additional cost for loosening (with pick), as the material is soft." (Please note that if giants were used *no additional cost for loosening would be incurred.*)

PROPOSED LAKE HELENA DAM, SAN DIEGO RIVER.

(Page 654.)

The proposed dam is 1100 feet long on top, 190 feet at base, 155 feet high, 25 feet wide on top, bottom thickness of 650 feet and to contain 789,000 cubic yards. "This site is considered favorable for hydraulic construction because of the abundance of material on both sides and the possibility of using *water under high pressure to loosen the material by powerful jets from hydraulic mining giants.*

DAM AT TYLER, TEXAS.

(Page 654.)

This dam, constructed in 1894, has the following features: Length 575 feet, height 32 feet, and contains 24,000 cubic yards. This impounds 1770 acre feet and covers 177 acres.

The water was pumped through a 6-inch pipe from the old city pumping station. This hill is 150 feet high and the pipe terminated halfway from its base, where a common fire hydrant was placed, to which was attached an ordinary 2½-inch hose with a 1½-inch nozzle. *The cost, including the plant and all the appurtenances of the reservoir, was 4¾ cents per yard.*

The following additional facts throw further light upon the secret of this remarkable result:

"The stream was directed against the face of the hill under a pressure limited to 100 pounds per square inch. The washing was carried rapidly into the hill on a 3 per cent. grade, which soon gave a working face of 10 feet or more, increasing gradually to 36 feet in vertical height. *By maintaining the jet at the foot of the cliff it was undermined as rapidly as it could be broken up and carried away by the water.*"

SAN LEANDRO AND TEMESCAL DAMS, CALIFORNIA.

(Page 655.)

These furnish part of the supply of the city of Oakland, having 60,000 inhabitants. They were constructed by their principal owner, Mr. A. Chabot, who had been a practical hydraulic miner.

The Temescal Dam was built in 1868. The work was continued a number of seasons by collecting storm water from time to time. The dam is 105 feet high and 18 feet wide on top, *covering only 18.5 acres*, with a capacity of 188,000,000 gallons.

The San Leandro Dam was built in 1874-75, and has a height of 120 feet above the stream bed. Total volume of dam is 542,-

HYDRAULIC EXCAVATION.

700 yards, of which 160,000 yards were deposited by the hydraulic process. The water was brought four miles in a ditch, and the sluiced materials were conveyed in a flume lined with sheet iron plates, laid on a grade of 4 to 6 per cent. The water used was 10 to 15 second feet, and the ground-slueing method was alone employed; *nevertheless the cost was estimated at one-fourth to one-fifth that of putting the earth in place by carts or scrapers.*

HYDRAULIC FILLS ON THE CANADIAN PACIFIC RAILWAY.

(Page 657.)

At trestle No. 374, North Bend, in Frazer River Canyon, there is required to fill the chasm an embankment 231 feet in extreme height and containing 148,000 cubic yards. The plant consisted of 1450 feet of sheet steel pipe 15 inches in diameter, 1200 feet of sluice boxes or flume 3 feet wide and 3 feet deep; one No. 3 "giant" monitor with 5-inch nozzle, and a large derrick driven by a Pelton water wheel. Piping head 125 feet. The sluice boxes were laid on grades from 11 to 25 per cent., partly supported on high trestles. The boxes were paved with wood blocks on the lighter grades and old railway rails on the heaviest. Fifty per cent. of the pit consisted of *cemented gravel*, 30 per cent. of loose gravel and 20 per cent. of large boulders which had to be removed by the derrick. Nevertheless, the entire cost of the work, including the plant, was \$5089, or at the rate of 7.24 cents per yard (and including explosives used on the cemented gravel). "Had the pressure of the water been greater (400 to 500 feet head) and the gravel loose, *the duty of the water would have been increased four-fold.*"

The entire force employed consisted of eight men, all common laborers except the pipeman. The water used was approximately 20 second feet or 1000 miner's inches, the duty performed being 1.77 yards per twenty-four-hour inch. At the crossing of Chapman's Creek the railway company, in 1894, made a similar fill of 66,000 yards at a total cost of 7.5 cents per yard, of which 3.2 cents was for plant. The actual work of sluicing cost but 1.78 (*one and seventy-eight hundredths*) cents per yard.

HYDRAULIC FILLS ON THE NORTHERN PACIFIC RAILWAY.

(Page 659.)

Work of a precisely similar nature has been in progress for a number of years past on the line of the Northern Pacific Railway, where several high and dangerous trestles have been replaced by hydraulic-made embankments of earth, gravel and loose

rock. During 1897, nine high trestles, requiring from 6200 to 108,500 cubic yards. Of this amount 377,000 cubic yards in eight of the trestles were moved and put in place at an average cost of 4.79 cents per cubic yard. The detail of the cost is given below:

Sluicing and building side levees.....	3.85 cents.
Hay used in levees09 "
Tools08 "
Lumber and nails22 "
Labor building flumes44 "
Engineering and superintendence11 "
Total	4.79 "

"In all the above work the water was carried to the borrow pits and the sluicing done by gravity. In one case, however, pumping was resorted to, and 42,250 cubic yards were moved by water thus lifted, at an average cost of 13.5 cents per cubic yard."

"The plant required is rather inexpensive. According to locality, one nozzle would require from 300 to 1000 feet of light sheet iron pipe costing $27\frac{1}{2}$ cents a foot and a No. 2 giant costing \$95. Outside of this nothing is required except picks, shovels, hoes and axes. From five to six men are required with each nozzle to build the levee, build sluice boxes and do everything else required."

THE DRAINAGE OF THE OKEFINOKEE SWAMP, GEORGIA.

In the "Engineering Society Annual of the University of Georgia," Vol. I, 1893, page 12, there is an article entitled "Hydraulic Excavation," by B. M. Hall, C.M.E., formerly a professor in the Georgia University. From this valuable paper we make the following extracts:

"Notwithstanding the fact that hydraulic gold mining has been in progress for so many years on the Pacific slope and in the State of Georgia, engineers seem slow to adopt this cheap plan of excavation for other work, such as railroads, canals, etc., even when the conditions necessary to successful operation are all present and in plain view.

"These conditions are:

"1. Material that is soft enough to be loosened and washed away by water.

"2. A sufficient volume of water at an elevation above the proposed cut.

"3. Sufficient grade, away from the bottom of the cut, for giving the water enough velocity to take away the material.

. . . Where booming is resorted to, for getting soft material out of the way, the cost is often as low as one cent per cubic yard. . . .

"The most important work of this nature that we know of is being done in Charlton county, Ga., by the Suwanee Canal Company, in excavating the outlet canal for the drainage of Okefinokee Swamp. That swamp, situated in Charlton, Clinch, Ware and Pierce counties, is a shallow fresh water lake, covering an area of 400,000 acres and filled with black muck. . . .

"The Suwanee Canal Company purchased the greater part of this land from the State of Georgia, and about 100,000 acres from individuals. The object of their undertaking is:




FIG. 8. DRAINAGE OF OKEFINOKEE SWAMP, GEORGIA. HOR. SCALE 1 MILE TO 1 INCH. VER. SCALE.

"1. To cut and place on the market this vast store of valuable timber, and,

"2. To thoroughly drain the lands for cultivation.

"A profile of the swamp and proposed drainage is shown by Fig. 8.

"In making plans for drainage, the first thing necessary was to provide a sufficient outlet by cutting a deep canal through the dividing ridge. It is here that the method of hydraulic excavation is being used on a grand scale and in a highly interesting manner. First, a narrow, shallow canal was cut across the ridge with teams and scrapers as in railroading. Its depth was about 17 feet at the summit, and it ran to nothing at each end, as its bottom was level across the ridge. . . . At the eastern mar-

gin of the swamp a pumping plant, consisting of two 80-horse-power boilers and two 14-inch centrifugal pumps, lifts 30,000 gallons of water per minute into a flume, producing an immense stream, which runs into and through the canal. At the eastern end of this preliminary cut, where the slope toward the mine is steep, the water began to do its work. A deep and wide canal is being carried rapidly back toward the swamp."

A "porcupine" harrow, made of a round log filled with harrow teeth, is dragged up and down the canal by steam power, a distance of 1000 feet. The excavated material is dumped into a lateral ravine of such storage capacity that nothing but clear water drains into the St. Mary's River. The average cost of excavation on the outlet canal is $2\frac{1}{2}$ cents per cubic yard.

HYDRAULIC EXCAVATION AT SEATTLE.

The Seattle and Lake Washington Navigation Company is opening navigable tidal channels by dredging and the reclamation of tide lands adjacent to the business center of Seattle, Washington, by filling with the fine black sand dredged from the channels. Two powerful dredges are used, each with a capacity of 600 to 700 cubic yards per twenty-four hours, which is pumped from the bottom of the channel through 18-inch pipes, a distance of 2000 to 4000 feet, and deposited to a depth of 18 to 20 feet over the area to be reclaimed. Some 36,000,000 cubic yards are to be handled in this way, and 1500 acres filled in solidly to a height of 2 feet above tide. About 1,000,000 yards had been put in place January 1, 1897, the cost of which was 16 cents per yard by contract.

In conclusion, the writer desires to call the attention of the Club to what he considers a rare opening for an extensive and profitable hydraulic cut and fill in Cincinnati. The whole of Mill Creek bottom, between Hopkins street and Harrison avenue and between the Cincinnati, Hamilton and Dayton and the Baltimore and Ohio Railroads, could be filled in by piping down the northern end of Mt. Harrison, to a level, say, ranging from 70 to 90 feet above datum. In the writer's opinion, little, if any, explosive would be required, provided not less than 20 second feet of water were used and under a head of not less than 250 feet. The water would be pumped from the river at the mouth of Mill Creek into a temporary reservoir on top of the ridge south of Liberty street. The reservoir need be only large enough to perform the function of a standpipe in maintaining an even pressure. A vertical cut of at least 200 feet could soon be established, when, by taking

advantage of soft layers at the base in undercutting, immense masses might be caved down. After the caves the softer parts and finer stone could easily be piped away, leaving the larger merchantable stone to accumulate on the floor of the cut, perfectly clean. Assuming that the stone averaged 20 per cent. of the bank, and that it is worth on the ground 40 cents per cubic yard, the stone would pay 8 cents per cubic yard of bank toward the cost of excavation. On this basis the writer estimated, some years since, that the work could be done at 15 cents per yard net, provided not less than 3,000,000 cubic yards were moved.

STREET LIGHTING OF CITIES.

BY HENRY H. HUMPHREY, MEMBER OF THE ENGINEERS' CLUB OF ST. LOUIS.

[Read before the Club, November 21, 1900.*]

THE proper lighting of streets in our modern cities cannot be overestimated. Their illumination is scarcely secondary in importance to the maintenance of grades and paving. When the streets are neglected until their surfaces have become uneven and unsafe, the necessity of illumination is heightened.

It is evident to any one at all observant that the recent developments in street illumination are in the direction of a uniform and diffused light, rather than along the well-beaten path of previous years which gave brilliantly lighted crossings and Egyptian darkness in the middles of the blocks. The development of the inclosed arc lamp and the growth of mantle gas lighting are illustrations of this point.

Some cities still cling to the old-style open arc lamp; notably the city of Chicago, which is still making all its increase with this type of lamp, and the city of Denver, Col., which is at present installing a new city lighting plant using open arcs for all but one of the circuits. It is reported, however, that this feature of this contract may be changed before the plant is completed and inclosed arc lamps installed throughout the city.

The question of the candle power of the lamp itself is one of importance, but is evidently not a "paramount issue." The old-style direct-current series open arc lamp is without doubt superior in actual candle power to any of the later types of inclosed lamps. Nevertheless, it is giving place very rapidly to inclosed arc lamps of either the direct current or alternating current type. Development along the lines of electrical progress is not always made in the interest of the public, or of the users of light. Many systems, improvements, etc., are developed by the manufacturing companies for the sole purpose of making an increased market for their goods. This development in arc lamps, however, passing from the open lamp to the inclosed lamp, is one that directly benefits the public and the user of light. Admitting that the candle power is considerably less, for the same expenditure of energy in the lamp, the light is so much easier on the eyes in the immediate neighborhood of the lamp, and the illumination is so much more uniform, that the result is far superior.

A comparison of candle powers between the direct-current open arc, the alternating-current inclosed arc and the direct-cur-

*Manuscript received December 10, 1900.—Secretary, Ass'n of Eng. Soocs.

rent inclosed arc lamps, is somewhat uncertain, owing to the different methods employed by different observers and to the different standards of light used. In fact, the result of candle power measurements of arc lamps has been so uncertain that very few authoritative data upon this subject have been published.

In Fig. 1 a series of curves, prepared by Mr. H. H. Wait, of Chicago, and presented to the Northwestern Electric Association, is reproduced here by his permission.




FIG. 1.

- I— D. C. Open arc.
- II— D. C. Inclosed arc, clear inner globe.
- III— D. C. " " alabaster inner globe, with reflector.
- IV— D. C. " " " " " " " "
- V— A. C. " " opal inner globe, without reflector.

No. 1 represents the direct-current open arc lamp.

No. 2, the direct-current inclosed arc lamp with clear inner globe.

No. 3, the direct-current inclosed arc lamp with alabaster inner globe and with reflector.

No. 4, the alternating-current inclosed arc lamp, with alabaster inner globe and with reflector.

No. 5, the alternating-current inclosed arc lamp, with opal inner globe and without reflector.

These curves show very decidedly the sacrifice of maximum illumination, in one direction, in order to secure a more uniform distribution of light and a better average illumination.

It is almost universally conceded that the direct-current inclosed arc lamp produces more light per watt than the inclosed alternating-current arc lamp, but the exact ratio between them has not, to my knowledge, been determined. The best data that I am able to find are the tests made by Prof. C. P. Mathews, of Purdue University, under the direction of the Committee on Arc-Light Photometry of the National Electric Light Association. His tests are based on constant-potential lamps, instead of upon series lamps, and his watt measurements are taken across the lamp terminals instead of across the arc only. He has tested 8 direct-current inclosed arc lamps and 7 alternating-current inclosed lamps, made by different manufacturers. The average difference in candle power between the direct-current lamps and the alternating-current lamps is 30 per cent., the average difference in watts consumed at the terminals of the lamp is 27 per cent.; the difference in watts at the arc is $12\frac{1}{2}$ per cent.

Taking one particular case, comparing the performance of a direct-current 558-watt lamp, with no outer globe and no shade, with a 418-watt alternating-current lamp, with shade, gives a difference of 39 per cent. in light in favor of the direct-current lamp at an expenditure of 23 per cent. more power in watts. There is apparently but slight difference between the efficiencies of these lamps when the watts across the terminals are considered.

His data also give the watts at the arc in each of these lamps. The average watts used by the D. C. lamps are 529, of which 384 are available in the arc, and 144 or 27 per cent. are wasted in the dead resistance and in the mechanism of the lamp. The average watts used by the A. C. lamp are 417, of which 342 are available in the arc and 74.5 or 18 per cent. are wasted in the mechanism. If we reduce the results obtained, to the basis of light produced by watts in the arc, we find that the difference in candle power with the same expenditure of energy in the arc is approximately 16 per cent. in favor of the direct-current lamp. The average current for the direct-current lamps was 4.90 and for the alternating-current lamps 6.29.

Fig. 2 shows two curves from his data for 450 watts-in-the-arc arc lamps. In this figure, curves 1 and 2 are for the direct-

STREET LIGHTING OF CITIES

current lamps; curves 3 and 4 are for the alternating 40 and 100 lamps. These are approximations only, since the candle power of the lamp varies greatly with different makes of carbons and with different current densities in the arc. These curves can be considered as approximating closely the conditions in series inclosed lamps, since in this type of lamp only 3 per cent. of the energy is used in the mechanism of the lamp.




FIG. 2.

The company which recently secured the electric lighting contract in St. Louis for the next ten years proposed, at the time of the award, to build a new power house and plant complete, equipped for commercial lighting as well as for public lighting. Many of the contracts for machinery were awarded and actually signed, when the sale of the stock of the company to local interests changed entirely the scheme and development of the plant. Believing that the engineering details in connection with this work may have some general interest, I will describe briefly the

principal engineering features connected with the new electric lighting system in this city.

The general design of this plant, as installed, was outlined in the report of the engineers of the Imperial Electric Light, Heat and Power Company, under date of September 3, 1897, as follows:

"In an enterprise of this magnitude it seems to us advisable to bear in mind the possibility of doing the city lighting from this same plant. For a steady load, such as all-night street lighting, when the generators can be worked to their full capacity during their entire run, there is no apparatus that surpasses the direct-current machine and series direct-current arc lamp. The new series inclosed 150-hour arc lamp is being put upon the market now and the reports that we have from it are entirely satisfactory. Large direct-current multiple-circuit series arc lighting generators can now be obtained, suitable for direct connection to engines, and give a large and efficient unit without the necessity of excessively high voltage. We believe that this type of generator would fulfill the requirements of city lighting better than any alternating current or constant potential direct-current apparatus would do."

Anticipating the city lighting contract, the company installed one extra duct throughout its entire underground system, and a trunk line of ten extra ducts north and south to the limits of the underground district for the purpose of arc lighting. This foresight has made it possible for the present contractors for city lighting to install their work in the underground district within the time available, an accomplishment that would have been impossible for any company having to install an entirely new system of conduits.

The question of type of apparatus, whether to use the direct-current series inclosed arc lamp, or its formidable rival, the alternating series inclosed arc lamp, was promptly decided by the adoption of the former. The comparative difference in candle power of the two lamps, with the same consumption of energy, was unquestioned, and, since the city lighting contract calls for an expenditure of 480 watts at the arc, leaving the question of candle power entirely out of consideration, it was the desire of the company to give the public the benefit of the 16 per cent. increase in light.

Advocates of the alternating-current system claim that they can deliver more light from alternating-current lamps, operated from large constant-potential alternating-current generators,

than can be obtained from the use of direct-current apparatus. While this is an open question, and one dependent almost entirely upon the economy of the steam-generating and steam-using apparatus in the station, it did not enter seriously into the consideration of design of plant under the existing conditions. The Imperial plant was already in operation, with a direct-current system that had proved its efficiency and adaptability to the service intended; and the city lighting load, consisting of but 525 K. W., was too small a factor to affect seriously the design of




FIG. 3. MOTOR-DRIVEN ARC DYNAMOS.

the entire plant. It is admitted that driving these arc dynamos by means of compound condensing engines would be more efficient, from coal to watts-at-arc, than the present motor-driven units which, as shown below, give an efficiency of transformation of $80\frac{1}{2}$ per cent. About one-third of this $19\frac{1}{2}$ per cent. loss is probably in the motor, and could have been saved by driving direct from the engine. It is believed, however, that the practical advantages to be obtained from a plant of this design, where a multiplication of small units is avoided, where one man can operate the entire station, and where each large unit in the Imperial plant is a reserve unit for the city lighting work, are so great that

they overbalance the saving in coal obtained by placing the prime movers directly connected to the arc machines.

The arc lighting plant consists of 12 110-light Western Electric series arc dynamos, built upon their standard 125-light frames, and each machine guaranteed capable of operating 110 500-watt series inclosed arc lamps through 40 miles of No. 8 B. & S. circuit. Each two arc machines are driven by a 200 horse-power direct-current 500-volt motor, the three comprising a self-contained unit, five of which are capable of operating the present city lights, leaving one unit as reserve. These machines




FIG. 4. 500-VOLT SWITCHBOARD.

are located at present in a temporary building adjoining the Imperial plant on the east side and located on the south side of St. Charles street, just west of Ninth street. In the design of the complete plant these arc generators will be on the second floor of the building, leaving the entire ground space available for boilers, engines and 500-volt direct-connected generators. Fig. 3 shows these machines.

Fig. 4 shows the 500-volt constant-potential switchboard, with switch, starting box, ampère meter, etc., for each motor-driven unit. The center of the board contains an illuminated-scale Weston 500-volt volt meter, showing the potential upon the

STREET LIGHTING OF CITIES

bus bars at all times. Inclosed fuses for each circuit are mounted on the rear of the board.

Fig. 5 shows the arc board, containing 12 dynamo circuits and 12 outside circuits. The terminals are widely separated, the positive being at the top of the board and the negative at the




FIG. 5. ARC LIGHTING SWITCHBOARD.

bottom. Each circuit contains a combination Weston ampere meter and polarity indicator. There is a transfer bus across the middle of the board, so that a dynamo at one end of the board can be connected to a circuit at the other end without stretching long connecting cables across the front of the board. The center

of the board contains a Weston 10,000-volt meter with terminal plugs. There is also a plug for ground connection, and two plugs for 500-volt connection used for testing circuit during the day. At the rear and above the board can be seen the static arresters which will be mentioned later.

The arc machines are of the ironclad, Gramme Ring armature, bipolar type, each equipped with the well-known Western Electric regulator. A special lightning arrester is placed upon the pole of the machine in such a manner that the stray magnetism from the pole piece blows out the arc when a discharge takes place.

The motors are 6-pole ironclad machines, and operate at a speed of approximately 675 revolutions per minute. Each motor has a special field rheostat, by which the speed can be regulated through a range sufficient to provide for the variation in voltage due to commercial load on the station bus bars supplying the motors.

There are three circuits in the underground district, each containing approximately 105 lamps. These are supplied through No. 8 B. & S. lead-covered cables, manufactured by the Standard Underground Cable Company, having 6-32 inch rubber and 3-32 inch lead. The cables are drawn into the ducts in continuous lengths, from the base of the iron arc lamp pole on one corner to the base of the iron arc lamp pole on the next corner, thus avoiding all joints, either inside the ducts or in the manholes. The district north of the underground district is supplied by four overhead circuits, each containing approximately 90 lamps. They are carried through the underground district to its limit at Ninth and Wash streets, by means of a 12-conductor lead-covered cable, the 12 wires being placed in one cable and surrounded by a lead sheath $\frac{1}{8}$ inch in thickness. This cable provides for four extra wires for increase of plant or for use in case of trouble on any one conductor.

The district south of the underground is supplied by three circuits of approximately 90 lamps each, carried to the limit of the underground district at Seventh and Spruce streets through a similar 12-conductor cable.

For the overhead circuits triple-braided weather-proof wire is used, supported on double-petticoat glass insulator.

The lamps are suspended at the corners of street intersections by means of iron arc lamp poles. The interior of the pole, as shown in Fig. 6, contains a hoisting windlass and pulleys for raising or lowering the lamp. The figure also shows the method

of insulating the wires where they leave the iron pole and going up to the lamp. The lead-covered cable is brought from the manhole, or service box in the street, through an iron pipe lateral, both cables of the circuit being placed in the same $2\frac{1}{2}$ -inch iron pipe. In the base of the lamp they end in special hard rubber




FIG. 6.

terminals, placed over the end of the lead sheaths and filled with paraffine to prevent any possibility of moisture entering the cable. From this special terminal a rubber-covered duplex cable, consisting of 2 No. 12 B. & S. flexible wires surrounded by $\frac{7}{64}$ inch of rubber and the two conductors braided together, extends up

through the pole. This cable passes out through the special porcelain insulator and up to the lamp, being supported above the lamp upon a porcelain knob spreader and connected to a solid wire which enters the binding post of the lamp, providing a solid and secure connection at the binding post. These solid wires are bared for a short distance at a point midway between the porcelain knob and the binding post of the lamp, providing a space where a specially constructed "jumper" can be readily attached whenever it may become necessary for a lamp to be changed while the circuit is in operation. The linemen carry insulated stools upon which they stand while handling the live circuits.

The use of a switch in the base of these poles, by which the lamp could be cut out of circuit entirely while a lineman is working upon it, would be very desirable, and such a switch was installed before the plant was put into operation. It took a very short experience, however, with these switches, which were the best the market afforded, to convince all connected with the enterprise that they were a failure in the position in which they were placed. Being convinced that it would be impossible to design a practical switch which would occupy the limited space available in the base of these poles and still be safely operative upon 8000 volt circuits, they were abandoned entirely and the solid connection was made as above described.

The use of iron poles for the suspension of arc lamps was a condition of the city contract, which left the engineers no option. The use of special terminals and the cable above described in the underground district, and the use of special triple-petticoat glass insulators on the poles on the overhead circuits, will, we believe, render the circuits safe from anything but the ordinary mechanical accidents incident to any class of apparatus placed upon the streets of a city.

As intimated above, some trouble, due to the static discharge from the underground cables, was encountered. This was not unanticipated; but it was believed that drawing both cables through the same iron duct, where they enter the base of the iron arc lamp pole, would provide a sufficient connection between the two, so that the lead sheaths would be practically connected together throughout the entire circuit. At the plant all of the six cables of the three circuits were drawn into the same duct of the conduit and with the same object in view. It was ascertained, however, soon after starting the plant, that these contacts were not sufficient. The static effect from the cables manifested itself

in the short-circuiting of arc lamps through the insulation at the top of the inclosing globe, where the full difference of potential of the lamp is effective. The lead sheaths of all the cables were securely soldered together in the manholes where they enter the lateral which goes into the lamp poles. They were also connected securely together at the plant just behind the switchboard. These efforts had little, if any, beneficial effect upon the operation of the circuits. In addition to this, a special static discharger, shown diagrammatically in Fig. 7, consisting of an ordinary Leyden jar condenser, was connected to the copper of each circuit at the rear of the switchboard in the plant. Each condenser is provided with a revolving contact arm, driven by a small motor which alternately connects the condenser to positive wire,




FIG. 7. STATIC DISCHARGER.

to ground, to negative wire and to ground, thus receiving a charge from the line and discharging it to ground about 30 times per minute. After this apparatus was installed the static effect of the cables has so entirely disappeared that it is not appreciable in the operation of the plant.

The city contract includes 739 32 candle-power incandescent lamps, located in the alleys throughout the electric-lighted district. These are all supplied from the regular 3-wire 235-470 volt mains of the Imperial Company, requiring, therefore, no special apparatus. It might be of interest, however, to show a special switch designed for switching these circuits in and out by means of the arc lighting current. This switch, which was designed by Mr. E. P. Warner, of Chicago, is shown in Fig. 8. When the arc current is turned on it operates upon the solenoid, which, acting through the lever, closes a 3-wire 500-volt switch, switching on

the alley incandescent lights throughout the district controlled by this particular switch. When the arc circuit is shut down in the morning the plunger of the solenoid is released, and, in falling, it opens the switch, cutting the incandescent lights out of circuit. This simple arrangement saves the services of a man, with horse and wagon, to go around and start the incandescent lights, saving also the loss of current in switching lamps on ahead




FIG. 8. 500-VOLT SWITCH ELECTRICALLY CONTROLLED BY ARC CIRCUIT.

of time where a considerable district must be covered and all the lamps in the district started not later than the schedule time.

In Table A are shown the data obtained under test of one of the motor-driven arc-light units, the test continuing from 12 o'clock midnight until the closing-down time in the morning. The first column gives the time; the second, third and fourth columns the ampères and voltage supplied to the direct-current motor, also the rise in temperature of the motor fields during the time of test. The fifth, sixth and seventh columns give the ampères, voltage and field temperature of one of the arc dynamos;

column eight and nine, the amperes and voltage of the other arc dynamo. Column ten gives the speed of the unit, column eleven, the temperature of the air in the room, and column twelve the efficiency, being the ratio of the electrical input to the electrical output of the unit. You will observe that each reading gives two

TABLE A.
TEST OF MOTOR-DRIVEN ARC UNIT.

MOTOR.			No. 7 ARC DYNAMO.			No. 8 ARC DYNAMO.			Speed.	Air Temp. F°.	Effi- ciency.
Time.	Amp.	Volts.	Field Temp. F°.	Amp.	Volts.	Field Temp.	Amp.	Volts.			
12-10	325	490	140	7.0	8580	128	7.0	9346	675	108	78.6
	300	482		6.7	8125		6.8	8850		110	
12-30	330	487	147	7.0	8791	130	7.1	9346	677	109	79.0
	302	480		6.8	8325		6.9	8850		114	
1-00	325	497	154	7.0	9425	135	6.9	9610	676	109	82.5
	305	488		6.8	8925		6.7	9100		114	
1-30	340	505	157	7.0	9610	140	7.0	9979	676	108	79.8
	320	493		6.9	9100		6.9	9450		110	
2-00	325	512	158	7.0	9610	142	7.0	9504	700	107	80.4
	303	502		6.8	9100		6.8	9000		109	
2-30	320	500	160	6.9	9346	144	7.2	9187	701	109	81.0
	300	490		6.8	8850		7.0	8700		112	
3-00	330	500	162	7.0	9504	147	7.1	9557	695	108	80.9
	310	490		6.8	9000		6.9	9050		107	
3-30	327	505	162	7.0	9400	148	7.0	9504	700	110	80.0
	305	495		6.9	8900		6.8	9000		116	
4-00	325	507	154	7.0	9504	151	7.0	9610	720	107	81.2
	305	498		6.9	9000		6.8	9100		107	
4-30	327	515	153	7.0	9557	152	7.0	9820	715	109	80.5
	305	504		6.9	9050		6.8	9300		115	
5-00	320	515	150	7.0	9900	152	7.0	9504	730	110	82.4
	300	503		6.9	9375		6.8	9000		117	
5-50	323	520	148	7.0	9451	148	7.0	9583		100	79.3
	305	507		6.9	8950		6.8	9075		110	
Average efficiency											80.5

figures, the first figure in each case being that of the standard test instruments, while the second reading is that of the regular station switchboard instruments. The test instruments read uniformly higher than the station instruments. They were carefully compared with recently calibrated instruments, and they are believed to be correct. The total capacity called for in each of

these arc machines, as given above, is 110-500 watt arc lamps each through 40 miles of No. 8 B. & S. wire. This is equivalent to a total voltage of 8750 volts at 7 ampères. The test shows that the machines ran above their rated load during the entire test, the load on one reaching as high as 9979 volts, which is 15 per cent. above the rating.

The guaranteed efficiency of the unit was $78\frac{1}{2}$ per cent. The average efficiency during test was $80\frac{1}{2}$ per cent., reaching, in one case, as high as $82\frac{1}{2}$ per cent. and in another 82.4 per cent. The machines came well within their guarantees regarding rise in temperature of all of their conductors. It will be noted that the temperature of the motor fields reached its maximum at 3 A.M., and from that time steadily decreased, although the work being done by the motor increased slightly during the test. This decrease in temperature is probably due to a slight increase in the speed of the unit following the high voltage at the bus bars. The voltage readings of the arc circuits show but slight increase during the night, after the number of lamps in circuit was allowed to remain constant. This increase of voltage is more noticeable on another type of lamp shown in the next table.

TABLE B.
TEST OF HIGH-VOLTAGE ARC CIRCUITS.

TIME.	NO. 2 CIRCUIT.		NO. 1 CIRCUIT.	
	Ampères.	Volts.	Ampères.	Volts.
6-36	6.5	5900	6.5	7000
7-00	6.5	6400	6.6	7300
7-35	6.5	6900	6.5	6500
8-00	6.5	7200	6.6	6900
8-30	6.5	7450	6.5	7400
9-00	6.5	7700	6.5	7900
9-30	6.5	7650	6.5	8350
10-00	6.5	7700	6.5	8550
10-30	6.5	7450	6.5	8600
11-00	6.5	7350	6.5	8750
11-40	6.5	7150	6.4	*6500
12-00	6.5	7150	6.5	6900
12-10	6.5	7100	6.5	6950

*Machine flashed just before reading was taken.

STREET LIGHTING OF CITIES

Table B gives data obtained from a test of another high voltage plant in a neighboring city; column one gives the time columns two and three give the ampères and voltage upon one




FIG. 9. LOAD CURVES, SHOWING ORIGINAL HYPOTHETICAL CURVE AND PRESENT ACTUAL CURVE WITH THE USE OF BATTERY
Oct. 1899 ALSO LOAD CURVE NOV. 1900 SHOWING CITY LIGHTING LOAD

FIG. 9.

circuit and columns four and five the ampères and voltage on the other circuit. These were both overhead circuits. The former contained 92 lamps and the latter 110. This last circuit had 5 lamps more than either of the circuits shown in the last table.

These lamps, an hour after they had been put in operation, used but 64 volts per lamp, including the loss in the line. After they had been in operation for about five hours, however, the voltage per lamp had increased to 68 volts and 78 volts, respectively, for the two circuits, the lower voltage per lamp of one circuit being accounted for by a number of newly-trimmed lamps upon that circuit. This characteristic of an arc lamp is a serious drawback for street lighting, inasmuch as the lights show dim during the first part of the night, when people are upon the street and the light is needed, and show up much brighter during the latter half of the night when the streets are practically deserted, and when the light is not so essential.

In a paper read before this Club last year I showed the load curve of the Imperial plant, which I will reproduce in Fig. 9. I repeat it here for the purpose of showing what a small effect the city lighting load has upon the total load of the plant. The lower line gives the preliminary load curve, prepared by the engineers before the plant was built and submitted in their preliminary report covering the design of the plant. The second line gives the load upon the plant one year after it had started, and a year and one month ago. It illustrated the use of the battery at that time, and attention was called to the large all-night load, the comparatively low peak or maximum load and the high average for the entire twenty-four hours, which is 39.27 per cent. of the maximum. A year ago the peak of the load was 5600 ampères. The third or highest curve gives the present load-curve of the plant, showing the changed use of the battery, which is no longer able to carry the night load and allow the shutting down of the plant. It is still available for doing its full load capacity at the peak of the load, and its use as a balancer and equalizer of pressure is the same as it was a year ago. The increase in the all-night load is only partly due to city lighting, the city lighting load being only about half of the present total all-night load. The dotted curve shows the load on the plant exclusive of city arc lighting.

The station at present shows a maximum load of over 13,000 ampères, which is more than twice the maximum of thirteen months ago, which was 5600 ampères. The average load for the twenty-four hours has increased from 2198 ampères to its present amount of 6345 ampères, approximately three times as much as that of a year ago, and greater than the maximum load on the plant at that time. The load-factor of the plant has increased from 39.27 per cent. to 47.7 per cent., giving a load-factor that can be equaled by few, if by any, plants in this country.

WATER POWER BY DIRECT AIR COMPRESSION.

BY WILLIAM O. WEBBER, MEMBER BOSTON SOCIETY OF CIVIL ENGINEERS.

[Read before the Society, November 21, 1900.*]

THE use of compressed air for power purposes and as a means for the transmission of power is much older than is usually conceded. It was used by Smeaton in 1786, by Medhurst in 1810, by Rennie in 1812, by Vallance in 1818, at the Triger mines of Challones in 1845, by Cubitt in sinking the piers of the Rochester bridge in 1851. Brunel also made a similar use of it at Saltash in 1854. It was also used by Brunel on the Thames Tunnel, by Barlow on the Thames Subway and in the shaft of the Marie Colliery in 1856.

Air has been transmitted for considerable distances and under a great range of pressures. At the Mont Cenis Tunnel, air was transmitted to the boring machinery 20,000 feet under a pressure of 105 pounds per square inch. In the installation at Paris, in 1881, by M. Popp, the length of the pipes slightly exceeded twenty-four miles. This plant, as well as the one installed by the same person in Vienna in 1877, was originally used for the running and regulating of clocks, but it afterward developed into power for working small motors. In Paris the main is a steel pipe 20 inches in diameter, and the air, maintained at 90 pounds pressure, transmits 6000 horse power.

At a large compressed-air plant at Offenbach, near Frankfurt-on-the-Main, air is distributed through 25,000 feet of cast iron pipe under 90 pounds pressure. At the Portsmouth Dock Yards, England, air is transmitted through 14,000 feet of pipe, varying from 3 to 12 inches diameter, under 60 pounds pressure, and is used to drive forty 7-ton capstans, five 20-ton cranes and machinery for working seven caissons.

There is also a large compressed-air plant at the Terni Steel Works in Central Italy. In this plant 1,200,000 cubic feet of air per day, under 75 pounds pressure, are used to drive a 100-ton hammer, a 100 and 150-ton crane and numerous engines.

In this country 2,500,000 cubic feet of air per day, at 60 pounds pressure, delivering 1700 horse power, are used at the Chapin mines in Michigan. The mains in this plant are 24-inch wrought iron pipes, one-quarter inch thick. Very successful compressed-air tramways have been operated for a number of years at Berne, Switzerland, and at Nantes, France.

*Manuscript received December 31, 1900.—Secretary, Ass'n of Eng. S.

Mekarski used compressed air for driving tramway cars in 1877.

In all of the above-named uses of compressed air, the compression was produced by steam-actuated mechanical compressors. The older ones were all simple compressors, Mekarski being the first to use compound compressors, and he was followed in this line by Northcote in 1878.

The adaptability of compressed air for various uses is very great. While electricity supplies power and light very directly, it cannot be used for heating except at a prohibitive cost. Gas is used very directly to supply heat, power and light, but is expensive for heating and power at the prices generally charged. City water pressure can be used to supply power, and indirectly light, by the use of a water motor driving a dynamo, but is too expensive for most purposes. Steam supplies heat and motive power almost directly, and indirectly light through a dynamo. It is, however, more expensive than compressed air, and involves more risk and attention. Compressed air can be used directly as a source of motive power, ventilation and refrigeration; also in the operation of elevators.

We have already mentioned its use in connection with power hammers, cranes and motors. For drying purposes it is even more efficient than heat. Compressed air is also largely susceptible to double uses. For instance, after it has been used cold, or without pre-heating expansively in a motor to produce power, the exhaust furnishes an efficient and cheap method of producing refrigeration. When pre-heated and then used through a motor the exhaust is still hot enough to contribute considerably to the heating of a building.

In the transmission of compressed air over long distances, the loss of pressure due to friction in pipes of proper sizes, and the loss due to leakage in properly constructed pipes and joints, are very small. Velocities of from 30 to 50 feet per second are allowable. When an air distribution system is introduced into a thickly settled community, the safety from the air main is much greater than from a steam main or a water main under pressure, and a leakage or even the bursting of such a pipe is attended with very much less damage.

Another great advantage in such a case is that power users require no new plant, and need incur no outlay for motors. Their present steam engines, with little or no alteration, are admirably adapted for serving as air motors.

Tests of small motors of from one to two horse power, using air at the ordinary atmospheric temperature and at 735 pounds per

square inch absolute, exhausting at from 33° to 54°, require a consumption of 1200 cubic feet of air per brake horse power per hour. At the Berne tramway the air is compressed to 150 pounds per square inch. On the average the cars use about 35 pounds of air per car-mile. This, however, was used in connection with hot water. In small motors of from one to two horse power, with the air pre-heated to a temperature of about 158° and exhausting at about the freezing point or 32°, 850 cubic feet of air per brake horse power per hour were used.

In some very carefully conducted trials made by Professor Riedler, using an 80 horse power engine which was actually giving 72 indicated horse power, using air at 80 pounds pressure, heated to 320°, with cylinders jacketed with hot air and exhausting at about 95°, about 425 cubic feet of air per brake horse power per hour were used. This showed an efficiency of about 92 per cent.

Practically all that has been said above refers to air compressed by the old methods of mechanical compression. We now come to the subject of air being compressed directly by falling water or under pressure. Air compressed by the ordinary methods of mechanical compression contains at least the same amount of moisture as the surrounding atmosphere from which it was compressed; and, in parting with the heat necessarily contributed to the air by the mechanical compression, it is inclined to absorb more moisture. There is incidentally a considerable loss of energy in parting with this heat. Air compressed directly by falling water is kept at the same temperature as this water. It is compressed isothermally, and the consequent expansion, when used in motors, produces an almost truly adiabatic expansion line. Tests, however, have shown that air compressed in this manner contains only one-sixth of the moisture originally in the surrounding atmosphere from which it is compressed. This is probably because the moisture in the bubble of air is pressed or squeezed out to its surface and then absorbed by the surrounding water. Incidentally there is no loss of power in parting with any heat, and there is a practical result which is of more importance,—the hydraulically compressed air can be expanded down to a temperature much below the freezing point, while atmospheric air, with the usual amount of moisture, mechanically compressed, cannot be used at all, owing to the freezing up of the exhaust passages of the motor in which the attempt to use it is being made.

During some tests made at Magog in September, 1899, owing to the conditions under which these tests were made, the change in the humidity in the air was not so great as above stated. The

moisture in the external air showed 90 per cent. of saturation, and, after compression, 29 per cent., or a little more than one quarter. In the Magog tests, using an old 75 horse power Corliss engine, with air at $53\frac{1}{2}$ pounds gage pressure, with cold air direct from the compressor at from 66° to 73° , and exhausting down to the extremely low point of 42° below zero, 850 cubic feet of air per brake horse power per hour were used; and, with the air pre-heated to from 205° to 295° Farenheit, and exhausting at from 67° to 68° , 620 cubic feet of air per brake horse power per hour were used.

Probably one of the oldest applications of the use of water power to the wants of man was a form of hydraulic air compressor which operated as an entrainment apparatus. This was the well-known water bellows or *trompe* of the Catalan forges.

This apparatus, briefly described, consisted of a bamboo pole, disposed at a slight inclination from the perpendicular, into the upper end of which a stream of water was led, entraining air with it in its downward passage. The lower end of this bamboo pole was introduced into a bag made of the skin of some animal, the air being allowed to escape from the water into the upper part of the bag, whence it was led by pipes or tuyeres to the forge, the water being allowed to escape from the lower edge of the bag. From this original device a great many improvements have been worked out, and besides this a number of other forms of hydraulic air compressors, or of compressors using other liquids for compressing air or other gases, have been designed.

Siemens invented an apparatus on the principle of the steam injector, but the use of this was confined principally to the production of a vacuum. It is used to operate the pneumatic dispatch tubes in London. It has also been used for blast purposes in Siemens's furnaces and in sugar works.

Another quite ingenious device, Fig. 1, shown in a patent granted to W. L. Horne, consists of two flat plates, A and B, inclosing between them an air space from which a pipe leads to the atmosphere. The upper plate A is perforated with conical holes, the smaller end of each hole being adjacent to the air space between the two plates. Directly opposite the apertures of the upper plate A are corresponding conical apertures in the lower plate B, with the smaller end of the aperture next the air-space, the lower and larger part of the conical openings being prolonged by tubes C C. The upper plate is kept under a head of water, and the water jet, passing across the thin air space referred to, draws in the air through the large air pipe D, and compresses it through the smaller orifices.

Another device, using a somewhat similar principle, was invented by M. Romilly. It consists of a conical tube attached to an air reservoir by its larger end, and having a check valve interposed in the passage so as to prevent the air from escaping. Water is then injected into the smaller end of this conical tube through an ajutage which gives it the form of a liquid vein at a given pressure. This vein entrains the air with it and causes it to be compressed in the reservoir.




FIG. 1. W. L. HORNE.

But all of the apparatus just described did not really employ the same methods as those used in the old trompe. One of the first inventions carrying out this idea, Fig. 2, was made by Mr. J. P. Frizell, of Boston, Mass., a member of this Society. His invention made use of an inverted siphon having a considerable horizontal run D between the two legs A and B. A stream of water was led into the upper end of the longer leg A, and at the top of the horizontal run D between the two legs of the siphon was provided an enlarged chamber C in which the air separated from the water. The water was then led off from the lower part of this air chamber and passed off through the short leg B of the siphon, the pressure of the air accumulated in the air chamber being there-

fore due to the height of water maintained in the shorter leg of the siphon. This application of carrying upward the water, after the air was separated from it, so as to produce a considerable pressure upon the air, seems to have been original with Mr. Frizell, and in this feature his device differs from the old trompe.

Mr. Frizell made two working models of this type of apparatus. In the first the legs of the siphon were 3 inches in diameter, the head of water being 25 inches, and an efficiency of $26\frac{1}{2}$ per cent. was obtained. A larger apparatus was then constructed at the Falls of St. Anthony, on the Mississippi River, a few miles above




FIG. 2. J. P. FRIZELL.

St. Paul. The longer leg of the siphon in this plant was 15 inches by 30 inches and the short leg of the siphon 24 inches by 48 inches in section. The height of water above the air chamber was 29 feet. The head in feet varied from 0.98 to 5.2, the first head being just sufficient to cause a flow through the pipes. The working head varied from 2.54 feet to 5.02 feet and the efficiency from 40.4 per cent. to 50.7 per cent., the quantity of water in these cases varying from 5.92 to 11.89 cubic feet per second.

From his experiments Mr. Frizell estimates that with a shaft 10 feet in diameter, a depth of 120 feet and a fall of 15 feet the efficiency would be 76 per cent., and that with a head of 30 feet and a fall of 230 feet the efficiency would be 81 per cent.

Another device, Fig. 3, differing somewhat from that of Mr. Frizell, was invented by A. Baloché and A. Krahnass in 1885, and consisted of a siphon B carrying water from an upper to a lower reservoir, the lower end of the siphon being projected through an inverted vessel R placed nearly at the bottom of the second reservoir. Just beyond the bend of the siphon, and in line with the vertical axis of its longer leg, an air pipe T projected into the descending leg of the siphon, thus entraining the air with the de-




FIG. 3. A. BALOCHE AND A. KRAHNASS.

scending column, which carried it down into the inverted chamber R, from which the air escaped at the top, while the water passed out from the bottom into the lower reservoir. This apparatus produced pressure on the air in the top of the inverted chamber, due to the height of the water column upon it.

Another device, Fig. 4, patented by Thomas Arthur in 1888, differs from the last in having a stream of water led directly into the top of the vertical pipe A. Inserted into the mouth of this pipe was a double cylindrical cone C forming an annular air passage between it and the walls of pipe A.

Owing to the increase in the velocity of the water in passing through the narrow throat of the double cone, air is inhaled through the pipe D through the annular space mentioned and through perforations in the lower cone, and is entrained with the falling water.

Through the down-flow pipe A rises a vertical delivery pipe Z for the compressed air, having its lower end H enlarged and open at the bottom. Projecting upward into this enlarged air-delivery pipe was a water-escape pipe F through which the water passed after having parted with the air. This escape pipe was in the form




FIG. 4. T. ARTHUR.

of an inverted siphon and maintained on the air in the delivery pipe Z a pressure due to the elevation of the water at its discharge point above the air line in the large end of the delivery pipe.

A number of other patents on apparatus of this type were issued to Charles H. Taylor, Nos. 543,410, 543,411, 543,412, July 23, 1895. His inventions, Fig. 5, consisted principally of a down-flow passage having an enlarged chamber at the bottom and an enlarged tank at the top. A series of small air pipes projected into the mouth of the water inlet from the large chamber at the upper end of the vertically descending passage, so as to cause a number of small jets of air to be entrained by the water, Taylor




FIG. 5.

seemingly having been the first to introduce the plan of dividing the air inlets into a multiplicity of smaller apertures evenly distributed over the area of the water inlet.

Taylor at first seems to have attempted to utilize centrifugal action in causing the separation of the air from the water in the larger chamber at the bottom of the compressed column; but he afterward abandoned this scheme and used, instead, deflector plates in combination with a gradually enlarging section of the lower end of the down-flow column in order to decrease the velocity of the air and water and cause partial separation to take place. The deflector plates changed the direction of flow of the water. This was evidently intended to facilitate the escape of the air.

The latter improvements on this device have been in the method of introducing the air into the mouth of the downwardly flowing water column, so as to insure the largest proportion of air being taken down with the water, and in methods of decreasing the velocity of the combined air and water at the bottom of the descending column, causing the water to part more readily with the air, the water then passing out at the bottom of the enlarged chamber into an ascending shaft, maintaining upon the air a pressure due to the height of water in the uptake, the air being led off from the top of the enlarged chamber by means of a pipe.

The first of these compressors on the Taylor principle was installed at Magog, Quebec, to furnish power for the print works of the Dominion Cotton Mills Company. The head of water is 22 feet; the down-flow pipe is 44 inches in diameter, and extends downward through a vertical shaft 10 square feet in cross section and 128 feet deep. At the bottom of the shaft the compressor pipe enters a large tank, 17 feet in diameter and 10 feet high, which is known as the air chamber and separator.

A series of very careful tests on this plant demonstrated that with 19.5 feet head, using 4292 cubic feet of water per minute, was recovered the equivalent of 1148 cubic feet of free air per minute, which would represent 248 cubic feet of air per minute compressed to 53.3 pounds pressure, showing that out of a gross water horse power of 158.1, 111.7 horse power of effective work in compressing air was accomplished, giving therefore an efficiency of 71 per cent.

In the tests at Magog we recovered 81 horse power, using an old Corliss Engine without any changes in the valve gear as a motor; this would represent a total efficiency of work, recovered from the falling water, of 51.2 per cent.

When the compressed air was pre-heated to 267° F. before being used in the engine, 111 horse power was recovered, using 115 pounds coke per hour, which would equal about 23 horse power. The efficiency of work recovered from the falling water and the fuel burned would be, therefore, about $61\frac{1}{2}$ per cent. On the basis of Professor Riedler's experiments, requiring only 425 cubic feet of air per brake horse power per hour, when pre-heated to 300° F. and used in a hot-air jacketed cylinder, the total efficiency secured would have been about $87\frac{1}{2}$ per cent.




FIG. 6. MAGOG. COMPRESSOR HEAD AND WEIR. THE AIR COMPRESSOR IS BLOWING OFF.

The second compressor on the Taylor principle is located on Coffee Creek, to the south of Ainsworth, British Columbia. The Available head of water is 107.5 feet. The down-flow pipe is 33 inches in diameter. The shaft is 32 square feet area and 210 feet deep. The maximum volume of water is 4200 cubic feet per minute and would represent, at 71 per cent. efficiency, 587 horse power. This compressor is expected to utilize about 5100 cubic feet of free air per minute or 734 cubic feet of compressed air at 87 pounds pressure, and give an air motor horse power of 360 horse power.

It is possible, however, that this plant may not give as high percentages as this, as the water passages are of smaller areas than those at Magog.

Three other plants are now under construction,—one at Peterborough, Ontario; one at Norwich, Conn., and one in the Cascade Range, State of Washington. The plant at Peterborough, Ontario, for the Government of the Dominion of Canada, is to be used in connection with one of the locks on the Trent Valley Canal, the chief dimensions being as follows: Head of water, 14 feet; gage pressure, 25 pounds; diameter of compressor pipe, 18 inches; diameter of shaft, 42 inches; depth below tailrace, 64 feet.

The whole plant is inclosed in the masonry wall of the lock, the usual rock chamber in the bottom of the shaft being built in concrete and only a few feet below the lower water level of the lock.

At Norwich, Conn., at what is known as the Tunnel Privilege on the Quinebaug River, the plant will give 1365 H. P. of air at a pressure of 85 pounds per square inch. The head of water is 18½ feet; diameter of shaft, 24 feet; diameter of compressor pipe, 13 feet; depth of the shaft, 208 feet.

The air will be transmitted a distance of four miles with a loss in transmission not exceeding 2 per cent., through 16-inch pipe, which will be laid with flanged joints and rubber gaskets.

The plant which is being constructed in one of the canyons of the Cascade Range of mountains in the State of Washington will give 200 H. P. of air at a pressure of 85 pounds per square inch. Head of water, 45 feet.

There is no shaft, as the apparatus is constructed against the vertical walls of the canyon. The diameter of the compressor pipe is 3 feet. The diameter of the up-flow pipe is 4 feet 9½ inches. The capacity of the plant is based on 2000 miners' inches of water, equal to 53.2 cubic feet per second. The total height of this apparatus is about 260 feet.

Besides what is now known as the Taylor type of compressor, some forms of hydraulic ram compressors were designed by Sommeiller and also by Mr. H. D. Pearsall. These operated in a nearly similar manner to the hydraulic ram and gave an efficiency of 80 per cent.

A MODERN AMERICAN BLAST FURNACE ITS CONSTRUCTION AND EQUIPMENT.

BY ARTHUR C. JOHNSTON, M.E., MEMBER OF THE CIVIL ENGINEERS' CLUB OF CLEVELAND.

[Read before the Club, November 27, 1900.†]

IN an article written in 1896, entitled "Forty Years of Progress in the Pig Iron Industry," John Birkinbine says: "A retrospect of four decades will show that this interval covers most of the advances in the production of pig iron made in the United States, and also those introduced in European countries, for, although the use of mineral fuel, the application of heated blast and the employment of steam blowing machinery were not uncommon features of smelting plants, the increased production of pig iron up to 1855 was due chiefly to an augmented number of blast furnaces and enlarged dimensions of stacks. But what was considered at that time a large furnace would now rank as small, while the quantity of metal obtained in a year from the greatest producers of forty years ago was equaled by the monthly output of a number of modern furnaces in 1895."

The relative proportions of representative furnaces, from 1855 to 1900, are well shown in Fig. 1.


Much has been written about the increasing size and output of furnaces generally, but, on account of the rapidity of development, very little concerning their actual construction and the means employed for bringing about the increased production. The object of this paper is to describe the mechanical construction of a modern furnace, its equipment and the appliances for concentrating and handling the enormous amount of material that is required to make 600 tons of iron per twenty-four hours in a single stack; and to

*NOTE.—Owing to the keen competition of commercial interests in the iron and steel industry in this country, great care has been taken to eliminate from this paper anything that would seriously affect the interests of the company owning the furnaces herein described. It is on this account that the paper is confined to a description—from the standpoint of a blast furnace engineer—of the mechanical construction of a complete modern furnace plant, the object being to show thereby the great advances that have been made in blast furnace construction and equipment during the last ten years, and to give an adequate idea of the enormous possibilities of the American iron and steel industry, which has at its command such producers as these. The subjects of ore and coke supply, the burdening and grades of ore used, the fuel consumption and the extent and cost of output have been carefully avoided, otherwise the paper could have been made much more interesting and valuable.

†Manuscript received December 8, 1900.—Secretary, Ass'n of Eng. S. 28.

draw some conclusions based on the operation of such a furnace, taking as a concrete example the plant of the Lorain Steel Company, at Lorain, Ohio. It is regretted that it will not be possible, within the limits of this paper, to introduce other furnaces for the sake of comparison, but it is hoped that the record of experience in the operation of the Lorain furnaces—two of the largest in the world—will be of value in the design of perhaps still greater iron producers.

The plant mentioned was built in 1899, and consists of two stacks, each 100 feet high from hearth level to furnace platform,



22 feet in diameter at the bosh and 14 feet at the hearth. By reference to Figs. 2, 3 and 4 it will be seen that they are arranged on the American system, which places two furnaces in a group, there being four heating stoves for each furnace and a boiler house and engine house common to both. The plant is arranged to be capable of extension by adding to the engine and boiler houses, making them of sufficient capacity for another similar group of two furnaces. Sections showing the lines and construction of the furnaces themselves are shown in Figs. 5 and 6. It will be seen that there is a slight difference between the lines of furnace No. 1 and those of No. 2.


The distinctive feature of these furnaces is the great depth of the hearth jacket, and the low level to which the furnace columns

are carried in consequence. The hearth jacket itself is also of novel design. It consists of two series of segmental steel castings, held together by bolts and buckstays, with rust joints at the abutting edges of the different segments. Between the jacket and the masonry there is inclosed a complete ring of individual vertical pipes, intended to serve the double purpose of a cooling system and a means of relieving the jacket of excessive bursting strains, due to the expansion of the contained furnace bottom, by the partial collapse of the pipes. The intention was to have the cooling water for the jacket discharged into the annular space at the top of the same and to carry it downward through the pipes from which it would seek its level within the wall surrounding the jacket, whence it would be led off through a waste pipe placed at the desired level. In accordance with modern practice, the tuyères are spaced as closely as possible, there being sixteen 6-inch tuyères in the circle. A special feature is the great number of cooling plates. As will be seen in Fig. 7, there are twelve rings of bronze coolers, two of which are below the tuyères and three additional rings of cast iron coolers above the bronze plates. Fig. 8 shows clearly the construction of the coolers with their socket plates, and Fig. 9 the details of the tuyères. There are, in all, 277 bronze and 48 cast iron coolers in each furnace. The stock lines are protected by twelve rings of cast iron segments built into the brickwork. The mantels are built of $\frac{3}{8}$ -inch steel plate, with two courses of $\frac{1}{2}$ -inch plate at the bottom and one at the top. The gases generated in the stacks are led off through two downcomers, each 73 inches in diameter and brick-lined to 63 inches inside diameter. The general outline of these downcomers may be seen in the general plan of the furnaces, Fig. 4, and it will be observed that, owing to the steep angle at which they are carried up, it is practically impossible for dust to lodge in them at any point, which is a very important consideration. As a matter of fact, when the furnaces were blown out, after a year's run, these pipes were found to be as clean as a gun barrel. In the dust-catcher (Fig. 10) the direction of motion of the descending gases is so suddenly changed upward that ample opportunity is given for the precipitation of the dust, which can then be dropped into railway cars standing on the track which runs through the tunnel under the foundations.

The gases are further cleansed by being precipitated against the surface of a body of water in the gas washer (Fig. 11). From the washer the gases are led into the gas main. A by-pass, however, is arranged whereby the washer can be cut out of the system. This is accomplished by making two connections direct from the

dust-catcher to the gas main, controlled by 56-inch cut-off valves, which are fitted with water-cooled seats and discs. The connections from the dust-catcher to the washer, and from the washer to the gas main, are controlled by cut-off valves of a different type (Fig. 12). In Fig. 13 are shown the various connections between the downcomer and the gas main.

The gas main is a steel shell 85 inches in diameter and brick-lined to 75 inches, and it extends along the front of the eight stoves, having a downward connection to the burner at each of them. Here again precautions are taken to precipitate the dust



carried over by the gas; also in the burner itself there is still another dust-catching chamber. The stove burner is 18 inches in diameter, with a 6-inch air supply pipe (Fig. 14), and the opening for it in the stove is 22 inches in diameter.

Furnace gases are slow in burning, and for economical results a long combustion chamber of ample size must be provided. By reference to the section through the stoves (Fig. 15) it will be seen that the combustion chamber is carried up to the top, and that the burnt gases descend through the rectangular passages formed by the stove bricks, which are heated thereby until they reach the desired temperature. Each stove has a heating surface of 34,000 square feet. The gases are passed from the stoves to the chimney

through a 50-inch valve with air-cooled disc and water-cooled seat; the air is brought down through the stem, as shown in Fig. 16. The chimney is 10 feet in diameter and 225 feet high, and brick lined to the top (Fig. 17).

In designing these furnaces it was figured that each of them would require from 45,000 to 50,000 cubic feet of air per minute, measured by piston displacement, when making 600 tons of iron each in twenty-four hours. To supply this volume the engine house is equipped with five horizontal compound blowing engines, with steam cylinders 44 and 84 inches in diameter, and two air cylinders 84 inches in diameter, all having a common stroke of 66 inches. The general design of these is shown in Fig. 18. The fifth engine is intended for a reserve, to be thrown on either pair of furnaces in the contemplated extension. They are designed to be capable of delivering air at a maximum pressure of 30 pounds per square inch, although the average blast pressure is only about 14 pounds. Any engine can be connected with either furnace at any time, as the two cold-blast mains run parallel with one another over the blowing cylinders, and each main has a connection with a shut-off valve to each cylinder.

The cold blast mains are 48 inches in diameter, and are rolled from $\frac{1}{4}$ -inch plate. Each is equipped with a 48-inch snort valve, which in closing opens a 14 $\frac{1}{2}$ -inch relief valve mounted on the same frame, and thus prevents a dangerous pressure from accumulating in the main when the blast is suddenly shut off from the furnace. In addition, there are three 8-inch safety valves on each pipe. Thirty-inch connections are made from the mains to the stoves (Fig. 19), and the valves in these branches have in their seats a smaller valve which opens first automatically and relieves the pressure, an arrangement which enables the main valve to be opened more easily.

The cold air from the blast mains passes into the stoves and up through the checker bricks, which have been previously heated by the burning furnace gases, and down through the combustion chamber—the gas burner having been withdrawn and its door and chimney valve closed—into the hot-blast main through a 32-inch hot-blast valve (Fig. 20). By referring again to Fig. 19 these connections will be readily traced. The hot-blast mains are 69 inches in diameter, and double brick-lined to 50 inches inside diameter. Before connecting with the bustle pipes, the hot-blast mains divide and join them with two connections in order to better equalize the pressure around the complete circle. From the bustle pipes the hot blast is led to the tuyères, and into the furnace.

through the tuyère stocks. Two 16-inch drop valves are placed on the bustle pipe. These open automatically when the blast pressure is shut off, and air is admitted instead of drawing dangerous gases back through the tuyères from the furnace; these also close automatically when the blast is turned on. Explosion doors are provided at the furnace top, and wherever possible in all pipes and chambers carrying gas.

For handling the stock at these furnaces an entirely new system is in use. The stock bins are placed underground (Fig. 21). There are five stock bin cars, with suspended weighing hoppers, for the two furnaces. The bins are 725 feet in length, and the ore, limestone and coke are delivered to the furnace skip car by the weighing cars, which draw their supply from the chutes in the bottom of the bins. The skip then carries the charges up the incline and delivers them at the furnace top, as shown in Fig. 22.

The stock bin cars are driven by two railway motors, and the door in the bottom of the suspended hopper is opened and closed by an air cylinder, the pressure being supplied by an electrically-driven air-pump carried on the car. The operator can weigh all charges from the car platform. The skip has a capacity of 240 cubic feet, and is hoisted, by means of four $1\frac{1}{4}$ -inch cables, by a pair of 14 x 16-inch engines geared 6.5 to 1 to a 72-inch drum. To complete a single "charge" the skip makes four trips,—taking first two loads of coke and then two loads of ore and limestone mixed. Two loads of coke, or of limestone and ore, are kept always on the bell in order to act as a seal and to keep it cool. When making 600 tons of iron in twenty-four hours the skip delivers ninety "charges," making 360 trips to the furnace top, an average of a return trip every four minutes. The skip is counterweighted, so that the engine does work both in raising and in lowering it.

For pumping water for the cooling plates there are two compound, fly-wheel Holly pumps, each having two double-acting water plungers 22 inches in diameter, with a stroke of 28 inches. These are capable of delivering 7,000,000 U. S. gallons of water per twenty-four hours each. As a reserve there is also a duplex pump with two double-acting water plungers, 14 inches in diameter and 10 inches stroke. All these pumps deliver water to a stand pipe 12 feet in diameter and 150 feet high. The water passes through from three to four cooling plates before being discharged into the waste troughs. Arrangement is made also whereby water from the boiler-feed system can be sent through the cooling plates, in order to force out deposits of sediment by means of the increased pressure. Brass ball-and-socket unions are used throughout the piping for the cooling system.

The boiler house is equipped with 24 vertical water tube boilers, each of 250 horse power; so arranged as to use either furnace gas or coal as fuel. A cross-section of the boiler house is shown in Fig. 23, as is also the type of boilers used. These boilers are admirably adapted for furnace gas as fuel, as, on account of their great height, there is sufficient time to effect the complete combustion of the slow-burning gases. The gas main from the furnaces is extended into the boiler house, and has a connection to the burner in front of each grate.

With the increasing output from single furnaces, it was soon found to be practically impossible to handle the pig iron quickly enough when cast in sand beds in the ordinary manner; and this was the first cause of the development of the pig casting machine, which, with the mixer or storage tank, is one of the most important of recent inventions in connection with the blast furnace. Fig. 24 gives a general idea of the form of the machine. It consists of two endless chains carrying molds or chills of pressed steel, the details of which are shown in Fig. 25. In operation the machine is beautifully simple. The molten iron is poured from the ladle into a trough terminating in two spouts, from which it runs into the chills. The chain then drops down under the surface of the water contained in the tank, and travels under water for a distance of about 100 feet. It then turns upward, and as it ascends the incline the pigs are sprayed with cold water from a spray pipe; and by the time they reach the head of the machine they are sufficiently cooled to be loaded on cars which stand on the loading track. They may, as an alternative, be delivered by the machine to a conveyor, which in turn delivers them to the stock piles for use in the cupolas. The chains travel at the rate of 20 feet per minute, and the chills are spaced 12 inches center to center, so that each chain delivers 20 pigs per minute, weighing on the average 110 pounds each; and thus it will be understood how very efficient this machine is and what a great saving of labor it represents. Instead of clay washing the molds to prevent the iron from fusing with them, they are smoked by two smoke furnaces just before they pass over the tail sprockets. A set of chills will, under ordinary circumstances, last for nine months or a year. In cold weather, however, it is necessary to heat the water in the tanks, otherwise the repeated sudden and violent difference of temperature soon cracks the chills. The ladles are tipped by an electric ladle-tipping machine, from the spindle of which a connection is made with the hand wheel on the ladle car. Provision is made for casting in sandbeds at the furnaces, using the space inclosed by the retaining walls between the

two stacks and opposite the stoves; but this is done only in case of accident to the casting equipment.

Fifteen-ton ladle cars (Fig. 26) are used to convey the molten iron from the furnaces to the pig-casting machine. By referring again to the general plan it will be seen that these stand in a row on the hot-metal track which runs along the front wall inclosing the furnace foundations, and that the iron runners from the tapping holes terminate in spouts at a sufficient elevation to allow the iron to pour into the ladles. Similarly, the slag runners have spouts projecting over the cinder track, which is parallel to the end retaining wall. The cinder ladles (Fig. 27) are of 200 cubic feet capacity, and have removable cast iron linings, which can be renewed when worn out. The furnaces are tapped six times per day each, drawing off 100 tons of iron at each cast when working at their full capacity. The tapping hole is stopped up after the cast by means of a steam tapping-hole gun, which is shown in Fig. 28, as is also its method of use. It is suspended from a small jib crane attached to one of the furnace columns, and can be swung out of the way when not in use.

When the iron from the furnaces is to be used direct in the steel mill without remelting, the ladle cars containing the molten metal are taken to the mixer building, which contains a large mixer or storage tank which is capable of holding 300 tons of molten iron, and the general design of which is shown in Fig. 29. Here the ladles are lifted off the cars by an overhead electric traveling crane, and the iron is poured into the tank, which serves the double purpose of a reservoir from which the steel works can draw their supply and also of insuring a very much more uniform grade of iron, since all casts are mixed together. The mixer itself can be tilted by hydraulic cylinders to pour the iron into the steel works ladle. The iron is kept from chilling by means of fuel-oil burners inserted in the doors placed on the center of rotation and in the pouring spout.

Furnace No. 1 was put in blast July 5, 1899, and blown out July 14, 1900; furnace No. 2 was blown in August 23, 1899, and put out of blast July 19, 1900. During these periods No. 1 made 162,687 tons of iron, and No. 2 made 132,290 tons. They were seldom worked to their full capacity. Figs. 30 and 31 respectively show the lines of the furnace walls obtained by actual measurement immediately after cooling off; measurements were taken at four points of the compass, as indicated in the figures. It will be seen that the diameter of the bosh has increased considerably for the short blast; bronze plates in place of the cast iron coolers would

probably have held the lines better at this point, and several of the furnaces are being so equipped. The cast iron rings protecting the stock lines were found to be badly warped inward; in many cases they had drawn the brickwork with them. This was probably caused by the high temperature at the furnace top when blowing out. However, it is very doubtful as to whether these rings are of any practical value. If they are used at all, they should be made light enough to prevent their warping from drawing the brickwork. There is a good deal of wear on the stock lines, as will be realized by referring to Fig. 32, which shows the profiles of stock as delivered by the bell; but with unprotected walls this would be evenly distributed all the way round, and the movements of the stock would probably be more regular on account of having no projections on the walls. The action of the bell and seal were very satisfactory.

The operators' houses were originally placed over the incline on each furnace top, which necessitated keeping two men in each house on account of danger from escaping gases, but later a single house was placed on the center of the stove platform, from which the bell apparatus for both furnaces was operated with much less expense and greater immunity from danger. The furnace top is equipped with six explosion doors placed directly under the platform. This proved to be a serious defect, as whenever gas leaking from these became ignited the mantel and platform were often badly warped by the heat; and in one instance the frame carrying the incline was also badly bent. This demonstrates the necessity of carrying the explosion-door frames out from the furnace clear of everything. The joints of these doors were originally made as shown in Fig. 33, a, but after the furnaces were blown out they were changed as shown in Fig. 33, b. The surfaces in this case were machined, and the door and frame brick-lined. The value of asbestos packing for doors that open frequently is very doubtful, as it soon becomes dry, hard and lifeless, which makes the prevention of leakage impossible. In another of the large furnaces recently built in this country the joints of the furnace-top explosion-doors were simply plain, flat, machined surfaces.

The cooling system of the hearth jacket was soon rendered ineffective by the stopping up of the pipes, due to leakages and small breakouts of slag from the bosh walls, which made it necessary to spray water on the outside of the jacket. The depth of the jacket is also unnecessarily great, and perhaps the only advantage of this type of jacket is that a section can be replaced when damaged by a breakout or other cause. The average amount of cooling water used for both furnaces was about 7,000,000 U. S. gallons per

twenty-four hours. This includes that used in the furnace-cooling system, and in the seats and discs of all water-cooled valves. The average rise in temperature of the water was 10.5° F. From these figures we may arrive at a very close approximation of the amount of heat carried away by the water. A complete system of cast iron runners for the hot metal was originally installed, but this was soon found to be useless and was dispensed with except at the spouts. There is a great difference of opinion in regard to the use of cooling plates below the tuyères; many claim that the tendency to chill the iron is too great, but it may be said that they were used with very satisfactory results in these stacks.

It is remarkable to what a small extent furnace designers have been guided by experience in the construction of heating stoves. Very many of the largest furnace plants have been badly crippled for long periods of time in order to allow the stoves to be reconstructed. The points of weakness are principally found in the plates forming the lower courses, and in the weakness of the stove fittings riveted to the shell. The plates of the bottom course in the Lorain stoves were $\frac{1}{2}$ inch thick, and many of these were badly cracked soon after the furnaces were put in blast. It will be seen, by referring to Fig. 19, that all the pipe connections are made at the bottom, and that cutting away so much of the plate makes it very weak. For a stove of this size, therefore, a plate not less than $\frac{3}{4}$ inches thick should be used. The flanges of castings, riveted to the stove shells, were about $1\frac{1}{4}$ inches thick, of cast iron. Many of these were also broken by the heat—especially the gas opening door—which caused bad and annoying leaks. These fittings were replaced by heavy steel castings, and no further trouble was experienced. Fig. 34 shows a gas opening door that has been very satisfactory. It will be noticed that the joint is of the spherical type, and that the door itself is brick-lined, which is the only sure way of preventing it from warping. The stove gas burner was originally designed 22 inches in diameter, with a 10-inch air-supply pipe, and the opening in the stove was made 28 inches in diameter. This burner was found to use too much gas, so that there was not sufficient for the boilers. It was modified to the dimensions shown with very satisfactory results.

The hot-blast valve (Fig. 20) is much heavier than the one originally used. The lighter valves were a great source of trouble, and in replacing them all the cast iron rings riveted to the shells were found to be cracked. All the castings, except the bronze water-cooled seats in the later valve, were of steel. On account of the hot-blast valve being opened and closed so frequently, and its

consequently greater liability to get out of order, and a check valve should be inserted between it and the hot-blast main, or, otherwise a crippled hot-blast valve cripples the furnace, since no pressure can be carried in the hot-blast main. The longer branch made necessary by the extra valve is also of great advantage, in that more freedom is allowed for the expansion of the main.

The blast temperature could be easily raised to 1200° or 1300° F. with these stoves. With large percentages of soft ores in the burden, however, it is found that a high-blast temperature causes a high-blast pressure. A 15-inch mixing pipe, connecting the cold- and hot-blast mains, was often found to be too small to reduce the hot-blast temperature by the desired amount, and a larger connection had to be made. An automatic controlling device, used with great success at another of the large furnace plants, was also contemplated. This consists of placing in the mixing pipe a butterfly valve, which is electrically controlled from the pyrometer, to keep the temperature of the blast within certain limits. The power necessary to move the valve is supplied by the blast pressure. At the plant mentioned it was found to be possible to keep the temperature of the hot blast within 5° above or below that desired.

One of the greatest sources of trouble at these furnaces was the "whipping" of the cold-blast main caused by the pulsations of the engines. This is an annoyance to which too little attention has been paid at many furnace plants, especially when it is considered how easily it can be avoided. The mistake is often made of trying to hold the pipe against these pulsations by strapping it to some solid foundation, but this can result only in loosening the rivets and causing leaks. All that is necessary is to provide a receiver of sufficient capacity to break up the column of air and absorb the pulsations.

The commercial efficiency of a furnace depends primarily upon the cost of delivering the raw materials of ore, limestone and coke at the furnace top, and of getting rid of its product as pig or molten iron. This plant is admirably situated with respect to its ore supply, for the reason that the ore is unloaded from vessels* directly to the stock piles without reshipment by rail. From the stock piles it is loaded by steam shovels into special pressed steel hopper-

*The dock machinery for unloading ore from vessels was fully described in a previous paper read by the author before this Club, and published in the JOURNAL OF THE ASSOCIATION OF ENGINEERING SOCIETIES, January, 1900, Vol. 24, page 1, and in an article in *Cassier's Magazine*, September, 1900, Vol. 18, page 355.

bottom cars of 50 tons capacity, similar to the standard steel railway cars, but much shorter. These cars are then brought to the stock bins, and their contents are dropped through the hoppers, ready for use in the furnaces. Placing the stock bins underground has the advantage that no trestle with heavy grade approaches is required, but it is very doubtful whether the great cost of construction and maintenance is fully warranted on this account, as in cold weather the ore seems to freeze in them as readily as when placed in elevated bins. Limestone and coke are received by rail, and the coke is stocked by means of a traveling cantilever crane operating a grab bucket.

The plan of the furnace yard is shown in Fig. 35. All the tracks are of standard gauge, and the sharpest curve is of 461 feet radius. The hot-metal ladle car has a rigid wheel base of 7 feet 6 inches, and the 461-foot curve has been found by experience to be about as sharp as it can round. It is very important to have the tracks carrying hot metal as free from curves, grades and other complications as possible, as a ladle full of molten metal off the track is a very serious matter. It will be noticed, by reference to Fig. 26, that the ladle cars for hot metal are equipped with hand-tilting gear. This is certainly an unnecessary expense and complication for a modern furnace equipment. Wherever the ladle must be tipped—namely at the pig-casting machine, the mixer and in the ladle repair house—there are cranes at hand to do this, and the hand gear is a drawback rather than a help. Especially is this so at the mixer, where the ladles are lifted off the car and replaced thereon after pouring. A much more satisfactory ladle car would be one mounted on a pair of swiveling trucks, with simply the necessary supports to receive the ladle trunnions and a lock to prevent the ladle from tipping while in transit. A satisfactory ladle is one of the most necessary adjuncts to a modern furnace equipment.




FIG. 2. GENERAL PLAN OF FURNACES.




FIG. 3. FRONT ELEVATION OF FURNACES.




FIG. 1. COMPARATIVE PROPORTIONS OF REPRESENTATIVE FURNACES 1855-1900.




FIG. 4. END ELEVATION OF FURNACES.




FIG. 5. FURNACE No. 1.



FIG. 6. LINES OF FURNACE. No. 2.




FIG. 9. DETAIL OF TUYERES.




FIG. 7. SECTION THROUGH BOSH WALL.




FIG. 10. DUST CATCHER.




FIG. 8. DETAILS OF COOLERS AND SOCKET PLATES.




FIG. 11. GAS WASHER.

FIG. 12. 75" GAS CUT-OFF VALVE.





FIG. 14. STOVE GAS BURNER.




FIG. 13.

CONNECTIONS BETWEEN DOWNCOMER AND GAS MAIN.

FIG. 15. SECTION THROUGH STOVE.





FIG. 10. 50" CHIMNEY VALVE.




FIG. 18. 44 X 84 X 84 X 66 BLOWING ENGINES.




FIG. 17. 10' X 22 1/2' STOVE CHIMNEY.




FIG. 19. STOVE COMPLETE WITH ALL CONNECTIONS.




FIG. 20. 32" HOT-BLAST VALVE.




FIG. 21. SECTION THROUGH STOCK BINS.




FIG. 22. FURNACE TOP.




FIG. 23. SECTION THROUGH BOILER HOUSE.




FIG. 25. CHILLS AND CHAINS FOR PIG-CASTING MACHINE.




FIG. 24. PIG-CASTING MACHINE.




FIG. 26. 15-TON HOT-METAL LADLE CAR.




FIG. 27. 200 CU. FT. CINDER LADLE CAR.




FIG. 28. TAPPING-HOLE GUN




FIG. 32. STOCK PROFILES.




FIG. 29. 300-TON HOT-METAL MIXER.



EXPLOSION DOOR JOINTS.



FIG. 30.
LINES OF FURNACE No. 1
AFTER BLOWING OUT.



FIG. 31.
LINES OF FURNACE No. 2
AFTER BLOWING OUT.




FIG. 34. GAS-OPENING DOOR.




FIG. 35. PLAN OF FURNACE YARD.

OBITUARY.

George W. Percy.

By the sudden and lamentable death of our highly esteemed President, on Friday, December 14, 1900, the Technical Society, and indeed the entire community, sustained an irreparable loss.

George Washington Percy was born at Bath, in the State of Maine, on July 5, 1847, his early youth being spent amid agricultural surroundings. He received his education as a boy at the Kent's Hill Academy, in his native State. It was during the progress of the Civil War that he found employment in the mercantile marine of this country. At this time he made a voyage to Europe, and also visited other countries.

Endowed with a natural aptitude for mechanical and mathematical pursuits, he decided about this time to study architecture, with a view to adopting it as his life profession. How wisely his choice was made is exemplified by the many structures which will stand for ages as monuments of his professional skill and intelligence.

His technical education was commenced in the office of Mr. Fassett, of Portland, Maine, and for some years his time was spent in faithful and painstaking study in qualifying himself for practicing the profession of his choice. Subsequently Mr. Percy entered the office of Bradley & Winslow, architects, of Boston, Massachusetts, and while there superintended several important works.

Coming to California in 1869, he settled in Stockton, returning to the East in September, 1871, immediately after the great Chicago fire, in which city he did some heavy work during the rebuilding operations, after which we once again find him located in Boston. Among other works with which Mr. Percy was associated in this latter city is the Equitable Life Insurance Building, a typical example of the class of work in which he took a special interest.

Returning once more to California, in 1876, and locating in San Francisco, still full of youth and energy, he immediately commenced to build up a successful and steadily increasing practice. Numerous important buildings in San Francisco and throughout the Pacific coast will testify for many generations to his professional ability and constructive knowledge. It is perhaps unnecessary to do more than mention the following as being among the more important of Mr. Percy's works: Stockton Insane Asylum, Stanford University library and assembly hall, girl's dormitory, Stanford University, Academy of Sciences Building, Market, near

Fifth street; Alameda city hall, Nevada State University, Reno, Nevada; Episcopal church, Stockton; Alvinza Hayward residence, San Mateo; Leland Stanford, Jr., museum, Palo Alto; Crassley dome and professors' homes, Mt. Hamilton; Methodist Episcopal church business building, Alameda; California School of Mechanical Arts, Sixteenth and Utah streets; San Joaquin county almshouse; De Fremery block, Oakland; children's house and playground and other buildings in G. G. Park; Strathmore apartment house, Larkin street; First Unitarian church, Geary and Franklin streets; Golden Gate Park panorama, Strawberry Hill; City Front Stables, Clay, near East street; John Benson office building, Leidesdorff and Pine streets; Hobart Building, Post street; the "Hobart" vault, Cypress Lawn Cemetery; Hoit's School, Menlo Park; the Bourn tomb, Laurel Hill Cemetery; Wells Fargo Building, Mission and Second streets; Alexander Young business block, Honolulu; Hayward Building, California and Montgomery streets.

In 1881 Mr. Percy traveled in Europe for pleasure and to study ancient and modern work, being especially interested in the archaeological remains of Rome of all ages. Indeed, his continued study and interest regarding ancient Rome in all its phases was maintained to the last, and probably few persons were better informed than he was concerning the materials and constructive methods of the Romans.

In addition to filling the presidential chair of the Technical Society, in which he took the warmest interest, Mr. Percy was an active associate member of the American Institute of Architects; also a trustee of the San Francisco chapter, American Institute of Architects, and also a member of the Pacific Lodge of Free and Accepted Masons. He was a member of the Berkeley Literary and Professional Club; also of the Astronomical Society of the Pacific Coast, and was an amateur astronomer of no small ability. He was the author of many instructive technical papers, which he read before the societies in which he took so deep an interest. His interest in young students of architecture was often manifested, many of whom applied to him for advice and assistance in their studies, and never in vain. His skill and experience has also been frequently sought in consultations involving questions concerning architecture and construction. Among many such cases may be mentioned the fact that he was invited to act as consulting architect in connection with the new Union Depot and ferry building of this city. Indeed, it may justly be said of him that he was at the very zenith of a successful career, and that he not only occupied a high and honorable position among the members of his own profession,

but also enjoyed the absolute and perfect confidence of his many clients.

Among contractors and business men with whom he was brought into contact in the construction of his buildings he was most highly respected, and invariably regarded by them as being absolutely fair and just in his requirements, dispensing equal justice to contractors and owners alike without fear and without favor.

A widow and four children—two sons and two daughters—are left to mourn the loss of a devoted husband and a loving father.

Mr. Percy possessed an exceedingly strong personality. His wide capability, his sterling integrity and earnestness and, above all, his absolute thoroughness were apparent in everything he undertook. These moral qualities and the knowledge that he was in every sense a manly man, as well as a genial gentleman, will ever be associated with the memory of our late fellow-member and friend.

G. ALEXANDER WRIGHT, *Committee.*

ASSOCIATION OF ENGINEERING SOCIETIES.

Articles of Association.

The following Articles of Association were adopted at a meeting held in Chicago, December 4, 1880. At this meeting there were present representatives of the

Western Society of Engineers,
Civil Engineers' Club of Cleveland,
Engineers' Club of St. Louis,

and the

Boston Society of Civil Engineers
was represented by letter.

FOR THE PURPOSE OF SECURING THE BENEFITS OF CLOSER UNION AND THE
ADVANCEMENT OF MUTUAL INTERESTS, THE ENGINEERING SOCIETIES AND CLUBS
HEREUNTO SUBSCRIBING HAVE AGREED TO THE FOLLOWING

ARTICLES OF ASSOCIATION.

ARTICLE I.

NAME AND OBJECT.

The name of this Association shall be "THE ASSOCIATION OF ENGINEERING SOCIETIES." Its primary object shall be to secure a joint publication of the papers and the transactions of the participating Societies.

ARTICLE II.

ORGANIZATION.

SECTION 1. The affairs of the Association shall be conducted by a Board of Managers under such rules and by-laws as they may determine, subject to the specific conditions of these articles. The Board shall consist of one representative from each Society of one hundred members or less, with one additional representative for each additional one hundred members, or fraction thereof over fifty. The members of the Board shall be appointed as each Society shall decide, and shall hold office until their successors are chosen.

SEC. 2. The officers of the Board shall be a Chairman and Secretary, the latter of whom may or may not be himself a member of the Board.

ARTICLE III.

DUTIES OF OFFICERS.

SECTION 1. The Chairman, in addition to his ordinary duties, shall countersign all bills and vouchers before payment and present an annual report of the transactions of the Board; which report, together with a synopsis of the other general transactions of the Board of interest to members, shall be published in the JOURNAL OF THE ASSOCIATION.

SEC. 2. The Secretary shall be the active business agent of the Board and shall be appointed and removed at its pleasure. He shall receive a com-

pen-sation for his services to be fixed from time to time by a two-thirds vote. He shall receive and take care of all manuscript copy and prepare it for the press, and attend to the forwarding of proof sheets and the proper printing and mailing of the publications. He shall have power, with the approval of any one member of the Board, to return manuscript to the author for correction if in bad condition, illegible or otherwise conspicuously deficient or unfit for publication. He shall certify to the correctness of all bills before transmitting them to the Chairman for counter-signature. He shall receive all fees and moneys paid to the Association and hold the same under such rules as the Board shall prescribe.

ARTICLE IV.

PUBLICATIONS.

SECTION 1. Each Society shall decide for itself what papers and transactions of its own it desires to have published and shall forward the same to the Secretary.

SEC. 2. Each Society shall notify the Secretary of the minimum number of copies of the joint publications which it desires to receive, and shall furnish a mailing-list for the same from time to time. Copies ordered by any Society may be used as it shall see fit. Payments by each Society shall in general be in proportion to the number of copies ordered, subject to such modification of the same as the Board of Managers may decide, by a two-thirds vote, to be more equitable. Assessments shall be quarterly in advance, or otherwise, as directed by the Board.

SEC. 3. The publications of the Association shall be open to public subscription and sale, and advertisements of an appropriate character shall be received, under regulations to be fixed by the Board.

SEC. 4. The Board shall have authority to print with the joint publications such abstracts and translations from scientific and professional journals and society transactions as may be deemed of general interest and value.

ARTICLE V.

CONDITIONS OF PARTICIPATION.

SECTION 1. Any Society of Engineers may become a member of this Association by a majority vote of the Board of Managers, upon payment to the Secretary of an entrance fee of fifty cents for each active member, and certifying that these Articles of Association have been duly accepted by it. Other technical organizations may be admitted by a two-thirds vote of the Board, and payment and subscription as above.

SEC. 2. Any Society may withdraw from this Association at the end of any fiscal year by giving three months' notice of such intention, and shall then be entitled to its fair proportion of any surplus in the treasury, or be responsible for its fair proportion of any deficit.

SEC. 3. Any Society may, at the pleasure of the Board, be excluded from this Association for non-payment of dues after thirty days' notice from the Secretary that such payment is due.

ARTICLE VI.

AMENDMENTS.

These articles may be amended by a majority vote of the Board of Managers, and subsequent approval by two-thirds of the participating Societies.

ARTICLE VII.

TIME OF GOING INTO EFFECT.

These articles shall go into effect whenever they shall have been ratified by three Societies, and members of the Board of Managers appointed. The Board shall then proceed to organize, and the entrance fee of fifty cents per member shall then become payable.

These articles were adopted by the several Societies upon the following dates:

Engineers' Club of St. Louis, January 5, 1881.

Civil Engineers' Club of Cleveland, January 8, 1881.

Boston Society of Civil Engineers, January 19, 1881.

Western Society of Engineers, April 5, 1881.

The Board of Managers was organized at Cleveland, January 11, 1881.

The following Societies have since certified their acceptance of the articles, and have become members of the Association of Engineering Societies:

Engineers' Club of Minneapolis, July, 1884.

Civil Engineers' Society of St. Paul, December, 1884.

Engineers' Club of Kansas City, January, 1887.

Montana Society of Civil Engineers, April, 1888.

Wisconsin Polytechnic Society, June, 1892.

Denver Society of Civil Engineers, January 24, 1895.

Association of Engineers of Virginia, February 1, 1895.

Technical Society of the Pacific Coast, March 1, 1895.

Detroit Engineering Society, January, 1897.

Engineers' Society of Western New York, January, 1898.

Louisiana Engineering Society, September 15, 1898.

Engineers' Club of Cincinnati, January, 1899.

The Wisconsin Polytechnic Society withdrew from the Association in March, 1894.

The Western Society of Engineers withdrew in December, 1895.

The Engineers' Club of Kansas City disbanded at the close of 1896.

The Denver Society of Civil Engineers and the Association of Engineers of Virginia disbanded in 1898.

Annual Report of the Chairman of the Board of Managers.

DECEMBER 31, 1900.

To the Members of the Board of Managers of the Association of Engineering Societies:

GENTLEMEN:—I have the honor to transmit to you and to the Association through you, the annual report of the Secretary of the Association for the year 1900. This shows an increase in membership during the year from 1475 in 1899 to 1541, while the number of the societies has not changed.

There has been a slight increase in the cost of the JOURNAL, as shown by the Secretary's report, causing a diminution in the net assets from those of 1899. The character of the JOURNAL is such that there should be no difficulty in making it self-sustaining, and the attention of the members of the Association is called to the fact that our JOURNAL has a circulation of about 1900 copies, and the advantages of advertising in such a journal will be evident to all.

In the report of the Chairman for 1899 he stated that no Engineer could afford to be without the JOURNAL. I desire to repeat that statement, and ask the members of the Association to keep this JOURNAL before their friends, with a view to inducing them to subscribe to it.

I also desire to call your attention to the able and efficient work of the Secretary, who does all the business of the Association, and gives a great amount of time and care to the work. It is desirable that the members of the Association should make every effort to secure advertisements for the JOURNAL among the members of the societies which they represent.

Respectfully submitted,

JAMES RITCHIE, *Chairman.*

Annual Report of the Secretary of the Board of Managers.

PHILADELPHIA, December 31, 1900.

Mr. James Ritchie, Chairman,

395 City Hall, Cleveland, O.

DEAR SIR:—I have the honor to present the following report upon the operations of the Secretary's office during the year 1900, and of the condition of the Association at the present time.

These data are concisely stated in the following statistical appendices:

- A. Statement of receipts and expenditures during 1900.
- B. Estimate of assets and liabilities at the close of 1900.
- C. Detailed statement of cost of JOURNAL during 1900, by months.
- D. Comparison of mailing lists of the JOURNAL at the close of 1899 and of 1900, respectively.
- E. Statement of material in JOURNAL during 1900, by pages.

F. Comparison of conditions, 1894 to 1900, inclusive.

A study of Appendix F shows an increase in the cost of the JOURNAL, with a corresponding diminution of net assets, due partly to a sharp advance in the printers' rates and partly to an increase of 18 per cent. in the amount of matter published. The close of the year, nevertheless, finds us with a cash balance in hand of \$1,448.24, and total net assets of \$2165.67.

During the year, no new societies have joined the Association, but the aggregate membership of our societies shows an increase of about $4\frac{1}{2}$ per cent. The present aggregate of 1541 members is greater than at any time during the history of the Association, exceeding, as it does, by about $4\frac{1}{2}$ per cent., the aggregate membership at the close of 1895, before the withdrawal of the Western Society of Engineers.

In my report for 1899 I was obliged to call attention to "a decided falling off in the amount of material presented for publication in the JOURNAL," the number of pages per thousand members having fallen to 369, the lowest reached during the preceding six years.

This condition has been, to a great extent, remedied during 1900; the number of pages of papers having increased from 958 in 1899, to 1130 in 1900, and the total per thousand members having increased to 432.

The close of the year finds us with considerable material on hand awaiting the January JOURNAL.

In my last annual report I called attention to the commendable activity of the Cleveland Society in obtaining advertisements for the JOURNAL, that society having, by means of the commission of 90 per cent. allowed by the Association, relieved itself entirely of charges on account of the Association JOURNAL.

At this writing the Engineers' Club of St. Louis is taking measures to follow the example of the Cleveland Society.

The List of Members of the Societies in the Association, first published in the JOURNAL for January 1899, and again in that for January 1900, now appears for the third time, and with further improvements in the matter of its typography.

Respectfully submitted,

JOHN C. TRAUTWINE, JR., *Secretary.*

APPENDIX A.

STATEMENT OF RECEIPTS AND EXPENDITURES DURING 1900.

CASH, 1900.

Dr.

To Balance, January 1, 1900.....	\$1,806 34	
“ Assessments, at \$2.00 per member :		
Boston Society of Civil Engineers.....	\$92 00	
Civil Engineers' Club of Cleveland.....	387 50	
Engineers' Club of St. Louis.....	407 00	
Civil Engineers' Club of St. Paul.....	58 00	
Engineers' Club of Minneapolis.....	28 50	
Montana Society of Engineers.....	168 00	
Detroit Engineering Society.....	171 00	
Engineers' Society of Western New York.....	83 00	
Louisiana Engineering Society.....	120 00	
Engineers' Club of Cincinnati.....	179 00	
Technical Society of the Pacific Coast.....	288 50	
	<hr/>	2,882 50
To Subscriptions	768 94	
“ Sales of JOURNAL.....	181 92	
“ “ “ Descriptive Index.....	26 50	
“ Advertisements.....	370 83	
“ Sales of reprints.....	104 25	
“ Interest on deposits.....	16 44	
“ Electros.....	25 25	
“ Letter-heads	6 25	
“ Copyright fee.....	1 00	
“ Illustrations furnished to authors, etc.....	65 17	
“ 792 misdirected envelopes sold.....	15 84	
	<hr/>	\$6,331 23

Cr.

By Patterson & White Co. (Printers).....	\$3,523 15	
“ Illustrations.....	558 10	
“ Secretary's salary.....	600 00	
“ Car fares.....	30	
“ Discounts on subscriptions.....	28 85	
“ “ “ sales.....	2 20	
“ Messenger service.....	4 42	
“ Stationery	17 40	
“ Telegrams	9 46	
“ Postage stamps.....	34 32	
“ Express charges.....	2 55	
“ Back numbers bought.....	50	
“ Binding JOURNALS for Paris Exposition.....	8 50	
“ Civil Engineers' Club of Cleveland, Amount due from advertisement.....	16 20	
“ Prof. Geo. D. Shepardson, expenses as chairman	5 00	
“ Engineers' Club of St. Louis, credit balance at end of 1899.....	9 50	
	<hr/>	
Forward.....	\$4,820 45	\$6,331 23

Forward.....	\$4,820 45	\$6,331 23
By Secretary's trip to Boston, Feb. 6.....	21 10	
“ “ trip to New York, March 9.....	4 00	
“ Copyright fee	1 00	
“ Subscriptions refunded.....	5 50	
“ Amount overpaid on subscription, refunded.....	2 00	
“ Advertising, including cost of cuts (\$24.80).....	28 94	
	<hr/>	4,882 99
“ Cash balance, December 31, 1900.....		\$1,448 24

APPENDIX B.

ESTIMATE OF ASSETS AND LIABILITIES AT THE CLOSE OF 1900.

AVAILABLE ASSETS.

Cash balance, December 31, 1900	\$1,448 24	
Less subscriptions for 1901, paid during 1900.....	53 00	
	<hr/>	\$1,395 24
Amounts receivable from Societies (for assessments, etc.):		
Boston Society of Civil Engineers	\$38 20	
Montana Society of Engineers.....	130 00	
Detroit Engineering Society.....	47 50	
Engineers' Society of Western New York.	34 55	
	<hr/>	\$250 25
Subscriptions due:		
For 1900.....	90 00	
“ 1899.....	100 80	
“ 1898 and earlier.....	192 00	
	<hr/>	382 80
For reprints	109 60	
“ Advertisements.....	306 33	
“ Sales of JOURNALS.....	22 50	
“ “ “ Index.....	7 25	
“ “ “ Cuts.....	2 75	
	<hr/>	\$1,081 48
		<hr/>
		\$2,476 72

LIABILITIES.

Patterson & White Co. (Printers):		
For December JOURNAL.....	\$168 50	
“ Reprints	7 00	
	<hr/>	\$175 50
Civil Engineers' Club of Cleveland, commissions		
on advertisements	\$108 90	
Engineers' Society of Western New York.....	70	
Illustrations.....	25 95	
	<hr/>	311 05
		<hr/>
Net Assets.....		\$2,165 67

APPENDIX C.

DETAILED STATEMENT OF COST OF JOURNAL DURING 1900, BY MONTHS.

1	2	3	4	5	6	7	8	9	10	11	12	13
Composi- tion.	Paper, Presswork, Binding.	Wrap- ping.	Postage.	Printer, Sum of 1, 2, 3 and 4.	Illustra- tions.*	Cost of Manufacture Sum of 1, 2, 6.	Wrap- pers.	Secy's Salary.	Sun- dries.†	Total Sum of 5, 6, 8, 9, 10.	No. of Pages.‡	Cost per Page. ‡
January	\$278 41	\$6 39	\$18 06	\$587 11	\$147 35	\$710 01	\$5 50	\$50 00	\$47 23	\$837 19	214	\$3 91
February	98 91	131 25	6 01	246 77	32 50	262 66	4 75	50 00	26 36	360 38	108	3 31
March	71 78	103 25	7 25	190 03	19 84	194 87	4 75	50 00	66 96	331 58	88	3 77
April	78 60	95 25	6 33	188 99	98 15	272 00	4 75	50 00	36 92	378 81	84	4 51
May	78 48	117 15	6 60	211 35	94 05	289 68	5 00	50 00	39 71	400 14	60	4 45
June	70 07	105 00	4 77	187 89	175 07	4 75	50 00	44 39	287 03	80	3 59
July	112 23	119 40	4 77	244 61	87 85	310 48	4 75	50 00	7 93	395 14	91	4 29
August	42 15	86 75	4 40	141 92	9 00	137 90	4 75	50 00	4 05	210 32	64	3 29
September	89 82	101 15	4 70	203 40	26 80	217 47	4 75	50 00	3 61	288 26	78	3 70
October	90 47	101 15	4 84	204 43	33 50	225 12	4 75	50 00	8 21	300 02	78	3 86
November	97 75	122 50	4 57	233 52	27 08	247 33	4 75	50 00	4 55	319 00	84	3 81
December	56 35	95 50	5 88	163 75	15 00	166 85	4 75	50 00	8 36	241 86	68	3 55
Totals and averages...	\$1,171 02	\$1,456 60	\$66 40	\$2,803 77	\$590 82	\$3,218 44	\$58 00	\$600 00	\$398 94	\$4,381 53	1150	\$3 85

* The figures in column 6 (Illustrations) include preparation of cuts and lithographic stones, and paper and presswork on insets.

† The figures in column 10 (Sundries) include all expenditures of the Association (such as stationery, postage, circulars, etc.) chargeable to the JOURNAL and not entered in any other column. They do not include the cost of preparing reprints of papers.

‡ The figures in columns 12 (No. of Pages) and 13 (Cost per Page) include 4 cover pages in each number, and 16 pages in indexes to Vols. XXIV and XXV.


APPENDIX F. COMPARISON OF CONDITIONS, 1894 TO 1900, INCLUSIVE.

Year.	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
	Number of Societies in Association, Dec. 31.	Aggregate Membership of Societies, Dec. 31.	Subscribers, Dec. 31.	Exchanges, Dec. 31.	Net Receipts from Advertisements.	Total Number of Pages in Journal.	Pages of Papers.		Cost of JOURNAL.*		Per Member.		Annual Assessment per Member.	Small Cuts.	Illustrations.		Net Assets, Dec. 31.
							Total.	Per 1000 Members.	Total.	Per Page.	Per Member.	Per Member per 1000 pages.			Plates and Full-Page Cuts.	Cost.	
1894	8	1174	176	110	\$4971 00	1290	653	556	\$5774 59	\$4 48	\$4 92	\$3 81	\$3 00	86	54	\$651 60	—\$758 91†
1895	11	1477	215	122	594 04	1182	792	536	5911 48	3 99	4 00	2 70	3 06	116	66	850 60	223 93
1896	9	1106	241	108	763 25	856	490	443	3928 42	4 59	3 55	4 15	3 00	62	56	771 39	1244 04
1897	10	1252	233	102	410 25	1016	638	510	3140 43	3 09	2 51	2 47	2 50	57	45	503 85	2502 04
1898	12	1370	246	114	465 58	1110	738	539	3462 08	3 12	2 53	2 28	2 00	100	42	720 38	2036 71
1899	11	1475	249	115	300 88	958	544	369	3233 44	3 38	2 10	2 20	2 00†	124	30	501 24	2442 06‡
1900	11	1541	216	116	370 83	1130	660	432	4351 53	3 85	2 82	2 50	2 00	112	27	590 82	2162 07

*The publication of the Descriptive Index of Current Technical Literature was discontinued at the end of 1895.

†During 1899, with an assessment of \$2.00 per member, the Association made a rebate of \$1.00 per member for the purpose of reducing surplus, making the actual charge only \$1.00 per member, and reducing the assessment by about \$1400.

‡Deficit at close of 1894. Since then, each year has shown a surplus.



ASSOCIATION OF ENGINEERING SOCIETIES. Organized 1881.

VOL. XXVI.

FEBRUARY, 1901.

No. 2.

This Association is not responsible for the subject-matter contributed by any Society or for the statements or opinions of members of the Societies.

BRICK AND CONCRETE-METAL CONSTRUCTION.

PAPERS PRESENTED AT THE MEETING OF THE BOSTON SOCIETY OF CIVIL ENGINEERS, HELD OCTOBER 17, 1900.

Economy and Strength of Brick and Concrete Arches for Floor Systems of Highway Bridges.*

BY WILLIAM D. BULLOCK, MEMBER BOSTON SOCIETY OF CIVIL ENGINEERS.

THE Weybosset bridge in the city of Providence spans the Providence River at Market square. There are three piers dividing into four spans the river channel, which is $132\frac{1}{2}$ feet wide. The channel at the bridge being on a curve the steel plate girders, which are $42\frac{1}{2}$ inches deep, are placed on radial lines, Fig. 1.

Extending from girder to girder, and riveted to them, are transverse floor beams 2 feet deep and spaced $8\frac{1}{2}$ feet apart. Supported on these floor beams are 10-inch I beams, spaced about 2 feet 5 inches apart in radial lines, between the main girders.

The spaces between the I beams and the main girders are covered by brick arches, leveled up with Portland cement concrete to within 2 inches of grade.

The area of the bridge is 31,610 square feet.

Located as this bridge is, in the center of the city and furnishing the main passageway between the east and west sides, it is subjected to very heavy and concentrated travel, including both highway and trolley car travel. Under these circumstances the question of designing a substantial floor at a reasonable cost became one of great importance.

*Manuscript received November 6, 1900. Secretary, Ass'n of Eng. Soc's.




FIG. 2.

The ordinary forms of flooring of steel shapes, at the price of 2.34 cents per pound paid for this bridge, would cost about 72 cents per square foot, and the concrete for leveling up ready to receive the asphalt paving would cost 15 cents per square foot, making a total cost of 87 cents per square foot for this form of construction at the former low price of steel. At the prevailing prices of steel during the past year, of say 5 cents per pound, the cost would be about \$1.68 per square foot.

The cost of the steel 10-inch I beams and dam plates was 26 cents per square foot of floor, and the cost of the brick arches and concrete for leveling up to grade was 26 cents per square foot, making a total cost, for the masonry floor, of 52 cents per square foot. This shows a difference of 35 cents per square foot in favor of the masonry floor as compared with the low contract prices. In addition to the saving in the first cost of the masonry arch floor, there is an additional saving in the reduced surface of metal to be painted.




FIG. 3. TEST OF ARCHES PROPOSED FOR DRIVEWAY FLOOR OF THE WEYBOSSET BRIDGE.

The weight of the steel floor of Carnegie shapes leveled up with concrete would be about 112 pounds per square foot and that of the masonry floor 118 pounds per square foot.

After the plans were decided upon and the actual work of construction begun, it was decided to make the concrete $2\frac{3}{4}$ inches thicker, in order to enable the trolley company to use deeper rails than originally intended. This increased the weight $39\frac{1}{2}$ pounds and the cost 7 cents per square foot. Fig. 2 shows the section of the floor as actually constructed.

The question is thus narrowed down to whether or not a thin floor of masonry arches between steel I beams will have sufficient strength to meet the trying conditions of a city highway bridge. In addition to various calculations made to determine this question, it was thought desirable to make some prac-

Number of Experiments.	Brand of Cement and Proportions.		Rise of Arch in Inches.	Thickness at Crown in Inches.	Number of Days from Construction to Destruction.	Greatest Pressure per Sq. In. of Shoe on Concrete without Indication of Crushing.	Loading in Tons, when:			REMARKS.
							Snapping Sound First Noticed.	Small Cracks Showing at Crown.	Arches Broken.	
1	Alpha	Atlas	6	7	8		33.3	16.5	34.0	Some yielding of tie bars, which probably hastened failure.
	1 1	1-2-4								
2	Alpha	Atlas	6	7	15		18.1	18.1	54.6	
	1-1	1-2-4								
3	Alpha	Atlas	6	7	22	2.0	45.6	17.7	60.6	Three trials: First interrupted by crippling of lever; second interrupted by failure of anchor age.
	1 1	1-2-4								
4	Alpha	Atlas	6	7	29	4.75	18.9	30.6	65.6	
	1 1	1-2-4								
5	Alpha	Atlas	6	7	57	3.8	48.2		75.9	Slight yielding of tie bars.
	1 1	1-2-4								
6	Alpha	Atlas	6	7	172	4.0	45.2	51.1	62.7	
	1 1	1-2-4								
7	Alpha	Alpha	7	5 1/2	8	2.0	20.3	31.0	55.1	
	1 1	1-2-1								

tical tests on arches of the same dimensions and exactly of the same construction as those proposed to be used. In the city bridge shop 6 brick arches were built between 10-inch I beams, leveled up with concrete, and the I beams tied together with iron clamp bars. In the absence of any testing machine a contrivance was improvised from materials on hand for making the tests, substantially as shown by Fig. 3. The arches were made of partially vitrified paving brick made by the New England Brick Company and laid in Atlas Portland cement mortar, 1 to 1. The concrete was made of Atlas and Alpha Portland cement 1 part, sand 2 parts and screened medium gravel 4 parts. The Atlas cement, tested neat in briquettes at the end of 24 hours, showed a tensile strength of 426 pounds per square inch and the Alpha 365 pounds per square inch.

The voids in sand were 30.3 per cent. of volume.

The voids in gravel were 35.9 per cent. of volume.

The weight of the brick arches per cubic foot was 150.3 pounds and the concrete 158.1 pounds.

The foregoing table shows the results of the tests. The bearing shoe was of the same width and curvature as some of the heavy low gears in use in this city. The yielding of the heavy $4 \times \frac{7}{8}$ -inch clamp bars in the first and sixth experiments showed that there was a large horizontal thrust from the arches.

A Test of the Strength of Rapp Floor Arches.*

BY FREDERIC H. FAY, MEMBER BOSTON SOCIETY OF CIVIL ENGINEERS.

FROM time to time the Engineering Department of the City of Boston has been asked by the Building Commissioner to make tests upon different types of fireproof floors. These tests, however, had nothing to do with fireproof qualities, they having been made solely to satisfy the Commissioner that the floors in question were capable of sustaining the load required by the city building laws. Hence we might call them tests of the "working strength." One of these, a test of some floor arches of the Rapp type of construction, is described herewith. Considering the fact that the test was made upon one of the floors of a building (which at the time was in process of construction), and that the arches had been built before the test was proposed, it is thought that the conditions found were those likely to be met in practice.

Details of this Rapp floor are shown in the accompanying figures.

Two adjoining arches near the center of the building were selected for the test, the span of each arch being, approximately, 7 feet 10 $\frac{1}{4}$ inches, and the width 16 feet 5 inches, the distances being measured between the centers of the supporting beams. The total area of the two is about 258 square feet.

The test consisted in loading the arches with a live load of about 500 pounds per square foot, the behavior of the arches during the test being studied by noting their deflection and spread.

CONSTRUCTION OF THE FLOOR.

Between columns 11 and 12 and columns 16 and 17 are two 18-inch I-beam headers. At right angles to the latter are three 15-inch I beams, the middle one being framed into the 18-inch beams and the other two connecting directly to the columns.

Curved Rapp tees are supported by the bottom flanges of the 15-inch beams. These tees consist of pieces of sheet steel 4 $\frac{1}{2}$ inches wide and 1-16 inch thick, bent so as to form a "T" section with about 2 $\frac{1}{4}$ -inch flange and 1 $\frac{1}{2}$ -inch stem. Separators, made by bending a strip of steel 1 $\frac{1}{2}$ inches wide by 1-16 inch thick, regulate the spacing of the tees at about 8 $\frac{3}{4}$ inches on centers.


The Rapp tees being placed with their stems upward, the flanges are available for supporting rows of bricks which form an

*Manuscript received November 6, 1900.—Secretary, Ass'n of Eng. Soc's.

arch of nearly 9 inches rise above the bottom of the beams. The bricks were laid dry, and after they were in place cement grouting was supposed to have been poured over the arch and into the joints between the bricks. Many of the joints, however, apparently contained but little mortar.

A filling of cinder concrete, said to be made of one part Atlas cement and eight parts cinders, was then deposited upon the arches to the level of the tops of the 15-inch beams. Thus there was about 4 inches of concrete above the brick arch at the crown, the depth increasing to a maximum of 12 inches of concrete at the springing. Neither the upper layer of concrete, inclosing the nailing strips, nor the wooden floor had been put in place at the time the test was made.

The 15-inch I beams were said to be connected by tie rods, which had been bent upward two inches or more out of line in order that they might not be exposed in the ceiling at the crown of the arch.



Details of Arch

DETAILS OF RAPP FLOOR IN BUILDING ON INDIA STREET.


DETAILS OF THE TEST.

The test was begun Wednesday, November 9, and ended Saturday, November 12. When the arches received their full load the concrete filling had been in place fifteen days. The loading was made by using bricks carefully piled in such a manner as to avoid breaking joints, thus allowing their weight to be uniformly distributed. A representative of the building department supervised the loading, and by weighing and measuring several lots of bricks secured the data from which the total weight of bricks was estimated from their volume. The maximum load applied was, very closely, 500 pounds per square foot.

The deflection of the floor was obtained by taking levels upon the under side of the beams and arches of the two bays tested, and

also upon two of the adjoining arches. The spread of the arches was determined by measurements with a steel tape and an engineer's scale.

The first series of levels and measurements was made between 10 and 2 o'clock of Wednesday, November 9, before any live load was applied to the floor. From 2 o'clock of Wednesday until noon of Thursday workmen were engaged in putting on the bricks.



PARTIAL PLAN OF SECOND FLOOR, SHOWING TESTED BAYS.

Friday morning, after the arches had been carrying their full live load for nearly twenty-four hours, the second series of readings was taken. Friday afternoon the load was entirely removed. After a period of rest of about sixteen hours the bays were again measured on Saturday morning, to determine to what extent the floor had recovered from the effects of the load.

Table I shows the deflections of the two arches tested. The deflections there given are *net*; that is, the total drops of the arches have been corrected to allow for the settlement of the supporting beams, so that the net results given are the same as though there had been no vertical movement of the arch supports.

TABLE I.
SHOWING DEFLECTION OF ARCHES.

POINT. [On Under Side of Arch].	DEFLECTION Under Live Load of 500 Lbs. per Sq. Ft.	UPWARD MOVEMENT Upon Removal of Load.	DEFLECTION Still Remaining after Removal of Load.
k	0.21 inch	0.11 inch	0.10 inch
l	0.20 "	0.14 "	0.12 "
m	0.24 "	0.16 "	0.08 "
n	0.18 "	0.13 "	0.05 "
o	0.30 "	0.19 "	0.11 "
p	0.22 "	0.16 "	0.09 "
Average for Arch klm	0.24 "	0.14 "	0.10 "
Average for Arch nop	0.23 "	0.16 "	0.07 "
Average for both arches	0.23 "	0.15 "	0.09 "

Measurements at the middle of the 15-inch beams showed the spread of the arches in the direction C D to be as given in Table II.

TABLE II.
SHOWING SPREAD OF ARCHES.

ARCH.	ELONGATION Under Live Load of 500 Lbs. per Sq. Ft.	CONTRACTION Upon Removal of Load.	ELONGATION Still Remaining after Removal of Load.
From b to e	0.16 inch	0.09 inch	0.07 inch
From e to h	0.09 "	0.07 "	0.02 "

Throughout the test levels were taken upon the two adjacent arches, at C and D, which were liable to deformation from the thrust of the loaded arches. No considerable movement was found in either adjacent arch, and apparently their shape was practically unchanged.

CONCLUSIONS.

Under the load of 500 pounds per square foot the average deflection of the two arches tested was $\frac{1}{4}$ inch. Sixteen hours after the removal of the load the arches had regained about 60 per cent. of their deflection, making the average deflection still remaining less than $\frac{1}{8}$ inch. Some permanent set might have been expected, due to the closing of certain joints between bricks which were only partly filled with cement grout. Still, it is possible that the arches had not entirely recovered from their fatigue, and that a further slight upward movement could have been detected had readings been taken at a longer interval after the removal of the load. The smallness of the spread of the arches was probably due to the fact

that the floor had been built in the adjoining bays, and its stiffness was sufficient to prevent much sidewise motion of the arches in question. It is not likely that the bent tie rods would be very efficient in holding the thrust, which must have been resisted principally by the sidewise bending of the supporting beams and outer walls. The practice of bending tie rods in arches is certainly not to be recommended, and it is understood that, in accordance with the suggestion of the Building Department, the rods of the other floors of this building have been made straight.

Expanded Metal as Used in Fireproof Building Construction and Other Work.*

BY WILLIAM M. BAILEY, MEMBER BOSTON SOCIETY OF CIVIL ENGINEERS.

THE object of this paper is to give briefly some information regarding the uses of expanded metal, and the results of a few tests made on expanded metal and concrete structures.

At intervals there have been submitted for the consideration of engineers and architects different combinations of plastic materials and steel, and of concrete and steel, with the steel in the form of isolated ribs acting entirely in tension; combinations where single rods are imbedded in the tension side of the concrete, and combinations of steel and concrete where the steel in continuous sheets is imbedded in the tension side of the concrete and acts also under transverse stress. Each of these methods claims to possess certain advantages. The expanded metal system belongs to the latter class, in which the expanded metal acts entirely in tension and is distributed through the tension side of the slab or beam. The metal should be placed as far as possible from the neutral axis where its moment of resistance is greatest, and at the same time be thoroughly imbedded in the concrete. In order to develop the full strength of steel it is also necessary that it should be held in place by some means possessing greater strength than the cohesion between the steel and the concrete.

Expanded metal is made from sheet steel cut with the grain, and expanded into diamond-shaped meshes, greatly increasing the original size of the sheet without any waste of material. Expanded metal lathing is made from the lighter gages of steel, Nos. 27 and 24, and is expanded only about three times the size of the sheet of steel. This lathing, besides being substituted for wooden laths, is used in the construction of fireproof partitions and outside walls. It is also almost exclusively used for the framing of cornice and ornamental plaster work. The metal generally used in floors is No. 10 or No. 4 gage, the short diameter of the diamond mesh being 3 and 6 inches respectively, making the finished product from eight to twelve times wider than the sheet of steel. This gives for each foot in width a sectional area of .168 square inch for the 3-inch mesh, No. 10 gage, and .282 square inch for the 6-inch mesh, No. 4 gage metal.

For fireproof floors cinder concrete is largely used, on account of its lightness and its great resistance to fire. Tests show that it

*Manuscript received January 2, 1901.—Secretary, Ass'n of Eng. Soc's.

is superior to either stone concrete, tile or brick work laid in Portland cement mortar. It weighs 100 pounds per cubic foot, and has an average crushing strength of 1200 pounds per square inch, mixed in the proportion of one part cement, two parts sand and five parts cinders. Where we require greater strength Portland




FIG. 1. RETAINING WALL AT THE NEW DOCK FOR THE JOINT USE OF THE F. R. R. CO. AND THE UNITED STATES NAVY YARD, BOSTON, MASS., SHOWING THE USE OF CONCRETE AND EXPANDED METAL.

cement stone concrete is used with heavy expanded metal. For this construction tight wood centering is put up between floor beams so that the concrete can be properly tamped, and the expanded metal is placed directly on the centers. The shape of the metal is such that it touches the centering at only one point in each

mesh, which allows space for the concrete to be worked in and around the meshes, thoroughly imbedding the metal. In joining one sheet of metal with another it is necessary only to lap the sheets




FIG. 2. COVERED WATERWAY.




Fig. 3.

SECTION OF PROPOSED CONDUIT FOR NEW JERSEY WATER CO.

from 6 to 12 inches, and the concrete will bond them together so securely that the metal will break before they can be pulled apart. The shape of expanded metal is such that it cannot slip or be pulled through the concrete. Concrete and metal have to work together;

no sudden shock or continued vibrations can break their bonds. A great advantage in expanded metal is that it gives tensile strength not only lengthwise, but also transversely. It forms a blanket system, distributing the load in all directions, the whole acting as a monolithic structure.

When steel is properly imbedded in Portland cement concrete or plaster, we may feel sure that it will not rust. The expansion and contraction of steel caused by changes in temperature is practically the same as that of concrete. Combined in one structure,




FIG. 4. EXPANDED METAL AS USED TO REINFORCE ARCH OF SEWER.

steel and concrete act so well that the expanded metal system has a wide field, and it is interesting to note the different designs where expanded metal can be used with a saving of material.

The walls of wooden and steel frame buildings are built of 2 inches of Portland cement and expanded metal lath. Large tanks and cisterns have been built with expanded metal and concrete. Sidewalks, floors and highway bridges, foundations in quicksand, conduits and sewers, coverings for reservoirs, flat arches and many other designs can be successfully built with this construction, and money saved by so doing.

The question arises, How much does expanded metal increase the strength of a concrete structure? Where crushing strength

only is required expanded metal does not add materially to the strength of the concrete, but in any structure that is subject partly to tensile strain expanded metal may be used with great advantage to develop the full compressive strength of the concrete. Load a concrete beam, for example. It gives way when the ultimate tensile strength is reached, which is possibly one-eighth of the com-





FIG. 5. LOAD SECTION OF CULVERT.



NO 8 SYSTEM

FIG. 6.

pressive strength of the same material. If by the introduction of a light rod or sheet of expanded metal we can make the beam stand until the ultimate crushing strength is reached, we have increased the strength of the beam at least eight times.

I will give the results of a few tests of the expanded metal system, that will prove all we can say for the strength of the combination. In most of these tests on flat floor slabs, tabulated below, the spans are short, but it is only a question of greater thickness of

concrete and heavier metal for equal strength on longer spans; and formulæ are now in use by which we design the composite structure with the same confidence that we have in designing wooden or steel structures.

TESTS OF CONCRETE AND EXPANDED METAL FLOORS. FLAT SLABS, SUPPORTED ON I BEAMS.

No. of Test.	Span.	Thickness.	Mixture of Concrete			Days Old.	Equiv. Dist. Load per Sq. Ft.	Deflection.	Size of Metal.	REMARKS.
			C.	Sand.	Cinders.					
1	4' 1½"	3"	1	2	5	30	2333		3" Mesh, No. 10 Gage.	Cement used in all these tests was American Portland. Test made on same slab as above.
2	4' 1½"	3"	1	2	5	31	2354		"	
3	5' 2"	3½"	1	3	6	30	775	16"	"	
4	4' 6"	3½"	1	2½	5	30	1750	None	"	
5	6' 0"	3½"	1	2	5	30	1100	14"	"	
6	6' 0"	4"	1	2	6	28	850	16"	"	This floor had 1" granolithic finish.
7	5' 4"	4"	1	3	6	30	914	16"	"	
8	5' 4"	6"	1	3	6	30	914	None	"	
9	11' 0"	6"	1	2	5	30	300	61"	2 Sheets, 3" No. 10.	When load was removed, 3¼" deflection remained.
10	4' 0"	2½"				30	20	Broke	No Metal.	
11	4' 0"	2½"				30	250	"	3" Mesh, No. 10 Gage.	

DESCRIPTION OF TESTS.

Test No. 1. The slab tested was a panel selected from floors built in an eight-story building. The mixture of the concrete was one part Alpha cement, two parts sand and five parts cinders, and when tested was thirty days old. In section it was like Fig. 8. The I beams supporting the slab were 4 feet 1½ inches on centers; thickness of concrete 3 inches, with one sheet 3-inch mesh, No. 10 gage, expanded metal imbedded in the lower part. The testing began by loading a platform 4 x 12 feet with pig iron. No deflection was perceptible until 13 tons had been put on, when there was a deflection of 1½ inch. It then increased under the loading as follows:

Tons.	Deflection
17½	3 32 in.
20	1 8 "
25	3 10 "
30	1 4 "
35	5 10 "
44½	3 8 "
48	9 10 "
58½	11 10 "

After twenty-four hours the load was removed and the floor returned to its original position, which shows considerable elasticity of the combination.

Test No. 2. This test was made the following day on the same slab as test No. 1 by loading a plank 12 inches wide, 9 feet 6 inches long, placed lengthwise in the middle of the bay. A total load of 23 tons was applied, with a deflection of $\frac{5}{8}$ inch. The slab gradually settled down and broke, resting on a false floor which had been placed 3 inches below. A final test on this slab was made by dropping a weight of 185 pounds (18 inches square on the end) 11 feet upon the broken slab, after the false floor had been removed, without apparently doing further damage. This floor was designed to carry a breaking load of 1600 pounds per square foot, and the tests showed over 40 per cent. increase of strength.

All of the tests tabulated, excepting Nos. 10 and 11, were made upon sections of floors selected by the architect or engineer from




FIG. 7.

buildings under construction, and therefore give a fair and practical idea of the strength of expanded metal and concrete flat slab coverings for floors, roofs, etc.

Without giving more details than are shown by the tables for tests similar to No. 1, we will compare Nos. 10 and 11. In both these slabs the concrete came from the same "batch" or mixture, and both were allowed to set under like conditions; so without doubt the average crushing strength of each per square inch was the same. In No. 10 the slab was composed of concrete alone, and broke under a uniformly distributed load of 26 pounds per foot. In No. 11 the concrete slab of same thickness as No. 10 contained one sheet of 3-inch mesh, No. 10 gage, expanded metal imbedded in the lower or tension side of the beam, and broke under a uniformly distributed load of 256 pounds per square foot. This shows that the metal increased the strength of the concrete beam about ten times.

In Fig. 3 we have a cross-section of a concrete and expanded metal conduit built by the New York Expanded Metal Company as

an experimental section for the Jersey City Water Supply Company from design of Mr. R. Godfrey, civil engineer. The concrete below the springing of the arch was composed of one part Nazareth cement, two parts fine stone screenings and sharp sand and four parts of crushed stone; the portion above the spring line was composed of one part cement, two and one-half parts screenings and sand and five parts crushed stone. When the concrete was seven days old the centering was removed, and at the age of twenty-one days the concrete structure was tested. Fig. 5 is from a photograph of the loaded 12-foot section. Twenty-five tons of steel rails were placed upon three wooden saddles fitted on the crown of the arch 6 feet apart. Slight cracks were developed at points marked a, b, c in Fig. 3. About one ton of steel rails was afterward twice dropped 11 feet upon the loaded section, and the cracks were slightly widened, which, with a total deflection of $\frac{7}{16}$ inch, was the only change in the structure. The results from the above test



FIG. 8.

were so favorable that the writer has since built a similar conduit for the Massachusetts Chemical Company, at Walpole, Mass. A wheel pit 33 feet deep and 15 feet in diameter, with an 8-foot diameter inlet and an arched tail-race 15 feet in diameter, are now under construction for the same company. The walls of the wheel pit are 18 inches thick at the bottom, and reinforced with expanded metal. The flume deck, carrying a weight of 20 feet of water, and the floor of the generator house above are concrete and expanded metal flat slabs supported on I beams similar to our No. 3 system, shown in Fig. 8. The tail-race is to be built part of the distance in a trench 22 feet deep, with the following dimensions: Span 15 feet, rise 18 inches, concrete 6 inches thick at the crown and increasing to 8 inches thick at springing. One sheet of expanded metal, 3-inch mesh, No. 10 gage, is imbedded in the concrete to give the tensile strength where required.

Mill engineers are becoming interested in the possibilities of concrete and expanded metal construction, as it may be applied to their work. One of the large pulp mills in Maine has recently accepted our designs for concrete and expanded metal bleaching

chests. They are circular, about 14 feet in diameter and 20 feet high; the walls at the bottom 6 inches thick, with enough expanded metal imbedded in the concrete shell to give it the necessary strength when filled to the top with water.

Entire buildings are now made of cement and concrete on wooden or steel frames, and are practically fireproof. Many owners carry no insurance, and when insurance is carried the difference in rates warrants the extra expense of concrete construction over wood.




FIG. 10.

In Fig. 9 are sections of outside walls, partitions, etc., as built with expanded metal and Portland cement.

A reservoir has lately been covered over with a flat slab or blanket of concrete and expanded metal, and was supported only by piers about 12 feet on centers each way. This made a simple and easily constructed covering only 7 inches thick, which did not require such expensive centering as is necessary with the groined arches.

There is a growing demand for concrete structures, and I have tried to show by these few tests and remarks that expanded metal of the right shape and strength, properly used with concrete or plaster, will give a maximum strength with a minimum amount of material, and is applicable to many cases where concrete alone could not be used.



chests.

high; the
metal in
strength

Enti

wooden
owners c
ference in
over woc



107



In F
with exp
A re
blanket c
by piers
and easil
require s
arches.

The
have trie
metal of
or plaste
of mater
could not

Description of Ransome System of Concrete Steel Floors.*

BY M. C. TUTTLE, OF THE ABERTHAW CONSTRUCTION COMPANY

In order to properly understand the strength of the concrete steel arch, or, more correctly, beam, it is necessary to first consider the principle of the combination of the steel bar with the concrete. Square bars of steel are gripped by the ends, and are twisted cold until the angle made by the edge with the axis of the bar is about 20° . The bar thus becomes a long screw. The mortar of the concrete imbeds itself in the concave whorls of the bar, and, when set, in order to remove the bar an area of concrete must be sheared off equal to the superficial area of the cylinder inclosing the bar. In addition, some portion of every face presents a resistance to drawing through the concrete in a direction inclined to the axis of the bar. One component of this is a compressive resistance. Thus the bar is thoroughly and rigidly held throughout its entire length, so that it cannot stretch or draw, and can at no point bring upon the concrete a concentrated stress greater than it can bear.

Thus for practical purposes the bond of union is perfect, and the composite beam can be figured accurately by using the steel as a tensile member and the concrete as a compressive member. The common formula, which is sufficiently accurate for all practical work, is obtained by equating the external force $M = \frac{LS}{8}$ (giving the bending moment in the beam for a uniformly distributed load) against the internal force of the working stress of the bar into the arm between it and the center of gravity of the upper third of the concrete, which is the compressive portion of the beam considered. Equating these gives the formula $f = \frac{LS}{6\frac{2}{3}D}$. Wherein f is the fiber stress in the bar in pounds per square inch, L is the total load on the beam in pounds, S is the span in inches and D is the depth of beam from its top to the center of the bar. As cold twisting of mild steel increases the tensile strength and raises the elastic limit from 10 to 15 per cent., there is no appreciable error in increasing the denominator 5 per cent., changing $6\frac{2}{3}$ to 7, which makes a simple formula for actual use $f = \frac{LS}{7D}$. Numerous experiments show that there is greater strength in the actual construction than is indicated in the formula, which nominally gives a factor of from 4 to 5.

For short spans, say up to about 10 feet, we use a flat slab of concrete with the rods imbedded in the lower surface. It will be

*Manuscript received December 5, 1900.—Secretary, Ass'n of Eng. Soc's

seen that the tensile members of the slab run in straight lines, and this is an important advantage of our construction over those which employ a metal mesh, for where heavy loads or long spans necessitate an increase in the depth of the slab we can core out between the lines of stress, and thus, while retaining the depth and strength,




FIG. 1. DESIGN FOR FLAT SLAB FLOOR, RANSOME SYSTEM.




FIG. 2. DESIGN FOR FIRE-PROOF FLOORS, RANSOME SYSTEM.

can decrease the weight of the slab. This construction gives an absolutely fire-proof and rust-proof floor, which is capable of carrying large loads over long spans. It will be observed that the bar is thoroughly encased in the concrete, but nevertheless it is never more than 2 to 3 inches from the lower surface. Experiments by

Mr. E. L. Ransome, by those interested in the Monier and Melan systems and by Professor Bauschinger, of the Munich Technical High School, all prove that concrete affords a thoroughly trustworthy means of protecting steel against rust.

Fig. 1 shows the construction of a flat slab floor. Fig. 2 shows a section of floor where the concrete has been cored out between the bars which form the tensile members of this construction. Going




FIG. 3. DESIGN FOR ROOF OF SEPTIC TANK. ISOMETRIC VIEW OF TYPICAL BAY.


Safe Superimposed Load, including 2 ft. Earth Fill = 250 lbs. per sq. foot. Weight on each Pier with Full Load = 15 tons. Load on soil 3 tons per sq. foot. Girders, each half, 6" x 15" + 1 1/4" bar. Beams 3" x 10" - 3/4" twisted steel bar. Slab 3" thick with 1 1/4" twisted bars 10" center to center. Piers 12" x 12" x 10' long. Footings 2' 3" x 2' 3" x 12" thick. Bays, 12' x 8' 6" on centers.

one step further, we build floors with concrete girders. The concrete beams head into these girders. Fig. 3 is an isometric view of the roof of a septic tank designed on these lines.

Probably the best example of Ransome construction is the building of the Pacific Coast Borax Company, at Bayonne, N. J. In plan the building is about 75 feet by 200 feet, and is four stories

in height. The floors take their bearing on concrete columns 18 inches square and upon the walls. The floor bays are 12 x 24 feet. The floors were designed for carrying loads of 500 pounds per square foot, besides supporting jarring machinery; but they are often entirely covered with borax to a load of 1000 pounds per square foot.

As regards the strength of this construction: In the police court building at Chelsea, Mass., we built a flat slab $4\frac{1}{2}$ inches thick which had a clear span of 14 feet 8 inches between supports, reinforced by $\frac{3}{4}$ -inch bars 6 inches apart between centers. It was designed for a live load of 100 pounds per square foot. Some ques-




RANSOME FLOOR CONSTRUCTION, EDISON ILLUMINATING CO.'S POWER PLANT,
PATERSON, N. J.

tion was raised as to its strength, and in order to reassure the doubters we put 40 barrels of cement three tiers high on the center of the span, giving a load equal to 200 pounds per square foot uniformly distributed. There was no apparent effect on the slab.

In 1897 the Building Department of the city of Boston made a test of a beam floor which spanned 15 feet. The beams were figured to carry 125 pounds per square foot, which equaled two tons each. The Building Department loaded one beam with six tons on the middle 13 feet. The deflection was 3-16 inch. This load remained on for three weeks, and the deflection disappeared when the load was removed.

At this building we constructed over an area a driveway with a span of 12 feet between supports. The thickness between the upper surface and the bottom of the concrete beams is about 12 inches. This driveway is subject to the usual jarring and pounding wear of a roadway. Heavy loads of flour are taken over it daily, and 4-horse loads of machinery have been hauled over it repeatedly. It is in as good shape to-day as the week it was built.


A specimen of our floor was tested by Professor Edward F. Miller, of the Massachusetts Institute of Technology. The concrete slab was 4 inches thick, 5 feet wide and 14 feet long, and was supported by 6-inch I beams spaced 4 feet 7 inches on centers.



RANSOME FLOOR, EDISON ILLUMINATING CO.'S POWER PLANT, PATERSON, N. J.

There was no side support. The specimen was 21 days old when tested. Imbedded at the bottom of the slab, and 6 inches apart on centers, were pieces of 3-inch square twisted steel. The slab was designed for a load of 500 pounds per square foot. One end span of the slab was first tested by piling bricks on it until it was loaded with a uniformly distributed weight of 480 pounds per square foot. Under this load the center deflection between the I beams was 3.32 inch. The load was then increased to 724 pounds per square foot, and the deflection under this load was 5.32 inch. With the maximum load still remaining on the first span, the second span was tested by dropping a stick of spruce timber, weighing 104½ pounds, from a height of 7 feet 10 inches so that it struck on

end in the center of the span. Five blows in all were struck in this way. Three of them were at an angle. The last two blows were fair, and both struck in the same space at about 20 inches from the I beam. No cracks were noticed after this. The third span was tested by setting a jack under an upright and turning it until a load of 7700 pounds was brought on an area $\frac{1}{4} \times 9$ inches. At this load a slight crack appeared, and the specimen gradually failed. The middle span was then loaded across the center through an I beam having a bearing surface $3\frac{1}{2}$ inches wide and 5 feet long. The maximum load put on at the center was 20,700 pounds, which equals



1900 pounds per square foot uniformly distributed, and the deflection at the time the first crack appeared at the bottom was 11-16 inch.

In our opinion, the most notable example of the strength of concrete steel floors is that of the Edison Electric Station at Paterson, N. J. Here the concrete floor has girders 9 $\frac{1}{2}$ -foot span and beams 12 $\frac{1}{2}$ -foot span, 18 inches in depth, united at the top by a panel 4 inches thick. The girders are supported by brick piers 20 inches square. A counter-shaft about 100 feet in length is bolted down to the panel of this floor; with 22 belts, two connected with 750 horse-power engines, the others driving dynamos, all pulling on one side. All the dynamos rest on the floor at any convenient point. Quite a number of compound engines of the vertical type are supported by two A frames bolted down to the floor, which in turn is supported

by long brick piers. The main shaft is about 18 feet in length, having a heavy fly wheel, and the armatures of two large dynamos wound on it, and supported by two pillow blocks which are bolted down to the 4-inch panel in the middle of the $12\frac{1}{2}$ -foot span. These engines run very smoothly, and there is scarcely a perceptible tremor when standing in contact with the pillow block while the engines are running.

There are many other applications of this system, such as the construction of walls, chimneys, arch bridges, retaining walls, etc. We have confined our description only to the so-called flat arch floor.

Tests of Roebling Fireproof Floors.*

BY ANDREW W. WOODMAN, C. E.

IN the many tests that have been made by the Roebling Construction Company on concrete floors as installed by them in modern, first-class buildings, the question that has always received the most careful consideration is the fire-resisting quality of the construction.

Incidental to these fire tests, however, there have been made a large number of load tests, which have demonstrated beyond a peradventure the fact that Roebling Standard Floor Construction will meet the requirements of the most exacting building laws.

As the subject of fireproofing is not the one under consideration, the records that will be here given relate only to the action of the arches tested under load.

The "Roebling Arch" consists of cinder concrete composed of 1 part high-grade Portland cement, $2\frac{1}{2}$ parts coarse, sharp sand and 6 parts clean steam cinders, laid on a permanent stiffened wire center which is sprung between steel beams.

This wire center is made of a wire netting having round steel rods woven in at frequent intervals, the size of rod depending upon the span and rise of the arch. The wire is woven with 4 meshes to the inch in one direction and $2\frac{1}{2}$ to the inch in the cross-direction. The stiffening rods are curved to the form of the arch, and are made of such length that at each end they project about 2 inches beyond the edge of the netting, so that when the concrete is laid there will be a good bearing of concrete on the lower flanges of the beams. After the center is sprung between the beams it is held in position by means of rods laid parallel to the axis of the arch and securely laced to the stiffening rods.

Fig. 1 shows such an arch with the cinder concrete filling in position and with a suspended wire lath ceiling attached to the lower flanges of the beams. This form of construction is well adapted for use in warehouses where provision must be made for heavy loads. In such cases a modified form of the arch, omitting the level ceiling and completely incasing the lower flange of the beam, is very extensively used. A section of this form of construction is represented by Fig. 2, and a photograph showing its appearance when finished is reproduced in Fig. 3.

The arch form of construction is somewhat more expensive than many of the lighter forms of fireproof floors, and, to meet

*Manuscript received November 24, 1900.—Secretary, Ass'n of Eng. Soes.




FIG. 1.




FIG. 2.

the competition of these cheaper floors, the Roeblings have developed a form of flat construction such as that represented by Fig. 4. This consists of a light steel framework imbedded in cinder concrete. The framework is built of steel bars placed on

edge, twisted at the ends and clamped tightly over the flanges of the supporting I beams, and braced or bridged throughout by means of steel spacers placed about 2 feet on centers. Underneath this light framework is placed either a permanent center of




FIG. 3

stiffened wire cloth or a temporary wood center, on which is laid the cinder concrete. Such floors are built with spans up to 10 feet, but the long spans are intended for only light, live loads.

With this brief description of forms and methods of construction, the reports of tests which follow will be more readily understood.

TESTS OF FLAT CONSTRUCTION.

Test I. An isolated section 4 feet wide, 8 feet between beams and $3\frac{1}{2}$ inches thick, with framing consisting of 2 x 3-16 inch bar, 16 inches on centers, was loaded at the center, the load being placed on a 12-inch plank across the slab. Under a load of 4000 pounds, which was equivalent to 250 pounds per square foot, the deflection was $\frac{1}{8}$ inch. Under 5200 pounds, which was equivalent to 325 pounds per square foot, the deflection was $5\frac{1}{8}$ inch.

In this test the beams were not held rigidly in place, and the test was not carried to the destruction of the slab.

Test II. On a continuous floor where the span between beams was 9 feet $8\frac{1}{2}$ inches, a room 7 feet 8 inches from wall to plaster partition was loaded up to 106 pounds per square foot. The framing consisted of 2 x 3-16 inch bars, 16 inches on centers, so placed that the bottoms of the bars were about $3\frac{1}{2}$ inches below the top of the concrete. A brick wall had been built on the beam at outside of building, so that it was impossible to clamp the bars over this beam as is customary. There was a hole in the floor about 1 foot square, 1 foot from the plaster partition and close to the inside beam. Eight layers of furring tile, amounting to 106 pounds per square foot, were placed free of walls, partitions and girders, covering a space 7 x 8 feet.

Under this load the deflection was 3-64 inch. In the original design of this particular building 5-inch beams were specified, which, on 9 feet $8\frac{1}{2}$ -inch span and under a 50-pound live load, would deflect about 5-16 inch, which is close to the limit on this span for the safety of the plastering.

Test III. At a building in Montreal where the spans were 15 feet $7\frac{1}{2}$ inches, a section 4 feet 5 inches wide was isolated by cutting with cold chisels. The slab was $8\frac{1}{2}$ inches thick and was framed with 2 x 3-16 inch bars placed 12 inches on centers. This was loaded with sand in wooden boxes, covering an area 15 feet 2 inches x 4 feet 2 inches. Loads and deflections were as follows:

With a load of 90 pounds per square foot the deflection was $\frac{1}{8}$ inch.

With a load of 120 pounds per square foot the deflection was 3-16 inch.

With a load of 180 pounds per square foot the deflection was $\frac{1}{4}$ inch.

It is interesting to note that under this load a 12-inch beam, designed in accordance with the Boston building laws, would deflect about 11-32 inch. The load was left standing one hour, then increased to 275 pounds and left standing over night. The




FIG. 4.

total deflection was 7-16 inch. On removal of the load the floor immediately returned 3-16 inch, leaving thus a permanent deflection of $\frac{1}{4}$ inch.

Test II.* This same slab was subsequently tested with a sand load in a 4 x 5-foot box on the center of the span.

Amount of Sand in Box.	Deflection.
1' 0" high	Not appreciable.
2' 0" "	1/16"
3' 0" "	1/8"
4' 0" "	5/32"
5' 2" "	1/4"
5' 8" "	1/4"

This amounted to 10,170 pounds or the equivalent of about 300 pounds per square foot. The load was left standing twenty-four hours, after which time, as there was no further deflection, it was removed.

TESTS OF ARCH CONSTRUCTION.

Test I'. A floor forming the top of a brick fire-test structure 11 x 15 feet inside was first fired, then drenched with water from a fire hose and then loaded. The arches were 10 inches deep, 3 inches thick at crown, on 10-inch I's, 3 feet 10 $\frac{3}{4}$ inches on centers. The center one of three bays was loaded with 150 pounds per square foot and the structure was then fired. Temperatures ranging from 2000° F. to 2550° F. were recorded after the fire was well under way. After two hours the fire was quenched with a stream of water, and on a subsequent day the center arch was loaded to 186 pounds per square foot. Deflections under this load were not recorded.

Test II. The form of construction as described in Test V, with 4-foot spans, was submitted to a five-hour test where the temperature reached 2300° F. as a maximum. The center arch was loaded with 150 pounds per square foot before the structure was fired. A fire stream from a 1 $\frac{1}{8}$ -inch nozzle, under 60 pounds pressure, was applied after five hours, at which time the temperature was 1950° F. Ceilings and walls were wet for fifteen minutes, then the top of the floor was flooded for seven minutes, after which time the fire on the grates was quenched. After the fire test the center bay was loaded with 600 pounds per square foot, with a resulting deflection of $\frac{1}{2}$ inch.

Test VII. A section of arch that was in the five-hour fire test previously recorded was subsequently loaded with a view to determining its ultimate strength. A portion of the arch 4 feet long was isolated by cutting through the concrete and the center space 2 $\frac{1}{2}$ x 4 feet was loaded. The beams supporting the arch were shored up to prevent deflection. The deflection of the arch was measured under various loads.

Under 10,500 pounds it was 0.06 inch.

Under 19,900 pounds it was 0.2 inch.

Under 24,420 pounds it was 0.245 inch.

Loading was continued until the pile was about 12 feet high, weighed 40,550 pounds and was becoming unstable owing to the small area on which the load was supported. Three men then went on top of the pile to commence unloading. At this time, under a load of about 41,000 pounds, or 4100 pounds per square foot of loaded area, the deflection of the arch was $\frac{3}{4}$ inch. After the load had been removed it was found that the permanent deflection was $\frac{5}{8}$ inch.

Test VIII. A 5-foot Roebling arch on 10-inch beams, 12 feet long between brick walls, was loaded in the center with 10,000 pounds of pig iron placed on an area of 7 square feet and subjected to a fire test. Alongside this arch was a similarly loaded tile arch of 10-inch hard-burned terra cotta, made from material that had been delivered at a building in course of erection. At the expiration of four hours and five minutes the 10,000 pounds of pig iron fell through the tile arch and stopped the test.

Test IX. A 5-foot Roebling arch 14 feet long was built alongside a 5-foot arch of 8-inch semi-porous tile, and each arch was loaded with 150 pounds per square foot. The fire test lasted three hours and sixteen minutes, after which time the tile arch collapsed.

The deflections previous to failure of tile arch were 3.65 inch on the tile floor and 1.4 inch on the concrete floor.

Test X. Sections of arch 12 inches long were cut from the floor tested as described by Test IX, and loaded by means of a hydraulic cylinder on the center of arch. One section failed at 3000 pounds, and a second failed at 3200 pounds. A section of the same floor 46 inches long, and similarly loaded, broke under a center load of 11,900 pounds.

Records of other tests describing the action of Roebling arches under various conditions of loading might be given, but the limits of this paper will not permit. Such as are herein given relate only to strength, and omit much that from the standpoint of fireproofing would be of great interest; but it is hoped that these will suffice to demonstrate the suitability of Roebling floor construction for modern building work, so far as the question of strength is concerned.

The use of the Roebling arch in bridge floors has never received much attention, but from the report on the strength and cost of the brick and concrete arches described in the paper on "Tests of Brick and Concrete Arches," it would appear that the field might be entered with advantage.

A REVIEW OF CONCRETE-METAL CONSTRUCTION.

BY CHAS. M. KURTZ, MEMBER TECHNICAL SOCIETY OF THE PACIFIC COAST.

[Read before the Society, March 1, 1901.*]

As indicated by the title, the nature of this paper is that of a review of progress along this line, as found in the various articles that have from time to time appeared in the engineering publications.

This paper might also be considered supplementary to the paper found in the transactions of this Society, written by our esteemed late president, Mr. G. W. Percy, which paper was read before this Society January 6, 1888, and entitled "Practical Applications of Iron and Concrete to Resist Transverse Strains."

In this paper Mr. Percy reviewed the applications of iron to concrete beams as invented by Thaddeus Hyatt and by E. L. Ransome. Stated briefly, Mr. Hyatt's method consisted in imbedding a skeleton of iron in the shape of a gridiron near the bottom of the concrete beam or slab, the principle of the construction being that the iron, used in the lower flanges of the beams, would serve only as the tie or tensile member, while the concrete formed the compression member and connecting web. His tests demonstrated that iron could be perfectly united with concrete so as to work in unison with it and form a compound beam or girder.

Mr. Ransome's method consisted in the substitution of square bars of iron or steel, twisted cold, instead of the iron frame of Mr. Hyatt's invention, to be imbedded near the bottom of concrete girders or flat slabs. This application of iron to concrete, though modified slightly in arching the beams transversely between the rods, has been used extensively and successfully in sidewalks and roofs.

Before describing the different systems, a few remarks will be made on the elasticity of concrete, the adhesion between concrete and iron, and the behavior of concrete as the preservative of iron.

Elasticity. As will be mentioned later, the elasticity of concrete has been practically demonstrated by the tests of the Austrian Society of Engineers and Architects,[†] and by numerous other tests; consequently, in combination of concrete and metal, both materials deform equally when subjected to a stress, and there-

*Manuscript received March 7, 1901.—Secretary, Ass'n of Eng. Socs.

[†]Oesterreichischer Ingenieur- und Architekten-Verein.

fore their stresses are as their relative moduli of elasticity. Mr. Thacher, in his formulas, puts the value of the modulus of elasticity of concrete at 1,400,000 pounds and that of steel at 28,000,000 pounds. The Austrian Society determined the value of the moduli of the elasticity of steel, concrete and mortar as follows:

For steel, 20,700,000 to 31,400,000 pounds.

For concrete, 1,400,000 to 4,000,000 pounds.

For 1:3 mortar, 5,000,000 to 6,000,000 pounds.

Expansion. M. Benneceau, a French author, gives the thermic expansion of Portland cement as 0.0000143 Celsius, while iron has 0.0000145.

Adhesion. It has been well demonstrated that there is a strong adhesion between concrete and iron. This great adhesion is attributed to a chemical connection between the silicates of cement and steel. Professor Bauschinger found the adhesion between mortar and iron to be between 570 and 640 pounds per square inch.

To determine values of the adhesion between iron and cement mortar, Mr. W. A. Hoyt, a student at the University of Wisconsin, last year conducted a series of experiments to determine the stress per square inch of metal surface required to pull imbedded bolts from the mortar. He experimented with polished bolts, rusty bolts, bolts with normal surface and bolts that had been coated with a neat cement mortar before being imbedded in the concrete. While his experiments were not entirely satisfactory, on account of a lack of uniformity in the sand used (which, however, is something liable to happen in practice), the average results of his tests are as follows:

Age of concrete, ten weeks.

Adhesion of polished bolts, 440 pounds per square inch.

Adhesion of rusty bolts, 520 pounds per square inch.

Adhesion of bolts with normal surface, 570 pounds per square inch.

Adhesion of bolts coated with neat cement, 820 pounds per square inch.

Adhesion (average), 588 pounds per square inch.

Concrete as a Preservative of Iron. It has been well proven that cement acts as a preservative of iron and steel, and many instances could be cited showing that iron or steel will not rust when imbedded in concrete, even if the concrete itself be immersed.

The common principle of all concrete-metal construction is that the imbedded metal supplies the quality of tension, a quality which is lacking in the concrete itself, and in return the concrete stiffens the metal.

Other systems besides the Ransome system of concrete-metal construction, which are specially favored in practice to-day, are the Monier, the Wünsch, the Melan, the Thacher, the Hennebique and the "expanded metal" systems. Each of these systems is individually a proper subject for a paper, so the discussion of the several systems will be made as brief as is consistent with a review of this kind.

The most important and popular practice in concrete-metal construction to-day is the reinforcing of the arch ring of a concrete arch by the imbedding of iron or steel in various forms. An arch fails usually by tearing apart near the center at the intrados, and at the haunches at the extrados, the material, at these places in the arch, being unable to withstand the tension to which they are subjected when too heavily loaded.

The most frequent employment of the Melan, Wünsch and Thacher systems is found in the concrete-metal arch. The Monier is the most flexible system, and consequently possesses the greatest




FIG. 1. RANSOME.

variety of applications. The Melan, Wünsch and Hennebique systems are extensively used for floors in Europe, while American practice seems to favor the Monier and modifications of the Monier system and the expanded metal system.

THE RANSOME SYSTEM.

It is a matter of special interest that the first concrete-steel arch built in the United States was constructed on the Ransome system. This arch is in Golden Gate Park, San Francisco, Cal., and was erected in 1889. A second or similar design was erected in 1891. In this system the twisted steel bars are imbedded in the concrete arch ring in pairs, about one foot C. to C., one bar of each pair being near and parallel to the intrados and the other near and parallel to the extrados. The merits of this system are so generally known and recognized, and no doubt, especially so by members of this Society, that further comment on it seems unnecessary.

THE MONIER SYSTEM.

The Monier system, until within the last two years, was practically unknown in this country, but since 1880 it has been applied in a great variety of constructions in Europe. Among these applications may be mentioned gas and water reservoirs, grain elevators, sewer pipe, flumes and culverts, fireproof floors and arch bridges.

In this system the metal consists of a netting of two series of parallel steel or iron rods, $\frac{1}{2}$ to $\frac{1}{4}$ inch in diameter, which intersect at right angles and are generally spaced from two to four inches. At the intersections the rods are bound together with wire $\frac{3}{16}$ to $\frac{1}{2}$ inch in diameter. In arches of this system a netting is imbedded near the intrados and sometimes a second one near the extrados. In the tanks, pipes, etc., the netting is imbedded near the center of the shell.

No attempt to construct an arch of a long span in this system was made until it had been well tested as to its merits by the Austrian Society, and then one of striking dimensions was built at Wildegg, Switzerland, in the autumn of 1890. It crosses an industrial canal at an angle of 45° , and has a total span of 122.1 feet, with a rise of only 11.5 feet, less than a tenth of the span. The bridge is 12.8 feet broad. The Monier arch proper is 7.9 inches thick at the center, and 25.6 inches at the abutments. The span-drel walls were likewise constructed on the Monier principle and are connected at each end by two ties. The abutments are of concrete, and a backing of this material is run up on the arch for some distance, as shown in the cuts. The bridge was required to support a uniform load of 84 pounds per square foot, but on completion it was put to the test for the maximum load it would ever carry as a highway bridge. The tests were very satisfactory. For further description of this bridge see *Engineering News* for May 23, 1891.

As pointed out by Mr. Edwin Thacher, member of the American Society of Civil Engineers, in his paper on concrete-steel bridge construction in *Engineering News*, September 21, 1899, this system has some practical disadvantages. Quoting from this paper: "The wire nets are so flexible and unruly that it has been found impracticable to imbed them in concrete containing coarse aggregates like gravel and broken stone, consequently all the strictly Monier arches that have been built up to this time have been built with 1 to 3 mortar, which, as compared with $1 : 2\frac{1}{2} : 5$ concrete, is weaker and costs considerably more."

The theoretical discussion of a Monier arch or any other concrete-metal arch is a difficult task, on account of the different materials combined, and it is not the purpose of this paper to take up the subject in that manner. Discussions may be found in the "Minutes of the Proceedings of the Institution of Civil Engineers," Vol. CXXXIII, page 376, and in the "Zeitschrift des Oesterreichischen Ingenieur- und Architekten-Vereines," for September 23, 1898.

An excellent descriptive article by Mr. E. L. Heidenreich on Monier construction is found in the *Journal of the Western Society of Engineers* for June, 1900. Mr. Heidenreich enumerates some of the wonderfully diversified applications of the construction,




FIG. 2. MONIER.

among which are reservoirs for storage of water, wine, oil, pulp, grain, cement, etc., bridges and preservation of steel in bridges and viaducts, buildings, floors and partitions, culverts and flumes, fortifications, etc.

One of the most recent applications of the Monier construction is the use of specially constructed pipes for pile covering, to protect the pile against the attacks of the teredo navalis, or cobra. This method of protecting piles was used in constructing five timber piers for a traffic bridge near Sydney, New South Wales (each pier consisting of a bent of three piles), and is described by Mr. E. M. De Burgh, member of the Institution of Civil Engineers, in a paper in the "Proceedings of the Institution of Civil Engineers." An extract of the paper appears in *Engineering News*, February 7, 1901. Briefly described, the method was this:

After a pile, having been previously coated with Stockholm tar, had been driven, sufficient length of the pipe to reach from below the silt and into the clay, to above high water, was slipped over the top of the pile and sunk to a proper depth by means of a water jet being worked around the bottom, and pressure being applied at the top by means of screw-jacks. Mr. De Burgh is satisfied that it will prove of great durability and outlast the pile, which, being iron-bark, may be counted on for a life of thirty years when protected from the teredo. The cost is estimated between 50 and 100 per cent. greater than that of coppering. The same paper also gives an account and description of Monier cylinders being used for foundations as a substitute for the cast iron cylinders used largely in New South Wales. That concrete-metal in sea water is a complete success is questionable. Experiments on the action of sea water upon concrete-steel show that electrolytic actions take place which cause deterioration of the steel or iron. See *Ann des Ponts et Chaussées*, Fourth Quarter, 1899.

THE WÜNSCH SYSTEM.

The concrete-metal arch known as the Wünsch system was invented by Robert Wünsch, of Hungary, in 1884. In this system, arch ribs of metal, consisting of an arched lower and horizontal upper member, both of which are run together and riveted at the crown, are imbedded in the concrete. The two members of the rib are connected at the piers and abutments by vertical and transverse lower members deeply imbedded in the concrete.

In Fig. 4 is shown an excellent example of this construction. It is the plan of a Wünsch arch of 83 feet span,—the longest, up to date, of this system,—constructed in 1897 over the Miljacka River at Sarajevo. The chords of the metal ribs are made up of two angles, and the vertical and transverse members of channels.

When a Wünsch bridge is made up of several spans, as is the case with the one constructed near Neuhausel, Hungary, the horizontal or upper chords of the metal ribs are made continuous from one arch to another. This bridge had six arches, of the following dimensions: Span, 55.8 feet; rise, 3.7 feet; thickness at the crown, 9.8 inches; at the springing line, 54.3 inches. The chords of the ribs were made up of two 3-inch angles spaced 20 inches C. to C. The entire ironwork weighed 88,180 pounds and the amount of concrete was 1346 cubic yards. The total cost was only \$13,700.

In building the arches, after the centering was in position, the iron members were put in place and the concreting began.

The concrete was made of one part Portland cement and six parts of sand and gravel for a layer of 10 to 12 inches thick. The arch concrete was carefully rammed in layers at right angles to radial lines, and especial care was taken in ramming the concrete that came below the arched bottom chords. The centering was left undisturbed for thirty days after the last arch had been finished, and the striking of the centers was commenced at the two center arches. The bridge was tested by the application of a uniform load of 82 pounds per square foot and also by a very heavy live load, the maximum deflection being 0.138 inches and the set 0.031 inches. For further descriptions see *Engineering News*, November 16, 1893.

The Wünsch system of concrete-metal arches does not seem to be an economical design. There is no arch ring proper, but the entire arch, from the under surface to the pavement of the roadway, is a massive monolithic mass of concrete. There are no bridges of this type in the United States.




FIG. 3. MONIER ARCH AT WILDEGG, SWITZERLAND.

THE MELAN SYSTEM.

This style of concrete-steel construction was invented by Joseph Melan, of Austria, in 1892, and was patented in the United States the following year. It consists of curved I beams or lattice girders imbedded vertically in the concrete of the arch ring and abutments. These ribs are sometimes connected transversely at their ends in the abutments by cross angles, and are sometimes provided with individual anchor plates. If the bridge consists of several arches, the ribs in each arch are, in some cases, independent of those in adjacent arches, being connected only by the concrete, but in the large bridge recently built at Topeka, Kan., the ribs were riveted to a common plate at the piers.

The merits of this system were quickly recognized in this country as well as in Europe. The result of such recognition has been the erection of bridges of the Melan type in parks where a handsome and esthetic design was desired, and the displacing of iron and steel truss bridges where *permanence* was the quality desired.

Among the more important of the park bridges of the Melan system constructed up to date is the Melan arch at Eden Park, Cincinnati, designed and built by Fr. Von Emperger, C.E., in 1895. This arch has a span of 70 feet and a rise of 10 feet, and carries an 18-foot roadway and two concrete sidewalks of 5 feet each. The concrete (in the proportion 1 : 2 : 4) is 15 inches thick at the crown and 48 inches at the haunches. The I beams are 9 inches deep, weighing 21 pounds per foot, spaced 36 inches apart, and are supported by a cross-channel at each end. As this arch is an excellent example of the Melan type, its construction will be briefly described.

After the excavation had been made and the false work erected, the bent ribs were laid, splices and cross-angles fastened and the concrete in the abutments started so as to inclose the ends of the ribs. Then wing walls and pillars were built to train the workmen, who were common laborers, paid at the rate of 13½ cents an hour.

The arch was built in two longitudinal halves, each of them started on both sides and closed up to the center in one day of twelve working hours.

On completion of the arch proper and the removal of the boards on the face walls, the filling of the bridge was put in and completed to the level of the coping stone, where the work was stopped for the winter. In the spring the false work was struck and the work completed.

After the removal of the false work the filling was compressed with a 15-ton roller, a very trying test, as the filling at the crown was not more than 6 inches thick over the concrete. See *Engineering News*, October 3, 1895. Other examples of this style of bridge constructed in parks are:

The two-arch bridge at Hyde Park, N. Y., on the estate of F. W. Vanderbilt, designed by the Melan Arch Construction Company and built by W. T. Hiscox & Co., both of New York. For description see *Engineering Record* of January 14, 1899.

The Franklin bridge in Forest Park, St. Louis, Mo., which has a span of 60 feet and a rise of 15 feet 6 $\frac{3}{16}$ inches. The ring is 11 inches thick at the crown, increasing to 30 inches at the springing line, and has imbedded therein eleven 8-inch, 18-pound steel I beams, spliced at the crown and spaced 3 feet C. to C. See *Engineering Record*, December 10, 1898.

The Melan arch at Stockbridge, Mass., designed and constructed by Fr. Von Emperger, C.E. This is a 7-foot foot-bridge of 100 feet span and 10 feet rise. The ring is 9 inches

thick at the crown and 30 inches at the haunches, and has imbedded four 7-inch I beams spaced 28 inches apart and raised 2 inches from the soffit. See *Engineering News*, November 7, 1895.

As examples of the Melan arch built by cities for carrying streets across rivers may be mentioned the concrete-steel arch bridge at Topeka, Kan., across the Kansas River; the bridge at Paterson, N. J., carrying West street across the Passaic River; and two concrete-steel bridges in Indianapolis across Fall Creek at Illinois street and Meridian street.




FIG. 4. WÜNSCH ARCH.

The Topeka bridge is the largest concrete-metal bridge ever built in the country. It was designed by Keepers & Thacher, civil engineers, and consists of five spans,—one 125 feet, two 110 feet and two $97\frac{1}{2}$ feet,—and carries a roadway 26 feet wide and two 7-foot sidewalks. It replaces an old six-span, iron truss structure of considerably greater length. In each span twelve lattice girders placed 3 feet C. to C. are imbedded in the concrete,

by which they are completely surrounded. See *Engineering News*, April, 2, 1896, for further description.

The West street bridge at Paterson, N. J., consists of three arches of 88.25 to 89 feet clear span, each arch having a rise of 9.5 feet. The concrete of the arch rings is 15 inches in thickness at the crown, gradually increasing to 66 inches at the skew backs and imbedding 10-inch I beams weighing 25 pounds per foot, spaced 3 feet C. to C. The bridge was designed by the Melan Arch Construction Company and Mr. Edwin Thacher, member of the American Society of Civil Engineers, and is an example of the adaptability of the concrete-steel arch to locations where the voussoir stone arch is not practical. The latter would hardly have been designed with a rise less than one-sixth the span, with the foundation available at this place, whereas the bridge built has a rise of only 1-9.4 of the span. A voussoir arch at the location would have given either objectionable grades on the approaches, perhaps with considerable property damages, or would have obstructed the river channel with several more piers, to an extent prohibitory. See *Engineering News*, March 16, 1899.

In Indianapolis the Board of Public Works, after considering the replacing of many of the old iron and steel bridges by new structures of a more permanent character, deemed it desirable to construct stone bridges across Fall Creek at Illinois street and Meridian street. It was first contemplated to have these bridges built entirely of natural stone, but in order to insure a greater waterway without greatly increasing the width of the stream it was found to be more economical to construct these bridges on the Melan system.

Both of these bridges are skew bridges, the lines of the piers and abutments making an angle of 70° with the street line. Each bridge is composed of three arches of 74 feet span, the piers being 8 feet wide and the abutments 20 feet. The thickness of the arch rings at the crown is 16 inches and at the piers 60 inches. Ten-inch I beams, 25 pounds per foot, spaced 3 feet C. to C., are imbedded in the concrete of the arches. The beams are bent at the mills to conform to the plan of the arch and were shipped in two sections. After they had been placed in position on the centering they were spliced at the center by means of top and side plates and thoroughly riveted. See *Municipal Engineering* for February, 1901.

A complete list of the Melan bridges built in the United States up to the year 1899 may be found in the *Polytechnic* for March, 1899.

THE THACHER SYSTEM.

This system can best be described by quoting from the article entitled "Concrete-Steel Bridge Construction," written by Mr. Edwin Thacher, member of the American Society of Civil Engineers, in the *Engineering News*, September 21, 1899.

"Steel bars in pairs, spaced at proper distances apart and spliced at convenient intervals, are imbedded in the concrete near the outer and inner surfaces of the arch, and extend well into the abutments or piers. The bars of each pair have no connection with each other, except through the concrete, but each bar is provided with projections, preferably rivet heads of extra height,




FIG. 5. MELAN ARCH.

but which may be lugs, dowels or bolts, spaced at short intervals, thereby providing a mechanical reinforcement of the adhesion between the steel and the concrete, so that a complete crushing or shearing of the concrete must take place before a separation can be effected. The bars act as the flanges of a beam to assist the concrete in resisting the thrusts and bending moments to which the arch is subjected. The shearing stresses are small, and the concrete is amply able to take them many times over." Continuing, Mr. Thacher says: "The principal advantages which this system offers over those previously mentioned may be stated as follows: It gives a larger moment of inertia, and consequently

greater strength for the same amount of steel. In the Melan system I beams are usually used, which, if buried in the concrete, are necessarily less in depth throughout than the depth at the crown, and as the greatest bending moments are always at or near the spring, the use of I beams gives the less strength and reserve of strength where the greatest is needed. If the beam is made of angles with lattice connections, as at Topeka, it is not practicable even then to follow out the lines of greatest strength, as the beams become too deep and unwieldy. A more reliable connection is secured between the steel and concrete than in any system that depends on adhesion alone." Mr. Thacher was granted a patent on his design January 10, 1899.

Mr. Thacher's paper also enters into some of the details of calculations of the Thacher and Melan systems, which I will not repeat here.

The most important bridges of this system constructed up to date are the new arch bridges at Niagara Falls, connecting the mainland with Green Island and the latter with Goat Island. The bridge between the mainland and Green Island consists of three spans, the two end spans being each $103\frac{1}{2}$ feet long, with 10 feet rise, while the center span has a length of 110 feet and a rise of $11\frac{1}{2}$ feet. The arch ring in the end spans is 38 inches thick at the crown and 70 inches at the springing line, and in the center span 40 inches at the crown and 76 inches at the springing line. Imbedded in the concrete, spaced 3 feet C. to C. and 3 inches from the intrados and extrados are pairs of flat steel bars, connected vertically by bolts at intervals of about 32 inches. The concrete in the arches between skew backs is composed of one part Portland cement, two parts sand and four parts broken stone or gravel, which passed through a $1\frac{1}{4}$ -inch ring, including the total product of the crusher between $1\frac{1}{4}$ inches and $\frac{1}{4}$ inch. For the foundation abutments, piers and span-drills the concrete is made in the proportion 1 : 3 : 6. Limestone facing covers the entire structure, including the piers and abutments below water, only excepting the soffit of the arches between the ring stones on each face and that portion of the abutments buried in the banks. In building, the concrete for the arches was started simultaneously from both ends of the arch and laid in longitudinal sections so as to inclose at least two ribs.

This bridge is of great architectural beauty, and adds much to the appearance of the state reservation at this point. For further description see *Engineering News*, December 6, 1900, and *Engineering Record*, February 16, 1901.

Other bridges built on this system are listed by Mr. Thacher in his aforementioned article in *Engineering News*.

THE HENNEBIQUE SYSTEM.

But little information is to be found respecting this system in English or American publications, as its employment in practice has been confined almost entirely to France, and the writer has not had access to the French publication entitled "*Revue Technique*."

In the discussion on Monier construction in the *Journal of the Western Society of Engineers*, June, 1900, the Hennebique system is described by Mr. Ralph Modjeski, member of the Western Society of Civil Engineers, as follows:

"The Hennebique system, which is used very extensively in France, has its principal application in floors of buildings, parti-




FIG. 6. THACHER ARCH.

tions, etc. The rods used here are much heavier than in the Monier system. Two or more of the rods are placed lengthwise near the bottom of the concrete beam, and are tied to the upper portion of the beam and to the floor slabs by thin vertical bars."

"Computations for Ribbed Beams of Iron and Concrete on the Hennebique System," a mathematical treatment of the proportions for concrete girders with imbedded iron rods, is found in the "*Zeitschrift des Oesterreichischen Ingenieur- und Architekten-Vereines*," September 15, 1899.

THE EXPANDED METAL SYSTEM.

Expanded metal has also been successfully applied to concrete in a manner somewhat similar to the application of the netting of rods in the Monier system, both in floors and arch bridges, but principally in floors.

The use of expanded metal in constructing fireproof floors, partitions, etc., is too familiar to require description. Many tests of slabs of concrete-expanded metal have been made in the last

three years. The best literature on these tests and the records of the tests themselves are found in the paper on "Steel Concrete Construction," by Mr. George Hill, associate member of the American Society of Civil Engineers, and in the correspondence and discussion of the same, in the "Transactions of the American Society of Civil Engineers, June, 1898." The results, tables and formulas in the paper and discussions were not entirely satisfactory, and will not be repeated here.

An arch of 21-foot span and 6-foot 8-inch rise, built at Oconomowoc, Wis., for P. D. Armour, Jr., designed by Mr. C. F. Hall, C.E., has imbedded in the concrete arch ring flat rods and a sheet of expanded metal of No. 16 gage, $2\frac{1}{2}$ -inch mesh. See *Engineering News*, October 19, 1899.

OTHER SYSTEMS.

A floor system that has been well tested experimentally by fire and excessive loads is the Roebling system. This system consists essentially of an arch of woven wire netting springing from the lower flanges of the floor beams and covered with a bed of concrete, which is leveled up with the upper flanges of the beams. The netting is strengthened by iron rods at intervals of about nine inches each way, the wires being woven around the rods so as to form one sheet of netting. See *Engineering News*, July 18, 1895. The fire tests are described in *Engineering News*, December 2, 1897.

There are other systems besides those above described, but as they are not important and are not extensively employed in practice, descriptions of them will be omitted.

THE AUSTRIAN SOCIETY TESTS.

This paper would be incomplete without some mention of the tests of brick, concrete, Monier and Melan arches made by the Austrian Society of Engineers. Tests to destruction were made for spans of 4.43, 8.86, 13.3, 52.8 and 74.5 feet. A synopsis of these tests is found in an article by Mr. Mansfield Merriman, member of the American Society of Civil Engineers, in the *Engineering News*, April 9, 1896. A more complete report appears in *Engineering* (London), February 21, 1896. These tests demonstrated that the theory of elasticity gives the only solid foundation for theoretic investigations, since the deformations were practically proportional to the stress in all cases where the elastic limits were not exceeded.

MISCELLANEOUS APPLICATIONS.

A factory building. A large monolithic factory building for the Pacific Coast Borax Company at Constable Hook, Bayonne, N. J., was designed and constructed by Mr. E. L. Ransome in 1898. The structure is built entirely of concrete reinforced by steel rods. The design embraced the construction of solid concrete floors, supported on reinforced concrete beams and joists and carried by hollow concrete walls and solid concrete columns and beam-piers in the hollow concrete walls. The Ransome system is employed throughout. See *Engineering Record*, July 30 and August 20, 1898.

Retaining walls. Concrete retaining walls reinforced by imbedded steel of different forms have been designed and built. One employing the Hennebique system was constructed at the




FIG. 7. HENNEBIQUE.

Paris Exposition of 1900. See *Engineering News*, February 15, 1900.

In making excavations for tall office buildings, retaining walls have been constructed of concrete reinforced by horizontal trusses of heavy lattice girders serving to give the wall strength against flexure and transmit the pressure to the ends of the longitudinal walls upon which they abutted. See *Engineering Record*, June 18, 1898.

A concrete-steel retaining wall was built in Columbus, Ohio, in 1900, by Mr. F. A. Bone, engineer of the Oregonia Bridge Company, Oregonia, Ohio. His construction employs the principle on which a tree depends for its stability. "The tensile strains at the back of the wall are transmitted by the metal to the concrete base, which is loaded by the earth and thus held down like the roots of a tree." See *Engineering Record*, November 10, 1900.

Roof of covered reservoirs. A new 25,000,000-gallon covered reservoir now under construction for the Louisville Water Com-

pany has a roof made up of groined concrete-metal arches, the reinforcement consisting of the steel bars of the Thacher system. The arches are supported by the division walls and concrete pillars. The spans are approximately 19 feet with a rise of 3.8 feet, and the concrete is 6 inches thick at the crown and 36 inches at the springing line in radial lines, and are constructed of Portland cement 1 : 2 : 4 concrete. See *Engineering News*, January 10, 1901.

Concrete-steel ties. Steel and concrete ties have been tried experimentally by the Pennsylvania Railroad in Chicago in one of the main tracks. They were in the track ten months and were then removed because of the failure of the device locking the rail to the tie, although 10 out of the total 30 had cracked at the end of seven months. The tie was patented by Mr. C. C. Harrel, of Chicago, but afterward modified by Mr. J. J. Harrell, of Wilmington, Del. As described in the *Engineering News* of January 10, 1901, it is as follows: "The design is a combination of two channel bars, seven feet long, forming the top and bottom of the tie, separated by distance pieces, and braced under the rail seats by vertical and inclined struts between the bars. A short piece of channel iron forms the rail seat, and through this pass the anchor bolts, the heads of which are under the lower channel bar. The whole structure is imbedded in concrete, with the exception of the rail seat. The rail rests on a shim or packing plate and is secured by bolted clamps, filling the rail base and the edge of the channel. The complete tie is 7 feet 8 inches long, 8 inches thick, 5 inches wide at the top and 8 inches at the bottom, the weight being about 300 pounds."

The cost of the ties used was about \$8 each, but it is believed that the cost will be less than \$1 each, if made in any quantity.

COMPARATIVE COST OF CONCRETE-STEEL BRIDGES.

In bidding on a bridge for Junction Hollow, Shenley Park, Pittsburg, Pa., Keepers & Thacher bid on a Melan arch having a clear span of 300 feet with a rise of 66 feet 2 inches, flanked by 70-foot and 61-foot spans, and having a width of 80 feet between parapets. This bridge was 590 feet long and covered 47,200 square feet in clear between stone parapets, erected and paved complete, ready for traffic, and their bid was about \$7 per square foot, only a trifle more than was paid for the steel arch which was accepted and built.

In St. Louis the Council, having appropriated \$5500 for constructing an arch bridge in Forest Park, Mr. John Dean, the

Engineer of the Park Department, prepared a plan for a concrete arch bridge of 60 feet span. Fearing that the appropriation was insufficient to provide for the structure as designed, the design was sent to the Melan Arch Construction Company, of New York. This company applied its system to Mr. Dean's design, inserting steel I beams in the ring and reducing the thickness of the concrete. The contract was then awarded for the work complete, exclusive of the roadway and sidewalk pavements, at a price several hundred dollars less than the appropriation.

A very important feature of the cost of concrete-steel bridges is that their first cost is their only cost,—a great advantage over the steel bridges, which invariably require a constant outlay of money for maintenance and depreciation.

In conclusion, while I realize that this paper has nothing new to offer to the engineering public by collecting and putting together the above data and information, it has been my aim to make something that will be of utility to any one desiring a general knowledge of concrete-metal construction. Considering the great progress in concrete-metal construction and its present popularity, its future seems very promising. Mr. George S. Morrison, member of the American Society of Civil Engineers, is quoted as saying: "I fully believe that we are now only at the beginning of concrete construction, and that, if the results which we hope for can be attained, with concrete structures with metal structures inside, the time will come when this will be the one method of building."

THE STEEL SKELETON CONSTRUCTION OF A TALL OFFICE BUILDING.

BY J. S. BRANNE, ASSOC. MEM. A. S. C. E.; MEMBER OF THE ENGINEERS' CLUB OF ST. LOUIS.

[Read before the Club, November 7, 1900.*]

THE tall, skeleton construction building originated when the modern city grew very large, so that the price of land in the business heart of the city became very high, and in some cases the land to be had was limited. Not being able to expand the building horizontally, it became necessary to increase the number of stories. Up to seven or eight stories, stone or brick walls were used; but when it became necessary to put up a building of, let us say, fifteen stories, it was found very expensive to make such walls of sufficient thickness to sustain the superincumbent load; and the thick walls occupied too much space. Iron, being capable of sustaining a much greater load per square inch than stone or brick, was then introduced as columns, either cast or wrought, carrying the floor loads, and relieving the walls. Afterward a system of wall girders was introduced at each floor, to carry the story height of stone or brickwork, making each story self-supporting and carrying the entire load, through the columns, to the footings or foundations. The walls in all the stories could now be made of the minimum thickness, giving the maximum floor space for each story. The footings for the columns were at first made of stone or brick masonry resting on the soil, where this was solid; and on piles, where soft soil or even quicksand was encountered. Gradually the stone or brick masonry in the footing disappeared, giving way to steel and concrete, developing into our present-day grillage footings, of various kinds to suit various conditions. As the skeleton constructions grew taller, and the wall thicknesses decreased, making the entire structure lighter, the attention of architects and engineers was called to the necessity of giving stability against the overturning tendency of wind. This has been found to be a difficult matter. It is sometimes accomplished by rod-bracing, where this is permissible; in other cases, by horizontal girder construction and knee-braces; and sometimes by regular portal construction between adjoining columns. At present the use of iron in tall building construction has almost disappeared, giving way to steel, which now combines cheapness and strength.

*Manuscript received December 12, 1900—Secretary, Ass'n of Eng. Soc's.

The usefulness of the tall office building is apparent to all. The business or professional man on the ground floor can easily and quickly reach the one in tenth or twentieth story; offices can be had in the most desirable locations of the city at comparatively low rent. Very often certain trades or professions flock to certain buildings, where those engaged in them can easily reach each other for consultation.

We now proceed to illustrate the steel skeleton construction of high office buildings; how the steel work is planned, for a certain width, length and height of a building, and, for a certain lay-out of the buildings, to suit the purposes and ideas of the owner and architect, so as to combine strength and economy.

Under economy it is well to note that quite often the problem is of such a character that a theoretical economy of steel cannot be obtained. For instance, the columns must stand at certain places to




Fig. 1

suit the interior space arrangement of the building, or the irregularities of the lot and the surroundings. Thus more restrictions are laid upon the structural engineer than upon the bridge engineer, who can, generally may, consult only economy in determining the depth of truss or girder, the section of the various members and the spacing of towers or bents in viaducts. To the structural engineer many of these features are laid down in advance; even to the depth of the floor beams, where a few inches in each floor amount to something considerable in a building of several stories.

In the following paper a certain size of building has been chosen and the steel work for it has been determined. By thus referring to a definite set of plans and elevations, each class of work treated can be clearly itemized. Fig. A, Plate 1, shows the front elevation of the building adopted for this paper. The lot is 50 x 100 feet, and the building is 16 stories high in front and 13 stories in rear. The basement is 12 feet deep in front and 15 feet in rear, where the heating and lighting apparatus and the elevator plant are placed. The first story is 17 feet high, and all the

other stories 12 feet high, from floor line to floor line. All the curtain walls (outside walls in building) are 13 inches thick, and inside partitions 4 inches thick, built either of hollow tile or expanded metal furring on vertical channel studding, plastered on both sides. The floor is of concrete, of which several excellent styles are on the market. No shelf angles will be required on the webs of the floor beams, as the concrete will be built up from the flange of the beam to the springing line of the arch; and whatever ties are needed to keep the floor beams from spreading are imbedded in the concrete arch. (See Fig. 1.) Expanded metal ceilings, heavily plastered, suspended from light channels, rest on the bottom flange of the floor beams.

All deep floor girders and all interior columns (the wall columns have a brick inclosure) are protected by fire-clay tile, or other arrangement to keep off the flames in case of fire. The steel work in the foundations will have three or four coats of paint and then be bedded completely in cement to prevent rusting.

The following dead and live loads have been used:

NUMBER OF FLOOR.	PER SQUARE FOOT.			
	Live load.	Dead load.	Calculate Beams for	Calculate Girders for
Roof.....	30 lbs.	50 lbs.	80 lbs.	74 lbs.
Sixteenth floor to third floor	60 "	75 "	135 "	123 "
Second floor.....	60 "	90 "	150 "	138 "
First floor.....	100 "	90 "	190 "	170 "
Sidewalk.....	150 "	50 "	200 "	170 "

The following unit stresses have been used:

Bearing on soil, due to dead load, 2 tons per square foot.

Bearing on soil, due to live load, 5 tons per square foot.

Rolled beams, tension or compression flange, 16,000 pounds per square inch.

Built girders (plates and angles), tension flange, 13,000 pounds per square inch; compression flange same as tension flange. Shear across web, 7500 pounds per square inch.

Z-bar columns, 12 feet long, compression 12,000 pounds per square inch for concentric and eccentric loads.

Z-bar columns, 15 and 17 feet long, 12,000 pounds concentric and 10,000 pounds eccentric.

Shop rivets, 10,000 pounds shear and 20,000 pounds bearing.

Field rivets, 7500 pounds shear and 15,000 pounds bearing.

Brickwork assumed to weigh 125 pounds per cubic foot. For wind load allow 33 per cent. higher values for columns and 50 per cent. higher values for wind-bracing girders.

The steel work for this building is divided into several classes, each of which, so far as possible, will be treated separately.

1. Foundations.
2. Floors.
3. Columns.
4. Wind bracing.
5. Typical details.

I. FOUNDATIONS.

Fig. C, Plate 1, shows the general arrangement of foundation grillage beams under columns marked No. 1 to No. 30, inclusive.

Before determining the size of any footing, the soil should be tested by digging or drilling to a depth of 20 feet below the deepest point of the proposed foundation. If, unfortunately, quicksand or soft soil is met with, piles must be driven. Old wells, in otherwise good soil, can be filled with broken stone and concrete well tamped. In the present paper the assumption is that good, solid soil was found, capable of resisting a dead load (weight of steel work, floors and walls) of 2 tons per square foot, without appreciable settlement. In this case the only obstacle was that the owners of adjoining buildings would not allow their walls to be underpinned, so that the footings for the wall columns of this building could be built partly on the other side of the lot line. This necessitated the introduction of cantilever girders between the following columns:

1 to 4	13 to 14	19 to 20
2 " 5	15 " 16	21 " 22
3 " 6	17 " 18	23 " 24

In determining the size of a footing, the influence of the dead load, always present, and that of the live load, variable in general and again variable as to wall columns and interior columns, should be considered separately. For example:

Column No. 2.

$$\left. \begin{array}{l} \text{Dead load} = 244 \text{ tons} \\ \text{Live load} = 54 \text{ tons} \end{array} \right\} \begin{array}{l} \text{Total, 298 tons; at 2 tons per square} \\ \text{foot, this will give 149 square feet} \\ \text{(size of footing).} \end{array}$$

Live load removed, pressure per square foot will be $244 \div 149 = 1.64$ tons, a decrease of 18 per cent.

Column No. 11.

$$\left. \begin{array}{l} \text{Dead load} = 295 \text{ tons} \\ \text{Live load} = 111 \text{ tons} \end{array} \right\} \begin{array}{l} \text{Total, 406 tons; at 2 tons per square} \\ \text{foot, this will give 203 square feet} \\ \text{(size of footing).} \end{array}$$

Live load removed, pressure per square foot will be $295 \div 203 = 1.45$ tons, a decrease of $22\frac{1}{2}$ per cent.

Clearly, in the long run, column No. 2 will settle more than column No. 11.

The writer proposes to give different values for live and for dead loads. In this case 2 tons have been used for dead loads and 5 tons for live loads.

Column No. 2 will then have $244 \div 2 + 54 \div 5 =$ about 133 square feet (size of footing); per square foot 2.24 tons.

Live load removed, pressure per square foot will be $244 \div 133 = 1.83$ tons, a decrease of 18 per cent.

Column No. 11 will then have $295 \div 2 + 111 \div 5 =$ about 170 square feet (size of footing); per square foot 2.39 tons.

Live load removed, pressure per square foot will be $295 \div 170 = 1.75$ tons, a decrease of 27 per cent.

Grouping the results in tabular form, we have:

DEAD AND LIVE LOADS AT 2 TONS PER SQUARE FOOT.

Column Number.	Pressure per Square Foot, due to Dead and Live Loads.	Pressure per Square Foot, due to Dead Loads only.	Difference in Pressure.
2	2 tons	1.64 tons	
11	2 "	1.45 "	0.19 tons

DEAD LOADS AT 2 TONS, LIVE LOADS AT 5 TONS PER SQUARE FOOT.

Column Number.	Pressure per Square Foot, due to Dead and Live Loads.	Pressure per Square Foot, due to Dead Loads only.	Difference in Pressure.
2	2.24 tons	1.83 tons	0.41 or
11	2.39 "	1.75 "	0.68

The maximum difference in pressure on soil, due to two different columns at one and the same time, evidently occurs when the dead and live loads are treated alike, and when only the dead loads act. Where different allowances are made for dead and for live loads, there is less *difference* between the pressures on the soil, caused by two columns at the same time.

It has been urged by some engineers that it would be more reasonable to consider dead loads only, and to figure so low a pressure per square foot of soil that the added live load would but slightly increase the pressure, thus reducing the differences between the pressures exerted by various columns at the same time.

As a general rule, the pressures exerted by interior columns fluctuate more than those of wall columns, the latter having to carry the constant wall load in addition to the concrete floors;

whilst the interior columns carry only the concrete floors, and are therefore more greatly affected by the live load.

Example 1. Footing Under Column No. 11.

Dead load = 295 tons; $295 \div 2 = 148$ } Total, 170.
 Live load = 111 tons; $111 \div 5 = 22$ (about) } (Square feet.)

Pier outline 13 feet by 13 feet.

Beams in lower layer are placed 20 inches apart, requiring 9 9-inch beams, 21 pounds per foot, 12 feet 6 inches long.

Beams in middle layer are placed 15 inches apart, requiring 7 18-inch beams, 55 pounds per foot, 13 feet 4 inches long.

Beams in top layer are placed 9 inches apart, requiring 3 20-inch beams, 65 pounds per foot, 7 feet 6 inches long.

These beams are figured by finding out how much pressure per lineal foot comes on each, by dividing the column load by the number of lineal feet in each layer. One end is fixed, the other end is free and the load is uniform. The beams are held together by $\frac{3}{4}$ -inch round tie rods, and properly spaced by gas pipe separators. The concrete should completely fill the spaces between the beams, and surround them at least 6 inches beyond their extreme ends, to prevent rusting.

Example 2. Footing Under Columns 2 and 5.

This is a case where, if the footing under column No. 2 were placed symmetrically, it would extend under the neighbor's wall; but, as this is not permitted, a cantilever girder has been placed, reaching from column No. 2 to column No. 5, as shown on plan No. 3.

The loads from column No. 2 are as follows:

Dead load, 244 tons; live load, 54 tons; total, 298 tons. Placing the center of bearing of footing No. 2 5 feet from lot line, we have:

$298 \times 19 = V \times 14$; $V = 404$ (tons), where V = the reaction at footing No. 2.

$298 \times 5 = V_1 \times 14$; $V_1 = 106$ (tons), where V_1 = the reaction at column No. 5.

Further considering footing No. 2, we have:

Pressure to provide for 404 tons, of which 330 tons are due to dead load and 74 tons are due to live load.

$330 \div 2 = 165$ } Total, 180 square feet.
 $74 \div 5 = 15$ (about) }

We find, according to plan, a lower layer of 7 beams, 12-inch, $31\frac{1}{2}$ pounds; a middle layer of 7 beams, 15-inch, 42 pounds, and a top layer of 4 beams, 20-inch, 65 pounds.

Further considering footing No. 5, we have:

Column load, 279 tons. Subtracting the upward reaction (produced by column No. 2) = 106 tons, we have only to provide for 173 tons, of which 120 tons are dead load and 53 tons live load. $120 \div 2 = 60$; $53 \div 5 = 11$ about. Total, 71 square feet. We find, according to plan, a lower layer of 7 beams, 9-inch, 21 pounds, 7 feet long, and an upper layer of 4 beams, 15-inch, 42 pounds, 10 feet long.

Note that the "live load" referred to in this class (1) includes 75 per cent. of the reactions produced in the columns by the wind pressure on the building (see Class 4). This ratio corresponds to the one used in proportioning the columns (see Class 3).

Cantilever Box-Girder.

This girder rests on footing No. 2 and footing No. 5, and transmits the load at column No. 2 to these two footings. The girder is made of 2 48-inch web plates, 3 24-inch cover plates on top and 3 on bottom, and 24-inch end cover plates, forming a complete box. At the points of loading, diaphragms are introduced for the sake of stiffness (see plan, elevation and section of girder, 2-5, Fig. D, Plate 1). It will be seen that the maximum bending moment occurs at the center of footing No. 2; that the shears are constant from column No. 2 to footing No. 2 and from column No. 5 to footing No. 2.

The cantilever is a very expensive feature of the building and should be avoided; and every effort should be made to obtain permission to underpin and build individual footings under adjacent walls.

2. FLOORS.

The construction of the several floors and for the roof at 13th floor level, and that of the roof over the 16th story, are shown on plans, while the "architect's plans," or those of the various floors, showing the arrangements of walls, windows and doors, stairways, elevators, etc., are shown on plans. The most important floor is the "typical office floor," Fig. F, Plate II, there being 10 such in this building,—viz, the 3d to the 12th floor, inclusively. As noted, the loads assumed were as follows:

<i>Live load</i> , 60 lbs. per square foot.	<i>Beams</i> figured for 135 lbs. per square foot.	<i>Girders</i> (carriers supporting two or more beams).
<i>Dead load</i> , 75 lbs. per square foot.		Dead load + 80 per cent. of live load = 123 lbs. per square foot.

The wall girders carry the floor loads plus the wall loads, and the latter are assumed at 125 pounds per superficial square foot. The walls are 13 inches thick. The walls, being cut up by windows, use 75 per cent. of a solid wall contained in panel over wall girder. In the case of the back wall, where there are few or no windows, use the entire wall, as though solid. Figure walls, on this basis, as uniformly loading the wall girders.

As to live loads, taken at 60 pounds per square foot, these consist of office furniture of various kinds, and human loads. Regarding the latter, Professor Burr, in his treatise on bridge and roof trusses, states that on a highway bridge a dense crowd of people will produce a load of 85 pounds per square foot. The late Mr. Hatfield, of New York city, found by experiment that it was hardly possible to exceed 70 pounds per square foot. Professor Merriman says that for highway bridges anywhere from 70 to 100 pounds per square foot may be taken. In an office building such a crowd can hardly be placed on each and every square foot. Considering desks, chairs, etc., it is the writer's opinion that 60 pounds are quite sufficient.

As to dead loads, we have a concrete arch of an average thickness of 4 inches, a filling between nailing strips of 1 inch, a plastered ceiling 1 inch thick; total, 6 inches, of an average weight of 80 pounds per cubic foot, or 40 pounds per square foot. Add to this nailing strips and flooring ($7\frac{1}{8}$ inch thick), weighing 10 pounds per square foot. The weight of the partitions, in a 12-foot story, divided into offices as noted on plan No. II, amounts to 15 pounds per square foot of floor. The weight of steel construction, 10 pounds per square foot of floor.

SUMMARY.

Concrete floor and plastered ceiling.....	40	lbs.	per square foot.
Nailing strips and flooring.....	10	" "	" "
Partitions.....	15	" "	" "
Steel construction.....	10	" "	" "

Total 75 lbs. per square foot.

The assumption that the girders, in the sense used here, are safe at 80 per cent. live load presupposes that all the beams framing into the girders have not their full live loads at the same time.

Considering a typical panel, as, for instance, that between columns Nos. 5, 6, 9 and 8, it will be found by trial that the most economical system requires 10-foot arches as shown on Fig. E, Plate II. This gives 12-inch, $31\frac{1}{2}$ pounds floor beams, and 15-

NUMBER OF COLUMN.

No. of Story	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	No. of Story
16										$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$							16
15										$8 \times 1_4$	"	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	"	$8 \times 1_4$	$8 \times 1_4$	"	$8 \times 1_4$	"	"	$8 \times 1_4$	"	$8 \times 1_4$							15
14										"	$8 \times 1_4$	"	"	"	$8 \times 1_4$	"	"	$8 \times 1_4$	"	$8 \times 1_4$	$8 \times 1_4$	"	$8 \times \frac{5}{16}$	"							14
13										$8 \times \frac{5}{16}$	"	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	"	$8 \times 1_4$	$8 \times \frac{3}{8}$	"	$8 \times \frac{5}{16}$	"	"	$8 \times \frac{3}{8}$	"	$8 \times \frac{5}{16}$							13
12	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	$8 \times 1_4$	"	$8 \times 1_2$	"	"	"	$8 \times 1_4$	"	"	$8 \times \frac{5}{16}$	"	$8 \times \frac{7}{16}$	$8 \times \frac{5}{16}$	"	$8 \times 1_2$	"							12
11	"	$8 \times 1_4$	"	$8 \times 1_4$	"	$8 \times 1_4$	"	$8 \times 1_4$	"	$8 \times 1_2$	"	$8 \times \frac{3}{8}$	$8 \times 1_4$	$8 \times 1_4$	"	$8 \times 1_4$	$8 \times \frac{1}{2}$	"	$8 \times 1_2$	"	"	$8 \times \frac{5}{16}$	"	$8 \times 1_2$							11
10	$8 \times 1_4$	"	$8 \times 1_4$	"	$8 \times \frac{5}{16}$	"	$8 \times \frac{3}{8}$	"	$8 \times \frac{3}{8}$	"	$10 \times \frac{5}{8}$	"	"	"	$8 \times \frac{3}{8}$	"	"	$8 \times \frac{5}{16}$	"	$10 \times \frac{3}{16}$	$8 \times \frac{5}{8}$	"	$10 \times \frac{3}{16}$	"							10
9	"	$8 \times \frac{5}{8}$	"	$8 \times 1_2$	"	$8 \times 1_2$	"	$8 \times \frac{3}{8}$	"	$10 \times \frac{5}{8}$	"	$8 \times 1_2$	$8 \times 1_4$	$8 \times \frac{5}{16}$	"	$8 \times 1_4$	$10 \times \frac{5}{8}$	"	$8 \times \frac{11}{16}$	"	"	$10 \times \frac{5}{8}$	"	$10 \times \frac{5}{8}$							9
8	$8 \times \frac{5}{16}$	"	$8 \times \frac{5}{16}$	"	$8 \times 1_2$	"	$8 \times \frac{5}{8}$	"	$8 \times \frac{5}{8}$	"	$12 \times \frac{11}{16}$	"	"	"	$8 \times 1_2$	"	"	$10 \times \frac{11}{16}$	"	$10 \times \frac{3}{4}$	$10 \times \frac{11}{16}$	"	$10 \times \frac{3}{4}$	"							8
7	"	$8 \times \frac{11}{16}$	"	$10 \times \frac{5}{8}$	"	$10 \times \frac{5}{8}$	"	$8 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$	"	$10 \times \frac{11}{16}$	$8 \times \frac{5}{16}$	$8 \times \frac{3}{8}$	"	$8 \times \frac{5}{16}$	$10 \times \frac{11}{16}$	"	$10 \times \frac{3}{4}$	"	"	$12 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$							7
6	$8 \times 1_2$	"	$8 \times 1_2$	"	$10 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$	"	$12 \times \frac{7}{8}$	"	"	"	$8 \times \frac{9}{16}$	"	"	$12 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$	$12 \times \frac{7}{4}$	"	$12 \times \frac{11}{16}$	"							6
5	"	$10 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$	"	$10 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$	$8 \times \frac{3}{8}$	$8 \times 1_2$	"	$8 \times \frac{3}{8}$ $2-14 \times \frac{11}{16}$	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$	"	"	$12 \times \frac{7}{8}$	"	$12 \times \frac{11}{16}$							5
4	$8 \times \frac{5}{8}$	"	$8 \times \frac{5}{8}$	"	$12 \times \frac{5}{8}$	"	$12 \times \frac{7}{8}$	"	$12 \times \frac{7}{8}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	"	"	$8 \times \frac{11}{16}$	"	"	$12 \times \frac{7}{8}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	$12 \times \frac{7}{8}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"							4
3	"	$12 \times \frac{3}{4}$	"	$12 \times \frac{11}{16}$ $2-11 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$ $2-11 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$	"	$12 \times \frac{7}{8}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{3}{4}$ $2-14 \times \frac{11}{16}$	$8 \times \frac{5}{16}$	$8 \times \frac{11}{16}$	"	$8 \times \frac{7}{16}$	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$							3
2	$12 \times \frac{5}{8}$	"	$12 \times \frac{5}{8}$	"	$12 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	"	"	$10 \times \frac{11}{16}$	"	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{7}{8}$ $2-14 \times \frac{11}{16}$	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"							2
1	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{7}{8}$	"	$12 \times \frac{7}{8}$ $4-14 \times \frac{7}{8}$	"	$12 \times \frac{7}{8}$ $2-14 \times \frac{7}{8}$	$8 \times 1_2$	$8 \times \frac{5}{8}$	"	$8 \times 1_2$	$12 \times \frac{7}{8}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{3}{4}$ $2-14 \times \frac{11}{16}$							1
Basement	$12 \times \frac{3}{4}$	"	$12 \times \frac{3}{4}$	"	$12 \times \frac{7}{8}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	"	"	$10 \times \frac{3}{4}$	"	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{7}{8}$ $2-14 \times \frac{11}{16}$	$12 \times \frac{3}{4}$ $2-14 \times \frac{11}{16}$	"	$12 \times \frac{11}{16}$ $2-14 \times \frac{11}{16}$	"							Basement

1

2

3

4

5

6

7

8

9

10

11
12
13

14
15
16

17

inch, 60 pounds floor girders. An 18-inch, 55 pounds beam would be equally cheap, and stiffer, but its use would involve the loss of 3 inches of head room, amounting to 3 or 4 feet in the entire building. In designing floor beams and girders, the deflection must be taken into account. If the deflection amounts to more than $\frac{1}{360}$ of the span, it is apt to crack a plastered ceiling. However, it must also be remembered that, when plaster is applied, all the dead load is already in place, and has produced its deflection, so that we have to consider only the deflection due to the live loads. The deflection of a symmetrical shape, for example, a beam, is

$$\text{For uniform loading} \quad \frac{5Wl^3}{384.E.I}$$

$$\text{For loading concentrated} \quad \frac{Pl^3}{48.E.I}$$

at center, where

W = total uniformly distributed load in pounds.

P = total concentrated load in pounds.

l = length of beam in inches.

E = modulus of elasticity (for medium steel $E = 29,000,000$ pounds).

I = moment of inertia.

If $W = 2P$ (equal maximum bending moments), the deflection under the concentrated load is only 80 per cent. of that under the uniform load.

The wall girder (6-9) will be made of an 18-inch, 55 pounds beam and a $12 \times \frac{5}{16}$ -inch plate riveted to its top flange, giving a good bearing for the 13-inch wall. This plate should be riveted to the beam, thereby increasing its inertia. In the case of another wall girder (20-24), in addition to the top plate, a bottom plate is riveted on, over half the length of the beam. This effects a saving in material; as, by merely giving the $12 \times \frac{5}{16}$ -inch top plate bolts to hold it in position, a 20-inch, 650 pounds beam would be required; and coming under the same price classification (fitted beams). (See Figs. 2 and 3.)

Beams at stair landings are figured as though the stairs were fully loaded. Beams at elevator openings are strong enough to carry the regular floor loads, and, in addition, a slight weight due to the elevator inclosures, guides, etc.

It will be noted that the transverse beams between columns are built of plates and angles, serving at the same time as wind-bracing girders, under which class they will be treated later on.

Whatever has been said about the typical office floor refers, with slight variations, to all other floors.

The first floor is figured for a live load of 100 pounds per square foot, and a dead load of 90 pounds per square foot. This increase of live load, as compared with typical office floor, is due to the fact that more persons are liable to congregate on a floor devoted to store purposes than on an office floor. Add to this the sometimes heavy loading of dry goods, counters, etc.

The increase in dead load is due to an extra heavy flooring for store room. The beams in the sidewalk are figured for 200 pounds per square foot, dead and live loads.

The second floor is figured for a live load of 60 pounds per square foot, and a dead load of 90 pounds per square foot, due to a marble ceiling over the first story. It will be noticed that the light court commences here, taking in the space between columns Nos. 4, 14, 13, 25 on one side and 6, 15, 16, 28 on the other.




Fig. 2




Fig. 3

These spaces are finished with glass, in which is imbedded $\frac{3}{4}$ -inch mesh steel wire netting, laid between tees 24 inches apart on centers.

The thirteenth floor is really, in part, a sloping roof, for rear of building, between columns 1, 3, 12 and 10, and, in part, a regular floor, between columns 10, 21, 24 and 12. The roof is figured for a live load of 30 pounds and a dead load of 50 pounds per square foot. The floor is figured for the same loads as the typical office floor. The roof slopes toward the rear $\frac{3}{4}$ inch per foot. The roof is formed by spanning concrete arches between beams, and giving to the surface several coats of asphalt and gravel.

The fourteenth, fifteenth and sixteenth floors are like the thirteenth floor.

The roof, over the sixteenth story, between columns 10, 21, 24, 12, is made like the one at thirteenth floor level between columns 1, 3, 12 and 10. On the roof is a dog house, or a brick inclosure,

12 feet high, located over elevators and main stairway, and covered with a slate roof. The purpose of this little house is to give a covering for the elevators, with head room enough to place sheaves and other fixtures for the elevator cars; also to give an exit to the roof, thus terminating the main stairway in a fireproof door leading to the roof at the very front of the building; and, extending for a few feet to each side, toward the rear, is a 5-foot projection for a terra cotta cornice. The terra cotta will be carried by 4-inch beams, 30 inches apart, again carried by main girders 21 to 24 and 8-inch beams parallel to the girders. The method of connecting the floor beams and the girders to the columns is shown in Fig. 11, Plate III, of "General Details." Beam is connected to beam by "connection angles," standardized by leading manufacturers into 6 or 7 different kinds to suit all sizes of beams and channels. These connections are designed for the largest loads that can be expected on the ordinary spans of beams. All connections should be riveted.

3. COLUMNS.

The columns carry the entire weight, including dead and live loads, and the wind pressure, into the footings, these again distributing said loads on the soil. The aim, as explained under footings, is to have an equal pressure per square foot of soil at the same time for all footings, insuring an even settlement. The columns adopted in this building are "Z-bar columns" (Fig. 4), very extensively used of late years; they are made of 4 Z bars and 1 web plate. Where this section will not suffice, extra plates are riveted on, forming a closed column. Where the closed column occurs, all the paint specified should be applied before riveting up or assembling. The columns rest either on the top layer of grillage beams in the footings, or on cantilever girders, to which latter they should be riveted, if possible; and, if not, bolted. The cantilever girders are 24 inches wide, and the grillage beams of the top layer are spaced 9 inches on centers; thus all base plates can be made 24 by 24 inches and $\frac{3}{4}$ inch thick. The columns are joined, one section on top of the other, in such a manner as to secure an equal and complete transmission of loads from story to story and finally into the footings. Fig. H, Plate III, shows a typical column splice, a 10-inch column resting on a 12-inch column. The top of the lower and the bottom of the upper column are planed, and a $\frac{1}{2}$ -inch butt plate is placed between them. Then there are vertical splice plates, $\frac{3}{8}$ inch thick, and fillers to make up the different widths of shafts. Generally the column shaft is spliced at every other floor, and the adjacent columns must break joints; that is, they must not be

spliced at the same floors. For instance, column No. 7 is spliced at the third, fifth and seventh floors, etc.; then columns Nos. 4 and 10 are spliced at the fourth, sixth and eighth floors, and so on. This is supposed to add to the stiffness of the structure, whereas it renders the erection more difficult. For intermediate columns, connections for beams and girders are generally concentric, but for wall columns this is rarely possible, as the latter must be set in far enough from the face of the wall to get at least one brick thickness outside; while wall girders are located at centers of walls. Any one of the floor plans will illustrate this, and detail plans Nos. 13 and 14 show connections in detail. Fig. H, Plate III, shows concentric connections of 15-inch floor girders, beams resting on bracket and held on top by angle lug. Fig. I, Plate III, shows connections to column No. 15 at sixth floor, where wall girders are $6\frac{1}{2}$ inches eccentric with column.




Fig. 4




Fig. 5




Fig. 6




Fig. 7

As to the proportioning of the columns, the following rules have been used:

(a) Proportion for entire dead load.

(b) Proportion for live load according to a "sliding scale," giving top story or attic columns full load, and basement columns 80 per cent. of all the live loads carried into them. For intermediate stories interpolate; thus, in a 16-story building, a sixth-story column would be proportioned for 88 per cent. of all live load above that floor. This is an entirely arbitrary ratio, and is recommended by the St. Louis Architectural Club, and incorporated into the building laws of St. Louis, dated August 1, 1898. It is based on the supposition that all floors are not at the same time loaded to the extent specified. As to permissible stress per square inch, for medium steel 12,000 pounds has been used for both concentric and eccentric loading for short columns (12 feet). For longer columns, use 10,000 pounds, in order to allow for eccentric loading. For wind load, raise the values by 33 per cent.,—that is, use 16,000 pounds or take 75 per cent. of the wind loads and use 12,000 pounds. See also (4) "Wind Bracing," below. Note that the eccentric loading does not accumulate downward through the build-

ing. Hence, all the eccentric loading carried by any one column is simply whatever load is brought into it at the floor immediately above. Thus, for large columns, the eccentric loading has a relatively smaller influence, the inertia of the section being large.

Other column sections quite frequently used are the "Phoenix" column (Fig. 5) and ordinary channel columns (Fig. 6) (composed of 2 channel bars, or of channels and plates). The "Gray" column (Fig. 7), made of angles, and having its outline section constant from basement to roof, has been patented and considerably used. The writer, however, prefers the "Z" or the "Phoenix" column, because in them the loads are almost instantly transmitted into the entire body of column.

The accompanying schedule for Z-bar columns gives the size of each column, from basement to roof. Note how the column splices are staggered (or joints broken). The 8-inch column is the smallest used, smaller sections being more difficult to handle in the shop.

4. WIND BRACING.

The pressure, in pounds per square foot, for which a building should be calculated is very often fixed at 30, and is supposed to be applied to the entire surface, from sidewalk level to cornice. If the pressure be called P , and the velocity in miles per hour V , it has been claimed that

$$P = \frac{V^2}{200}$$

and also that
$$P = \frac{V^2}{100}$$

There is quite a difference in opinion between scientific men and engineers in regard to the relation between the velocity of the wind and the pressure it exerts on a vertical surface, of larger or smaller extent, and at a larger or smaller height; also as to the continuity of such pressure.

Mr. C. Shaler Smith, in his paper on "Wind Pressure upon Bridges," read before the American Society of Civil Engineers on December 5, 1880, cites a few examples of actual results, and then calculates what pressure could produce such results.

In a violent storm in 1871, a locomotive was overturned at East St. Louis. This feat represented a wind pressure of 93 pounds per square foot of actual surface.

He also cites numerous cases of car derailments when the pressure required would be 30½ pounds per square foot of actual surface. He gives, as a general opinion, that 30 pounds per square foot is enough for an average truss bridge (about 150 feet

long) as he knows of only one case where the path of the tornado was over 60 feet wide.

In the discussion of Mr. Smith's paper it was contended that anemometers had shown as high as 90 pounds pressure per square foot; and the opinion is expressed that this high figure may be caused by the shock, or impact of the oncoming storm.


The building code of New York city, adopted October 10, 1890, calls for 30 pounds horizontal wind pressure for every square foot exposed; also, that the overturning moment of the wind shall be equal to, or less than, 75 per cent. of the moment of stability of the structure. It further requires that "If the resisting moment of the ordinary materials of construction, such as masonry, partitions, floors, connections, are not sufficient to resist the moment of distortion due to wind pressure, in any direction," wind bracing must be put in. The building laws of St. Louis call for 30 pounds per square foot, from sidewalk level to extreme top of building.

It is well to note that, up to the fifth or sixth floor level, buildings generally are protected by adjoining or nearby structures. A building offers a large surface, and, according to most persons who have studied this subject, the large surface does not receive, over its entire extent, the intensity of pressure that a small surface receives. In the opinion of the writer, 30 pounds per square foot for the entire surface is enough for a building such as that described in this paper.

The best and cheapest method of bracing is by means of rods, running diagonally between columns, from top to bottom. But in most cases this is entirely out of the question, as it will interfere with free passage from room to room, and along the corridors. This is especially objectionable in the first story, which often is thrown into one room, as a store. Another method is to use a deep girder, with knee braces at the ends, connecting it with the columns, and relying on the resistance of the girders to bending. Again, knee braces quite often become undesirable when there is no convenient wall or partition to hide them, and in this latter case have been used plate girders, as deep as possible, connected to columns by enough rivets to transmit into columns the end shears due to wind loads and dead and live loads, and to resist the couple described later (see Fig. 9 or Fig. 12). This latter is the system used in this building, and is illustrated in Fig. J, Plate I, with a detailed connection to column shown in Fig. H, Plate III.

Fig. J, Plate I, shows the wind-bracing system between columns 4, 5, 6 or 7, 8, 9. The plate girders are 30 inches deep, up to

and including the sixth floor; while the remainder are only 24 inches deep. These girders act both as floor beams in their respective floors, and as wind-bracing girders. The connection to the Z-bar column is indicated in detail in Fig. 11, Plate III. The gusset plates at the columns should be brought down if necessary below girder to get enough rivets. In a narrow building the columns should be so placed as to bring the web plate of the column perpendicular to the long axis of building. This makes easier and more direct connections between girders and columns. Sometimes the gusset plate is run through the column, forming part of it. In the present case connection angles are used, fastening the girders to the face of the column. This is more economical and requires



one planed joint less. The method used for calculating sections of bracing girders is as follows, using system 4, 5, 6 as an illustration:

Find the wind load at each floor (being equal to number of square feet transferred into bracing system at floor multiplied by 30). If the question is to determine section of girder at fifth floor, add the wind load from roof to fifth floor, inclusive, amounting in this case to 61,200 pounds. (See Fig. 8.)

With the bracing girders properly riveted in place, the column system 4, 5, 6 is supposed to be rigid, so as to act as one piece, and so that all shears are ultimately carried into the footings, being transferred from the bracing girders at one floor through the columns, straining these on bending, to the girders at floor below and so on to base of columns. Referring now to Fig. 9, showing the bending moments, and to Fig. 10, showing the shears, the following notations have been used:

p = one-third of the total shear (horizontal) at fifth floor. (In this case $\frac{1}{3} \times 61,200 = 20,400$ pounds.)

V = the vertical reaction at column No. 4 or column No. 6.

H = the height of fourth story.

W = the distance, center to center, between columns No. 4 and No. 5, or between columns No. 5 and No. 6.


D = the total dead load on girder.

L = the total live load on girder.

Assuming the wind to blow in the direction of the arrow (refer to Fig. 9),

$$3.p.H - 2.V.W = 0$$

$$V = \frac{3.p.H}{2.W}$$



If we now investigate the bending moments on girders connecting columns No. 4, No. 5 and No. 6, we find:

On the right side of column No. 6 $+ p.H$. (Compression in top flange.)

On the left side of column No. 5 $+ p.H - V.W$. (Tension in top flange.)


On the right side of column No. 5 $- p.H + V.W$. (Compression in top flange.)

On the left side of column No. 4 $- p.H$. (Tension in top flange.)

These are the extreme positive and negative moments on girders.

The bending moments due to the dead and live loads will have their maximum value at centers of girders $= \frac{(D + L)W}{8}$.

In Fig. 9 the bending moments due to wind are drawn with dotted lines, the bending moments due to dead and live loads are drawn with dot and dash lines, and the resultant moments with full lines. The ordinates in the shaded polygons will give the bending moment at any place along the top flange of girder. The bending moments along the bottom flange will be somewhat smaller, and generally of opposite sign.



Assuming the wind to blow in the direction of the arrow (refer to Fig. 10), it will be seen that the vertical shear

$$\text{On the right side of column No. 6} = -V + \frac{D+L}{2}$$

$$\text{On the left side of column No. 5} = -V - \frac{D+L}{2}$$

$$\text{On the right side of column No. 5} = -V + \frac{D+L}{2}$$

$$\text{On the left side of column No. 4} = -V - \frac{D+L}{2}$$

Column No. 5 occupies the center of the building, and it has been assumed that this column causes neither a positive nor a negative vertical reaction. In proportioning girder, note that the extreme fiber stress has been raised by 50 per cent., 13,000 pounds being used for dead load and live load, and 20,000 pounds for wind load stresses; as the wind load stresses seldom occur, and taken altogether with the dead and live load stresses, the stress per square inch runs considerably below 20,000 pounds. The girders are also subject to direct compression (due to wind loads), but the writer thinks this compressive stress can be safely disregarded, as the con-

crete floor can be relied upon to carry this load, or to help in doing so.

The next thing to consider is the influence of the wind pressure on the columns. Considering system 4, 5, 6, Fig. J, Plate I, there is, at the roof, a wind load of 3600 pounds; at floors from the twelfth to the third, inclusive, 7200 pounds; at the second floor, 8700 pounds, and at the first floor, 5100 pounds.

The load on column 4 (or 6) caused by the wind will be:

$$\text{Twelfth story } \frac{3600 \times 12}{32} = 1350 \text{ pounds.}$$

$$\text{Eleventh story } \frac{10,800 \times 12}{32} + 1350 = 5400 \text{ pounds.}$$

$$\text{Tenth story } \frac{18,000 \times 12}{32} + 5400 = 12,150 \text{ pounds.}$$

$$\text{Ninth story } \frac{25,200 \times 12}{32} + 12,150 = 21,600 \text{ pounds,}$$

and so on, down to the footings.

In other words, the moments, due to wind loads, are found at each floor; the resultant moment divided by the distance, center to center, between outer columns, No. 4 and No. 6, will give the stress in columns No. 4 and No. 6, which evidently is tensile on the windward side and compressive on the leeward side. Column No. 5, being at the center of the building, will get no allowance for the wind loads. By an inspection of the shear diagram, Fig. 10, it will be noticed that the vertical shear, due to wind loads, is constant from column No. 6 to column No. 4. In proportioning columns, note that for stresses due to wind pressure, 16,000 pounds per square inch has been used, or 33 per cent. more than for dead and live loads.

The direct bending moments on columns due to wind loads have not been considered in proportioning these columns. By trials it was found that for a story height of 12 feet, and a width of building of 32 feet, these bending moments did not raise the fiber stress to any great extent. The influence of these direct bending moments should, however, be investigated for each separate design; as, for a very narrow building with high stories, it may become necessary to increase the amount of metal in columns.

The general treatment of the wind-bracing system between columns 17, 18, 19 and 20 is similar to that above described, but we now have four columns where before we had but three. (See Fig. 11.)

Fig. 11 shows columns 17, 18, 19, 20 at twelfth floor. The bracing girders are riveted in place, and the shear at twelfth floor







FIG. E. TYPICAL OFFICE FLOOR (3RD TO 12TH INCLUSIVE).








FIG. F. ROOF.



- Roof -

FIG. G. TYPICAL OFFICE FLOOR
(3RD TO 12TH INCLUSIVE).






NOTE ALL CONNECTIONS RIVETED



NOTE—ALL CONNECTIONS, BEAMS TO BEAMS, AND BEAMS TO COLUMNS, ARE RIVETED.



will be transferred from the bracing girders through the columns in eleventh story, straining these on bending, to the bracing girders at eleventh floor, and so on to the base of columns.

Referring now to Fig. 11 and to Fig. 12, showing the bending moments, and Fig. 13, showing the shears, the following notations have been used:

p = one-fourth of the total horizontal shear at twelfth floor (in this case $\frac{1}{4} \times 39,600 = 9900$ pounds).

X = the vertical reaction at column No. 17 or column No. 20.

Y = the vertical reaction at column No. 18 or column No. 19.




Fig. 11




Fig. 12

H = the height of eleventh story.

W_2 = the distance, center to center, between columns No. 18 and No. 19.

W_1 = the distance, center to center, between columns No. 17 and No. 18, or No. 19 and No. 20.

D and L , D_1 and L_1 , total dead and live load on girders. (Assumed uniform in order to simplify the treatment.) The center of the building lies halfway between columns No. 18 and No. 19; and it has been assumed that the strains in the columns, caused by wind loads, are proportional to the distance of column from center of building; or

$$\begin{aligned} X : Y &= 24 : 7 \\ X &= \frac{24}{7} Y \dots\dots\dots (a) \end{aligned}$$

Assuming the wind to blow in the direction of the arrow (refer to Fig. 12):

$$4.p.H - X(2W_1 + W_2) - Y.W_2 = 0 \dots\dots\dots (b)$$

From equations a and b X and Y can be easily found.

If we now investigate the bending moments on girders connecting columns Nos. 17, 18, 19, 20, we find:

On the right side of column No. 20 + p.H. (Compression in top flange.)

On the left side of column No. 19 + p.H - XW₁. (Tension in top flange.)

On the right side of column No. 19 + 2.p.H - XW₁. (Compression in top flange.)

On the left side of column No. 18 - 2.p.H + XW₁. (Tension in top flange.)

On the right side of column No. 18 - p.H + XW₁. (Compression in top flange.)

On the left side of column No. 17 - p.H. (Tension in top flange.)

These are the extreme positive and negative moments on girders.

The bending moments due to the dead and live loads will have their maximum value at centers of girders = $\frac{(D + L)W_1}{8}$ and $\frac{(D_1 + L_1)W_2}{8}$ for outer and inner girders respectively. The bending moments due to wind loads and dead and live loads are shown

similarly to what was shown in Fig 9, and the resultant moments along top flange of girder can be scaled off; the moments along the bottom flange are slightly smaller and generally of opposite sign.

Assuming the wind to blow in the direction of the arrow (refer to Fig. 13), it will be seen that the vertical shear:

$$\text{On the right side of column No. 20} = -X + \frac{D + L}{2}$$

$$\text{On the left side of column No. 19} = -X - \frac{D + L}{2}$$

$$\text{On the right side of column No. 19} = -X - Y + \frac{D_1 + L_1}{2}$$

$$\text{On the left side of column No. 18} = -X - Y - \frac{D_1 + L_1}{2}$$


On the right side of column No. 18 = $-X + \frac{D+L}{2}$

On the left side of column No. 17 = $-X - \frac{D+L}{2}$

As to the influence of wind pressure on columns Nos. 17, 18, 19, 20, the procedure to find stresses is similar to the one explained for columns Nos. 4, 5, 6; that is, after finding the values of X and Y for each story (X_{16} and Y_{16} , X_{15} and Y_{15} , X_0 and Y_0) summarize their numerical values, downward, until the basement is reached. For instance, column load for sixteenth story is X_{16} and Y_{16} ; fifteenth story is $X_{16} + X_{15}$ and $Y_{16} + Y_{15}$; fourteenth story is $X_{16} + X_{15} + X_{14}$ and $Y_{16} + Y_{15} + Y_{14}$, and so on.

In other words, the overturning moments of the wind are resisted by two couples:

$$X(2W_1 + W_2) \text{ and } Y.W_2$$



By an inspection of the vertical shear diagram, Fig. 13, it will be noticed that the shear, due to wind loads, is constant from column No. 20 to column No. 19 ($-X$), again constant from column No. 19 to column No. 18 ($-X - Y$) and finally constant from column No. 18 to column No. 17 ($-X$).

The writer believes that the method above illustrated for proportioning girders and columns will be quite useful and safe for all practical purposes, without laying claim to absolute correctness. The more perfect the column connections are, the more reason is there to expect close results. As in any other general rule, there are, of course, special cases that must be treated by themselves, as exceptions. The columns should be anchored by strong rods into or below the foundations, if the graphical lay-out of the wind pres-

sure and dead weight of the building shows that the resultant at level of foundation falls outside the middle third of the base. As to bracing this building in its longitudinal direction, the standard connections between beams and columns are quite sufficient. For the lower part of the building (terminating at the thirteenth floor level) the ratio of length to height is as 1 : 1.64. For the upper front part, terminating at roof over sixteenth story, the ratio of length to height is as 1 to 1.20. Between columns No. 10 and No. 11 is a brick wall, running continuously from second floor to roof, helping to stiffen the building transversely.

5. TYPICAL DETAILS.

The typical details, shown on plans Fig. D, Plate I, and Plate III, have already been mentioned in describing the various classes of work to which they belong. In Fig. D is shown the cantilever girder between columns No. 13 and No. 14; one column (wall column) rests on top of the girder, while the anchor column (No. 14) rests directly on the grillage and the girder is framed into it. Plan No. 13 shows the connection of wind-bracing girders and floor girders to columns, and shows column splice. This floor girder (15-inch beam, 60 pounds) rests on a bracket riveted to column. The beam flange will be riveted to this bracket, and the top flange of the beam will be riveted to an angle shelf, to steady the beam. Plan No. 14 shows some eccentric beam connections. It will be seen from the floor plan that the loads carried into column by the wall girders are rather small, therefore the connections are light.

Very often an eccentric wall load is balanced, or partly balanced, by the intermediate beam loads. For example:

Load transmitted by wall girders = P .

Load transmitted by intermediate beam = P_1 .

Moment of wall girders = Pd .

Moment of intermediate beam = P_1d_1 .

Pd may be equal to, or larger or smaller than, P_1d_1 .

Fig. 14 shows such a case. This should be considered when wall columns are proportioned, as the eccentric load may be less than is expected.

Fig. K, Plate III, shows steel construction in bay window framing in front of building, as shown on the general front elevation, Fig. A, Plate I. At the floor level, and attached to front girders by bent plates and a cantilever construction carrying the loads into the floor construction, are channels properly framed to follow the outline of the bay window. A concrete floor will be built in between the channels and the front girders. The framing

is suspended by 3 x 3-inch angles, as indicated; angles being fastened to cantilever construction, as indicated, at fifteenth, twelfth, ninth, sixth and fourth floors.

GENERAL REMARKS.

It is important to write out a specification for the kind of material wanted in the various parts of a steel structure. The special requirements for steel, as to amount of sulphur and phosphorus allowable, and as to tests and inspection of raw and finished material, are decided by each architect or engineer for himself; still there are some general points which should not be overlooked. All beams used in foundations should have three to four coats of paint, raw linseed oil forming the binder, and oxide of iron or red lead the pigment. Before applying paint, the surfaces should be absolutely clean. If hammering and wire brushing will not render them




Fig. 14

so, the sand blast should be used. The grillage box girders should be tight, so that no water can get in under any circumstances that might arise. These also ought to have three to four coats of paint. The floor beams should have end connections strong enough to carry the load safely into the girders. In short spans the standard connection angles may not suffice. Where wall girders or other beams connect with columns eccentrically, connections should be so designed as to transfer the load into the entire column, not into part of it only. Where wall girders have cover plates, the rivets should be flattened on top of the cover plate, in order to give better bearing for brick or stone work. Where beams connect to columns with a connection angle above (connecting to top flange), give an allowance of one-eighth to one-quarter inch to allow for irregularities in depth of beam. As to paint, the writer believes that, as long as the body of the paint is good unadulterated linseed oil, it is immaterial whether the pigment is oxide of iron or red lead.

The estimated weight of steel in the building here described is 795 tons, and the estimated cost price for furnishing all steel and erecting it at St. Louis, riveting all connections and giving all steel an extra coat of paint after erection, is \$47,000 at prevailing prices, September, 1900. Analyzed, the weight and price appear as follows:

Number of cubic feet in building, using outside dimensions, 745,000.

Weight of structural steel, per cubic foot of building, 2.13 pounds.

Cost price of structural steel, per cubic foot of building, 6.31 cents.

Cost of structural steel, per pound, 2.96 cents.

The writer wishes to express his thanks to Mr. Wm. Frye Scott, architect, New York city, formerly a member of the Engineers' Club of St. Louis, who assisted in getting up the architectural features, arrangement of rooms, stairways, elevators, etc., for the building discussed in this paper.

**THE ENGINEERING SOCIETY—ITS RELATIONS TO THE
ENGINEER AND TO THE PROFESSION.**

ANNUAL ADDRESS BY H. J. MALOCHEE, PRESIDENT LOUISIANA ENGINEERING
SOCIETY.

[Read before the Society, January 12, 1901.*]

By constitutional right your President has the floor on this occasion, and he begs your indulgence if, at any time, he should become tiresome or should say anything that does not meet with your approval or should offend any one by any statement that he may make. He wishes, however, to assure you that the privilege is one that he fully appreciates, and one that has given him no little concern since his elevation to the presidency of your Society, wishing then, and now, as he has always done, to continue in the footsteps of his predecessors and to further at all times the interest of your body and that of the profession. Being sensible of the honor conferred and fully aware of the futility of his own efforts, but for the support given him by the members of the Society and by his associates on the Direction, he wishes to acknowledge with gratitude their assistance on all occasions when the future of the Society was involved, its interests were at stake and its development and advancement under consideration.

A retrospect of the Society's progress during the three years of its existence will, by way of introduction to what I have to say, serve to place before the members of the Society, and before those of the profession who have not honored us with their valued membership, some idea of the good to be derived from such membership, professionally, personally and otherwise.

Beginning with twenty-six charter members, the Society has gradually increased to the comparatively large membership of seventy-five members of all classes. It has increased its furniture and other assets; it has preserved intact its cash balance in bank; it has, through the establishment of a well-furnished library, given to its members free access to books and periodicals worth a hundred-fold their annual dues. Its members have listened to a number of important papers specially prepared for its meetings, the value of which has been fully recognized by every one. A movement of importance was started toward the protection of the public against the imposition of the charlatans in the profession, and it bids fair to be successful in a short time. The social features have not been neglected, and we count in three

*Manuscript received January 17, 1901.—Secretary, Ass'n of Eng. Soes.

years' existence two outings and two smokers of unusual significance and success, the first two being especially so through the delightful and beneficent presence of a large number of ladies.

In view of the great work already done and of the large amount still remaining to be done by this organization, in view of its importance and power for good, would it be amiss to consider the Engineering Society from the theoretical and practical standpoint, to consider its duty to its members, its duty to the profession at large, its ability as a teacher, as a social factor and as a factor in forming public opinion on the value of engineering service?

Throughout the past ages man has sought his kind, has formed associations for his protection and advancement, and, as Montesquieu says, this state of association has in itself developed a state of war, the very reason for this latter state being the recognition of his own superior strength or weakness. Comparisons of the strength or weakness of this or that individual, and the confidence, derived from these comparisons, in one's own strength, made this state of war possible. This state of war has not, however, caused the destruction of the race; it has improved it; it has made of it a living, active body, and the more active this state of war the greater has been the effort to live through it and the greater the results attained. Our civilization, our commerce, our industries, our government, our states, our municipalities, our buildings, our homes, our fight for life, all are combined to make this state of war and to increase the world's efforts toward the goal which it has set for itself,—viz, the happiness of all.

And in this work the engineer stands as the exponent of the highest aims, the leader in some of the most important works, the creator of new methods and processes for the improvement of mankind and its condition, the maker of opportunities never dreamed of, the designer of magnificent monuments and buildings that serve to elevate us and stir us on to the ultimate aim for which we have been created.

But all of this work, all of this designing, all of this execution, all of this leadership,—in fine, all this display of genius,—has not been arrived at without effort, constant and persistent. It has been reached only after studious research and varied experiment of the most serious and assiduous kind, until nature, after opening its great book of laws to the engineer, has, through these very laws, become, together with its materials, his slave for the advancement of the entire race and the personal comfort and benefit of its members.

The engineer has arrived at this very enviable position through a number of causes besides the one of self-preservation mentioned heretofore, but none can be considered of greater importance nor productive of greater results than the technical college and the technical society. It is true that there come into the world some men so vigorous of mind and body, so transcendental in their genius, that they are not in need of the assistance of their fellows; but those men are few and far between, and it must be admitted that the larger proportion owe to education the knowledge with which they are endowed, or the thoughts which emanate from their brains. This is possibly truer of the engineer than of most men, for the engineering knowledge of centuries has been condensed into the knowledge of the present day by constant study of the results attained under the tentative methods that formerly prevailed and by the examination of the various applications of the principles and laws of nature as shown by the works of the great scientists and engineers.

Through the means of the high-class experimental laboratories of the present day, we have peered into the hidden world, into the methods and doings of nature itself, until we have practically discovered all of its great secrets with the exception of the essence of life. But who has preserved all the details of this experimentation? Who has collected the data and the results? Who has verified them? The answer comes quickly and naturally,—the technical college and the engineering society. But they have done more yet, they have conjointly elevated the standard of the profession, improved its ethics and by proper records preserved for all engineers the knowledge, research and investigations of all the engineers of the world.

The great and important duty and work of the technical college in training the youth of this generation in the knowledge necessary for the proper direction of their energies without engaging them in the serious mistakes which must, of necessity, be the result of direction by untrained men. This duty and work need no elucidation, no commendation, no praise from any of us; for the results, the work of its graduates, show for themselves without any words from me. This training is so well recognized as a prerequisite to the acquirements necessary to one who wishes to enter the field of engineering that some of the large machine shops do not take in any other apprentices than young men who have graduated from technical schools of recognized standing, and the requirements for membership in either the American Society of Civil Engineers or the American Society of Mechanical Engineers almost demand such education or its equivalent

Has the technical society done its part of the work? Emphatically, yes. The young engineer leaving college has only been taught correct principles, and informed upon the methods which have been found most successful. But his technical education has fitted him for the battle of life, and particularly for the post-graduate work which he needs in order to keep abreast of the times. It has placed him in a position wherein he can, through correctly directed judgment, discern between right and wrong, technically speaking as well as professionally, and I ask, what are the means at hand for this advanced work, for the study of ever-changing conditions and applications?

Such means are found in the experience acquired by each individual, in the experiences of others, as published in the technical press, in the valuable bulletins and catalogues issued by manufacturing companies, and in the papers presented before the various technical societies of the world. But, by reason of man's tendency toward association, by reason of local interest, of personal acquaintance derived from such association, of the light acquired by discussion between individuals, by reason of the social features attached to such organizations, the Engineering Society is the most attractive of these means of improvement, and we find it increasing in its membership, in the value of the papers presented, in the advantages it offers and in the fraternal feeling it engenders between the various members of the profession.

Considered from the theoretical standpoint, such a society as ours is a rendezvous or meeting place for its members, for an exchange of views, for the discussion of experiences, for the collection of a library and for the presentation of new ideas and their discussion, for a more intimate personal acquaintance, for the consideration of questions of ethics and other matters of interest to its members, for the recognition of services rendered to the profession at large, for the instruction of the world in the ideals which the profession has set for itself, for the exposition of the benefits to be derived from the raising of these ideals and for the education of the younger by the older members,—in fact, the aim of the Society is the general advancement of its members and of the profession at large. Practically speaking, what does such a society as ours bring forth? It gives us all of the above advantages in a greater or lesser degree. The eminent engineer learns to know the younger member from a different point of view than in the light of an assistant; the chief learns of the hidden ability in the more timid employe; the assistant has the opportunity of placing himself properly, possibly in a prominent

way, before the head of his department by correct discussion of matters presented to the Society; the plane of equality upon which they meet opens the door for a more thorough understanding of their dispositions and characters, and the chaff is unconsciously separated, or at least distinguished, from the wheat. The sensible increase of a library, and the improvement in its cataloguing and therefore in its value, and the emulation derived from the consideration of the work done by the other members, form not the lesser advantages to be gained from such association. All these things we have, but we must not stop here. A larger number of members should take active part in the proceedings; the membership should be increased so as to include every member of the profession deserving such membership; the ethics of the profession should be zealously guarded, and, if possible, their standard heightened; the certificate of membership in this Society, although to-day a recognized guarantee of ability and integrity, should become a passport into the most carefully guarded and exclusive places in the world, and the voice of authority should be that of its members.

The Engineering Society owes it to its members to take up and study all subjects of engineering interest that may come up in the natural course of events. It should express itself against all methods that tend to affect injuriously the standard of the profession, and should, without fear or favor, condemn those who, through their conduct, tend to lower that standard. The value of the services rendered by professional engineers should be recognized to be as great as, if not greater than, that of any of the other learned professions, and it behooves the Engineering Society to discredit the men or man who would have us give an opinion for a mere pittance or design some great work for a mere living salary. It owes it to its members to investigate carefully the professional, business and social standing of the men who knock at its doors for admission, for surely integrity, honesty, and conscientious devotion to duty and truth are the necessary attributes of an engineer as well as the qualifications necessary to a gentleman.

In the light of our experience during the latter part of the nineteenth century, in the light of the increased importance of the engineer in our daily life and of the position assumed by him with relation to our industrial life, how can we expect his influence to be *nil* during the next century? For my part, I cannot see in what sphere of action this influence will not be felt. It is now felt throughout the world. There exists to-day neither time nor

distance on this earth. The telephone, the telegraph; the railroad, the steamship; the street car, the automobile; the merchant ship, the battle ship; the magazine rifle, the 100-ton breach-loading gun; the silk dress, the cotton goods; the blast furnace, the cotton mill; the necessities of life, its luxuries,—all these things, and more, owe their existence to the engineer and to his genius of design and application. Can this influence be diminished? The engine of twenty years ago was of 300 H. P.; the engine of to-day is of 5000 H. P. The steamship of a few years ago was a 1200-ton ship; the steamship of to-day is a "Deutschland" or an "Oceanic," with 16,000 tons carrying capacity and 33,000 H. P. of driving machinery. There must and can be no stop in the world's progress. The engineer, as the leader in this march toward the goal of universal happiness, must forever and with vigilance watch the opportunities for advancement and improvement. Sanitary and health conditions must be looked into, so as to lengthen the life of the human race; the cost of the poor man's loaf and of his cotton and woolen goods must be decreased, the productiveness of his labor must be increased; and to the engineer we shall turn as the benefactor of mankind, the promoter of its happiness, the user of the resources of the world, the creator of its opportunities, the framer of its most important destinies.

Editors reprinting articles from this journal are requested to print not only in the JOURNAL, but also the Society before which such articles were read.

ASSOCIATION OF ENGINEERING SOCIETIES.

Organized 1881.

VOL. XXVI.

MARCH, 1901.

No. 3.

This Association is not responsible for the subject-matter contributed by any Society or for the statements or opinions of members of the Societies.

A STUDY IN HYDRAULICS.

BY GEORGE H. FENKELL, MEMBER DETROIT ENGINEERING SOCIETY.

[Read before the Society, May 18, 1900.*]

THE student in hydraulics at first is often led to believe that the formulas for the flow of water through channels of different kinds, through orifices and over weirs, are derived from certain well-known laws, such as those of gravity and friction, whose character and nature have been so thoroughly studied that they admit of little or no variation. His belief in that line is strengthened when he finds how long many of these formulas have been in general use and the number of years they have appeared in precisely the same form in text-books and manuals.

If the subject is pursued farther, however, it will be observed that all have been founded upon, or at least verified by experiments made at different times, by different persons and under various conditions. Many have evolved formulas from their own results, and perhaps a limited number of others that agree with their own fairly well, disregarding those made under as favorable conditions, but which do not seem to follow the same laws.

A large number of formulas have been derived to determine the friction in closed pipes or conduits running full, under pressure, such as cast iron, wrought iron, steel and wood; and so often, in fact, has this ground been beaten over that many, after various attempts to find rules that will fit all cases, have given

*Manuscript received March 14, 1901.—Secretary, Ass'n of Eng. Soc's.

up in despair and gone back to some simple equation, believing, with Hamilton Smith, Jr. ("Hydraulics," page 200), that "It is very doubtful whether one general expression with constant coefficients can be framed, which will, with a fair degree of accuracy, give the value of v — r , s , and the conditions of the wetted surface being known."

It seems probable that, if all the experiments that have been published to the present time had been made with only that allowable amount of error which even the most careful cannot avoid, many of the peculiarities entering into the different formulas would be missing, and that one set of experiments would tend to check another. From the time when Couplet, who was one of the first to recognize the value of accuracy, published the result of his work at Versailles in 1732 ("Récherches sur le Mouvement des Eaux"), down to within a few years ago, very little attempt was made to separate those experiments which had been made with skill and care from those which were but approximations or were the result of careless and indifferent work.

In 1885, Hamilton Smith, Jr., member of the American Society of Civil Engineers, published his "Hydraulics," and in it, for the first time, so far as the author can ascertain, an endeavor was made, by plotting v with c (Chezy formula, $V = c\sqrt{r\bar{s}}$) on squared paper, to pick out those experiments which, by the smoothness of the curve thus obtained, showed accurate and careful work. The result of his investigations led him to believe that the co-efficient c increased in some unknown relation to the velocity, although above one foot per second the increase in c was very slight.

During the past few years several sets of experiments have been made on large pipes of various kinds, and it is the intention of the author to discuss the published results obtained from these, as well as most of those reviewed by Mr. Smith.

In the discussion on "Experiments on the Flow of Water in the Six-Foot Steel and Wood Pipes," etc., by Marx, Wing and Hoskins (Transactions of the American Society of Civil Engineers, Vol. XLIV, December, 1900), the author made some comments on the flow of water in large riveted pipes, and Plates Nos. 7, 8 and 9 of this paper were there presented.

As $V^2 = 2gh$, $h = \frac{V^2}{2g} = H_v$ = velocity head. (The author has used 64.4 as the value of $2g$.) If the loss of head or friction (H_f) varies as the square of the velocity, and the velocity head (H_v) be plotted with the loss of head (H_f) on squared paper, a

straight line through the origin will be the result.* If the line so obtained is not straight, the observed loss of head does not vary as the square of the observed velocity.

In this discussion, the average straight line through a number of points is found by first obtaining the center of gravity of all the points, by dividing first the sum of the ordinates and then the sum of the abscissas by the number of observations. The centers of gravity of these points on either side of this center are then found, and, as these three points lie in a straight line, they determine the average line as given on the plates and in the table. It may be that the method of least squares would have been preferable, as the probable error could have thus been obtained. The method used, however, involves less labor than the former and is much more satisfactory than averaging with a fine thread.

For some time past, many engineers, including those engaged in hydraulic work, have employed some method of plotting to obtain co-efficients or exponents. Dr. Osborne Reynolds presented a paper, "An Experimental Investigation of the Circumstances which Determine whether the Motion of Water shall be Direct or Sinuous, and of the Law of Resistance in Parallel Channels," before the Royal Society of London, March 15, 1883 (Proceedings Royal Society of London, Vol. XXXV, page 84), in which, by plotting the logarithms of the resistances per unit length as abscissas and those of the velocities as ordinates, a straight line results, *provided* the velocity varies directly as some power of the friction. The slope of the line found gives the values of the exponent. Professor Edwin C. Pickering, Director of Harvard College Observatory, has for many years plotted by means of logarithms, and in 1893 John R. Freeman, M. Am. Soc. C. E., Member of the Boston Society of Civil Engineers, prepared lithographed sheets drawn to a logarithmic scale on both abscissas and ordinates, which admit of a wide use, and have been extensively used by Mr. Freeman and others in experiments on flow of water.†

*The most satisfactory way of converting velocities into velocity heads is by means of diagrams made on sheets of cross-section paper about 16 x 20 inches. Plot enough points from a table to give an accurate curve, and if necessary increase the scale for low velocities. When more convenient the square of the velocity may be used instead of the velocity head.

†These sheets are 20 x 20 inches, ruled both to a 10-inch and a 20-inch base, and the scale and print are remarkably good. The author is indebted to Mr. Freeman for several sheets.

Rudolph Hering, M. Am. Soc. C. E., Member of the Boston Society of Civil Engineers (Transactions American Society of Civil Engineers, 1879), published several diagrams in a paper, "The Flow of Water in Small Channels, after Ganguillet & Kutter," etc., and similar diagrams were published by Arthur N. Talbot, Member of the American Society of Civil Engineers (*Engineering News*, August 11, 1892), in an article, "Diagrams for Flow in Pipe Sewers," and by F. S. Bailey, in "Diagram for Discharge of Two-to Seven-Foot Brick Conduits Flowing Full" (*Engineering News*, November 15, 1894), in which the velocity or quantity is plotted at an arithmetic scale on the ordinate and the grade or slope at a logarithmic scale on the abscissa, the different sizes being represented by a diagonal line.*

In Diagrams "A" and "B" in the "Graphical Solution of Hydraulic Problems" (New York, 1897), Freeman C. Coffin, M. Am. Soc. C. E., Member of the Boston Society of Civil Engineers, employs logarithmic ruled paper to determine graphically the increased friction in old pipes over that in new ones.

The advantages in using logarithmic ruled paper are many, especially for the purpose of obtaining fractional exponents, and diagrams that could otherwise be represented only by curves of a complicated nature are much simplified; but for the case at hand, to study graphically the relation existing between velocity and friction in closed pipes, and especially the initial error in the observations or reductions, if such exist, the author believes the method adopted in this paper to be at least as simple and, owing to uniformity of scale, more easily comprehended by inspection than any other yet published. It was first suggested in 1897 by Gardner S. Williams, M. Am. Soc. C. E., Member of the Detroit Engineering Society, and used quite extensively by him and by Mr. C. W. Hubbell, Assoc. M. Am. Soc. C. E., Member of the Detroit Engineering Society, and the author in reducing experiments on frictional loss in curves of different radii in large cast iron pipe.

It is very difficult to obtain a series of experiments on as complicated a subject as the flow of water through pipes without some errors entering into the results; but many of these errors, under ordinary conditions, such as air in gage connections, calibration of instruments and leaks in instruments and connections, are nearly constant for all velocities; while others, such as personal error of observers, tend to balance each other. As nearly

*Since presenting this paper, a somewhat similar diagram appeared in an article "Diagram Giving Discharge of Pipes by Kutter's Formula," by John H. Gregory, Jun. Am. Soc. C. E. (*Eng. Record*, Nov. 3, 1900).

all experimental results include some of these errors, it is hardly to be expected that, even if H_f varies as the square of the velocity, the resulting line will pass *exactly* through the origin. The equation will, therefore, become $H_f = aH_v^2 + b$, in which b is a constant for each set of experiments and indicates the distance from the origin at which the line cuts the H_f axis. If we move this line, parallel with itself, until it passes through the origin, it will then represent the relation existing between H_v and H_f .

There are many things that may affect the final results obtained to such an extent that when H_v and H_f are plotted together some kind of a curve will result, and it is evident that, when such is the case, it is impossible to transform them into a straight line. It seems possible that peculiarities of this kind may have been sometimes caused either by the effect of curvature in the line of pipe experimented upon or by errors made in determining q , v or H_f . Many of these experiments were gaged by means of weirs or orifices, and, judging from the discussion in various articles which have recently appeared, it seems possible that co-efficients were used which may have been in error several per cent. In the following plates, points which do not plot straight are connected with a broken line.

In this paper the author has deduced the values of c in the Chezy formula. If the relation between H_v and H_f can be represented by a straight line passing through the origin, $H_v \propto H_f \propto s$. If $v = c\sqrt{rs}$, $c = \sqrt{rs}$. As $v^2 \propto H_f$, and as r is constant for each size of pipe, c will remain the same for all velocities in the same pipe. This constancy of c holds good in any formula of the form $v = cr^x s^y$ provided $y = 2$.

On the following plates, all the experiments which the author has been able to plot in this way are shown at various scales. Many experiments, however, which have been conducted with great care are omitted in this discussion because there is not enough range in the velocities used, to determine accurately the locus of H_f and H_v . It is also necessary that this range in velocities should be made on the same section of pipe, covering as short a period of time as possible, as the various effects of curvature in different lines, and the ever-changing conditions of interior surface, may cause considerable variations. Many of the experiments made by Clemens Herschel, M. Am. Soc. C. E., on the riveted pipes of the East Jersey Water Company ("115 Experiments" by Clemens Herschel) are omitted here for this reason. It may be that some experiments that should have been

included have been entirely overlooked by the author. It is believed, however, that no serious omissions have been made.

Table I, accompanying the following plates, is self-explanatory. The equation of the average straight line, as shown on the plates, is:

$$H_f = aH_v + b,$$

and, when moved parallel with itself until it passes through the origin, it becomes:

$$H_f = aH_v.$$

Multiplying the velocity head, of any velocity, by a , the product is the loss of head per 1000 feet of pipe. Column 14 contains a , and Column 15 contains b in the foregoing equations. Column 16 contains c , as figured from H_f . As explained before, c is constant for all velocities. It is not the intention of this paper to advance the formula just mentioned as one to be used in every-day practice for estimating friction, discharge, etc., as the range in the values of a entirely unfits it for such a purpose. Neither is it the author's intention to cast discredit on any set of experiments. As the name of this paper indicates, it has been the author's aim to throw more light on this important subject in hydraulics by a systematic study of previous experiments. It has been claimed that the *ideal* formula is $v = c r^x s^y$, in which x and y have such values that c will be independent of the size of pipe and of different slopes of the same pipe. This can be possible only if y remains constant for all sizes of pipes.

The question has often been discussed, whether the friction varies as the square of the velocity, and many attempts have been made to prove or disprove this proposition. The author will not attempt to analyze any of these discussions, but will mention a few of the most recent papers which have attempted to solve this problem.

1. In a very interesting paper by William E. Foss, member of the Boston Society of Civil Engineers, "New Formulas for Calculating the Flow of Water in Pipes and Channels" (JOURNAL OF THE ASSOCIATION OF ENGINEERING SOCIETIES, June, 1894), from the line obtained by plotting the logarithm of v with the logarithm of s (see Plates 1 and 2 of that paper) on squared paper, it is found that $v^{1.75} \propto s$.

2. Desmond FitzGerald, M. Am. Soc. C. E., Member of the Boston Society of Civil Engineers, deduced from the results of his experiments on the 48-inch cast iron Rosemary pipes ("Flow of

Water in Forty-eight-Inch Pipes," Transactions American Society of Civil Engineers, Vol. XXXV, 1896) that

$\tau \propto s^{2.42}$ when tuberculated, and

$\tau \propto s^{1.41}$ after being cleaned.

Plate 6 shows these experiments, together with those made on the same pipe by F. P. Stearns, M. Am. Soc. C. E., when new in 1885. These two series were conducted with great care and are among the best that have ever been published. It will be observed, from Mr. FitzGerald's results, that $\tau^2 \propto H_f$ very nearly, and even if plotted to a much larger scale than shown in Plate 6, it will be seen that the point falls in a straight line with remarkable precision.

3. In "The Flow of Water in Pipes," by C. H. Tutton, member of the Engineering Society of Western New York (JOURNAL OF THE ASSOCIATION OF ENGINEERING SOCIETIES, October, 1899), by the use of logarithms, plotting on squared paper, he finds that if $\tau = cr^m s^n$, c will remain constant; that is, that $\tau \propto s^{.51}$.

4. Mr. M. E. Sullivan ("New Hydraulics," Denver, 1900) assumes, as one of the laws of friction as applied to a liquid in contact with a solid: "The friction on any given unit of surface will increase as the square of the velocity." An attempt is made to prove by theory, and to substantiate by a limited number of pipe experiments, that, if $\tau = c\sqrt{r^3}\sqrt{s}$, c will remain constant.

All of these papers and discussions make the assumption that, in all experiments, the curve representing the relation between friction and velocity, if plotted from the actual observation, will pass through the origin. The author believes this assumption to be generally somewhat in error. As has been explained before, if a series of observations, as plotted on the following plates, fall in a straight line passing through the origin, $\tau^2 \propto H_f$: If the following plates are carefully examined, it will be found that most of the best experiments on large pipes plot straight, although none pass exactly through the origin. There are exceptions, however, in the smaller sizes.

Plate 19 shows experiments on two kinds of mill hose, by John R. Freeman, M. Am. Soc. C. E. (Transactions of the American Society of Civil Engineers, Vol. XXI). Their accuracy is beyond question, but the line of their points is slightly curved.

Although most of the experiments on large pipe plot straight, it will be observed that many, made on smaller pipes, are more or less curved (many of these were made by Mr. Darcy; see Plates 3, 5, 11, 13, 14 and 18), and some of those which the author has

reduced to straight lines show a slight arc. This indicates that H_f does not vary as v^2 . In several sets, a line passing through the observations forms a sine curve, which appears much plainer if plotted to a larger scale. (See Plate 5, No. 11; Plate 7, Nos. 19, 20 and 21; Plate 8, No. 23; Plate 11, No. 30; Plate 12, No. 29; Plate 13, Nos. 35 and 37; Plate 16, No. 40, and Plate 17, Nos. 44 and 45.) These have all been averaged straight, as the variation is so slight. It must be admitted, however, that whether straight, as the larger pipes show, or slightly curved, as a few of unquestionable accuracy plot, they should pass through the origin; for, if there is no velocity, there should be no friction. In other words, if v and H_f are plotted on cross-section paper, a curve is the result. If it does not pass through the origin it should be moved in some way until it does; or, if H_v is plotted with H_f , as shown on the accompanying plates, the line, whether straight or curved, passing through these points must pass through the origin if we eliminate what error we can. If a straight line will represent an average of the points, the constant in its equation should be eliminated, thus making c (in Chezy formula or any other formula of the form $v = cr^x s^y$, in which $y = 2$) constant for all velocities; or, if slightly curved, this curve should be moved until it passes through the origin, whence c will vary slightly with different velocities, although much less than has generally been computed. When co-efficients in any formula for the friction in pipes are obtained for each observation, they will generally be found to be of much less practical value than when the entire set is taken as a whole, and when one co-efficient is deduced, representing, as nearly as may be determined, a general average after making all possible corrections.

All values of a ($H_f = aH_v = b$), and c ($v = c\sqrt{rs}$), as published in the table, are shown graphically on Plate 21, and, if examined carefully in connection with the other plates, many peculiar variations will be noted which can hardly be accounted for by reasons ordinarily advanced.

The following are a few velocities, with their respective velocity heads, which may aid in understanding the plates:

Velocity in Feet per Second (v).	Velocity Head in Feet (H_v).
0.5	0.0039
1.0	0.0155
1.5	0.0349
2.0	0.0621
2.5	0.0970
3.0	0.1398
4.0	0.2485
5.0	0.3882
6.0	0.5590
7.0	0.7609
8.0	0.9938

TABLE No. 1.
TABLE OF PIPE EXPERIMENTS COLLECTED AND TABULATED BY GEO. H. FENKELL, 1900.

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
PIPE NO.	SERIES NO.	CHAMBER NO.	WHERE FOUND	AUTHOR.	MADE BY	DATE.	RANGE OF VELOCITIES	VELOCITIES MEASURED BY	Kind	Diam	Length.	No. OF OBSERVATIONS.	Value of a.	Value of b.	Value of c.	Lowest.	Highest.	CONDITION
													$v = c \pm b$	$v = c \pm 15$				
1	1	20-215	Hydraulics	H. Smith, Jr	Darcy	1849-51	0.3-10.7	Tank	Cast Iron	0.2687	366.1	13	95.990	+ 0.305	100.3	75.1	100.5	New
2	2	219-228	"	"	"	"	0.5-15.4	"	"	0.4495	365.7	10	45.003	+ 0.139	112.8	94.1	113.5	"
3	3	222-137	"	"	"	"	0.7-16.2	"	"	0.6168	375.4	9	35.403	+ 0.357	108.5	99.3	106.0	"
4	4	221-137	"	"	Iben	1874-99	1.0-31.7	"	"	1.004	17684.0	4	20.843	+ 0.415	116.3	109.5	120.0	Coated with asphaltum.
5	5	211-74	"	"	"	"	1.0-31.1	"	"	1.004	17684.0	4	20.211	+ 0.523	112.5	89.3	102.7	"
6	6	222-278	"	"	Lampe	1870	1.6-3.1	Reservoir	"	1.373	25,441.0	4	13.900	+ 0.061	116.5	110.5	110.4	Smooth varnish.
7	7	222-285	"	"	Stearns	1885	2.6-6.2	Weir	"	4.000	1747.2	4	3.113	+ 0.212	143.8	140.1	146.7	Coated with asphaltum.
8	8	170-185	"	"	Darcy	1849-51	0.2-2.1	Tank	"	0.1179	374.9	7	625.399	+ 0.027	59.1	58.1	61.7	Old; uncleaned.
9	9	180-182	"	"	"	"	0.4-3.7	"	"	0.1194	374.9	7	217.597	+ 0.766	94.5	80.5	99.1	" the above cleaned.
10	10	181-168	"	"	"	"	0.4-3.7	"	"	0.2068	374.9	7	211.597	+ 0.177	92.0	89.9	92.0	" uncleaned.
11	11	192-205	"	"	"	"	0.6-5.0	"	"	0.2628	366.3	7	112.973	+ 0.376	93.2	86.2	93.2	" the above cleaned.
12	12	215-218	"	"	"	"	1.0-12.6	"	"	0.7979	365.3	8	57.041	+ 0.017	75.3	73.6	78.8	" uncleaned.
13	13	216-213	"	"	"	"	0.9-14.7	"	"	0.8028	365.3	8	33.761	+ 0.041	97.7	86.3	99.8	" cleaned.
14	14	215-201	"	"	"	"	0.8-10.4	"	"	0.9744	365.3	8	24.376	+ 0.026	104.1	96.9	105.5	Very well cleaned
15	15	215-201	"	"	"	"	0.8-21.8	"	"	1.107	12,700	7	73.455	+ 0.133	97.4	98.6	130.3	8 years old, tuberculated.
16	16	181-181	Graf Sol of Hyd Problems, Coffin	Fitzgerald	Fitzgerald	184-5	0.2-3.5	Weir	"	4.00	1615.7	21	5.544	+ 0.004	107.5	88.6	114.8	Old, tuberculated.
17	17	XXV-XXXI	Trans. Am Soc C. E., 1869	"	"	"	0.2-3.5	"	"	1615.7	5	5.911	+ 0.004	104.4	101.2	107.1	"	
18	18	XXV-XXXI	"	"	"	"	3.7-5.6	"	"	1615.7	5	5.457	+ 0.023	108.6	109.8	115.7	"	
19	19	XXV-XXXI	"	"	"	"	0.4-7.2	"	"	1615.7	21	3.172	+ 0.002	142.5	143.6	143.6	Very well cleaned	
20	20	34-31	Hydraulics	H. Smith, Jr	H. Smith, Jr	1877	17.1-0.0	"	Riveted	0.611	684.9 10	5	20.177	+ 1.869	115.4	107.1	115.5	Quite smooth.
21	21	34-31	"	"	"	"	4.5-10.1	"	"	1.056	684.9 10	4	18.495	+ 0.485	122.8	109.4	114.4	"
22	22	49-51	"	"	"	"	4.4-12.1	"	"	1.230	684.9 10	6	13.742	+ 0.954	93.5	116.6	121.5	"
23	23	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	2.1-5.0	Venturi	"	3.50	511.00 10	11	6.076	+ 0.051	110.1	109.1	110.1	New
24	24	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Kuchling	Kuchling	1867	0.5-1.2	Reservoir	"	3.167	493.00 10	6	6.349	+ 0.006	113.2	109.1	116.6	"
25	25	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Mark Wing & Hoskins	Mark Wing & Hoskins	1867	0.5-1.8	Venturi	"	6.02	4367.10	29	3.866	+ 0.0079	195.5	68.	137	"
26	26	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Mark Wing & Hoskins	Mark Wing & Hoskins	1867	0.7-5.4	"	"	6.02	4367.10	39	3.866	+ 0.0079	195.5	68.	137	"
27	27	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
28	28	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
29	29	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
30	30	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
31	31	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
32	32	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
33	33	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
34	34	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
35	35	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
36	36	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
37	37	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
38	38	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
39	39	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
40	40	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
41	41	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
42	42	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
43	43	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
44	44	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
45	45	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
46	46	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
47	47	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
48	48	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
49	49	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
50	50	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
51	51	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
52	52	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
53	53	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
54	54	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
55	55	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
56	56	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
57	57	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
58	58	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
59	59	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
60	60	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
61	61	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
62	62	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
63	63	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
64	64	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
65	65	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
66	66	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
67	67	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
68	68	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867	0.5-4.5	"	"	5.55	4427	39	2.567	+ 0.001	106.1	105.6	106.1	"
69	69	219-227	ITS Experiment-Rochester Am Soc C. E., 1867	Herschel	Herschel	1867												

PLATE 1




PLATE 2




PLATE 3





PLATE 4









PLATE 17




PLATE 18




PLATE 19






PLATE 21



DISCUSSION.

MR. ALLEN HAZEN.—The paper of Mr. Fenkell takes up some very interesting problems of the flow of water in pipes. The method of plotting the velocity heads with the friction heads is most interesting. The observation that the points so plotted are generally in a straight line, and the supposition that the distance which this line passes from the origin represents constant error and can be eliminated by drawing another line parallel to it and through the origin, is very interesting and undoubtedly correct in some cases.

The question of the revision of the formula of the flow of water in pipes is always interesting. If we take the general formula $V = CR^x S^y$, suggested by Tutton in the JOURNAL OF THE ASSOCIATION OF ENGINEERING SOCIETIES, Vol. XIII, page 151, it will be agreed by every one that the value of C is not constant, but must vary according to the condition of the surface of the pipe and other circumstances; but perhaps the variation depends more upon the accuracy with which the values of x and y are taken than upon any other conditions. If correct values of x and y are taken, C will vary but little for a given condition of interior surface, while with values of x and y far from the truth the variations in C will be greater and more difficult of analysis.


In the Chezy formula x and y are each taken as 0.50. This value for y appears approximately correct. For x it is certainly too low, for the value of C increases with the value of R with considerable regularity. In Kutter's formula for determining the value of C in the Chezy formula, C is made to increase with R , and to such an extent that, for ordinary pipe sizes, and with other conditions remaining the same, V varies nearly as $R^{0.75}$. In Sullivan's formula, which is mentioned by Mr. Fenkell, x is taken as 0.75. As a matter of fact, I believe that 0.75 is nearly as much too large as 0.50 is too small. Tutton, as a result of a discussion of old data by a new and very interesting mathematical method, found, for iron pipe, $x = 0.66$.

A method of estimating the value of x , which occurred to the author before he saw Tutton's paper, and which resembles somewhat Tutton's method, although the procedure is a little different, is the following: The value of y is assumed to be 0.50, and on this assumption the velocity of water in each size of pipe is computed for $S = 0.001$. That is to say, for the purpose of discussion, the various experiments are reduced to a constant value for S . This slope of 1 in 1000 was selected as convenient and as representing approximately the average slope in actual work,

although this is not essential. The velocities for $S = 0.001$ are then plotted on logarithmic paper with the sizes of pipe in inches. If the points should prove to be in an approximately straight line, the values of x and C could be determined from it and would be constant. Such a diagram, showing the results given in Fennell's paper, is given herewith (Plate 22). I have followed Fennell in his computation of constant error, and have taken into account only the value of the ratio between the velocity head and the friction, and from this I have computed, in each case, the velocity for $S = 0.001$. I have also plotted, upon the same scale, velocities given by Fanning for this slope, with the various sizes of pipe, and also the velocities shown by Weston's tables. Weston's tables do not show the precise velocity corresponding to a slope of 1 in 1000, so this value has been computed from the nearest values given. The corresponding velocities, computed by Kutter's formula, with n respectively 0.009, 0.011, 0.013 and 0.015, are also shown. This diagram shows clearly that Kutter's formula is not adapted to the computation of the flow of water through pipes, as with it the value of n varies almost as much as the value of C varies in Chezy's formula; and the use of Kutter's formula thus increases the complexity of computation without increasing the accuracy.

The tables of Weston and Fanning agree in a general way with each other, and with the experimental results herewith shown; but the minor curves in them are hardly warranted by any experimental data, and probably the straight line corresponding to the formula $V = 130 R^{0.625} S^{0.50}$, which I have added, and which differs but little from them, is quite as accurate and more consistent.

It is, of course, not to be supposed that any formula could be derived in which the value of C would be constant; but if a formula should come into use in which the value of x was more nearly correct than in the Chezy formula, the variations in C would be correspondingly reduced, and discussion of results would become more satisfactory and more likely to lead to a correct understanding of the conditions controlling the flow. The value of x is certainly more than 0.50 and less than 0.75. Perhaps the existing data are not such as to warrant a very close approximation to an average value; but a figure could certainly be taken which is more nearly correct than the 0.50 used in the Chezy formula. It may be that originally the convenience in computation led to the selection of the exponent 0.50; but, with the facilities afforded by slide rules and logarithmic paper, there is



although this is then plotted on. If the points show the values of x constant. Such paper, is given his computation only the value of friction, and for $S = 0.001$. The values given by the pipe, and also the tables do not of 1 in 1000, values given. The formula, are also shown. The formula is not through pipes. The value of C in the formula thus increasing the

The table with each one shown; but the experimental data to the form which differ is consistent.

It is, of course, derived in the formula should be nearly correct. It would be correct and would be correct and the value of x in the existing formula. The information taken which led to the formula. The facilities and

certainly no longer reason for continuing to use a round but incorrect figure because of the facility of computation.

In connection with the flow in very small pipes, it should be remembered that, with capillary tubes, x becomes 2 and y becomes 1, while the value of C depends in large measure upon the temperature of the water and its consequent viscosity. The conditions which control the friction in such tubes are undoubtedly quite different from those in large pipes, but it may be expected that the values of x and y will increase somewhat with very small pipes. Darcy's formula takes this into account in some measure, and new experimental investigations of the friction in small pipes would be of considerable interest.

In computing the actual flow of water through pipe lines, the following procedure has been found convenient: A table is prepared of the velocities and discharges in gallons per 24 hours for pipes of various sizes when the slope equals 0.001. To this is added a column showing those lengths of pipe in feet, in which the frictional loss is equal to the velocity head. As both the friction and the velocity head increase as the square of the velocity, this length is the same for all velocities. The following is such a table, based upon the heavy line in the diagram:

TABLE No. 2.
FLOW OF WATER IN PIPES.
When $S = 0.001$.

$$V = 130 R^{0.625} S^{0.50}.$$

Diameter in Inches.	Velocity, Feet per Second.	Gallons Daily.	No. of Feet of Pipe in which Friction Head is Equal to the Velocity Head.
1	0.37	1,300	2
2	0.56	8,000	5
3	0.73	23,000	8
4	0.87	40,000	12
6	1.12	142,000	20
8	1.34	303,000	28
10	1.54	544,000	37
12	1.73	877,000	47
16	2.07	1,867,000	67
20	2.38	3,354,000	89
24	2.67	5,412,000	111
30	3.06	9,720,000	147
36	3.43	15,000,000	184
42	3.78	23,510,000	224
48	4.11	33,400,000	264
54	4.42	45,500,000	306
60	4.73	60,000,000	350
72	5.30	97,000,000	440
84	5.83	145,000,000	533
96	6.34	206,000,000	630

This table is used with the slide rule as follows: The loss of head due to bends in pipe, entrance velocity, etc., in addition to the loss by friction in straight pipe, is usually expressed in multiples and fractions of the velocity head. These fractions are computed in the usual way and added up for the entire line, and the sum is multiplied by the length of pipe in the last column. The length so obtained is the length of straight pipe in which the friction loss is equal to the additional losses in the particular case under consideration. In other words all loss of head due to special resistance is reduced to an equal loss by friction in straight pipe. This computed length is added to the actual length of pipe, giving the length of straight pipe of equal resistance to the actual pipe line with bends, etc. One-thousandth of this length is the loss of head in feet, when the velocity and discharge are the amounts shown for that size pipe in the table. The index of a slide rule is put upon this amount (that is, the head) on the upper scale, and the moving part is set so that the marker shows the discharge in gallons, or the velocity in feet per second, on the lower or square root scale. If another value of C is desired, as, for instance, 100 instead of 130, for steel pipe or old tuberculated pipe, the scale can be moved a corresponding amount. The index can then be moved to show other heads and quantities, which can be taken off without further setting. This short table is readily put in a notebook, and with it and a slide rule the flow of water in pipes can be computed quickly and perhaps as accurately as by other methods.

MR. CLARENCE W. HUBBELL.—The writer desires to add his testimony to the statement of the author that the failure of the locus of the ratio existing between velocity head and frictional loss, to pass through the origin, indicates the presence of an initial error which should be eliminated before final reductions are made and conclusions drawn therefrom. During the past two years the writer has conducted a number of experiments on comparatively short lengths of cast iron water pipe connected with the distribution system of the Detroit Water Works, in which very delicate, specially designed and carefully calibrated difference gages were used, capable of indicating a loss of head corresponding to 0.002 of a foot of water on single readings, and much closer results when a number of readings were averaged. It was in each case possible to test the gages and gage connections under a condition of absolutely no flow, which should have given zero readings. The gages, however, could seldom be brought to read absolute zero, although a careful inspection would frequently bring to light some unus-

pected leak or air bubble, the elimination of which tended to correct the apparent error.

In a series of observations on twenty-one consecutive sections of 30-inch pipe, the longest section being 667.86 feet and the shortest 23.51 feet, the observed frictional loss, with absolutely no flow, was: In four lengths, zero; in seven lengths, positive; in ten lengths, negative.

If the gages had never indicated zero, or if the apparent error had always been of the same sign, the failure to close might have been explained by some theory of internal motion. Under the circumstances, however, the only reasonable explanation seems to be that an initial error did exist in the gages or gage connections. In almost every case it has been found necessary to eliminate the initial error in order to obtain comparable results. In short lengths of large pipe, the error, while small in actual quantity, was frequently equal to the frictional loss corresponding to an initial velocity of one foot per second.

A constant initial error can be readily eliminated by the method adopted by the author, if the assumption that $H_f \propto H_v$ holds true; and this assumption seems to be fairly well established, within reasonable limits of error, for sizes of pipe above 12 inches in diameter.

However, errors which do not remain constant during a series of observations tend to make the locus of $\frac{H_f}{H_v}$ a curved line, and therefore cannot be eliminated by such a simple method. Indeed, it is usually impossible to eliminate such errors by any process of reduction whatever.

As to the two methods of plotting,—i.e., $\frac{H_f}{H_v}$ and $\frac{\log H_f}{\log 1}$,—the writer believes that each system has its strong and its weak points. The first method (that adopted by the author) exaggerates errors at the upper end of the series and minimizes those near the zero point, which seems to the writer preferable to the exactly opposite tendency of the second method.

Again, the first method will detect and eliminate any initial error which remains constant throughout a series of observations, while the presence of such an error will cause the locus obtained by the second method to be a curved line convex on the upper side ($\log H_f$ vertical ordinate):

(1) When H_f , as observed, contains a negative error or is less than the true frictional loss.


(2) When the velocity contains a positive error, or is greater than the true velocity, and concave on the upper side:

(3) When H_f , as observed, contains a positive error or is greater than the true frictional loss.

(4) When the observed velocity contains a negative error or is less than the true velocity.

On the other hand, as stated by the author, if no errors be present in the observations, a curved line, obtained by the first method, indicates that the frictional loss does not vary as the square of the velocity, but according to some other power which may be obtained by the second method. It therefore seems to the writer that, taking everything into consideration, the best general results are likely to be obtained by using the first method in reducing observations on pipes of large diameter, and the second method for those of small diameter, while in certain cases a combination of both methods may be used to advantage.

PLATE 23



The method used by the author in determining the average straight line, represented by a number of observed points, has one thing in its favor not mentioned by him,—viz, the fact that numerical results obtained are checked graphically where the three points are plotted. For, if they fall in an absolutely straight line, it is sufficient proof that no appreciable errors have entered into the derivation of ordinates; while, on the other hand, if they fail to fall in a straight line by ever so little, it is at once apparent that the reductions are in error and must be recomputed.

Plate 23 gives the results of an experiment on 2000 feet of 12-inch cast iron water pipe at very low velocities. The frictional loss was determined with extreme accuracy, to be used relatively with other results.

Incidentally, the velocity was computed from the register of a new 6-inch Thomson meter, in good condition, but which

has never been rated. Errors, if any, are those due to the error in registry of an ordinary 6-inch Thomson meter.

The observed points are numbered and plotted by both methods, thus illustrating the exaggeration of each system. The value of C , in $V = c\sqrt{rs}$, is 115.9, obtained by the method employed by the author, and averaging the four highest points.

The results are also given in Table No. 3:

TABLE No. 3.

EXPERIMENTS ON FLOW OF WATER THROUGH 2000 FEET OF 12-INCH TAR COATED CAST IRON WATER PIPE CAREFULLY LAID TO LEVEL GRADE.

No. Readings Taken.	Loss of Head in Feet (H_f) per 2000 Ft.	Log. H_f .	Velocity, Feet, per Second.	Log. Velocity.	Velocity Head in Feet (H_v)	$\frac{V}{C\sqrt{rs}}$
34	0.00102	-3.008600	0.01050	-2.021189	0.0000017	20.41
18	0.00504	-3.702431	0.01790	-2.252853	0.0000049	22.56
29	0.02268	-2.355043	0.13106	-1.120574	0.000269—	78.55
28	0.02516	-2.400711	0.15140	-1.180126	0.000556	85.39
28	0.08628	-2.935910	0.32586	-1.513084	0.001648+	90.19
30	0.28209	-1.450388	0.63158	-1.800442	0.0062000	100.32
40	0.48842	-1.088794	0.85831	-1.933639	0.011449	100.85
36	0.72661	-1.861301	1.06685	0.028124	0.0176897	111.00
38	0.74832	-1.874088	1.08571	0.035124	0.0183208	112.30

MR. GARDNER S. WILLIAMS.—Inasmuch as the writer was in a measure responsible for starting the investigation, the results of which have been presented in the paper entitled "A Study in Hydraulics," he feels that he may very properly apologize to a long-suffering public for the presentation again, below, of experiments that have been discussed by almost every writer on the subject of hydraulics since the close of the last century. No one realizes more fully than he that if one-half the time and energy that has been spent in discussing old and questionable observations had been expended in making reliable ones, the science of hydraulics would be much further advanced to-day, and no one more heartily appreciates the feelings of an eminent hydraulic engineer who recently exclaimed: "In the name of nineteenth century progress let us get through telling what the Abbé Bossut did in 1776." Nevertheless, if, after all its threshing over, there still remain, among the mass of chaff and straw, some kernels of grain that have escaped the sifting of those who have labored before, the writer feels that he is warranted in making one more examination of the well-worn data, and having, as he believes, found therein some evidence of the existence, not of new laws, but of some that have been apparently forgotten, or overshadowed by more recently discovered

ones, he offers this as his excuse for calling attention again to those old experiments of Bossut and others.

The assumption that the loss of head of water flowing in pipes of uniform cross section varies as the square of the velocity, upon which the investigation presented by the author is based, is the same as that upon which the Chezy and nearly every other flow formula rests, and is one that has been tacitly accepted with practical unanimity in nearly all hydraulic discussions; and, while such acceptance does not prove the assumption to be correct, it nevertheless goes far toward showing that, for the cases coming within ordinary practice, it is not very seriously in error. But in these days of rigorous requirements in all lines of investigations, it is in every way desirable that the correctness or incorrectness of all such assumptions be determined, and, if there are limits to the application of them, that those limits be ascertained as well.

The plates presented by the author show that in many of the series studied the line $H_f = a H_v$ does not pass through the origin, and this the author attributes to errors of observation. Such an interpretation is probably, in a measure, correct in every case, but the presence of an intercept $\pm b$ has another possible signification, *i.e.*, it may indicate curvature of the locus which is so slight as to be imperceptible except close to the origin, or in other words it may indicate that H_f does not vary exactly as H_v or V^2 . Referring to Fig. 2, Plate 24, it will be seen that if $H_f \propto V^{1.50}$ there is an intercept $+b = 0.7371$; if $H_f \propto V^{1.80}$ the intercept is $+b = 0.5519$; if $H_f \propto V^{1.90}$ the intercept $+b = 0.3191$, and if $H_f \propto V^2$ the intercept is zero and the line passes through the origin. From this it is at once apparent that the presence of a negative intercept on the H_f axis, or a positive one on the velocity head axis, may indicate that H_f varies as a higher power of V than the square. In examining the author's plottings, it is noticeable that in only twelve cases,—less than 20 per cent.,—does the line $H_f = a H_v \pm b$ cut the velocity head axis; *i.e.*, have a negative b and in all of these except 14a and 59 the intercept is so small that it may almost be neglected. In 59 it will be noted that the diameter is very great, and in five of the others giving a negative b the diameter is greater than 3 feet; on the other hand the $+b$ intercepts are numerous and many of them of considerable magnitude, and are confined, with few exceptions, to the smaller sizes of pipe. The uniformity with which these $+b$ intercepts appear on the smaller sizes is fair ground for the assumption that they are due to something more than errors of observation, since it is hard to account for the net result of such errors being always

of the same sign. This, taken with the fact pointed out by the author, that experiments with small diameters do not give straight lines when H_f is plotted to the velocity head, has led the writer to investigate this phase of the subject and to enquire whether any relation exists between the diameter and the exponent of V in $H_f = M V^n$ and if so, how the relation is affected by roughness and curvature in the pipes.

Reviewing the history of the matter we find that Prony, about the beginning of the present century, began to recognize the fact that the losses of head in flowing water did not vary exactly as the square of the velocity, and, in the Proceedings of the Royal Society for 1808, Dr. Thomas Young, in discussing his investigations upon the flow of water in pipes, says: "I began by examining the velocities of the water discharged, through pipes of a given diameter, with different degrees of pressure, and I found that the friction could not be represented by any single power of the velocity, although it frequently approached to the proportion of that power of which the exponent is 1.8, but that it appeared to consist of two parts, the one varying as the velocity and the other as its square. The proportion of the parts to each other must, however, be considered as different, in pipes of different diameters, the first part being less perceptible in large pipes or in rivers, but becoming greater than the second in very minute tubes, while the second also becomes greater for each given portion of the internal surface of the pipe, as the diameter is diminished." Dr. Young had at his disposal only the experiments of Couplet, Bossut, DuBuat, Gerard, Gerstner and himself, all of which were made with small pipes, except those of Couplet, which were confined to very low velocities.

In 1855, before the Institution of Civil Engineers,* discussing DuBuat's formula, we find Mr. Thomas Hawksley quoted as follows:

Reporter's Abstract.—"Mr. Hawksley was not aware of ever having stated, and he certainly never intended it to be understood, that the formula was applicable to all cases. It was applicable, however, to all cases which fell within the ordinary practical application of hydraulic science; but it was not applicable for those extreme cases of minute diameter and sluggish velocity, in which what ought to be really termed the friction of water, required to be taken into account. What was usually denominated friction, by writers on hydraulic science, was not friction at all, but was a resistance of impact, which varied as the square of velocity, and

*Min. Proc. Inst. C. E., 1855.

that was the great resistance experienced in the conduct of water, and was that given by the formula. In addition to this, there was another resistance which only varied as the simple velocity,—the resistance of adhesion or viscosity, as it had been called, but in reality of friction proper.”

But having got so far in the explanation of phenomena of flow, Mr. Hawksley was led astray into the acceptance of the then universally adopted theory of DuBuat, of the fluid envelope and consequent non-effect of character of surface of the inclosing conduit, which later investigations, particularly those of Darcy, have shown to be wholly erroneous. The idea of two kinds of resistance to be dealt with is considered in some of the older formulæ of flow, although the terms providing for the real friction, were, in ordinary cases, so insignificant that the older hydraulicians themselves frequently omitted them, and in the popular Chezy formula they are wholly unrecognizable, the variation of the coefficient C being relied upon to provide for them. Mr. Edmund B. Weston, member American Society of Civil Engineers, after a very painstaking and exhaustive investigation of existing experiments, published in Volume XXII, Transactions American Society of Civil Engineers, concluded that the formulæ which best fitted the experiments with large pipes were not satisfactory for small ones, and for such pipes proposed a formula involving V^2 and V^3 .

The writer has no inclination to present any new formulæ for the flow of water in pipes; but, continuing in the line of Mr. Hawksley's reasoning, with the advantage of our present and more correct knowledge of the influence of roughness of surface, he would call attention to the fact that the recent investigations as to the effect of such roughness have in a measure overlooked the co-existing effect of diameter. Hamilton Smith, Jr., has stated that C in the Chezy formula increases with the diameter and with the velocity. If the deductions of the author are correct, or even approximately so, they force us to account for the variation of C by the changes in diameter alone, leaving out, for the present, considerations of roughness. A high value of C in that formula generally means that the exponent of S or of R is also high, while a low value of C indicates a low value of the exponent of R or S , R and S being less than unity; for, if we accept as correct the experimental data in any case, it follows that V , R and S must be correct, and therefore the variation of the result by formula from the experimental one is due to errors in either coefficient or exponent or both, and any change in one may be compensated by corresponding change in the other for any specific case.

Insomuch as there is a very widespread misconception regarding the friction of liquids upon solids, for which the text-books themselves are in a measure responsible, it being often stated that the frictional resistances in flowing water increase as the square of the velocity, it may be well to draw attention to the fact, quite clearly proven by experiment, that the friction of water upon a solid, or upon itself when moving in straight lines, varies nearly as the first power, and not as the square, of the velocity. The opposite conception is at the foundation of a recent formula* for the flow of water, which, by one of those rare circumstances of two errors balancing each other, gives, in its resulting values, some remarkably close approximations to actual conditions. However convenient or useful this formula may be as an instrument, the basis upon which its derivation rests is radically wrong.

The flow of water through capillary tubes affords a case where internal resistances, those due to impact, must be almost wholly obliterated, and the loss of head observed must therefore be practically that due to skin friction, and all the accepted experiments in this field show that the loss of head varies very nearly as the first power of the velocity. In the flow of water through fine sands there is perhaps a more perfect example of the effect of skin friction alone, and here again the loss of head is found to vary as the first power of the velocity. If further evidence be required, the investigations of Prof. Osborne Reynolds show that so long as the motion of the particles of water in a pipe is rectilinear, the loss of head varies with the first power of the velocity, and if still more is asked reference may be made to the experiments of Rennie, Coulomb, Beaufoy, Froude and Unwin with various surfaces dragged or rotated in still water, in all of which the evidence is that until vibrations are set up in the water itself, the force required to maintain motion varies as some power of the velocity much below the second. It is to be remarked that in dragging or rotating any body in still water, it is practically impossible to separate the force overcoming true skin friction from that expended in creating motion in the adjacent water, and for this reason it is only at extremely low velocities that we would find the resistance to vary with as low a power as the first, but under these circumstances that power has been quite closely approximated.

In the case of water flowing at ordinary velocities, where the impact conditions have attained their normal importance the true friction—that varying as the first power of the velocity—is probably restricted mainly to the particles of water in contact with the


*Sullivan's Formula $V = CD \sqrt{S}$ with $C = 50$ for cast iron pipe.

bounding surface, while the impact effects extend through the whole volume of the liquid, and it therefore appears that the ratio of importance of the two forms of resistance in determining the whole loss of head will be proportioned nearly to the ratio of the area of the cross-section to the wetted perimeter, which is R , and in circular pipes a function of the diameter alone. It is therefore seen that for pipes of uniform smoothness, when of large diameter, the resistance at the circumference is quite insignificant as compared with that in the interior, and that for very small pipes the condition is reversed, and it may be consequently expected that if in the equation $H_f = m\tau^n$ — in which H_f is the loss of head due to both forms of resistance,—*i.e.*, that usually indicated by the fall of pressure between two points in a closed pipe of uniform section after regular flow has become established, and V is the mean velocity of flow, and m a coefficient,—the value of n the exponent of V is determined, it would range from unity for capillary tubes as found by Poiseuille and others, to nearly 2 for large pipes, as demonstrated by the author's plottings.

Considering now the effect of roughness on this exponent, it may perhaps appear at first sight, that since the true friction must be greater in a rough than in a smooth pipe, the effect of increased roughness while undoubtedly increasing the coefficient m would be to decrease the exponent n . On the other hand it may also appear that a roughened surface will add to the internal resistances, and the increase in that function on that account may balance or even exceed the increase of the true friction, and the exponent remain unchanged or be increased. So it is hardly safe to prophesy the result of increased roughness without a careful experimental examination of the matter, and the latter is extremely difficult to manipulate in such a way as to afford the kind of evidence sought in the present case. The especial difficulty lies in the determination of a unit of roughness for it may be readily conceived that any number of pipes may have the same mean sections and yet have their maximum and minimum sections vary to an almost unlimited extent, so in dealing with the experimental data at hand no very definite agreements can be expected in the results of observations upon rough or tuberculated pipes.

For such an investigation of the question $H_f = m\tau^n$ as is proposed above, the most convenient method is by plotting the corresponding logarithmic equation, which is: $\log H_f = \log (m\tau^n)$ $= \log m + n \log V$ and if n and m are constants this is seen to be the equation of a straight line, it being of the general form $y = ax + b$, and therefore the tangent of the inclination of the line to the

PLATE 24
D IN FEET



axis of x is the value of n and the length of the ordinate $\log H_f$ at ($V = 1$ or $\log V = 0$) is $\log m$. This equation may, of course, be plotted and the results deduced by the use of a table of logarithms and ordinary cross-section paper, but by the use of logarithmic cross-section paper, for which the writer is indebted to Mr. John R. Freeman, Member American Society of Civil Engineers, the labor can be considerably reduced, without a great sacrifice of accuracy, and it is by this means that the results about to be presented have been obtained. In estimating their value it is to be remembered that this method in no way provides for the condition which the author has shown to frequently exist, of there being, as he concludes, a constant error in the observations of one sign, so that the experimental locus does not pass through the origin, and consequently the exponent value may be considerably affected by such causes without the reason being detected.

The writer has examined the results of over sixty series of experiments upon pipes with diameters ranging from 0.00575 feet to 0.9744 feet, made by fifteen different investigators under quite varying conditions.

The results of a part of these investigations are presented in the accompanying table No. 6, and are also represented graphically on Plate 24, Fig. 1.

In dealing with these experiments it must be remembered that they have been made under two quite different plans of observation. The first and oldest is that of allowing the water to flow from a reservoir into the pipe and to discharge either into the open air or beneath the surface of water in a second reservoir, the loss of head measured being that between the surfaces of water in the two reservoirs, or, when into air, between the center of the section of discharge and the surface in the feeding reservoir. The head so obtained is then corrected by the subtraction of the head required to produce the observed velocity and for an assumed loss due to the contraction at entry, the remainder being assumed to represent the loss of head in the pipe alone. This is the method of Couplet, Bossut, DuBuat, Leslie and Hamilton Smith, Jr., the latter especially favoring it, and strongly (though it seems not with entire justification) condemning the second method, that of Darcy, Jacobson, Rowland and Freeman, which consists of observing, by means of radial perforations in the pipe wall, the heads at different points in the pipe experimented upon, and by their difference obtaining directly the loss of head from one point to another. In the writer's opinion, when the piezometric openings and the section experimented upon are properly located, the latter

method is to be preferred. As to the method of measuring the discharge, whether by weight or volume, it has been passed upon and accepted by Hamilton Smith, Jr., in nearly all the cases cited, and in most of the remaining ones the intrinsic evidence of the results of the experiments when plotted goes far to establish the accuracy of the observed quantities.

It is conceived that less confidence is to be placed in experiments upon short lengths of pipes when made by the former of the two methods described, because it seems doubtful whether the effect of entry has ever been accurately determined or properly explained, and any error in allowing for this will have a greater influence upon the results in short than in longer pipes. For this reason greater weight is given to the work of Darcy than to that of the other observers, as from his work it is possible to take the loss of head in a section of pipe of a good length that is preceded by a longer section in which the effect of entry has had a fair chance to work itself out, and it may therefore be expected that the loss of head obtained will be the true loss under consideration, unaffected by any but normal conditions.

Darcy's pipes were attached to the end of a closed cylinder 3.28 feet in diameter and 9.76 feet long by a square joint. Manometer No. 5 was attached to this cylinder. Within 1.5 feet of this cylinder was manometer No. 4, and in all cases except that of the glass pipe and the lead pipes manometer No. 3 was placed 13 to 18 feet further down stream, manometer No. 2, 164 feet beyond that and manometer No. 1 another 164 feet distant, which was usually from 20 to 25 feet from the outlet. In the glass pipes manometer No. 4 was omitted and Nos. 3, 2 and 1 were separated by the distances 70.75 feet and 76.39 feet, the total length being 147 feet. For the lead pipes manometer No. 4 was 2.3 feet from the inlet, No. 3 was from 4.59 feet to 4.92 feet from No. 4 and Nos. 3, 2 and 1 were 82 feet apart, No. 1 being then about 1.1 feet from the outlet. All the manometers were attached to a single piezometric opening in the side of the pipe.

In reducing these experiments, the velocities as given by Hamilton Smith, Jr., have been accepted, but the slopes have been determined by the readings of manometers Nos. 1 and 2, not 1 and 3 as was done by other commentators and by Darcy himself. Using these slopes, instead of those for the longer section, the erratic results criticized by former investigators are very largely eliminated, and it was upon those incongruous results, which it appears were due to the proximity of the upstream piezometer No. 3, to the

inlet, that Hamilton Smith, Jr., based his severe arraignment of the piezometric method of observation.

In this connection it may be remarked that since piezometric openings in the pipe wall do not give the mean pressure head in the cross section, but only that in the layer of water next the opening, it follows that if for any reason the velocity of the particles in this layer at one point of observation is greater or less than at another the difference of the pressure heads observed will be increased or decreased as the case may be, by the head represented by the change of velocity between the two points. It is not, therefore, to be expected that a piezometric observation taken near a contraction or a curve or a gate in a line of pipe will give data comparable with that shown by similar openings elsewhere, so that the desideratum for this sort of observation is a long length of smooth, straight pipe preceding the section to be experimented upon. How long this preceding length must be is yet to be determined, but that it should be many times longer than has been heretofore supposed is proven by the experiments of Darcy, Jacobson and Reynolds, as well as by more recent ones which might be cited.

For the experiments of Hamilton Smith, Jr., the data as presented in his *Hydraulics* has been accepted, and from the same source have been taken the experiments of Bossut and DuBuat.

The experiments of James Leslie with $2\frac{1}{2}$ -inch lead pipe, 100 feet long, the only ones in his series which seem sufficiently reliable to be included here, have been computed from his data as presented in the *Proceedings of the Institution of Civil Engineers of Great Britain* for 1855, the observed heads being corrected for velocity, but not for entry. This pipe was coiled in a spiral 90 feet in diameter, the loss of head was measured by the difference of level of water in tanks at the inlet and outlet ends, and the discharge was measured in a tank.

The experiments of Thomas F. Rowland, given in *Transactions American Society Civil Engineers*, Volume XIX, have been similarly reduced. In these experiments the diameters were not measured, but the pipe is described as $\frac{1}{4}$ -inch, $\frac{1}{2}$ -inch and 1-inch wrought iron. For these reductions the present standard diameters of these sizes of pipe have been taken and are given in the table. The discharge was determined by weight and the loss of head by Bourdon Gages. The experiments have been rejected by Hamilton Smith, Jr., with justification, but they are included here as the only ones on record with very small wrought iron

pipe, and for the smallest diameter the observations seem to be fairly consistent.

The experiments of Prof. Osborne Reynolds have been taken from the Royal Philosophical Transactions for 1883. These pipes were of lead $\frac{1}{4}$ and $\frac{1}{2}$ -inch diameter and 16 feet long. They were attached by trumpet mouthpieces to a tank, and the heads were read piezometrically at points five feet apart near the downstream end, the upstream piezometer being 9.6 feet from the inlet. In Professor Reynold's own discussion of these results he says that the loss of head varied as the 1.722 power in both pipes. From a study of the published data this conclusion appears erroneous. The value here obtained of 1.725 for n with the larger pipe is as close a corroboration as could be expected, but in the case of the smaller pipe the observations fall in two groups, separated from each other by a change in m the coefficient of l' and apparently indicating an unsuspected change of condition. Each set has a perfectly definite and regular inclination when plotted logarithmically, and in both cases it is considerably below that of the larger pipe, being about 1.637 for the lower velocities and 1.551 for the higher ones. It appears that Professor Reynolds took both groups together and found n from the inclination of the line best fitting all observations; but this, from the appearance of the data, does not seem justifiable, and his conclusion is, moreover, antagonistic to the indications of the rest of the experiments investigated in the present discussion. The experiments themselves appear to have been made with great care and to be entitled to the highest confidence as representing accurately the conditions encountered.

The experiments of Dr. Heinrich Jacobson were made at Koenigsberg, and were published in the "Archiv für Anatomie, Hygiene," etc., in 1860 and 1861. The pipes were connected to a cylindrical reservoir by a conical brass mouthpiece. The losses of head were measured both from the surface of the water in the reservoir and from the height of a manometer column connected to the tube at a point at varying distances from the inlet, being generally, in the experiments selected, about 0.03 foot away; the pipes discharged freely into the air, so that the total head measured at this point was presumably the loss of head in the remaining section of pipe. The diameters were determined by weighing the water in the pipes, which had been previously selected from a large number for uniformity of bore. Distilled or filtered water was used, and the discharge was determined by weight. These experiments were very carefully made and show remark-

ably harmonious results, though it appears that the piezometer was in some cases too close to the inlet. With these small diameters the temperature has an important bearing, but those experiments only have been selected for the present investigation, in which it was either constant or of small range.

The experiments of John R. Freeman, member American Society Civil Engineers, upon hose have been taken from Volume XXI, Transactions American Society Civil Engineers, without alteration. It, however, seems that the length of 25 feet usually existing between the hydrant and the first piezometer was not sufficient for the elimination of entry effects, and that this accounts for some of the peculiarities of the series.

The experiments credited to Iben and Elmann are given upon the authority of Hering and Trautwine's Appendix to "The Flow of Water in Open Channels." They lack completeness of data, as obtained from this source, and are presented only as being in a measure corroborative of the conclusions drawn from the more reliable investigations.

The experiments upon the 3-inch riveted pipe and the 2-inch brass pipe were made in the Hydraulic Laboratory of Cornell University during the latter part of 1899 and the early part of 1900. The former investigation was made by Messrs. L. C. Giltner and D. A. Ketchum, Jr., as a graduating thesis in the College of Civil Engineering, and the latter was made by the writer. The arrangement of the apparatus is shown in Plate 25. The water was taken from a tank in the top of the building, where the head was maintained constant by a float valve controlling the supply from the university reservoir, and admitted to the experimental system through the pipe D, which was of standard 2-inch wrought iron. By a similar pipe E it was conducted into the regulator chamber F F, in which it passed through a screen consisting of a brass plate drilled with $\frac{1}{8}$ and $\frac{3}{32}$ -inch holes. The outlet of this chamber was a cycloidal mouthpiece G, whose curve was generated by a rolling circle of diameter equal to one-fourth that of the following pipe H, and rolling parallel to the pipe axis. The pipe H was of seamless drawn brass tubing 0.416 foot in internal diameter, and at its outlet was a similarly constructed cycloidal mouthpiece I, connecting to the seamless drawn brass pipe J, K, L, M, N, O, of which L was the experimental section used in the experiments of the writer here presented, although observations were also taken upon H, I, J and K.

The pipe O was standard 2-inch wrought iron and P was standard 3-inch wrought iron, as was also the outlet section U,

TABLE No. 4.

EXPERIMENTS ON 3-INCH RIVETED PIPE. BY L. C. GILTNER AND D. A. KETCHUM, JR.

Mean Diameter, 0.2502 ft.

SERIES I. FLOW FROM A TO C.

SERIES II. FLOW FROM C TO A.

Section A B—L. 21.24'.					Section B C—L. 24.90'.					Section C B—L. 24.96'.					Section B A—L. 24.24'.				
No. of Exp.	Velocity in Feet Per Second. V .	Loss of Head in Feet. H_f .	Coef. in V^2 . C .	No. of Exp.	Velocity in Feet Per Second. V .	Loss of Head in Feet. H_f .	Coef. in V^2 . C .	No. of Exp.	Velocity in Feet Per Second. V .	Loss of Head in Feet. H_f .	Coef. in V^2 . C .	No. of Exp.	Velocity in Feet Per Second. V .	Loss of Head in Feet. H_f .	Coef. in V^2 . C .	No. of Exp.	Velocity in Feet Per Second. V .	Loss of Head in Feet. H_f .	Coef. in V^2 . C .
112	0.5121	0.635	80.7	112	0.5121	0.70	75.6	42	0.5033	0.88	75.1	42	0.5033	0.805	79.1	42	0.5033	0.805	79.1
110	0.7815	1.420	82.5	110	0.7815	1.53	79.1	34	0.8439	1.85	77.5	34	0.8439	1.700	81.0	34	0.8439	1.700	81.0
124	0.9230	1.970	82.8	124	0.9230	2.17	78.5	31	0.9305	2.25	78.0	31	0.9305	2.050	82.2	31	0.9305	2.050	82.2
128	1.0268	2.400	83.2	128	1.0268	2.64	79.2	25	1.1037	3.09	78.7	25	1.1037	2.800	83.1	25	1.1037	2.800	83.1
40	1.1033	2.970	85.1	40	1.1633	3.31	80.2	22	1.1014	3.60	78.9	22	1.1914	3.240	83.3	22	1.1914	3.240	83.3
40	1.2200	3.330	84.4	46	1.2290	3.69	79.9	21	1.2003	3.69	78.4	21	1.2063	3.320	83.0	21	1.2063	3.320	83.0
39	1.2439	3.340	85.0	99	1.3539	4.39	81.0	14	1.3585	4.55	79.7	14	1.3585	4.180	83.5	14	1.3585	4.180	83.5
99	1.3539	3.980	85.3	37	1.4706	5.16	81.6	11	1.4109	4.95	80.0	11	1.4109	4.500	83.5	11	1.4109	4.500	83.5
37	1.4706	4.000	85.4	27	1.5727	5.84	81.8	8	1.5227	5.05	80.3	8	1.5227	5.140	84.5	8	1.5227	5.140	84.5
27	1.5727	5.240	86.5	38	1.6833	6.61	82.0	4	1.5882	6.13	80.4	4	1.5882	5.600	84.4	4	1.5882	5.600	84.4
38	1.6833	5.970	86.0	95	1.7872	7.45	82.2	3	1.6320	6.51	80.3	3	1.6320	6.050	84.4	3	1.6320	6.050	84.4
74	1.8715	7.340	86.9	93	1.8524	8.00	82.4	70	1.7454	7.35	80.7	60	1.7975	6.850	85.0	60	1.7975	6.850	85.0
72	1.9331	7.700	87.0	104	1.9499	8.83	82.3	67	1.8387	8.10	80.9	88	1.8180	7.400	85.0	88	1.8180	7.400	85.0
70	1.9870	8.200	86.8	106	1.9980	9.30	82.0	64	1.9440	8.99	81.4	85	1.9304	8.150	85.4	85	1.9304	8.150	85.4
60	2.1207	9.280	87.8	88	2.1091	10.20	82.8	59	2.0945	10.32	81.5	81	2.0788	9.350	85.4	81	2.0788	9.350	85.4
64	2.1027	9.640	87.8	87	2.1553	10.61	82.9	57	2.1386	10.75	81.0	79	2.1058	10.080	86.0	79	2.1058	10.080	86.0
61	2.2538	10.400	87.8	85	2.2308	11.30	83.3	53	2.2400	11.70	82.1	70	2.2581	10.800	86.0	70	2.2581	10.800	86.0
58	2.3220	10.920	88.4	80	2.3189	12.13	83.1	50	2.3273	12.47	82.4	72	2.3394	11.120	86.5	72	2.3394	11.120	86.5

No. of Constructions, 48

No. of Constructions, 50

No. of Constructions, 50

Temperature of Water, 59° to 42° Fahr

the last reducing to 1-inch pipe with a controlling valve V. The riveted pipe was comprised in the four sections Q, R, S and T. It was made of galvanized iron 0.0503 inch thick, which was rolled into conical joints 7 inches long and riveted with 1 longitudinal lap-seam having 7 rivets with a pitch of 1 inch. These joints were riveted together with a single circumferential row of 9 rivets with a pitch of 1.05 inches. These rows were 6 inches apart longitudinally. The rivets, both longitudinal and circumferential, had button heads $\frac{5}{16}$ inch in diameter at the base and $\frac{3}{8}$ inch high. The joints were then made tight by soldering on the outside of the pipe. The flange unions were so put on as to allow the lengths to telescope in the same manner as the minor sections, but the circumferential rivet rows were replaced at these joints by eight rivets with heads $\frac{1}{2}$ inch in diameter at the base and $\frac{3}{16}$ inch high, fastening one flange to the pipe; the second flange, on the next section, was fastened by a similar row 3 inches away, and 3 inches from the next regular circumferential rows of 9 small rivets. The joints in the brass pipe were made with flanges. The ends of the pipes, being turned true in a lathe and the burr scraped from the inside, were butted tightly and held by the flange bolts, a guide having been also turned in the flange to hold the two ends truly in line.

The entire experimental pipe system was suspended from hangers in the ceiling and the center line was very nearly level for its entire extent.

The diameters were determined by calipering the ends of the individual lengths. With the brass pipe, the lengths ranging from 11 to 17 feet, two diameters at right angles were calipered at each end. The riveted pipe was calipered on each side of the longitudinal lap and at right angles to the diameter through the lap, the arithmetical mean of these caliperings being accepted as the value of D. The calipers used were made by Darling, Brown & Sharp, and were read to 0.0001 inch. The lengths were measured with a steel tape. The discharge was determined by weight upon a scale of 4000 pounds capacity, whose error was determined by comparison with a standard to be $\frac{1}{1140}$, and the correction neglected. The losses of head were measured piezometrically by differential gages of a special type, designed by the writer, with which differences of head amounting to 0.0006 foot of water could be readily detected. Readings were taken once each minute. The piezometric openings were radial and 90° apart, and in the case of the brass pipe were $\frac{1}{16}$ inch in diameter and communicated directly to a circumferential chamber, while with the riveted pipe

they were $\frac{1}{8}$ inch and communicated by short $\frac{1}{4}$ inch diameter tubes with an equalizing chamber of 1-inch pipe. The gages were connected by $\frac{3}{8}$ and $\frac{1}{2}$ -inch diameter rubber hose to the circumferential or the equalizing chambers.

The duration of a single experiment was not less than five minutes, the flow having been previously started and the water allowed to run to waste for three or four minutes through one

TABLE No. 5.

EXPERIMENTS ON 2-INCH BRASS PIPE. By G. S. WILLIAMS.
Length, 40.376 feet. Mean diameter, 0.1738 feet

Experiment.	Velocity in feet per second.	Loss of head per 1000' in feet.	Temperature of Water, 39° to 49 Fahr.
a	0.53084	0.06	
b	1.1130	3.49	
c	0.75410	1.79	
d	0.09501	1.58	
e	0.50857	1.15	
f	0.50020	1.00	
g	0.39456	0.54	
h	0.25446	0.27	
i	0.53857	0.98	
j	2.0914	10.34	
k	1.8371	8.27	
l	1.6144	6.65	
m	1.2735	4.42	
n	1.0570	3.00	
o	1.3055	5.00	
p	0.47837	0.70	
q	1.1216	4.06	
r	0.82243	2.04	
s	2.1432	10.66	
t	2.2535	11.34	
u	1.6801	9.25	
v	1.6391	6.71	
w	0.92584	2.48	

side of the discharge spout W, which was divided by a vertical diaphragm. At the proper time this spout, which was suspended so as to swing freely, was swung over until the jet discharging at V was delivered into the other half of W and to the scale. The time required for thus diverting the flow was less than one second. The time was taken with an ordinary watch, and may be considered accurate within three seconds. In the riveted pipe experiments the water was brought to rest at the close of each experiment, and the static reading of the gages observed. In the brass pipe

investigation, static readings were taken once in five or six experiments. Dynamic readings were then corrected by the mean of the static readings at the beginning and end of the experiment. The riveted pipe was first experimented upon with a flow from A to C, being from the large to the small end of the sections, and then was reversed so that the flow took place from C to A and against the butts of the joints.

The experiments of Messrs. Giltner and Ketchum embraced observations upon two sections of the pipe, A B and B C, whose lengths were 24.24 feet and 24.90 feet, respectively, in the first series, and C B and B A in the second series. The observations on both sections were made simultaneously up to velocities of 1.75 feet per second, and separately for higher ranges. The plotting of these experiments upon logarithmic cross-section paper gives the following values for the loss of head per 1000 feet in feet of water, H_f .

For upstream section A to B, $H_f = 34.36 \sqrt{1.872}$.

For downstream section B to C, $H_f = 38.01 \sqrt{1.884}$.

For upstream section C to B, $H_f = 39.10 \sqrt{1.882}$.

For downstream section B to A, $H_f = 35.61 \sqrt{1.892}$.

It is notable that the section A B gives a lower loss of head per thousand, both direct and reversed, than the section B C. This section was slightly curved in the portion Q or that near the A end, the deflection from a straight line in continuation of the axis of the rest of the pipe being about two inches. The pipe being made up by hand was none of it so straight as could be desired, but the curvature near A was the greatest anywhere. Owing to the short lengths used, general deductions from the observations may be misleading, although the writer doubts if there are many series of observations on record that have been more carefully conducted. The results do, however, quite clearly and consistently show what they were primarily undertaken to investigate,—viz, the effect upon the loss of head of reversing the flow in such a pipe, and prove that the resistance is increased when the flow takes place against the butt ends of the joints. They seem also to indicate that the effect of the expansion in the pipe area near the inlet end (from O to P, O being a piece of 2-inch and P a piece of 3-inch wrought iron pipe, the diameters being approximately 2.067 and 3.067 inches, respectively) is to decrease the apparent loss of head in the section immediately following. Other experiments have shown this to be the case with a contraction, and it is perhaps not surprising that the same effect should appear with an expansion.

The entire series of the experiments of Messrs. Giltner and Ketchum is plotted with loss of head as ordinate and velocity head as abscissa, upon Plate 26, and the reduced results of seventy-two observations from the series are given in table No. 4, as computed by the experimenters, and similar data for the twenty-three experiments by the writer are given in table No. 5.

Table No. 3 gives the elements of the several series of the experiments used in the plottings shown on Plate 25, Fig. 1. Data with numbers having subscripts are not included in the plate on account of the special conditions of those experiments, but are included in the table for purposes of comparison.

Considering now Fig. 1, Plate 24, the values of n in the equation $H_f = m\pi^n$ are plotted as ordinates and the values of the diameter D as abscissas.

The first thing noticed is that the values of n for the small diameters decrease quite rapidly when D is less than 0.1 foot, and that the values of n are lower for the smooth pipes than for the rough ones.

In the series with glass pipes, Nos. 1 to 10, inclusive, there is first a set of six points from Jacobson covering three very small diameters, but which show n to increase with some power of D . Then there are three points, Nos. 7, 8 and 9 from Smith, giving as many diameters and one from Darcy, No. 10. No. 7, of Smith, appears to be high, and from the table it is seen that this was a very short pipe as compared with the others of the larger diameters, being only about 11 feet long, while the next in length, No. 8, was 35 feet.

On brass pipe there are only two points, Nos. 11 and 12, and these being by different observers are perhaps surprisingly coincident in showing that the value of n for brass is less than for glass.

On lead pipe are three points from Reynolds, Nos. 13, 14 and 15, giving two diameters, three by Darcy, Nos. 16, 17 and 18, giving three diameters and No. 19, by Leslie, which it will be seen falls below the value of n to be expected from the others. It is recalled, however, that this pipe was coiled in a long spiral, and it may be at this point suggested that curvature possibly has the effect of lowering the value of n . In the table, experiment No. 19, *a*, by Iben, gives a value for n of 1.728 for $D = 0.082$. This experiment was rejected by Hamilton Smith, Jr., and the data available is incomplete. It is, however, not far away from the Darcy value for $D = 0.0886$ of 1.765.

On coated wrought iron pipe the points, Nos. 20, 21, 22 and 23 are from Darcy with sheet iron pipes coated with bitumen, and the point No. 24 is by Smith with a wrought iron pipe similarly coated, which comes very close to the Darcy value No. 20 for practically the same diameter.

Under smooth wrought iron are included only the experiments with modern pipes, as there is fairly good reason to suppose that the art of producing smooth interiors in Darcy's day was not so well perfected as in the time of the later experiments, and it is seen that the two experiments of Smith, 31 and 32, fall very close to the lead pipe values, while the Rowland small pipe values, 25 and 26, fall somewhat above. As already said, the reliability of Nos. 27 to 30 is considered questionable. Referring to the table the value of n for Hamilton Smith's short wrought iron pipe, 16 feet long is 1.842, while the value, No. 32, for a longer length, 60 feet, of the same size, is only 1.772, which corroborates the inference in the case of the glass pipes that short lengths, when treated by the Smith method of observation, give high values of n .

This conclusion is contradicted by the experiments of DuBuat on tin pipes, where, as shown in 33 and 33 *a* of the table, the exponent for a length of 65 feet is 1.730 and for a length of 10 to 12 feet 1.686. Hamilton Smith has expressed the opinion that as an experimenter DuBuat was less expert than Bossut, and the added fact that in these experiments the discharge was part of the time into air and part of the time under water, warrants the questioning of this evidence as against that of Smith, which latter is further corroborated by the Rowland value for the 30-foot length of $\frac{1}{4}$ -inch pipe No. 30 *a*. The points from Bossut for tin pipes, Nos. 34 and 35, show very low values of n decreasing with the diameter, and not far from the brass pipe value obtained by the writer.

The next set of points is from Darcy, with his wrought iron pipe, Nos. 36, 37 and 38, which, as explained above, is considered to have been more rough than the pipes of Smith and Rowland. This conclusion is strongly supported by the coincidence of the Smith point, No. 39, on an old wrought iron pipe, 60 feet long, with No. 37 of Darcy on essentially the same diameter. These values it is seen fall about midway between the smooth pipe series and those of the rougher cast iron.

For cast iron, new and cleaned, there are six points plotted from Darcy. These pipes were not coated. No. 46 is beyond the range of the plate and it is not considered as reliable as the

others, probably on account of the large diameter and slow velocities. The author's plotting of these observations, No. 58, Plate 3, shows the irregularity of the results. Nos. 40, 41 and 42 are with new pipes, and Nos. 43, 44 and 45 with old pipes that had been cleaned. The series as a whole shows very clearly an increase in n as the diameter increases.

With the exception of No. 50, the points from the Darcy observations on tuberculated pipes corroborate the general conclusion that roughness increases the value of n .

Strange as it may seem, there is, outside of Darcy's work, a scarcity of good experimental data on cast iron pipes of the smaller diameters. From the experiments of Ehnann (see tables Nos. 46 *a* and 46 *b*) values for n of 1.822 and 1.912 are obtained for a diameter of 0.164, the latter of which comes somewhere near the Darcy curve; but the former does not fit at all. These experiments failed to pass the severe scrutiny of Hamilton Smith, Jr., and as they were made upon street mains having bends and other obstructions they cannot be considered of equal value with Darcy's work, but they may possibly be considered as adding their mite to the evidence that curvature decreases the value of n . Being coated, they were also probably smoother than were Darcy's pipes, and hence should give a lower value of n .

Hamilton Smith's wood pipe, made by boring with an auger a log of wood, probably gave a condition of surface not very different from that of cast iron pipe such as Darcy had,—*i.e.*, uncoated cast iron, and the plotting of this point 51 seems to be quite consistent with the Darcy values for cast iron.

The experiments of Messrs. Giltner and Ketchum, No. 52, show the value of n to be considerably above the Darcy smooth pipes, and corroborates the conclusion that roughness increases the value of n .

The Freeman experiments upon hose do not give as satisfactory information upon the effect of diameter as had been hoped. This is probably partly due, as before suggested, to the comparatively short length of hose between the hydrant and the upstream piezometer, and partly to the many varying conditions encountered, as roughness, elasticity, very slight sinuosity, constriction at couplings, etc., all of which may be very likely to have an influence upon n . These experiments do, however, afford most interesting evidence as to the effect of sinuosity and curvature. In sample E, with the hose laid straight, $n = 1.001$, and when allowed to assume a sinuous position, the curves having a radius of about

six to eight feet, the value of n is reduced to 1.904. Similarly sample L, when straight, gives $n = 1.900$, and when sinuous 1.860.

Experiments upon the effect of curvature were also made with hose D, which are designated by the letters V, W, X, Y and Z in the table.

In V the hose in its middle portion was bent around four 45° curves of 2 feet radius. In W it was coiled around a full circle 2 feet in radius. In X it was bent around four 90° curves of 2 feet radius. In Y it was bent around four 90° curves of 3 feet radius, and in Z it was similarly bent around four 90° curves of 4 feet radius. The curves were arranged one left, two right and one left, a length of tangent equal to their radius being laid between each pair of curves. Fifty feet of hose A was connected between the upstream piezometer and the hydrant, thus improving the conditions over those of the original experiments with this hose. As originally tested, hose D gave a value for n of 1.911. At the beginning of these curve experiments it was again tested straight, D' in table, and gave $n = 1.891$. At the close of the curve experiments it was again straightened out and gave $n = 1.873$, D'' in table.

When curved, it uniformly gave a lower value of n , the minimum being for X where $n = 1.803$, and the highest being that for the full circle where $n = 1.858$, all of which strongly confirms the inference drawn in considering the Leslie experiment that curvature tends to decrease the value of n .

As indicated by Mr. Hawksley, and since proven by Professor Reynolds, under certain conditions, even in pipes of considerable size, the resistance at low velocities increases as the first power of the velocity up to a certain critical velocity, the flow below this velocity being nearly rectilinear. This critical velocity appears to be somewhat dependent upon the diameter of the pipe. In the logarithmic plotting of several of the series of experiments, it has appeared that the low velocities gave low values of n , which gradually increased as the velocity increased until a velocity was reached above which the locus became a straight line showing n constant. In determining the values of n in this investigation, we have rejected in every case the curved portion of the locus and have taken for n its constant value.

Professor Reynolds was able to observe only the conditions indicating the establishment of a critical velocity when the water entered his pipes from a state of prolonged rest in his tank, and it is to be noted that in the writer's own experiments upon the brass pipe, and in those of Messrs. Giltner and Ketchum upon

the riveted pipe, in both of which velocities as low as one fourth of a foot per second were observed, which are the lowest recorded for pipes of their sizes, there is no evidence of the exponent of V changing in value appreciably. Therefore the probability of the critical velocity, as Professor Reynolds defines it, being a factor in the engineer's practical computations, may be considered as questionable.

To summarize the results of this investigation, we find:

a. That the loss of head in pipes increases with a power n of the velocity, which power increases with the diameter from about unity in capillary tubes to about 2 for the larger sizes of water pipes.

b. That n increases with increased roughness.

c. That n decreases with increase of curvature from the straight pipe.

d. That the material of the pipe seems to have an influence upon the value of n .

e. That for the cases of pipes coming within the range of the engineer's practice, 2-inch diameter and above, the value of n may range from 1.8 for very smooth pipes, to about 2.0 for ordinary uncoated cast iron.

f. That when the loss of head is measured in the manner of Bossut, DuBuat and Smith, a short pipe will give a value of n that is high as compared with longer pipes, which seems to be on account of the special resistance generated at entry to the pipe.

To show graphically the effect of the application of the equation $H_f = a H_v$ to cases where the exponent of V is less than 2, there are plotted in Fig. 2, Plate 24, as abscissas, to the velocity head as the ordinate, the values of H_f when: I, $H_f = ml^{1.50}$; II, $H_f = ml^{1.80}$; III, $H_f = ml^{1.90}$, and IV, $H_f = ml^{1.70}$ for $V = 0.5', 1.0', 1.5', 2.0', 3.0', 4.0', 5.0', 6.0'$ and $7.0'$. The straight lines A, C, B for the three curves have been plotted according to the method presented by the author using all the points and in the case of $H_f = ml^{1.70}$ the line A', C', B' has been similarly computed, using only the values of V from 1.5 feet to 7.0 feet, inclusive.

These plottings demonstrate that, although the lines may fit the points with considerable accuracy, they do not rightly pass through the origin, although the true curve does. They also show that for a range of velocity from 1.5 feet to 7.0 feet, which covers that ordinarily met with in pipe experiments, the straight line gives a very close approximation to the true curve, even in the extreme case of the exponent being as low as 1.70.

The equations of these lines A, C, B, are: I, $H_f = 36.504 H_v + 0.7371$; II, $H_f = 44.147 H_v + 0.5519$, and III, $H_f = 53.299 H_v + 0.3191$, and that of the line A', C', B' is $H_f = 35.02 H_v + 1.327$.

With a clear understanding of the limits to the applicability of the straight line equation, it will be found a great assistance in the field and elsewhere in determining the approximate accuracy of work as it proceeds or is brought up for examination. As the author has pointed out, it is actually unnecessary to compute or use the velocity head itself, since the square of the velocity follows the same law, and may be therefore used in its stead, so that the labor of applying the straight line criterion is considerably less than might at first be supposed.

From the graphical method of obtaining the values of n in this investigation it follows that the third decimal place is beyond the limit of accuracy. The second is certainly as far as the accuracy can be relied upon, and that is chiefly valuable for comparison with the other values as given here. Another investigation treating the same data by the same process might very probably obtain values of n differing in the second place from those here presented.

The plottings of the author for large pipes indicate that there may be some very interesting developments at that end of the series, for they appear to show that n may have a higher value than 2, a point which is corroborated by some of Coulomb's experiments. The problem then naturally arises: Since the true friction varies as the first power, and the losses due to impact as the square of the velocity, and these are the principal causes now recognized as retarding flow, can a value of n greater than 2 be accounted for, unless it is admitted that the mean of the velocities of the individual particles of a flowing stream increases more rapidly than does the mean velocity of the stream as a whole?


MR. JOHN C. TRAUTWINE, 3D.—In a series of tests on water meters to determine the relations between resistance and velocity, the writer made a few experiments on meters from which all moving parts had been taken, and also a few experiments on short lengths of pipe with connections of various kinds. While these experiments do not give results for straight pipe alone, yet they all go to show that, in the formula $v^n = 2 g h$, the exponent n is by no means invariably $= 2$; that it is usually less, and that it increases with the projections and roughnesses. Thus, lengths of $1\frac{1}{2}$ to 3 feet of small tubes, with couplings and meter unions, gave $n = 1.81$ to 1.83; but the insertion of defective packings in the meter unions,

TABLE No. 6.—EXPERIMENTS WITH SMALL AND MEDIUM-SIZED PIPES.
Discussed by $H_r = mV^6$ by Logarithmic Paper.

	Authority.	Kind of Pipe.	Diameter in Feet	Velocity, ft. per second.	Total Length, Feet	Length Head, Feet.	Value of m .
1	Johnson	Glass	0.00575	1.895—2.654	1.892	1.782	1.011
2	"	"	0.00587	2.073—2.641	1.700	1.670	1.014
3	"	"	0.00587	1.351—1.856	0.921	0.894	1.113
4	"	"	0.00553	1.302—2.659	1.434	1.404	1.114
5	"	"	"	3.169—3.470	"	"	1.134
6	"	"	"	2.583—3.186	1.700	1.679	1.062
7	H Smith, Jr	"	0.04186	1.055—5.010	11.127	11.127	1.755
8	"	"	0.06220	1.308—4.370	34.941	34.941	1.763
9	"	"	0.07640	2.077—4.441	63.902	63.902	1.777
10	Harvey	"	0.16300	0.502—6.920	117.200	76.300	1.834
11	Williams	Brass	0.00040	1.393—2.305	2.115	2.095	1.129
12	Williams	"	0.17300	0.254—2.250	113.150	46.376	1.747
13	Reynolds	"	0.02017	8.773—15.385	14.600	5.600	1.551
14	"	"	"	2.311—8.731	"	"	1.637
15	"	"	0.04150	1.143—21.300	"	"	1.725
16	Harvey	"	0.04500	0.131—4.230	172.400	82.420	1.761
17	"	"	0.08500	0.313—5.510	172.400	"	1.765
18	"	"	0.13450	0.394—7.500	100.000	"	1.790
19	I Leslie then Harvey	"	0.20830	0.276—6.900	100.000	100.000	1.773
20	"	"	0.08200	2.700—9.110	350.300	350.300	1.728
21	"	Sheet iron, coated	0.08720	0.680—8.230	371.800	164.050	1.760
22	"	"	0.27100	0.328—12.700	365.100	"	1.801
23	"	"	0.04300	0.501—19.720	365.100	"	1.801
24	"	"	0.08700	1.410—2.540	365.100	"	1.814
25	"	"	0.05100	1.207—10.520	365.100	"	1.810
26	H Smith, Jr	Wrought iron, coated	0.08730	2.220—5.440	60.264	60.264	1.772
27	Rowland	Wrought iron, new	0.03030	0.100—12.700	60.000	60.000	1.712
28	"	"	0.03030	11.760—16.780	60.000	60.000	1.714
29	"	"	0.05190	17.000—22.730	64.000	64.000	1.844
30	"	"	0.05190	22.120—31.570	32.000	32.000	1.705
31	"	"	0.07230	18.120—47.730	97.000	97.000	1.730
32	"	"	0.08730	24.490—33.310	63.500	63.500	1.740
33	"	"	0.08730	34.830—43.800	31.000	31.000	1.852
34	H Smith, Jr	"	0.05230	1.009—3.880	60.127	60.127	1.747
35	"	"	0.08750	0.968—5.390	60.172	60.172	1.772
36	"	"	0.08760	2.333—6.880	16.685	16.685	1.742
37	"	"	0.08800	1.410—2.540	65.146	65.146	1.730
38	"	"	0.08800	0.772—7.540	10.30 to 12.30	10.30 to 12.30	1.686
39	"	"	0.11840	0.116—3.060	63.95 to 191.34	63.95 to 191.34	1.691
40	"	"	0.17850	1.455—3.820	161.050	161.050	1.717
41	"	"	0.04000	0.113—3.930	374.000	"	1.800
42	"	"	0.08730	0.190—7.170	372.200	"	1.858
43	"	"	0.12060	0.205—8.520	371.900	"	1.855
44	H Smith, Jr	Wrought iron, old	0.08530	0.910—4.270	60.250	60.250	1.857
45	Harvey	Cast iron, new	0.20870	0.280—10.710	366.100	174.050	1.950
46	"	"	0.44950	0.480—15.400	365.700	"	1.974
47	"	"	0.61680	0.673—16.170	365.400	"	1.978
48	"	"	0.11940	0.371—3.690	374.900	"	1.960
49	"	"	0.26280	0.633—5.010	365.300	"	1.930
50	"	"	0.50280	0.912—14.750	365.300	"	1.992
51	"	"	1.61490	1.380—3.700	"	"	1.942
52	Ehmann	Cast iron in use	0.16100	0.610—2.950	2,138.600 ?	2,138.600 ?	1.822
53	"	"	0.17850	0.810—2.200	374.900	374.900	1.942
54	Harvey	Cast iron, tuberculated	0.17850	0.167—2.050	366.300	164.050	2.000
55	"	"	0.26700	0.403—3.750	366.300	"	1.980
56	"	"	0.26700	1.107—12.580	300.300	"	1.983
57	"	"	0.07140	1.180—3.700	62.050	62.050	1.944
58	H Smith, Jr	Wood, bored	0.10530	1.053—3.990	62.050	62.050	1.984
59	"	"	0.20200	0.170—2.330	54.080	24.900	1.883
60	"	"	0.25000	12.500—20.000	178.000	155.900	2.013
61	Culter & Kenlum	Riveted sheet iron	0.21670	11.600—18.140	179.500	154.500	1.986
62	Freeman	Hose, sheet rubber	0.20700	13.450—18.700	173.000	154.500	1.986
63	"	"	0.20700	13.400—20.000	186.000	161.500	1.915
64	"	"	0.20750	13.200—21.000	107.200	57 and 170	1.911
65	"	"	0.22130	7.500—17.800	178.000	153.200	1.901
66	"	"	11.010—13.550	"	"	"	1.904
67	"	"	0.20830	11.630—22.000	76.700	51.700	1.972
68	"	"	0.21670	12.320—19.000	180.000	155.600	1.960
69	"	"	0.21850	11.070—19.500	183.341	158 and 316	1.908
70	"	"	0.22420	11.500—18.000	182.000	157.000	1.908
71	"	"	0.23330	10.500—15.600	127.300	102.300	1.908
72	"	"	0.24100	3.500—19.000	137 to 393	112 to 338	1.952
73	"	"	0.16170	3.500—20.000	180.000	154.900	1.900
74	"	"	0.16170	7.270—13.500	"	"	1.860
75	"	"	0.16170	14.000—21.800	131.000	106.200	1.778
76	"	"	0.19170	12.590—15.000	178.000	153.000	1.800
77	"	"	0.20750	17.000—21.300	157.000	57.000	1.891
78	"	"	0.20750	17.000—21.300	"	"	1.816
79	"	"	"	17.000—21.300	"	"	1.868
80	"	"	"	17.000—21.300	"	"	1.863
81	"	"	"	17.000—21.300	"	"	1.852
82	"	"	"	17.000—21.300	"	"	1.816
83	"	"	"	17.000—21.300	"	"	1.873
84	"	"	"	17.000—21.300	"	"	1.873
85	"	"	"	17.000—21.300	"	"	1.873
86	"	"	"	17.000—21.300	"	"	1.873
87	"	"	"	17.000—21.300	"	"	1.873
88	"	"	"	17.000—21.300	"	"	1.873
89	"	"	"	17.000—21.300	"	"	1.873
90	"	"	"	17.000—21.300	"	"	1.873
91	"	"	"	17.000—21.300	"	"	1.873
92	"	"	"	17.000—21.300	"	"	1.873
93	"	"	"	17.000—21.300	"	"	1.873
94	"	"	"	17.000—21.300	"	"	1.873
95	"	"	"	17.000—21.300	"	"	1.873
96	"	"	"	17.000—21.300	"	"	1.873
97	"	"	"	17.000—21.300	"	"	1.873
98	"	"	"	17.000—21.300	"	"	1.873
99	"	"	"	17.000—21.300	"	"	1.873
100	"	"	"	17.000—21.300	"	"	1.873



EXPERIMENTS ON RIVETED PIPE
BY
L. C. GILTNER AND D. A. KETCHUM, JR.



forming irregular orifices within the pipe, brought the value up to 1.98. Again, of two disc meters, otherwise of exactly the same size and type and running under similar conditions, one, which had exceedingly meager, tortuous and rough-edged passages, gave $n = 1.93$, while the other, with much freer passages, gave 1.82.

Experiments were made also with a disc-shaped box, into which the water was led either tangentially or radially, and from which it discharged axially. When the water entered tangentially, a whirl was formed, producing a great difference of pressure between the circumference and the center, owing to centrifugal force, the pressure at the circumference being of course the greater. In this case $n = 2.13$. When the water entered radially, no whirl occurred, the difference in pressure was much less, and $n = 1.83$.

In all these experiments, which were carefully made, n showed a marked tendency to be less for low than for high velocities; and, since an average had to be taken, it was found useless to attempt to give n to more than two places of decimals.

MR. GEORGE H. FENKELL.—The author feels that he can say but little in conclusion.

The discussion by Mr. Hazen is not only very interesting, but is of great practical value, especially to those engineers who are accustomed to use the slide rule in all ordinary computations. As to the formula $V = c^1 r^{0.625} s^{0.50}$, it is probable that none has as yet been advanced which gives any more uniform values for the constant than this.

The following table, No. 7, gives values for the constant in Mr. Hazen's formula, corresponding to various values for the same in the Chezy formula. The numbers in italics in the table are the nearest values of c^1 to 130, the co-efficient used by Mr. Hazen in Table No. 2; and they show, in a general way, the divergence in values of the constants in the formulæ.

The discussion by Mr. Hubbell on some of the uses of logarithmic paper is timely, and, in a general way, coincides with the author's experience. Many of those who have heretofore made use of this valuable instrument in the reductions of various observations seem to have partly, at least, lost sight of its disadvantages, as well as some of its most valuable features, and the reduction of the experiments on 12-inch pipe given by the same writer illustrates several of these points.

It is not necessary for Mr. Williams to apologize for presenting, in his discussion, the results derived from again reducing the observations made by some of the pioneers in experimental

hydraulics. We can never hope to attain perfection in our work, and it is only by careful study of the past that we can hope to improve in the future.

In Fig. 2, Plate 26, Mr. Williams shows that the intercept $\pm b$, as shown on Plates 1 to 20 and in Table I, "may indicate that H_f does not vary exactly as H_v or V^2 ." We know that this is true with the smaller sizes of pipes, and it may be that in some cases the author has averaged as straight some that are actually curved.

He has, however, endeavored to avoid this. The experiments on the 3-inch riveted pipe and on 2-inch brass pipe are valuable

TABLE No. 7.

COMPARISON OF CONSTANTS IN CHEZY AND HAZEN'S FORMULÆ.

CHEZY FORMULA— $\tau = cr^{0.50} s^{0.50}$.HAZEN'S FORMULA ($-\tau = c^1 r^{0.025} s^{0.50}$).(c and c¹ Remain Constant for All Values of s.)

Size of Pipe.	c	c ¹	c	c ¹	c	c ¹	c	c ¹	c	c ¹	c	c ¹	c	c ¹
2	00	133.0	100	148.8	110	163.7	120	178.5	130	193.4	140	208.3	150	223.2
4	"	122.8	"	136.4	"	150.1	"	163.7	"	177.4	"	191.0	"	204.6
6	"	116.7	"	129.7	"	142.7	"	155.6	"	168.6	"	181.6	"	194.6
8	"	112.6	"	125.1	"	137.6	"	150.1	"	162.6	"	175.1	"	187.7
10	"	109.5	"	121.6	"	133.8	"	146.0	"	158.2	"	170.3	"	182.5
12	"	107.1	"	118.0	"	130.8	"	142.7	"	154.6	"	166.5	"	178.4
16	"	103.1	"	114.7	"	126.2	"	137.7	"	149.1	"	160.6	"	172.1
24	"	98.2	"	109.1	"	120.0	"	130.9	"	141.8	"	152.7	"	163.6
30	"	95.4	"	106.1	"	116.7	"	127.3	"	137.9	"	148.5	"	159.1
36	"	93.3	"	103.7	"	114.0	"	124.4	"	134.8	"	145.1	"	155.5
42	"	91.5	"	101.7	"	111.9	"	122.0	"	132.2	"	142.4	"	152.5
48	"	90.0	"	100.0	"	110.0	"	120.0	"	130.0	"	140.0	"	150.0
54	"	88.7	"	98.5	"	108.4	"	118.2	"	128.1	"	138.0	"	147.8
60	"	87.5	"	97.3	"	107.0	"	116.7	"	126.4	"	136.2	"	145.9
72	"	85.6	"	95.1	"	104.6	"	114.1	"	123.6	"	133.1	"	142.6

contributions to hydraulic literature, and Table 6, with values of n , arranges the data of previous experiments in small pipes in very convenient form.

The brief discussion by Mr. Trautwine is particularly interesting, inasmuch as it deals with the loss of head usually occurring in meters, a subject apparently much neglected in the past, especially in sizes over one inch.

Probably one reason for this apparent neglect in the past has been the difficulty in measuring accurately the losses of head when velocities are extremely low with any apparatus yet proposed.

SUBMERGED PIPE CROSSINGS OF THE METROPOLITAN WATER BOARD.

BY CALEB MILLS SAVILLE,* MEMBER OF THE BOSTON SOCIETY OF CIVIL ENGINEERS.

[Read before the Society, February 26, 1901.†]

IN the fall of 1895 the work of laying pipes for the water supply of the district immediately surrounding Boston was begun by the Metropolitan Water Board, two members of this Society, Mr. F. P. Stearns and Mr. Dexter Brackett, having been appointed, respectively, Chief Engineer and Engineer of the Distribution Department. In laying the pipes to the several parts of the district a number of rivers were crossed, and the methods employed in laying the pipes at some of these crossings, while perhaps not presenting any novel features, were of some interest, if for nothing more than their variety.

MYSTIC RIVER CROSSING—36-INCH PIPE.

Of the two 48-inch pipe lines running from Chestnut Hill Reservoir to Spot Pond, the easterly one crosses under the Mystic River, just east of the bridge on Middlesex avenue, between Medford and Somerville. At this point the river is a tidal stream about 1100 feet wide at high water and about 300 feet wide at low water. The average range of the tides is about 10 feet, and at low water there is a depth of about 9 feet in the channel. Rod soundings were made along the line of the proposed location, and it was found that, except near the Somerville shore, where gravel and sand were found, from 10 to 20 feet of river mud overlaid, and imperceptibly blended into, a stratum of sandy silt of unknown depth. The work done at this crossing consisted in laying two parallel lines of 36-inch cast iron pipes 5 feet 9 inches on centers under the river and connecting them by means of Y-branches with the 48-inch pipes previously laid on each shore.

In the early part of March, 1897, the contract for doing this work was awarded to MacRitchie & Nichol, of Chicago, who commenced operations about the middle of April. The first work was the excavation of the trench for the pipes, and this was done by the Eastern Dredging Company. The trench was dug about 35 feet wide at the top, and had an average depth of about 8 feet below the surface of the mud, the lowest point

*Division Engineer, Metropolitan Water Board.

†Manuscript received March 16, 1901.—Secretary, Ass'n of Eng. Soes.

dredged being about 16 feet below mean low water. During this work the dredges were kept in line by ranges set upon shore, and the depth was regulated by tide gages and marks on the dredging apparatus and by sounding chains. Three different styles of dredges were used, each suited for the particular place in which it worked. From near the channel to the north shore the bed of the river rose gradually; and, beginning at the channel, a large dipper dredge excavated the material, working against an almost perpendicular face, the material standing well if not left





PLATE I. SECTION OF SPECIAL JOINT FOR PUTTING PIPE TOGETHER UNDER WATER.

Spigot turned off and lead cast in bell.

too long. Across the channel, where the bottom was comparatively level, and where, on account of navigation and the opening and closing of the draw, it was necessary to use a dredge more easily handled, an ordinary clam-shell dredge was used. South of the channel and well out of the way of vessels, a dredge having an A frame and long boom on which was a clam-shell bucket was used. From the north shore to the channel the material was loaded into scows, towed about half a mile and dumped on the mud flats, from which it was afterward re-dredged for filling around the pipe. From the channel to the south shore the material was deposited on the mud flats alongside the trench by the scow with the long boom, and later replaced by the same

scow. The work of excavation occupied about forty-four days, during which there were excavated about 11,000 yards of material, an average of about 250 cubic yards, or 27 lineal feet, of completed trench per day. In backfilling, the trench was filled to a point about two feet above the tops of the pipes; 19 days were employed on this work, 500 cubic yards being replaced per day,—equivalent to backfilling about 63 lineal feet of trench. The costs of the excavation and backfilling were respectively 54 cents and 23 cents per cubic yard. On account of the material encountered, it was decided to use a pile foundation for the pipes throughout the entire length of crossing. The piles were of spruce, driven about 23 feet into the river bottom by a floating pile driver having a hammer weighing about 2000 pounds, working with a fall of about 15 feet. The piles were driven 6.3 feet on centers, in two-pile bents, crosswise of the trench, and the bents were spaced 12.1 feet apart and in such position that each pipe, when laid, would have a bearing on a pile bent about four feet back of the face of the bell of the pipe, except at the spherical joints, where an extra bent was driven in order that there might be a support on each side of this joint. The piles were capped with 10 x 10 spruce timber and were cut off and the caps bolted on under water by a diver. The cost of cutting the piles and bolting on the timber was \$3 per pile, and the price for furnishing and driving the piles was 12½ cents per gross pile foot.

The pipes under the river below Elevation 5, Boston city base,* were furnished by the contractor after being inspected and accepted by the Metropolitan Water Board. They were 1.65 inches thick and were of five different kinds, as shown in the following table.

	Length, Feet.	Weight, Lbs.	Cost per Ton.	Lead per Joint, Lbs.	Depth of Lead in Joint.
Spherical bell with spherical spigot	12.53	8260	\$23.90	248.0	8 ins.
Spherical bell with bead spigot	12.17	8140	23.90	248.0	8 "
Grooved bell with spherical spigot	12.59	8040	23.90	81.5	3 "
Grooved bell with bead spigot	12.10	8210	17.90	81.5	3 "
Grooved bell with taper spigot	10.10	8030	22.90	81.5	3 "
Sleeves	40.00	128.3	4 "

The spherical joints were similar to the Ward joint, a flexible ball-and-socket joint designed for a maximum deflection of 1 in 10 in any direction without the spigot leaving the bell. In these

*Boston city base is 0.64 feet below mean low water.

joints, however, the lead always remains in the spherical bell, while a raised portion, cast on the spigot end of the next pipe and turned truly spherical, plays against the stationary lead in the pipe bell when the joint is deflected. At the base of this raised portion is a stop, against which the face of the bell is pressed when the maximum deflection of the joint is reached, while in the spherical bell is a raised ring turned to a true circle, which presses tightly against the raised portion cast on the spigot, and prevents lead from running into the pipe when the joint is run. On Plate I are shown sections of the spherical and taper joints, and on Plate II is an elevation of the pipe-laying scow, showing the method of laying the pipes. The scow used was of the ordinary pattern, about 70 feet long and 23 feet wide, with a flush deck. On this deck were erected two stiff-legged derricks for laying the pipe, four winches for moving the scow, a 4-inch centrifugal pump for jetting out the trench if it became filled, an hydraulic pressure pump, furnishing power for pipe laying, an air compressor used in testing for leakage and a boiler furnishing steam to the pumps and the air compressor. On one side of the scow was a straight truss, about 75 feet long, suspended from the derrick in such a manner that a section of pipe fastened to the lower chord of the truss would hang parallel with and just clear of the side of the scow. On the opposite side of the scow was a smaller scow, loaded with gravel, which was fastened to the pipe-laying scow, and which served as a counterweight to balance the pipe on the truss.

The pipes were made up on a temporary wharf, erected for the purpose, not far from the work, usually in sections of six pipes each. At one end of a section was a pipe with a grooved bell and taper spigot, the other pipes being usually of the ordinary pattern. Into the bell end of the last pipe in each section the taper spigot of another pipe was temporarily inserted and the joint run with lead.

When this joint had cooled, this spigot was pulled out, leaving the lead joint in the bell. The pipe with this taper spigot would be the first pipe used in the next section, and when this next section was put in place this spigot would again be fitted into the lead joint from which it had been pulled. After the section was fastened to the truss by chains, the scow would be warped into exact position by means of the winches and anchors. When properly located, the section would be lowered on the truss and placed as directed by a diver. On the end of the truss nearest the pipes already laid was a hydraulic cylinder, to the




PLATE II. ELEVATION OF PIPE-LAYING SCOW, MYSTIC RIVER, 1897

piston of which was fastened an iron rod with a hook at the end. A chain having been fastened back of the bell of the last pipe laid, this hook would be fastened into it, and, when oil was forced into the cylinder, the truss would be drawn forward and the spigot of the first pipe attached to it would be forced home into the bell of the last pipe laid. Fastened to the bell was an iron collar which served the double purpose of enabling the diver to more easily enter the spigot, and it also seemed to protect the lead joint in the bell from being forced out of place by the spigot being carelessly entered. Wooden bulkheads were kept in the ends of the pipe sections until just before the spigot was forced home, in order to keep mud and foreign bodies out of the pipe line. Plate 10 shows a section of pipe ready to be lowered.

Across the river the pipes were laid in a straight line horizontally, but where vertical deflections occurred the spherical joints were used. These pipes with their joints were built into the sections, the same as the other pipes, the joint being deflected to fit the position in which it was to be placed. After the pipes were all laid they were thoroughly calked by the diver, and then tested for leakage before the trench was refilled. For use in testing, a $1\frac{1}{2}$ -inch hole had been drilled in the top of that pipe of each line that was to be at the lowest point. While being laid, a plug was screwed into this hole, but, when ready for testing, the plug was removed by the diver, a bushing screwed in and a 1-inch wrought iron pipe screwed through the bushing. One end of this pipe was opened and placed about one inch from the bottom of the pipe. On the other end was a check valve, opening outward. Manhole pipes, for allowing access to the interior of the pipe lines, were placed on each line on both sides of the river, and through the covers of these pipes on the Somerville shore holes were drilled and a flexible steam hose laid from the air compressor on the pipe-laying scow moored near by. Air pressure being put on, the water in the pipes was forced out through the check valve on the inch pipe. When the water was all discharged, this pipe was withdrawn, and the plug screwed back by the diver. The 36-inch pipes were then inspected by members of the engineering force, who went through both lines from end to end. After this, air was pumped into the pipes, and a pressure of 25 pounds per square inch maintained for about a week. During this time, several large leaks, that were indicated by the air bubbles, were stopped by the diver calking the lead in the joints. Water was then admitted, and after several trials of air and water pressure a satisfactory pipe line was obtained. The same methods

and pipe-laying plant employed at the Mystic River were also used in laying double 36-inch pipe lines under the Charles River in two places in Cambridge.

The total cost of this work, including pipe, labor, materials and an allowance for the use of the tools and plant, was about \$13.25 per lineal foot, of which \$6.75 per lineal foot was paid for the pipes.

MALDEN RIVER CROSSING—36-INCH PIPES.

The 48-inch pipe line, a part of which has just been described, also crosses under the Malden River just north of the bridge on Medford street, Malden. At this place the river at high tide is about 120 feet wide and 10 feet deep, while at low water there is only a shallow stream a few feet wide. The material encountered was a thin layer of river mud, overlying a stratum of sand and gravel a few feet thick, under which was a stiff blue clay, which made an excellent foundation on which to lay the pipes, and an ideal cut-off into which to drive the sheet piles of a coffer dam. On the east side of the river was a granite sea wall, and in the center was a wooden draw pier about fifteen feet wide, on a pile foundation. On the west bank, at the beginning of the work, the marsh flats sloped to the water; but later, under a separate contract with the owner of the land, a wooden bulkhead was built by the firm doing the work for the Metropolitan Water Board. As at the Mystic crossing, the work to be done was to lay two lines of 36-inch cast iron pipes under the river, and by Y-branches connect the two lines with the 48-inch pipes previously laid on each side. In this case, and in those following, the pipes were furnished by the Metropolitan Water Board. A contract for doing this work was made with Moore & Co. and W. H. Ward, of Boston, and the work was begun about the middle of October, 1897, and finished February 1, 1898. As there was very little navigation passing this point, especially at this season of the year, the contractors decided to use a coffer dam for laying the pipe. The first work done was to set up three large steam derricks, one on each side of the river and one on the pier about half-way between the other two. These derricks were so arranged that materials could be passed by them from one end of the work to the other. In order to build the coffer dam and lay the pipes, it was necessary to take down portions of the sea wall, bridge and draw pier. In removing the sea wall, it was found to rest on piles, which it was expected could be capped for a platform for supporting the sea wall over the pipe lines. When, however, the attempt was made

to saw these piles off, they fell out of their places, being only about five feet long, and it was necessary to drive new piles for the support of the wall. In taking down the bridge pier it was desirable to remove several oak piles. Two attempts were made to draw them; one by means of a chain attached to the piles and to the end of the derriek boom, and the second by means of a long timber used as a lever, the long end of which was likewise attached to the boom. Although a force estimated at about twelve tons was exerted, neither method was successful, and the piles were sawed off. The walls of the coffer dam were composed of a single thickness of 6-inch spruce and 4-inch yellow pine timber, supported by spruce piles and 8 x 12 spruce waling, tied together and braced as shown on Plate III. The sheeting had grooves, into which hard pine splines 1 inch thick and 2 inches wide were placed. This sheeting was about 24 feet long, and was driven by an ordinary land pile-driving machine into the clay about two feet below the bottom of the proposed pipe. In driving, the sheeting was kept close up to that already driven by an iron dog and an oak wedge which was tapped with a maul from time to time as it loosened under the driving. For the support of the pile driver, a few spruce piles were driven out in the river by means of the pile-driving machine erected on a raft made of oil barrels and large timbers. On these piles and the bridge a scaffolding was placed, and on this the pile driver worked while driving the sheet piles in the coffer dam. Between the walings, the coffer dam was 14 feet 6 inches wide, and was built in two sections, each extending to the middle of the river, and one removed before the other was built. The first section was about 85 feet long, and at its river end two cross walls about eight feet apart were built. When the rest of this section was removed, these walls and the longitudinal walls connecting them were not removed, but became the river end of the second section. In each of these cut-off walls a gate was built, so that the dam could be flooded if necessary. The coffer dam was comparatively tight, but to avoid straining it was customary to open the gate and flood the dam when the tide had risen to within two or three feet of the top. When the tide fell, the gate being open, the water would fall inside the dam to the bottom of the gate and the remainder would be pumped out by a 6-inch centrifugal pump. About two hours was necessary to free the dam from the water. In removing the coffer dam, an attempt was made to draw the sheeting for use in the other portions, but after

several attempts had been made without success, it was cut off about one foot below the top of the pipes. In removing the round piles, they were first sawed off as low as possible and a 1½-inch hole bored down into the pile four or five feet. A dynamite cartridge was then pushed to the bottom of the hole and exploded by a battery on shore, and the pile would be broken off as low down as the cartridge was placed. Across the river the pipe was laid with its top about five feet below the river bed. The pipes used were about 1.65 inches thick; the lead space in the joint was about five inches deep and took about 150 pounds of lead when run solid. In laying the pipes, work was begun in the center of the river and the pipes laid up each side. The spigot end of the first pipe to be laid was put through a circular hole in the inner of the two cut-off walls mentioned above, and the space between the plank and the pipe calked tightly, to prevent water coming in when this inner wall became the outside wall of the next section. When the next section was ready, a sleeve was put on this spigot end and then the pipes were laid up the bank. On account of the cold weather and the large amount of lead to be poured into a joint, it was found expedient to run the joint at two pourings,—one from the sides and the other on top. A clay roll was used long enough to go completely around the pipe and make sufficient gate at the top. For the first pouring this roll would be brought two-thirds the way round the pipe and lead poured into the joint from each side of the pipe up to this point; the ends of the roll would then be brought over the top of the pipe and the remainder of the joint poured in the ordinary manner. These joints were perfectly satisfactory, and when the pipe was tested it showed no leakage whatever. The excavation, backfilling, pipe-laying and handling timber and machinery were done by the derricks, and on this account only a minimum number of men were employed. The estimated cost of building the coffer dam was about \$13 per lineal foot.

MYSTIC RIVER CROSSING—20-INCH PIPE.

As a part of the main pipe line supplying the town of Arlington with water, a 20-inch pipe was laid under Mystic River just north of the bridge on High street, Medford, which is also just below the lower of the two Mystic Lakes. For this crossing a pipe 1 inch thick and weighing about 2700 pounds per 12-foot length was used. This pipe was of the ordinary bell-and-spigot type, but made extra thick to provide for deterioration from rust, etc.



The location of the pipe crossing is 60 feet north of the bridge, the river being here about 35 feet wide and having a maximum depth of $3\frac{1}{2}$ feet. The top of the pipes were laid one foot below the bottom of the river bed at its lowest point. On the east side the ground slopes gradually to the water, while on the west bank there is a rough retaining wall about $1\frac{1}{2}$ feet high. The work of making this crossing was included in the pipe-laying contract of Bruno & Salomone, of Boston, and was begun about the 1st of June, 1899, on the east bank of the river.

A section of coffer dam 5 feet wide inside, starting about fifteen feet back from the edge of the stream, was built about thirty feet out into the river and securely bulkheaded. The sheeting used on this section was ordinary spruce plank 2 inches thick and about 8 feet long, driven about one foot below the bottom of the trench. The material taken from this trench was sandy clay and was banked about outside of the sheeting. Very little water came in through this material, one hand pump easily keeping the trench dry. Three pipes were laid in this trench and a bulkhead built just back of the last bell. When this work was done, pairs of 4 x 4-inch stakes about 5 feet long were driven on each side of the line of the proposed trench at intervals of about ten feet across the river. These stakes were thoroughly secured to each other by 2-inch planks, spiked between them both with and across the current. On this foundation was placed a platform for supporting the derricks, pumps, etc. Later, other 2-inch planks were spiked to the posts cross-ways of the river and fastened to them as far down in the water as was possible. These planks helped to confine the gravel and clay that was packed around outside the sheeted trench.


About ten or twelve feet on each side of the line of the trench, and also across the end about two feet beyond where it was intended to stop this section, a dam of sand bags was built. The bags used were 50-pound coffee bags filled with sand, and were laid three or four tiers high.

After this portion of the work was finished, 3-inch tongued-and-grooved planks, about 8 feet long, were driven in two parallel lines about five feet apart, and the material excavated was thrown around the outside of the sheeting, between it and the sand bag dam previously built. In the bottom of the trench the material was found to be gravelly, but one hand pump was sufficient to handle the water. When the pipes were laid in this section, a bulkhead similar to that used in the preceding section was built. These bulkheads served as the rear end of the trench



when a new section was opened, and allowed the bell end of the pipe already laid to project into the new section of trench. After the pipe was laid and backfilled, the sheeting was pulled, and the sand bags in the side walls were taken up and moved ahead



Section on AB.



0 2 4 6 8 10
Feet



0 1 2 3 4
Meters

PLATE III. PLAN AND SECTIONS OF
COFFER DAM, MALDEN RIVER, 1898.

PLATE IV. PLAN AND SECTIONS OF
COFFER DAM, MYSTIC RIVER, 1899.

to form the walls of the next section, which extended from about the center of the river to the west bank and completed the crossing. The sand bags in the end were also taken up and moved back into the stream till they were just back of the bulkheaded portion of the pipe, and when the same process of filling with clay

and driving the sheeting had been finished, this portion of the pipe was inside the coffer dam. Less care was taken with this section, and three hand pumps were necessary to take care of the water. Plate IV shows a plan and sections of the coffer dams. The total cost of the work was estimated to be about \$7 per lineal foot.

SAUGUS RIVER CROSSING—20-INCH PIPE.

Nahant and Swampscott having, in 1898, applied for permission to enter the Metropolitan Water District, it became necessary to lay a main for their supply. On the line of this main it was necessary to cross the Saugus River on Broadway at the Fox Hill bridge, between Lynn and Saugus.

The Saugus River at this point is a tidal stream varying in width from about 500 feet at high water to about 250 feet at low water, the average rise and fall of the tides being about 10 feet, and there being a maximum depth of about 5 feet in the channel at low water. From rod soundings it was found that the bed of the river was composed of a stratum of river mud varying in depth from 4 to 10 feet and overlying a stratum of silt containing more or less coarse sand. Three plans were somewhat considered for crossing this river: one to lay an entirely submerged line, another to lay the pipe wholly above water in a box attached to the bridge and the third a combination of the other two. The principal objection to the first was the expense, especially as it seemed likely that a pile foundation would be necessary the whole distance. To the second plan the objection was that, although the existing draw was very narrow and had not been used for a long time, yet, on account of certain wharf privileges further up, it would have been difficult, without considerable expense, to obtain permission to permanently close it to navigation. The third method was adopted, and it was decided to carry the pipe inclosed in a box on the bridge as far as the channel and to cross this by an inverted siphon similar to those in use at several of the river crossings in Boston and described by Mr. Brackett in a paper before this Society published in the *JOURNAL OF THE ASSOCIATION OF ENGINEERING SOCIETIES* for February, 1886. This siphon consisted of a cast iron pipe surrounded with concrete and boxed with heavy timbers thoroughly bolted together. The shape of this siphon was like three sides of a parallelogram, the middle side resting on the bottom of the river about twelve feet below Boston city base and the two other sides standing one on each side of the channel forty-five feet apart.

About the time it was intended to lay this pipe, the Lynn and Boston Street Railway Company decided to widen the existing bridge and so obtain a portion that could be used exclusively by them. Arrangements were made with the railroad company and their plans modified to the extent of driving extra piles west of the bridge in all the pile bents and extending their girder caps about six feet. On the foundation thus formed was placed the pipe box afterward built.

In the last part of March, 1899, the contract for building the pipe boxes and siphon was awarded to W. H. Ryan & Co., of East Boston, and the work of getting ready the materials was at once begun.

The siphon box was framed and fitted at a lumber yard at East Boston, then partially taken apart, loaded onto a lighter and carried to the site of the proposed work. The box was built of first quality hard pine lumber, bolted and strapped together. The dimensions of the lumber and detail of the bolting is shown on the plan and elevation on Plate V. A trench was dredged across the channel to receive the bottom portion of the siphon, and two of the four guard piles about each of the upright portions were driven to serve as guides in lowering the box.

In the dredged trench two bents of two spruce piles each were driven and cut off as far down as possible at low water. These piles were capped with 14 x 14-inch hard pine riders at right angles to the trench, the caps being held in place with iron dogs. At high water the bottom portion of the box was floated into place directly over the pile caps, and at low water it was allowed to settle down upon them, where it was securely held from again floating by cross-braces bolted to the surrounding piles. The outer and two side pieces of the vertical portions were then bolted into place during succeeding low water periods, while at high water work was done on the pipe box on the bridge. Before placing the inner sides of the vertical portions and the top of the horizontal part, the pipe was laid by the Maintenance Force of the Water Board. As there was only 2 feet and 8 inches clearance inside the box, which was not sufficient to properly calk the joints after the pipe was put in, the pipe for the bottom portion, including the two 20-inch one-quarter curves, was made up and bolted together with 1½-inch steel rods and turn buckles, the pipe resting on cross timbers which in turn rested on the side walls of the box, so that the pipe was directly over its proposed position. When the joints had been made up and calked, the pipe was raised by four pipe jacks, the cross-timbers taken out and the

pipe lowered into its place in the box. After lowering, the joints were carefully examined, and, no movement being apparent, Portland cement concrete in the proportion of 1-2-4 and mixed rather wet was put all around the pipe up to the top of the side timbers, and the top was then bolted on.

The vertical pipes were readily placed in position, as all the inside timbers and the outside key pieces were left out in order to give room for the pipe work. After one pipe had been placed in the uprights on each side, the timbers were bolted on and the space between the pipe and box was filled with concrete, thoroughly rammed with a long stick. The upper pipes in the verticals were not laid until the siphon had been lowered, and then at low water the bells of the pipes already laid were out of water. The vertical portions were tied together with 1½-inch rods, which were held in place by templates while the concrete was being put in.

For lowering the siphon, several methods were suggested,—one, that professional riggers be employed and lower it by means of shears erected on the bridge; another, that two lighters be used, which, being lashed to the siphon at high water, would allow it to settle into place with the fall of the tide. Either of these methods was feasible, but the following method was employed and was much the cheapest and in many respects the most satisfactory. A building mover having been engaged, the four guard piles which had now been driven about the vertical portions were cut off level with the tops of the girder caps in the bridge. Two 14 × 14 hard pine timbers were placed, one on each side of the upright portions; on these timbers a crib work of blocking, such as is used in house moving, was built around the upright parts of the siphon to a point about two feet below their tops. The method employed in lowering the siphon is shown on Plate IX.

At the top, four heavy timbers were tightly clamped to the verticals by means of ½-inch iron rods, and just above these clamps holes were bored in the timbers and iron plugs, 2 inches in diameter, were driven in. Under the clamps, and resting upon the blocking, building movers' jack-screws were placed. At first eight were used to each vertical, but later six were found to be enough. When all was ready, the screws were tightened just enough to raise the siphon box clear of the pile caps on which it rested; these caps were then removed and the work of lowering the box was begun. This work was continued without accident

On account of the depth of water, there is considerable traffic on the stream at all stages of the tide to and from the numerous iron foundries and coal and oil wharves. One of the existing pipe lines was 20 inches in diameter and was laid about 1850; the other line was 24 inches in diameter and laid in 1871. The former line was so badly tuberculated and corroded that it had been practically out of commission for the past few years, and existed only as an emergency line in case of accident to the other. The Boston Water Department had intended to relay this line and had bought the pipes, but before the work of laying them was begun both lines were taken by the Metropolitan Water Board, and the work was done under its direction, the pipes being brought from the city of Boston. In the paper by Mr. Brackett, mentioned above, sketches of the flexible joints used on both lines are shown and a description is given of them. Concerning the method of laying the older pipe, Mr. Brackett says: "This pipe was prepared on a staging and lowered by tackle into the trench, which was then filled with gravel and clay." After the trench was dredged for the new pipe line, the diver encountered a number of piles at various places across the channel, which probably were portions of this staging, and when the old pipes were removed, nearly all the flexible castings had a rope sling about them.

Previous to letting the contract for the pipe laying, both lines of pipe were located as well as possible by rod soundings. These soundings were taken, from a raft anchored in the stream, by men using a rod made up of 15-foot lengths of $\frac{3}{4}$ -inch gas pipe coupled together. The soundings were located by angle and stadia distance from a point on a platform built on one of the fender guards near by. On account of the depth of water and the strength of the current and the peculiar manner in which the pipes were laid, much difficulty was experienced in locating the pipe, and at times it seemed as if the bottom of the river might be covered with pipes. However, after repeated soundings, a line was at last determined upon, where the pipe at any rate ought to be located, and later, when the pipe was removed, it actually was found very nearly as expected. Early in August, 1900, the contract for removing the existing 20-inch pipes, laying the new line of 24-inch pipes and rebuilding the pile fender guards and dolphins, which were badly decayed, was awarded to Messrs. MacRitchie & Nichol, of Chicago, the same firm that had successfully laid the submerged pipes at the Mystic and Charles River crossings.

For about 200 feet on the Chelsea side and for about 750 feet on the East Boston side of the channel the existing pipes rested on a pile foundation, raised only a very little above the surface of the mud flats, and were wholly exposed and unpro-




PLATE VI. SCOW RAISING OLD 20-IN. PIPE

tected at low water. These pipes were of the ordinary bell-and-spigot type, but only 9 feet long. Originally the walls of the pipes had been seven-eighths of an inch in thickness, as was shown by the measurement of the spigot end of a pipe which was pulled out of the bell on the next pipe to it. Beside the

fact that the whole barrel of these pipes was somewhat reduced in thickness, there were also many places where the rim had become softened and could be cut into for a quarter of an inch with a knife. After removal, both the pipes above low water, as well as those below, were found to be very badly tuberculated, the inside diameter of the pipes being reduced as much as two inches with a solid mass of incrustation. Below low water the pipes were laid with a peculiar swivel joint, which was so designed that it allowed the freest possible motion vertically, but allowed no deflection horizontally. These pipes and specials were all connected together with flanged joints. The straight pipes were 9 feet in length and at the end of each three pipe section one of these joints was used, making a right-angled offset in the pipe line.

These pipes were $1\frac{3}{4}$ inches thick, and when covered with clay the iron was excellently preserved. After the pipes were uncovered by a dredge they were lifted from the bottom in short sections by the shears and tackle on a large wrecking scow and taken away, becoming the property of the contractor. The method of raising is shown on Plate VI, where a section with one of the flexible joints is being hoisted. Above low water the pipes were broken by sledges into two-pipe sections and raised by the scow afterward employed in laying the 24-inch pipes. The pipes relaid above low water were 0.95 inches thick, having ordinary bell-and-spigot joints, and the iron of which they were made was of a special composition which it was expected would resist corrosion to a considerable extent. Below low water the pipes were 1.25 inches thick and had ball-and-socket joints similar to those used at the Mystic and Charles River crossings, and described above. In laying the pipes, both above and below low water, a large scow about 75 feet long and 25 feet wide, with a flush deck, was used. The scow was hired by the contractors, who themselves fitted it out with winches, derricks and slide for lowering the pipe. Winches were employed to move the scow by means of anchor lines. For lowering the pipe two stiff-legged derricks and a curved slide were used for the pipe laid below low water, while for that laid above low water only the derricks were used. The slide or cradle by means of which the pipes were laid below low water was about 75 feet long and built curved in shape to an 80-foot radius, which was a little less than the maximum deflection to which the pipes could be laid. This slide was well braced and trussed and hung by wire ropes from the larger of the two derricks, the other derrick being used to raise or lower the tail end




PLATE VII. ELEVATION AND SECTIONS OF PIPE-LAYING SCOW, CHELSEA CREEK, 1900.

of the slide, so that it might at all times be tangent to the bottom of the dredged trench. The tackle was so arranged that the whole slide could be raised or lowered vertically or tipped at any angle in a vertical plane. On the tail end of the slide was a wooden shoe, about 4 feet long, for the purpose of making the slide rest more evenly on the bottom; this shoe also probably served to even off small irregularities along the bottom of the trench. An elevation of this scow is shown in Plate VII. In the first place, this slide was filled with pipes, the joints of which were leaded. The scow was then worked into proper position at high tide, and the tail end of the slide was tilted down until it rested on the bottom of the river, but at such a depth that the end of the pipe would be exposed at low water. This end of the pipe was then securely anchored and the scow pulled ahead about twelve feet, causing the pipe to be pulled down the slide. Another pipe was then placed in the slide by a small boom derrick and the process repeated until all these pipes had been placed in the cradle and slid down into the trench dredged across the channel. This work is shown on Plate VIII. During the work the pipes were stored on a large lighter moored a short distance away, while for the immediate work ten or twelve pipes were stored on the pipe-laying scow and a smaller scow that served as a tender. The laying of the fifty-four pieces of submerged pipe actually occupied two weeks. Above low water the pipes were laid on the same pile foundation as had supported the previous pipe line; the piles were thoroughly examined, and, although they had been in use such a long time, they were found to be perfectly sound below the mud line, and only a little decayed on the outsides of the piles for the portion above the mud. In laying this portion of the pipe line the pipes were usually made up in four-pipe sections on the scow, which was floated approximately into position at high water and the pipe lowered onto the pile caps. At low water these sections were pulled together with tackle and falls and the joint between them leaded. After the pipes were all laid, the joints both above and below low water were thoroughly calked. When completed, the pipe line was subjected to a hydrostatic test of eight-four pounds per square inch for sixty minutes and the leakage recorded by the flow through a $\frac{3}{4}$ -inch meter was barely perceptible. For dredging and lining the pipe, ranges were set up on each shore, and by means of the quarter lines, the scows were easily kept in line. For stationing and location, ranges were set on the Meridian street bridge, which was about 1000 feet away and about parallel

with the work. These ranges were so placed that lines drawn through them and a prominent church spire in Charleston would intersect stations on the pipe line. To distinguish the station, large squares of white canvas, with solid black figures about a foot high, were nailed under each of the ranges. For keep-




PLATE VIII. SCOW LAYING 24-IN. PIPE, CHELSEA CREEK.

ing the slide from which the pipe was laid in proper position in relation to the bottom of the trench, a profile of the trench was drawn on paper and a paper model of the slide cut out to the same scale as that to which the profile was drawn. Knowing the depth of the water at any station from elevation of

the tide, read from tide gages located near by, the bottom of the slide could be readily adjusted and kept tangent to the bottom of the river by placing it in similar position to that of the model. In the spherical joints 130 pounds of lead per joint was used, while the ordinary joints took about 53 pounds. Of the lead used, about two tons was recovered from the joints in the old 20-inch line.

The cost of this work per lineal foot, estimated from the force accounts kept by the inspector, was :—

For removing the existing pipe and laying the pipe with spherical joints, \$8.25, and for removing and laying the pipe with ordinary joints above low water, \$2.25. These figures do not include the cost of the pipe, nor do they take into account anything which may have been received for the old pipe. A rental value for the use of the plant is included, and the cost of the dredging was estimated from a rental value of the dredges.

The costs which have been given above for the several river crossings are the actual costs to the contractors doing the work, estimated from notes and force accounts kept by the inspectors on the work. In giving these costs, it has seemed that the cost per lineal foot would be of as much value as a more detailed statement. While there is every reason to believe that the figures are very near the actual cost, yet this work itself is of such special nature that the same conditions under which it was done might never again be encountered, and other conditions would probably modify the cost so that the detailed figures could only be used by one thoroughly familiar with the circumstances under which the figures were obtained.

It may also be said that the actual cost of any engineering work which has been successfully completed without accident should only be used as a basis for estimating similar work.

Experience and judgment should dictate allowances to be made for unexpected conditions or mishaps.

DISCUSSION.

MR. CLEMENS HERSCHEL (by letter).—To the description of the several methods of laying water pipe under and across rivers given by Mr. Saville, it seems fitting to add another, showing a method devised and used by the writer five years ago to convey water across the Passaic River at Belleville, N. J. At this point the Passaic River is a tidal stream, with a mud bottom, mud flats or wharves on either side, about 600 feet wide between highwater lines, some 15 feet deep, and about 4 feet of tide and considerable

navigation on the river daily. The problem was to connect two 42-inch steel pipes, carrying some 40,000,000 gallons daily under some 350-foot head at the river, and it seemed to the writer that no form of flexible joint would answer the purpose; for the reason that such joints, even when well made and water-tight at the outset, would, under the pressure named, soon wear or cut out and cause an undue loss of water by leakage. At such high pressures lead will cut out under the action of even very minute jets of water, like a softer substance would under the effect of streams at ordinary pressures, and any effect of that sort will proceed more and more




PLATE IX. LOWERING 20-IN. SIPHON BOX, SAUGUS RIVER.

rapidly as the escaping streams enlarge and as time goes on. It seemed to the writer that this consideration and the locality named positively excluded all forms of leaded joint.

Instead, he was led to reflect that while the ordinary screw-joint may be called a stiff joint, yet a pipe line 600 or more feet long, when made up of 20-foot lengths with screw joints, would have considerable flexibility. A piece of bamboo two or three inches long is a very stiff thing when observed by our gross senses, but the same bamboo twenty feet long can be bent into a circle without breaking and with perfect ease. Similarly, a four-

foot riveted steel pipe is a rigid structure, in the ordinary sense of the term, but a line of it 500 feet long will readily bend to a circle of 1500 feet radius, and, what is very important, without even starting leaks in it. I have seen such a pipe (500 or 600 feet in length) float out of the trench it had been laid in, arrange itself in graceful reversed curves on the surface of the ground, and yet be apparently none the worse for its adventure after it had again been forced back into the original ditch.

Most pipe lines would float in water, and to remain on the bottom, while empty, would have to be loaded.

The plan adopted was, therefore, upon these considerations, to lay seven parallel lines of 18-inch lap-welded steel pipes, with screw joints, and loaded by cast iron reinforcements at each joint, by means of dragging the pipe line across the bottom of the river in a trench dredged for the purpose, and this was successfully done without the slightest mishap except unimportant ones during the first attempts on the first of the seven lines. The seven lines have been in use now about five years and have never leaked. I know this, because there is a Venturi meter on each side of the river, both of which are read and compared daily.

The pipe lines were put together on one shore in 200-foot sections; that is to say, 200 feet of pipe was put together, a temporary cap was placed at the two ends, and while keeping the pipe full of compressed air (to detect leaks) the 200-foot length was hauled out into the river by an ordinary hoisting engine set up on the opposite shore. The loading of the pipe having been so proportioned that there was only a slight excess of weight over the power of flotation, this hauling over was really a very simple matter. The first 200 feet once hauled out into or under the river, the inshore cap could be taken off, another 200 feet joined on, the cap be now replaced and the process first above described could be repeated, and again repeated, until the end first launched appeared above water on the opposite shore.

So satisfactory was the plan pursued that, were I to repeat it, I should not hesitate an instant to haul across one 42-inch riveted pipe in the manner described, rather than seven lines of 18-inch pipe. At moment of writing, this plan of operation has been adopted for laying a 6-foot steel, riveted pipe across a tidal stream. In this case the pipe must be braced on the inside to withstand the water pressure tending to collapse the pipe, but this bracing will form the load needed to keep the pipe on the bottom until it is laid from shore to shore. In this, and in every case of hauling pipes or tubes in the manner here described, the




PLATE X. LAYING 30 IN. PIPE, COVERING

loading need never cause the pipe or tube to weigh more than a desired amount in water, thus making the work of hauling the pipe or tube across a simple matter. To diminish the amount of flexure of this pipe, it will be built on a vertical curve.

Once across, the 6-foot pipe is to be encased in concrete and this again loaded with rip-rap, upon which the interior bracing may be removed; the bracing to be made originally in form permitting of an examination or caulking of the pipe from the interior, while it is being hauled across.

So much being said, it follows that pipes or tubes of any diameter could thus be hauled across and underneath navigable waterways; and I have, in fact, proposed this method not only for the laying of sub-aqueous gas and water pipes and sewers, but also for the construction of sub-aqueous tunnels.

In the case of gas and water pipes and sewers, the method above described is by far the most economical, and produces, moreover, a tight and durable pipe, where flexible joints would give trouble from excessive leakage. The same advantage of reduced cost is true in most cases of sub-aqueous tunnels.


MR. F. A. McINNES (by letter).—The methods recently employed by the Boston Water Department, under the direction of the City Engineer, in laying a 12-inch main under Shirley Gut, in Boston Harbor, differ from any described in the Saville papers, and, while extremely simple, may prove of some interest.

Shirley Gut is a short, narrow channel separating Deer Island from the mainland. At the point where the pipe crossing was made it is 350 and 150 feet wide, at high and at low water respectively, with 12 feet of water at low tide. At the same point, fifty years ago, it was 400 feet wide and 50 feet deep at low water.

A storm from almost any direction will often materially change its topography, while under the best conditions the sand and gravel, through which the channel flows, offer no inviting field for excavation, particularly as the current is extremely fast and the periods of slack water very short. These conditions demanded quick work, and made the possibility of failure unpleasantly prominent.

The pipe line was first put together on a cradle (on the Winthrop shore) extending back from high-water mark on a slightly rising grade. Under the cradle were 4-inch wooden rolls, resting on a platform. Each pipe was made fast to a 4-inch hawser, the latter being strained tightly as the "seizings" were made. A trench, 5 feet deep, very wide on each shore and about 3 feet deep in midstream, was then dug across the channel. This part of the

work was done in four days by an ordinary dipper dredge, its success depending entirely upon good weather. The trench completed, it was necessary to finish the work with all possible speed. A 4½-inch line, fastened to a "deadman" on the Deer Island shore, was carried across the Gut through a block on the 4-inch hawser at the end of the pipe; again across the Gut through a second block, and thence to a steam winch. At the first period of slack water, power was applied and the pipe moved readily, being kept on the platform by a number of men "cutting" the rolls as occasion demanded. As it entered the water, empty oil casks, which had previously been recoopered and fitted with fastenings, were tied to the pipe, the object being to reduce the weight a little more



SECTION OF 12-IN. FLEXIBLE PIPE.

Length over all, 12 ft. 6.07 in. Figured weight, 1815 lbs. Deflection, 1 in. 4.8.

than one-half. It was absolutely necessary that the pipe should remain in the trench, at all points, out of the full force of the current. With a few slight interruptions, caused by its flexibility on the platform, the pipe moved steadily across the channel to a point about half way between high- and low-water mark. Here progress became so slow, and the strain on the ropes so great that it was deemed wise to "let well enough alone" and to lay the next two or three pipes at the succeeding low tide. At slack water the casks were cut away by a diver. After two or three small leaks near the shores were calked, the line was tested and found to be practically tight. The trench was then filled in. Under favorable conditions of small current and stable bottom, a short pipe line can be laid, very cheaply and safely, in the general manner described above.

The pipe used was one inch thick, weighing 1820 pounds per 12-foot length. It was of special design, very similar to one of the pipes described by Mr. Saville. The spigot is turned to a true spherical form, and a raised ring is also turned in the bell, to fit the curvature of the spigot. A stop prevents too much deflection in the joint. Two lead scores were used. This design, shown in detail in the accompanying figure, causes the lead to remain in the bell whatever position the pipes lay, a desirable point when joints must be calked under water.

EXTENSION OF THE GROUP THEORY OF ATOMS AND MOLECULES.

BY ARTHUR A. SKEELS, MEMBER OF THE CIVIL ENGINEERS' CLUB OF CLEVELAND.

[Read before the Club, February 26, 1901.*]

THE great importance of a clear understanding of the laws which govern the properties and phenomena of matter, both physical and chemical, is self-evident.

The great achievements of modern science are due to the fact that we understand nature and her laws better than did our fathers, and the still greater marvels to be accomplished in the future will be due to a still better insight into the natural laws which govern matter in its properties and transformations.

So vast is the importance of this knowledge that it is surely worth our while to consider *anything* which even *possibly* may give us a little more light upon the many difficult problems ahead.

The contents of this paper give a few of the results and conclusions of several years of study. The limits of the paper will naturally allow only a brief discussion of these conclusions, and,



Fig. 1

if some of the ideas advanced seem to be radically different from those commonly accepted, it must be remembered that, while a thing is not always advantageous because it is new, yet if we follow exactly in the footsteps of our predecessors we cannot hope to learn new truths.

Scientists in general believe matter to be composed of molecules, and the molecule to be made up of atoms. For example, a molecule of water is the smallest particle of water that can exist as water. The molecule of water is in turn taken as composed of two atoms of hydrogen and one atom of oxygen; but only recently has the possibility of the divisibility of the atom been seriously considered.

When light is refracted, as by passing through a prism, it is also dispersed; the waves of shorter length are separated from the longer ones, forming a spectrum. Different substances, in general, give out different kinds of light, and so form different spectra. The spectrum of hydrogen is approximately as Fig. 1.

*Manuscript received March 18, 1901.—Secretary, Ass'n of Eng. Soc's.

The four lines show four different wave lengths of light, corresponding to 6562, 4861, 4340 and 4101 ten-millionths of a millimeter.

There may be other lines outside of the visible spectrum, not yet discovered, but at any rate the spectrum shows that hydrogen gives out light of at least four different wave lengths. If the vibrations of molecules produce this light, and if the molecules are exactly similar in all respects, how can they give four different wave lengths?

If the vibrations of atoms produce this light, how can the vibration of atoms, which are exactly alike in all respects, give four different wave lengths?

If the vibrations of both atoms and molecules produce the light, how can we account for more than two different wave lengths?

The spectrum of oxygen is approximately as Fig. 2.

That is, oxygen gives as many different wave lengths as there are lines in the spectrum. How can the vibrations of one kind of




Fig. 2

molecules or one kind of atoms produce so many different wave lengths?

It seems to me that the only logical conclusion is that the atom of oxygen is composed of as many parts as there are lines in the spectrum and that the vibrations of these parts cause the light. Also the different wave lengths show that these parts have different masses, or are acted upon by varying attractions while vibrating, or both.

The study of the spectra of all elements leads us to the same conclusions: that the atom is not the ultimate particle of matter; that the atom is composed of parts, and that the number of these parts may be determined, more or less accurately, by the number of different kinds of light emitted; that is, by the number of lines in the spectrum.

Upon this as a basis, aided by other important considerations which will appear as we proceed, we think we have good evidence to believe that in the same way that molecules are groups of parts called atoms, so are the atoms groups of smaller parts, which we may call sub-atoms. The sub-atoms are groups of still smaller parts, which we may call sub-subatoms; and by analogy these sub-subatoms are groups of even more minute parts, and so on until

a sub-atom is reached which is capable of no further division, and we have the ultimate atom.

We know that a few elements, by different groupings of the atoms and molecules, can form an almost innumerable number of compounds widely differing in properties. We go a step farther, and assume that all substances are made up by different groupings and compounded groupings of the ultimate atoms of one single absolute element.

The question now naturally arises, is this theory consistent with observed phenomena? Evidently the limits of this paper will not permit the discussion of all phenomena. We will consider some of the most characteristic.

We assume from the spectrum that the oxygen atom is composed of more than forty sub-atoms. The laws of gravitation alone will explain why these sub-atoms collect to form an approximately spherical group. The difference in wave length of light emitted by these sub-atoms is evidence that they differ from each other, and hence the atom cannot be homogeneous.



Fig. 3



Fig. 4



Fig. 5



Fig. 6

While we would naturally expect that the heavier sub-atoms would collect at the center, we also would expect that, in the formation of the atom, centrifugal force, outside attraction or other causes might modify this.

The chemical behavior of oxygen seems to indicate that the atom has one side denser than the other, as shown by the shaded portion of Fig. 3. The center of mass, then, instead of being at the geometrical center of the atom, is displaced to within the shaded portion.

Two atoms of oxygen, placed as in Fig. 4, would have a much stronger attraction for each other than they could have for any other atom of oxygen, for no other can get its center of mass so near to be attracted. Hence ordinary free oxygen gas molecules are made up of pairs of atoms.

A very high temperature is necessary to separate these atoms, and a very low temperature is necessary in order that the twins shall have attraction enough to collect and form a liquid.

Similarly the chemical behavior of hydrogen indicates that its atoms also have a denser portion on one side, and that the free

gas molecules also exist in the form of twin atoms. We believe also, from the fewer lines in the spectrum, its smaller atomic weight, its greater diffusibility, etc., that hydrogen atoms are much smaller than those of oxygen.

If, at the ordinary temperature, oxygen and hydrogen gases are mixed, we may see by Fig. 5 that the centers of mass of the hydrogen molecules cannot get very close to the oxygen molecules; no particular attraction takes place, and hence no combination.

If, however, the temperature be raised to a point that breaks up the twins, the oxygen atoms are separated, the hydrogen twins can get nearer the centers of mass of the oxygen atoms, and a combination like Fig. 6 results, forming molecules of water. In changing from the grouping of Fig. 5 to that of Fig. 6 potential energy is changed to kinetic; that is, heat is given off.

Even at ordinary temperatures, the oxygen twin atoms, in collisions with other atoms, are continually subjected to strain, differing with the temperature, the atoms against which they impinge and the position of the atoms when struck; thus, at points below ignition, some of the twin atoms of oxygen will be broken up, leaving the single oxygen atoms ready to unite with the atoms against which they collide, and we say the substance is slowly oxidized.

The electric spark, in passing through oxygen, breaks up the twins, leaving separate oxygen atoms; but the passage of the spark is momentary, and the oxygen atoms, in rushing together again, in general, form ordinary twins, but some of them strike in such a way as to form triplets; that is, ozone. Fig. 7.

A comparatively slight disturbance dislodges one of the oxygen atoms, and the group of three becomes an ordinary pair and a single oxygen atom. The single dislodged atom, however, by reason of its dense part being exposed, is able to attract very strongly any other atom which may be near, hence the powerful oxidizing property of ozone.

An atom of oxygen may fasten to the side of a water molecule to form a molecule of hydrogen dioxide, Fig. 8; but this extra atom is easily dislodged, leaving a water molecule and a single oxygen atom; thus, like ozone, forming a powerful oxidizer.

In general any process which leaves single oxygen or hydrogen atoms leaves them in a position to unite powerfully with others; this is the so-called nascent state.

If we attempt to make any other compounds of hydrogen and oxygen, they must be made by putting the centers of mass of the added atoms so far away that the attraction is too weak to form a

stable group, hence the reason why the compounds of oxygen and hydrogen are so few in number.

We might assume the possibility of a molecule like Fig. 7, that is H_2O , but hydrogen atoms usually occur in pairs, and conditions which favor any combination would favor the combination of both atoms of the hydrogen pair. Even if molecules like Fig. 9 were formed, they would unite in pairs or twins and form $\text{H}_2(\text{O})_2$, or hydrogen dioxide.

It has been found by experiment that at temperatures between 1146° and 2741° only one-half the usual amount of hydrogen will unite with oxygen. This seems to show that the dense part of the oxygen atom is not of uniform density, but rather as shown in Fig. 10. An atom of hydrogen, then, will be held more strongly at "a" than at "b." At temperatures between 1146° and 2471° the collisions are violent enough to dislodge the hydrogen atom clinging at "b," but not the one at "a," leaving the form of the molecule as HO .

The nitrogen spectrum consists of many fine lines, hence we conclude that the atom contains many sub-atoms. By the same



Fig. 7



Fig. 8



Fig. 9



Fig. 10

course of reasoning already presented, we find the center of mass to be on one side of the atom and that the elementary molecule is a twin atom. The so-called inertness of nitrogen, that is, the difficulty found in getting free nitrogen to unite with other elements, gives us reason to believe that the attraction between the atoms in the elementary molecule is stronger than in oxygen. It is more difficult to separate the atoms of nitrogen to get them in a position to unite with other atoms. The fact that a single atom of nitrogen unites with three atoms of hydrogen to form ammonia suggests also this stronger attraction, or at least that the dense portion of the nitrogen atom occupies a larger portion of the side than in the case of oxygen.

It will also be noticed that it requires a much lower temperature to liquefy NH_3 than H_2O . This shows that the attraction between molecules of H_2O is stronger than between molecules of NH_3 , that at a given temperature the molecular velocity of H_2O is less, or that it depends upon both taken together.

A study of the boiling points, freezing points, relative chemical attractions and atomic weights, together with the forms of crystal-

lization, hardness, ductility, etc., will give data from which to determine, approximately, at least, the positions of the centers of mass of the different molecules and atoms.

In the case of nitrous oxide, Fig. 11, we have a group of three atoms. When the temperature reaches a certain point the group is broken up, the two nitrogen atoms unite to form a pair, leaving the oxygen atom in the single form ready to unite with other atoms; that is, nitrous oxide acts as a powerful oxidizer after the temperature has reached a certain point.

Fig. 12 shows a molecule of nitric oxide. The molecule of N_2O is more easily decomposed than NO , because the two atoms of nitrogen in N_2O tend to form a twin atom or elementary molecule. This aid to an outside force is not present in the molecule of NO . However, at a very high temperature the NO is decomposed, leaving the oxygen free, and it is then a supporter of combustion.

Let us now pass to chlorine. When a free gas, this also exists as twin atoms, showing the center of mass of the atom to be nearer one side.



Fig. 11



Fig. 12

It would seem that the dense portion of the atom is in a comparatively small spot, since but one atom of hydrogen is held, as in hydrochloric acid. The small attraction of the chlorine atoms for each other is shown by the comparative ease by which the elementary molecules are broken up, leaving the chlorine atoms in a position to be very active in combining with other atoms.

Activity in combination, however, is not necessarily the same as power of combination. Two atoms may readily unite, and yet not powerfully unite.

Since light is produced by the vibration of the sub-atoms, conversely, light will cause the sub-atoms to vibrate, the atoms will expand, the centers of mass of the atoms will move farther apart, the attraction between them will become less and the elementary molecules may be more easily broken up. Hence, light facilitates combination of chlorine with other atoms. In a similar way light, by expansion of the atoms, changes the equilibrium and combinations in photographic processes.

Of course light would tend to produce the same effect in a great many substances, but the laws of sympathetic action, together

with other forces, would, in general, cause this effect to be unnoticeable.

Bromine, iodine and fluorine resemble chlorine, so we need not stop with them here except, perhaps, to consider the remarkable fact that fluorine will not, as far as known, combine with oxygen. If it is impossible to form compounds of oxygen and fluorine, it may mean nothing more than that the oxygen atoms have a stronger attraction for each other than they do for the fluorine. That is, if such a combination were conceived, it would be broken up by the oxygen atoms uniting to form twins or free oxygen molecules.

Carbon seems to have four dense parts in its atom. If we imagine surfaces "ab" and "cd" passed through the atom, we may consider each of the four portions to have a center of mass of its own. Four hydrogen atoms then would naturally cling, as shown by Fig. 13, representing CH_4 .

Some other representative compounds are as shown below:





Fig. 14



It would seem reasonable to suppose that the four dense portions of the carbon atom would not be exactly the same; that is, their attractive powers would be different. The compound CH_2 would tend to show that the attraction is stronger upon two sides, forming the group of Fig. 15. The compound CO tends to show the same thing. One oxygen atom taking the place of the two hydrogen atoms of CH_2 .

The compounds CH_2 and CO would naturally be formed when there was a scarcity of hydrogen or oxygen, the stronger sides of the carbon taking up all of the atoms of hydrogen or oxygen.

Instead of forming twin atoms, as do oxygen, hydrogen, etc., free carbon tends to collect indefinitely, since there is a strong attraction on four sides. It therefore tends to form a solid which requires an extreme high temperature to vaporize. The two forms of crystals show two different arrangements of the atoms, the octahedral or diamond, shown in section by Fig. 16, and the hexagonal or graphite, as shown in section by Fig. 17. The diamond having the dense portions in closer proximity to each other tends to give a stronger attraction, hence the greater hardness.

Amorphous carbon is quite possibly a mass of extremely small crystals of graphite.

The ability to attract in four directions makes carbon a powerful link in binding together other atoms. It connects the atoms of soft iron to make hard steel, while most of the molecules in the organic world would fall to pieces were it not for the powerful cementing influence of the inclosed carbon.

The spectrum of sulphur leads to the conclusion that its atom has a great many sub-atoms, and a study of its properties leads us to believe that the atom has two dense parts or centers of attraction at about 90° from each other. The sulphur naturally existing in clusters of six atoms, as would be represented by Fig. 18, if we conceive an atom in the center front and another in the center back. Collections of these clusters would make octahedra, the natural form of sulphur crystals. When the sulphur is heated the clusters of six move more freely amongst each other; the sulphur melts.



Fig. 16




Fig. 17

At a higher temperature two of the atoms of the cluster of six are dislodged, leaving the cluster of four as shown by Fig. 18. The atoms disengaged uniting to form other clusters of four. The cluster of four, however, still retains considerable attraction in two directions, those from which the two atoms were dislodged, and by continually clinging to its neighbors (though but weakly) is retarded in its motions; the liquid sulphur becomes viscous. At a higher temperature, however, this tendency is overcome and it becomes liquid again.

Suddenly cooling the viscous sulphur will increase the side attraction, without giving time to arrange in crystals, by bringing the clusters nearer together, hence the rubber-like mass.

Clusters of four will evidently form different crystals than clusters of six; they form rhombic or monoclinic crystals, which, however, gradually revert to the natural or cluster of six form. This change, as we might expect, is facilitated by heat or vibration.

In general, the crystal forms will aid us greatly in locating the relative positions of the dense portions of the atoms. The cleavage and fracture will also be important helps.

If it is true that the atoms are made up of sub-atoms, it seems

quite within the limits of possibility to find some way to break them up and make new elements of the fragments. We may even advance to the point where we can make a given element out of other elements as we now make a given compound out of other compounds. When this day arrives the old dream of the alchemists may find its realization; we may be able to make gold.

It has been found that the spectrum of sulphur, as well as many other elements, differs at different temperatures.

Light is caused by the vibrations of the sub-atoms and possibly some of the smaller groups of sub-atoms. As the mechanical collisions set the molecules of a body vibrating, so will the collisions of the molecules set the atoms vibrating, and, in the same way, the collisions of the atoms will set the sub-atoms vibrating and produce light.

In the same way that the vibration of the molecules expands a body, so will the vibrations of the atoms expand the molecule, and the vibrations of the sub-atoms expand the atom. But this disturbance among the sub-atoms very likely would modify the group-



Fig. 18



Fig. 19

ing and certainly modify the attractive force among the sub-atoms, and change the frequency of the vibrations, which would mean a change in the spectrum.

Suppose "a" and "b," Fig. 19, be two sub-atoms of exactly the same mass, but "a" is at surface of atom and "b" in the interior. "a" and "b" would have different vibration frequency, because they are acted on by different attraction, analogous to pendulums on and below surface of the earth.

If the light waves caused by the vibrations of the internal sub-atoms can get out of the atom, we would have all wave lengths corresponding to these different attractions from circumference to center; and, if the sub-atoms were numerous, a band spectrum, even though the sub-atoms were all of the same size. With sub-atoms of different mass, the band spectrum would vary in density.

On the other hand, if the atom be opaque, only the surface sub-atoms can send out light and we have a different wave length for each different kind of sub-atom; that is, we have a line spectrum.

Evidently, an atom partially opaque would have a combination of line and band spectrum.

That some lines are brighter than others may be explained by saying there are more sub-atoms of that particular kind than others, and hence give more light; or that some sub-atoms are near the surface of the atom, and hence give more light than those partly covered up.

Even the surface sub-atoms of the atoms would be affected by the proximity of other atoms; and a change in the temperature, bringing about a change in the position of the atoms, would affect the vibration number of the sub-atoms, and hence a change in the spectrum.

An element in the gaseous form giving a line spectrum, because the vibrations of the sub-atoms are nearly unaffected by the proximity of other atoms, will give a continuous spectrum in the liquid or solid form, because, as we go from the surface of the liquid or solid downward, the sub-atoms are gradually more and more affected, and have their wave lengths gradually changed, hence producing all the wave lengths between certain limits.

In vibrating, a body sets up sound waves in the air, a substance whose molecules are of similar magnitude to the molecules of the vibrating body. Analogously, the sub-atoms, in vibrating, set up light waves in the ether, a substance whose particles are of the same or similar magnitude as the particles of the vibrating sub-atom; that is, the ether is a gas-like substance whose particles are sub-subatoms.

Furthermore, analogy and a study of phenomena lead us to believe that there is another gas-like substance, occupying a position between the ordinary gases and the ether, a gas-like substance whose particles are sub-atoms. We may call this a sub-gas.

In general, then, the smallest particles of ordinary gases are composed of pairs or groups of atoms. The smallest particles of a sub-gas are pairs or groups of sub-atoms, and the smallest particles of the ether are pairs or groups of sub-subatoms.

Furthermore, since we have a variety of different gases, so we may have a variety of different sub-gases, a variety of different ethers, and even a variety of different sub-ethers, etc.

Here are substances fine and delicate enough for the enthusiast to build up the principle of life existing in germs, to fashion the intellect, memory, yes, even to construct the human soul.

Bodies vibrating in ordinary gases produce sound waves, sub-atoms vibrating in the ether produce light waves. Analogously we might expect that atoms or clusters of atoms vibrating in the sub-gas would produce a set of waves which can not be classed among sound or light waves.

When a body is heated, its molecules are caused to vibrate, and at the same time it gives off what is termed radiant heat. Is it possible that this radiant heat consists of waves in the sub-gas instead of (what is generally assumed) in the ether? We have thus far failed to recognize a single fact which would show that radiant heat could not be a wave motion in a sub-gas as well as in the ether. It would seem that, if the velocity of radiant heat, or even perhaps the wave length, could be determined independently of any connection with light, this doubt could be cleared up. If radiant heat were a wave motion in a sub-gas, its wave length would be much greater and its velocity much less than those of light.

Phenomena seem to show that electricity is a motion in the sub-gas, while magnetism is a motion in the ether. A discussion of this, however, does not properly belong to this paper, which discusses the constitution and properties of matter, rather than the motions of matter. The motions of matter are, however, so intimately connected with the properties and constitution, that it is impossible to separate them entirely.

Mechanical collisions form molecular vibrations or heat; molecular collisions, or heat, produce vibrations of the sub-atoms, or light. Mechanical energy can be changed to heat and vice versa. Molecular energy, heat, can be changed to light and vice versa.

Some substances require less mechanical energy than others to raise the molecular vibration sufficiently to send out radiant heat. Similarly some substances require less molecular energy, heat, to raise the vibration of the sub-atoms sufficiently to send out light. As substances have different "specific heats," so do they have different "specific lights." Phosphorus is a substance of low "specific light;" a comparatively low temperature or slight collision of the molecules causes the sub-atoms to vibrate enough to send out light.

When light rays fall upon a substance the light vibrations set the sub-atoms vibrating, especially if the sub-atoms naturally send out that same kind of light. By reason of inertia, these sub-atoms continue to vibrate for a short time, even after the exciting rays are cut off, and thus give out or glow, as shown in the phenomena of phosphorescence.

Calorescence, the changing of heat rays to light rays, would be a change of energy form, analogous to change of sound to heat, when sound waves are absorbed by a body. The converse, the change of light to heat, would be analogous to the change of heat to sound, as is illustrated by numerous examples.

Whether there are any motions in the sub-ether which man is able to detect is a question. Possibly, however, if we can accept as a fact what thousands have asserted, and what thousands and millions believe, that there is a mysterious connection between mind and mind, this connection may be through the sub-ether.

If the molecules of a substance have the centers of mass close together, as in Fig. 20, they attract each other strongly, the substance is hard; but if a force sufficiently strong acts, a small actual motion in almost any direction becomes a large relative motion, the molecules are permanently torn apart, there is no appreciable "give" to the substance, we say it is brittle. Carbon affords a good example of this. If, on the other hand, the center of mass is at or near the geometrical center, Fig. 21, a much smaller force will cause a much larger actual motion without affecting the relative distance so much and without affecting the actual attraction very much. The body is not ruptured. The less force shows the body to be soft. The molecules will roll around each other, there being about as much attraction in one position as in another; the substance is ductile or malleable.



Fig. 20



Fig. 21

One body may be harder than another, showing a greater attraction between the molecules, and still be found by experiment to be less tenacious than a softer body which has less molecular attraction.

This is due simply to the fact that the molecules of the harder body have but little "give" to them. A stress in any direction will cause a great strain on some molecules and none on others; these molecules pull apart, throwing the stress upon others; these give way, then others, and so on until the rupture is complete. It is like breaking a great cable one strand at a time. In the softer body, however, the molecules "give," so before any rupture takes place the whole cross-section of the body is resisting the stress. It is practically stronger than the first body, notwithstanding that its molecular attraction is less.

It would seem that the rigidity of solids furnishes almost positive proof that their molecules are not only actually, but relatively close together, that at absolute zero the molecules and atoms are as much in contact as are the stones in a stone pile. At any other temperature the relative distance apart is but small, and can be cal-

culated from the amount of expansion from the absolute zero to the given temperature. For example, if a solid increases its length 0.25 per cent. when heated from absolute zero to any given temperature, the distance between the centers of the molecules will also increase 0.25 per cent. Also since the change from a solid to a liquid is usually accompanied by but a slight change in volume, the liquid molecules and atoms are also very nearly in contact. Hence the relative densities of the molecules and atoms of liquids and solids are approximately the same as the relative densities of the liquids and solids themselves.

We may use this principle to determine the approximate sizes of different molecules. For example, the molecular weight of sulphuric acid is about 98, about $5\frac{1}{2}$ times that of water. That is, a molecule of sulphuric acid has about $5\frac{1}{2}$ times the mass of a molecule of water. If the molecules of sulphuric acid were of the same size as those of water, the density would be about $5\frac{1}{2}$; but being only 1.8 about, or about 1.3 as much, it means that a molecule of sulphuric acid has about three times the volume of a molecule of water.



Fig. 22

If a series of pendulums, as shown in Fig. 22, were made of ivory or glass balls, they could be made to vibrate at a certain amplitude amongst each other with much less expenditure of energy than if the balls were made of lead; the leaden balls would absorb much more energy in themselves. Different substances are made up of different atoms and molecules. Naturally some of the atoms and molecules are more elastic than others and require less energy to raise their temperature; they are said to have a low specific heat.

We find the specific heat of hydrogen to be 3.409, and that of oxygen 0.2175. Approximately (1), Sp. Ht. of O \times Mol. Wt. = Sp. Ht. of H \times Mol. Wt.

One gram of H requires about 16 times as much energy to raise it one degree as one gram of O. Therefore one volume of H requires about the same energy to raise it one degree as one volume of O. This means that it requires about the same energy to raise one molecule of H one degree as one molecule of O.

But equation (1), given above, is only approximately correct. If the specific heat of O were 0.2129, instead of 0.2175, the equation would be exactly correct; that is, the actual specific heat of O

is a little greater than the theory of equation (1); that is, the molecule of O requires a little more energy to raise it one degree than the molecule of H. This extra energy required is due to the energy absorbed by the internal parts of the O molecules. Collisions of the molecules set the atoms and sub-atoms vibrating, thus taking up some of the energy; but the O molecule, being more complex than the H molecule, absorbs more energy.

Take a molecule of steam, instead of oxygen, in equation (1). If the specific heat of steam were 0.378 instead of 0.48, equation (1) would be true; that is, more heat energy is required to raise one molecule of steam one degree than a molecule of hydrogen, and not only more, but relatively more than to raise a molecule of oxygen one degree. Much more energy is absorbed by the internal parts of the steam molecule than by the H or O. It is more complex.

Water has about twice the specific heat of steam. The molecules are closer together, the collisions are more frequent, the internal disturbance is greater, and hence the greater amount of energy absorbed by the atoms and sub-atoms.

If we use equation (1) to compare water with common salt, the calculated specific heat of the NaCl is 0.307, but the real Sp. Ht. is 0.219, hence the amount of energy to raise one molecule of NaCl one degree is less than that of water. The NaCl is less complex. If we compare water with potassium sulphate, the calculated specific heat of the K_2SO_4 is 0.103, while the real Sp. Ht. is 0.196; that is, the molecule is so complex that it requires more energy to raise one molecule of K_2SO_4 one degree than one molecule of H_2O . More energy is absorbed in the internal groups.

If we compare lead and tin, the calculated Sp. Ht. is 0.0552, the real Sp. Ht. 0.0548; that is, each molecule requires about the same energy to raise it one degree, about the same amount of energy is absorbed by the internal parts of each molecule. This same agreement holds for all the metals as well as chlorine, bromine, iodine, selenium, tellurium and arsenic. If we compare hydrogen and lead, using a molecule of H and an atom of Pb the calculated Sp. Ht. of the Pb is 0.0330, the real Sp. Ht. is 0.0315, showing that the energy required to raise a molecule of H and an atom of Pb is about the same.

We interpret this to mean, in general, that all kinds of molecule require the same energy to raise them one degree (remembering that a molecule is sometimes composed of but one atom), except for the part of the energy which is absorbed by the internal groups of the molecule.

But when molecules are raised one degree it means that they are capable of imparting a certain additional energy to a thermometer; so when we say that all molecules, except as above mentioned, require the same energy to raise them one degree, we are simply saying that the same energy given to all kinds of molecules will enable them to give the same additional amount to a thermometer; that is, in other words, that the same energy given to all kinds of molecules will increase their energy the same amount. This is, of course, self-evident, and the whole investigation shows that part of the heat energy is absorbed in the internal groups of the molecule, and that atomic heat is no special property, but a natural consequence following the different molecular weights.

There seems to be little doubt that a body is raised in temperature when the kinetic energy of its molecules is increased. Potential energy has nothing to do with temperature. When water is turned to steam the molecules move farther apart, the potential energy is increased at the expense of the kinetic energy, and is apparently losing heat; this, together with the energy taken up in the interior groups of the molecules themselves, accounts for the latent heat of steam.

In the same way that vibratory motion can be transmitted through a row of elastic balls more easily than through inelastic ones; so can heat be conducted through a substance composed of elastic molecules and atoms more easily than through inelastic ones. This would tend to show that bodies with low specific heat would be good conductors; but this conductivity is modified by the attractive forces which may prevent the molecules from readily moving to communicate the heat motion to its neighbors.

We know that light passes through certain bodies which we call transparent. Either the light passes as ether waves between the atoms like water waves between rushes or else the vibrations pass through the substance itself like sound passes through a wall. A thin layer of ordinary carbon is perfectly opaque, while a thick and much denser layer of diamond is transparent. Facts like this seem to point to the latter explanation. The transparency of a body, then, will depend upon the elasticity, continuity and freedom of motion of the sub-atoms.

In the same way that mechanical vibration will be absorbed by a non-continuous mass, like sand, or inelastic matter, like lead, so will light vibrations be absorbed by inelastic and non-continuous sub-atoms.

The irregular expansion of water may be explained as follows:

When heated from the ordinary temperature, water gradually expands, but the rate of expansion gradually increases as the tem-

perature rises. The high specific heat of water shows that the molecules are inelastic. A great deal of energy is absorbed by the molecules themselves, but this absorption of energy causes a vibration of the parts within the molecule, and the molecule itself expands. This gradual increase in the size of the molecules, added to the regular expansion, causes the increase in the rate of real expansion. When water cools, it contracts to 4°C ., then expands slightly, then greatly as it freezes. Water crystallizes in hexagonal plate-like forms; that is, when the vibration of the water molecules becomes slow enough, gravitation draws them together, forming hexagonal clusters of six, Fig. 23. In this form the centers of mass are as near as possible. This forms the elementary crystal, and, by collections of these, all the varied forms shown by snowflakes are built up.




Fig. 23

A few of these clusters begin to form at 4° , and this arrangement takes up more room. The water expands. When all form hexagonal clusters, the water becomes ice and the expansion is considerable.

The six water molecules in the cluster are held together as in a vise. The relative vibration is largely stopped, and this kinetic energy is given to outside bodies. The cluster of six then acts as a molecule. When ice again melts, it naturally requires considerable energy to again break up these clusters, hence the apparent disappearance of heat. This hexagonal molecule of water plays an important part in the formation of many crystals, as water of crystallization. The occurrence of $6\text{H}_2\text{O}$, $12\text{H}_2\text{O}$, $24\text{H}_2\text{O}$, etc., suggests this. Other groups seem to be formed by replacing one or more of the water molecules in the hexagonal molecule by another atom or molecule; for example, the compound, $\text{Cl} + 5\text{H}_2\text{O}$.

**ENGINEERING EXPLORATIONS IN MONTANA AND
ELSEWHERE IN THE ROCKY MOUNTAINS.**

ANNUAL ADDRESS OF FRANCIS W. BLACKFORD, RETIRING PRESIDENT MONTANA
SOCIETY OF ENGINEERS.

[Read before the Society, January 12, 1901.*]

I HAD read with interest the journals of most of the expeditions mentioned in this paper before I had ever set foot west of the Mississippi River or thought of making my home in Montana, but later professional work took me over a large extent of the country traversed by them, and I again read the journals with increased interest, and from my acquaintance with the country was enabled to locate the various routes of travel in accordance with present geographical terms. Others might have the same interest in such things, but not the time or opportunity to gratify it. I therefore selected this as my subject.

These explorers pointed out the way and stimulated immigration and permanent settlement, which made possible the construction of the Union and Northern Pacific Railways, great undertakings and great engineering work in any age. The period of exploration covered pretty well the first three-quarters of the century and I deem it not improper to review them now at its close.

Such a review would logically begin with the expedition of Lewis and Clarke, which started from a point on the Missouri River, near the present site of Kansas City, in the spring of 1804.

Lewis and Clarke were both captains in the United States Army, and the expedition was organized and equipped by the authority of the Government to explore a part of the then recent Louisiana purchase. The instructions of the commanders were, briefly, to follow the Missouri River to its head, thence cross to the head waters of the Columbia and follow it to its mouth, and come back overland if practicable. In pursuance of these instructions this expedition traveled by a keel-boat and canoes to a point near the present site of Bismarck and went into winter quarters, where they spent the winter of 1804 and 1805. As soon as the river was free from ice in the spring they resumed their journey and reached the Great Falls of the Missouri, the first interruption to traffic, in the month of June, 1805. After a laborious portage of their goods, they again embarked in canoes made above the falls and continued up the Missouri to the Three Forks thereof, thence by the Jefferson to the confluence of the Big Hole and Beaverhead, thence by the

*Manuscript received March 8, 1901.—Secretary, Ass'n of Eng. Soc's.

Beaverhead to the Horse Prairie, thence by said creek until it became too shallow for their boat. Here they made a cache and proceeded by pack train, composed of horses purchased from the Indians, and under the direction of Indian guides, over Horse Prairie and across the main range of the Rocky Mountains to a tributary of the Salmon, thence down said stream to a point near the present site of Gibbonsville, thence almost due north across a high spur of the main range to Ross Hole, in the Bitter Root Valley, thence down the Bitter Root Valley to a point some six miles south of the present site of Missoula, thence westward by what was known as the North Nez Perce Trail, up the Lolo to the summit of the Bitter Root Mountains, down on to the waters of the Clear Water, and up again to the higher ground lying between the Clear Water and Clark's Fork of the Columbia, upon which ridge and its spur the trail lay for many miles, finally taking them to the Clear Water near its confluence with the Snake, at which point they made boats and reached the mouth of the Columbia in December of 1805.

Returning, the expedition traveled by the same route as far as the mouth of the Lolo, near Missoula, where a separation took place. Captain Clarke and part of the party went up the Bitter Root Valley to Ross Hole, thence across what is now known as Gibbons Pass to the Big Hole Basin, thence south to Horse Prairie and the cache made the year previous. They then proceeded down the valley of the Beaver Head and the Jefferson to the Three Forks of the Missouri, where the party again divided, a part joining Captain Lewis with the boats at the Great Falls of the Missouri, while Captain Clarke proceeded up the Gallatin and its tributaries, passing near the present site of Bozeman to Bozeman Pass of the Belt Mountains, and to the Yellowstone River near to where Livingstone now stands. There they made boats and proceeded down the Yellowstone to its mouth, near which, in August, 1806, they met Captain Lewis, who had left the mouth of Lolo at the same time and traveled as follows: Down the Bitter Root to the Hell Gate, up that stream to the mouth of the Big Blackfoot, thence up the Big Blackfoot to its head, crossing the main range of the Rocky Mountains at what is now known as Lewis and Clarke Pass, thence to the Great Falls of the Missouri, where they embarked and proceeded down the Missouri to the mouth of the Yellowstone, near which they met Captain Clarke.

In the year 1806 Lieutenant Pike, of the United States Army, ascended the Arkansas River to a point near its source and returned via the South Platte, discovering, upon his way, the peak

which now bears his name and which has always been a prominent landmark for a large section of the State of Colorado. The honor of first ascending this peak, however, belongs to Dr. James, of Major Long's expedition. This expedition approached the mountain via the South Branch of the Platte in the year 1820. The high peak lying some sixty miles northwest of Denver gave this expedition the first glimpse of the Rocky Mountains, and has since been known as Long's Peak. Major Long gave the name of James Peak to the mountain first seen by Lieutenant Pike. Notwithstanding this, the name of Pike has stuck to the peak first seen and reported by him, and the name of James has been given to the peak lying immediately south and about ten miles distant from Long's Peak. I have stood upon the summit of the last-named peak, which is somewhat lower than either Pike's or Long's Peak, both of which are visible from its summit.

The view from this point is very impressive, and, in addition to its grandeur, gives one an excellent knowledge of the geography of the surrounding region.

Major Long's party did not penetrate the mountains very far, but confined their explorations to the district lying east thereof. The next expedition of importance was that of Captain Bonneville. This was semi-official in its character, and more a fur-trading than an exploring expedition. Captain Bonneville was an officer in the United States Army and had served on the frontier; being desirous of extending his knowledge of the country lying to the westward, he obtained from the Secretary of War a leave of absence with the understanding that upon his return to the army he was to report the result of his travels and explorations to the War Department. He then associated himself with some capitalists who furnished the means to outfit a trading and trapping expedition. The outfit consisted of about one hundred men with wagons and pack animals. It started from the frontier in the spring of 1832 and traveled westerly to the North Platte, thence by the North Platte to the Sweetwater, thence by the Sweetwater to South Pass, thence to Green River, where a cache was made, which remained the headquarters of the expedition for the next three years. Captain Bonneville was the first to cross the Rocky Mountains with wagons.

He then went up Green River and on to the Snake River at what was then known as Pierre's Hole, a valley lying immediately west of the Three Tetons, this was a general rendezvous for the trappers of the American and Rocky Mountain Fur Company. The country, even at that early period, was full of trappers, who

went in every direction from this point in search of fruitful fields for their occupation.

Captain Bonneville's expedition did not prove a financial success, but, during his three years' sojourn in the mountains, he traveled extensively and increased the knowledge of the geography of this section of the country, which was then very meager. He made two trips from the Green River around the eastern slope of the Wind River Mountain to the Yellowstone; spent one winter upon the head waters of the Salmon, immediately west of Horse Prairie; traveled upon the Beaver Head and its tributaries, and spent a part of one winter near Fort Hall, a trading post situated on the Snake River, near the mouth of the Portneuf.

In the year 1834 he made two trips down the valley of the Snake River, up the Malheur via Grand Rond Valley, across the Blue Mountains and down the John Day River to Walla Walla, returning by practically the same route. In traveling from Fort Hall to Green River he sometimes went by the way of Pierre's and Jackson's Hole, and sometimes by the Portneuf or Blackfoot and Bear River to Sublett's Pass and Ham's Fork, following very nearly the route afterward taken by the Oregon Short Line Railway.

Finding a herd of buffalo imprisoned by the snow in the valley of Bear River in the winter of 1834 and 1835, the expedition, or what was then left of it, camped with the buffalo until spring, it is needless to say to the discomfiture of the latter. They then proceeded eastward via the South Pass and Platte River, reaching the settlements in August, 1835.

In July, 1833, a detachment from this expedition traveled down Bear River to the Great Salt Lake and made an exploration partly around its southern end. They then struck across the desert lying to the westward, and after various adventures and extreme hardships crossed the Sierra Nevada Mountains to the valleys of California.

Returning, they crossed the mountains further south, probably by the Tehachapi Pass, thence to the southern end of Salt Lake and via the Bear River to the rendezvous on Green River.

It was the intention of Captain Bonneville to have this party thoroughly explore the Great Salt Lake, of which little was then known. The leader and his men proved unreliable, however, and wasted their stores and means in the trip to California, and added but little to the knowledge either of the extent of the lake or of the country thereabout.

This lake was called Lake Bonneville by Washington Irving in his "Astoria," but it was well known before Captain Bonne-

ville visited the country, having been seen and reported by James Bridger, a trapper, in 1825. It may have been discovered by the Spaniards at an earlier period, but their information concerning it was very vague and uncertain.

The next exploration, in the order of occurrence, was that of Lieutenant John C. Fremont, who made three expeditions to and beyond the Rocky Mountains, beginning in 1842 and ending in 1846.

Fremont was eminently fitted for such work, having had several years' practical experience as a civil engineer engaged in railroad surveying and kindred work, notably a reconnaissance for a railway from Charleston, S. C., to Cincinnati, over a very broken and mountainous country. He was also an accomplished mathematician, having been instructor in the United States Navy. At the time of his appointment as chief of this exploring party, he was an assistant engineer in the engineering department of the army.

During all of his expeditions he was supplied with instruments for obtaining temperature, latitude, longitude and altitude, and such determinations were frequently made, except at rare intervals when his instruments were broken or out of repair.

His descriptions of the country traversed are so full and plain that his route can be easily followed, by means of these alone, by any one who is at all familiar with the topography of the country. I have surveyed railway lines over more than a thousand miles of his trail, and have traveled by wagon and in other ways over other parts of it, and can, therefore, speak from personal observation.

The object of these expeditions was mainly to increase the geographical knowledge of the country for the aid and encouragement of immigration to Oregon and the Northwest.

The first expedition left the Missouri River, near the mouth of the Kansas, in June, 1842, traveled northwesterly, thence via the Main Platte and its South Fork, reaching the base of the mountains just east of Long's Peak, near St. Vrain's Fort. Thence the route lay along the eastern base of the mountains to the North Platte River, thence via the Platte and Sweetwater to South Pass. The latter he described as being so extremely easy of access that it was only by the most careful observation that the highest point could be discerned.

From South Pass the party traveled toward the Wind River Mountains, and, after a number of days of arduous labor, Lieutenant Fremont and several of the party succeeded, on the 25th of August, in reaching the summit of the highest peak of the range,

and planted thereon the American flag. This peak has since borne his name, and it was thought then to be the highest peak in the Rocky Mountains.

The party then retraced their steps as far as Fort Laramie, and from there followed down the Platte to its mouth. Then, by boats built for the purpose, they descended the river to St. Louis, where they arrived on the 17th day of October, 1842.

Fremont's second expedition was much more extensive than the first, and the results were of greater geographic value. His instructions were to connect his reconnaissance of 1842 with the surveys of Captain Wilkes, of the United States Navy, on the coast of the Pacific Ocean, near the mouth of the Columbia River.

This expedition left the mouth of the Kansas on the last of May, 1843, traveled nearly westward to St. Vrain's Fort, at the base of the mountain, thence southward to Pueblo, up the Arkansas about seventy-five miles, across to the South Platte in South Park, thence to St. Vrain's Fort, making a reconnaissance completely around Pike's Peak, and including much of the head waters of the Arkansas and the South Platte.

Leaving St. Vrain's Fort on July 26, they passed up the Cache La Poudre to the tributaries of the Laramie River, thence along the eastern slope of the Medicine Bow Mountains, over the Laramie Plains, striking the Sweetwater a short distance east of South Pass, thence by the Emigrant Road to Green River, at a point about twenty miles north of the present crossing of the Union Pacific Railway.

From here they traveled westward to Ham's Fork, up that stream to the dividing ridge between the waters of the Colorado and those of the Great Basin, crossing the same very near, if not at, Sublett's Pass, now occupied by the Oregon Short Line Railway, thence down a tributary to Bear River, which stream they followed to Soda Springs, thence by the Portneuf to Fort Hall in the Snake River Valley. From near Green River to Fort Hall the route followed very closely that taken forty years later by the Oregon Short Line.

While the main party was journeying down the Portneuf, Lieutenant Fremont and a few men traveled from Soda Springs down the Bear River to the Great Salt Lake, and explored its eastern shores as far as the mouth of Weber River. He visited one of the islands, from which he obtained a good idea of the extent of the lake.

He then traveled northward to Fort Hall, following up the Malad and down Bannock Creek instead of the route afterward

followed by the Utah and Northern Railway, which lies a little to the eastward.

His route then lay down the valley of Snake River to Burnt Fork, thence up that stream and on to the Powder River, passing near the site of Baker City, thence via the Grand Rond Valley, across the Blue Mountains to the Columbia River, near Fort Walla Walla.

There were a few white inhabitants engaged in the fur trade along the route of travel from Fort Hall to this point, notably at the mouth of the Boise and in the Grand Rond Valley. There were also emigrants along the way bound for the valley of the Willamette.

Leaving the main party at the Dalles of the Columbia, Lieutenant Fremont proceeded to Fort Van Couver, near the mouth of the Willamette, where he laid in a supply of provisions for his contemplated explorations southward from the Dalles. He had thus fulfilled his mission and connected his survey with that of Captain Wilkes.

Lieutenant Fremont reports that Mount Rainier and Mount St. Helen were then in action, the latter having scattered ashes over a large extent of country the year previous.

The extent of the Great Basin lying between the Wasatch and Sierra Nevada Mountains was not then known. It was thought that a part of that section drained into the Gulf of California and a part into the Bay of San Francisco by the Rio Buenaventura, which had a conspicuous place upon the maps of the period. It was supposed to have its source in the Rocky Mountains and to break through the Sierra Nevadas. To extend the geographical knowledge of this territory was, therefore, the object of this part of the expedition.

The country previously traveled was well known to trappers and traders, and no difficulty was experienced in procuring guides to conduct the party over well-known and, in most instances, well-worn trails or roads. The party, which consisted of twenty-five men, was now confronted with a very different undertaking,—viz, the entrance into an unknown country at the beginning of winter, with its attendant hardships and perils. Notwithstanding these conditions, the party left the Dalles in good spirits on the 25th of November, and traveled southward along the east base of the Sierra Nevadas, over a country more or less broken by spurs from the mountains and interspersed with lakes and plains. They suffered considerable hardships from hunger and fatigue occasioned by the scarcity of game and the inclement weather.

They finally reached a point near Lake Tahoe, which they knew from the latitude was nearly as far south as San Francisco Bay. Not having found a river draining westward the chief surmised that the country did not drain into the Pacific Ocean. He then decided to make an effort to cross the Sierra Nevada Mountains to the valleys of California, which his principal guide, Kit Carson, had visited some fifteen years before. This was a hazardous undertaking in the month of February, but the supplies were almost exhausted, and but little hope was entertained of being able to live on the country where they were until spring. The passage of the mountains was therefore undertaken, and made between the 3d and 20th of February, at a point about forty miles south of the pass subsequently used by the Central Pacific Railway. The snow in the mountains was very deep, and it was necessary to beat down a trail with malls to enable the animals to cross at all. After passing the summit they traveled down the middle fork of the American River, and reached Sutter Fort and settlement on the 6th of March, 1844. This fort was about eight miles from the site of the city of Sacramento.

The expedition then proceeded southward through the valley of the San Joaquin, and crossed the mountain at the Tehachapi Pass, thence by the Spanish trail easterly and northeasterly across a barren country to Utah Lake, thence around the southern end of the Uinta Mountains, crossing the Green River and reaching the Platte not far south of the point afterward crossed by the Union Pacific Railway. Thence they traveled up the Platte and through North Park, crossing back to the Pacific slope by what is now known as Arrapahoe Pass, thence through Middle Park and up the Blue River to its source at the Middle Fork, over into South Park, thence to the Arkansaw near Pueblo, where they arrived on the 29th of June. Traveling eastward, they reached their starting point, the mouth of the Kansas, July 31, 1844, having made the entire circuit in almost exactly fourteen months. The party took with them carts as far as the Dalles of the Columbia and a twelve-pound mountain howitzer to a point some distance north of where they crossed the Sierra Nevada, where the howitzer was abandoned because of the difficulty of hauling it over a rugged country devoid of trail and covered with snow.

Considering the character of the country traversed, some of which was entirely unknown, and the difficulties which beset the traveler in a land far from supplies and full of Indians more or less unfriendly, if not actually hostile, this is thought a very remarkable journey, requiring great energy, perseverance and executive ability.

Lieutenant Fremont's expedition of 1845 and 1846 took him to the head of the Arkansas at the pass which has since borne his name, and which is situated about ten miles from the city of Leadville, thence down the Blue River to Middle Park, westward via the White River to the Green and to Utah Lake, thence to Salt Lake and westward to Humboldt River, making a more extensive survey of the Great Basin as far north as the head water of the Klamath, also in the valleys of California.

On March 3, 1853, Congress passed a resolution authorizing and directing the Secretary of War to make reconnaissances to ascertain the most practicable and economical route for a railway from the Mississippi River to the Pacific Ocean. This work was very thoroughly done by the engineer officers of the army, assisted by civilian engineers, who had had experience in building railways in the Eastern States. They went so far as to make preliminary estimates of the cost of construction based upon these reconnaissances.

The routes examined were those of the 47th to 49th parallel, called the Northern Pacific route, the 41st to 42d parallel, the 38th to 39th parallel, the 35th parallel and the 32d parallel.

The route by the 38th-39th parallel was thought impracticable because of the great elevation of the passes of the Rocky Mountains, and the rough and broken country beyond. Upon all other routes, estimates were made and their advantages and disadvantages set forth in voluminous reports to the War Department. The examination of the route of the 47th-49th parallel was intrusted to Isaac I. Stevens, Governor of Washington Territory, and Lieutenant George B. McClellan, afterward General McClellan, who figured so prominently in the military operations of the first two years of the Civil War.

Governor Stevens's examinations covered all of the territory, excepting that part between Puget Sound and the Columbia River via the passes of the Cascade Range, and, as most of his time and that of his assistants was spent within what are now the boundaries of the State of Montana, the geography of which should be familiar to us all, I shall treat principally of his movements and their results.

No organized exploring party had been through this section of the country since that of Lewis and Clarke, and exact knowledge of its physical characteristics was very meager in the year 1853.

Governor Stevens's principal assistants were Lieutenant John Mullan, Lieutenant A. J. Donaldson, officers of the army, and A. W. Tinkham, F. W. Landor and James Doty, civilian engineers.

The parties were supplied with compasses, odometers and barometers, also astronomical instruments for determining latitude

and longitude. From determinations made with these instruments, maps and profiles were made of the various routes examined, and from these profiles and notes estimates of the cost of wagon roads and of a railroad from St. Paul to Puget Sound were prepared.

Governor Stevens began operations at St. Paul in May, 1853, and by the first of September had reached Fort Benton, the civil engineers having made a reconnaissance thus far, also a superficial survey of the Missouri River. By the 30th of September Governor Stevens and others of his party had reached St. Mary's village in the Bitter Root Valley.

This was made headquarters for the expedition during its stay in this section, which included the remainder of the year 1853 and a part of the year of 1854.

The several parties passed a number of times from Fort Benton to St. Mary's, now known as Stevensville, going via Cadotts and Lewis and Clarke's Pass at the head of the Big Blackfoot, thence down the Big Blackfoot to Hell Gate, near the present site of Missoula, also via two passes at the head of the Little Blackfoot, thence via the Little Blackfoot and Hell Gate Rivers to Hell Gate and Stevensville.

Lieutenant Mullan took a wagon from Fort Benton to Stevensville between the 17th and 30th of March, 1854, traveling via the north bank of the Missouri, the Sun River and the Little Prickly Pear, to the pass at the head of the Little Blackfoot, which was afterward used by the Northern Pacific Railway and which has for many years been known as Mullan's Pass. From this pass he went down the Little Blackfoot by the same route as that taken by the Northern Pacific in 1882.

Lieutenant Mullan's first expedition, that of September, 1853, went south from Fort Benton to a point south of the Musselshell River, thence back to the Musselshell and nearly directly west, crossing the mountains at the same pass.

Mr. A. W. Tinkham made a reconnaissance from Stevensville across to the Flathead, thence by the east shore of Flathead Lake and the Flathead River to Marias Pass and Fort Benton, between the 7th of October and the 1st of November, 1853. His route, from the head of Flathead Lake to the eastern base of the mountains, was practically the same as that taken by the Pacific Extension of the Great Northern Railway in 1892-1893.

The most extensive single expedition from Stevensville as a base was that of Lieutenant Mullan between November 28, 1853, and January 11, 1854. From Stevensville he traveled up the Bitter Root to what is now known as Gibbon's Pass, thence to the Big

Hole Basin and southward to Horse Prairie, which he followed nearly to the Beaver Head, thence by one of its tributaries southward, crossing the main range by the same trail^{*} used by Captain Bonneville in 1833, thence to Fort Hall on the Snake River.

Returning, he came via Market Lake and Beaver Canyon, crossing the main range at the head of Beaver Canyon by the pass now used by the Utah and Northern Railway, thence northward, following almost exactly the route afterward taken by the Utah and Northern Railway to the mouth of the Deer Lodge River. After crossing the pass at the head of Beaver Canyon, he crossed over Red Rock Creek, and, by a low divide, to the waters of what is now called Black Tail Deer Creek, thence to its mouth near the present site of Dillon. With this exception I doubt whether his trail from Market Lake to Garrison was anywhere more than two miles distant from the present line of the Utah and Northern Railway as built in 1881-1882.

A number of routes were examined westward from Stevensville by Governor Stevens himself and several of his assistants. That by way of the Jocho, the Flathead and Clarke's Fork, of Columbia, very nearly followed later by the Northern Pacific, was thought the most feasible and was looked upon with the most favor.

Between November 20 and December 30, 1853, Mr. Tinkham made an examination of the route by the South Nez Perces Trail, afterward known as the Elk City Trail. It goes up the West Fork of the Bitter Root, thence westward across the Bitter Root Range, a very high and broken country, to the mouth of the Clear Water and to Walla Walla.

Lieutenant Mullan passed over what was known as the North Nez Perces Trail, now commonly known as the Lolo Trail, between September 19 and October 2, 1853. He also made an examination up the Flathead Valley via the west side of the lake, up Maple Creek and over on to the Kootenay River in April and May, 1854, returning to Stevensville by a trail lying some fifty miles to the westward. He also crossed over the Bitter Root Mountains via the St. Regis Borgia to Lake Cœur D'Alene, and pronounced it a very excellent route for a wagon road.

The North Nez Perces Trail was traveled by Dr. Evans, United States Geologist for Oregon, in 1850, also by Lewis and Clarke in 1805-1806. Evans and Mullan say it traverses a very rough and rocky country, much broken by spurs and very uneven, the trail lying on the mountain sides much of the way. It is the same as that followed by Chief Joseph with his entire people and all their effects, in their masterly retreat from the United States soldiers in 1877.

^{*}This trail, I judge from the description, lies some thirty miles west of Beaver Canyon.

Lieutenant McClellan's examinations were confined to the territory between the Columbia River near Walla Walla and Puget Sound.

With the exception of a few missionaries in the Flathead and Bitter Root Valleys, there were then no white inhabitants in any part of the territory under examination, which lay east of the west boundary of Montana. The different parties, however, were always supplied with Indian guides who were well acquainted with the country and who seemed to be perfectly willing to impart their information to the whites. In fact, I have seen no mention of the examination of any route where there was not already an Indian trail then in use.

Large numbers of Indians living west of the mountains went to the plains east thereof each year to hunt the buffalo, and occasionally the warlike Crows and Blackfeet crossed to the west side to steal the horses of their more peaceful neighbors. There were, therefore, a great number of excellent trails crossing the mountains, usually by the best passes; in fact, all the principal passes now in use were used then.

The Indians were in all cases peacefully inclined. In all the journals heretofore referred to I saw no mention of actual hostilities worse than the stealing of horses, except in the journals of Bonneville and of Lewis and Clarke. In the latter instance the trouble was occasioned by the killing of a Blackfeet Indian by Captain Lewis near the Falls of Missouri.

During the years 1859-1860 Captain Mullan constructed a wagon road, for military purposes, from Fort Walla Walla to Fort Benton via the St. Regis Borgia, the Bitter Root and Little Blackfoot, crossing the main range at the Mullan Pass, thence via the Little Prickly Pear and Dearborn Rivers to the valley of the Missouri.

The late Colonel Walter W. De Lacy, one of the charter members of this Society, was an assistant to Captain Mullan during the construction of this road. Captain Mullan says, in his report, that the services of Captain De Lacy were especially valuable to him because of the experience which he had obtained in railway construction in the Eastern States.

This military road was 624 miles long, and cost \$220,000. Immediately upon its completion the settlement of the State began.

Captain Mullan was the most active of all Governor Stevens's assistants during the period of exploration under his charge, and I cannot close this paper without expressing my admiration for the clear, forcible and elegant style of narrative employed in his reports, and the energy, perseverance and skill displayed by him during his seven years' operations within what are now the boundaries of the State of Montana.

OBITUARY.**James S. B. Hollinshead.**

JAMES S. B. HOLLINSHEAD was born in Lexington, Kentucky, in 1866, and died suddenly of heart failure in Butte, Montana, July 19, 1900.

His father was Peter C. Hollinshead, and his mother Elizabeth Mills.

He was their only son, and the last surviving male member, with the exception of an aged uncle, of the Hollinshead family. He received his early education in private schools in Kentucky, but when a youth the family moved to Dayton, Ohio, where he attended the Dayton High School.

In 1886, when seventeen years of age, he entered Lehigh University, Bethlehem, Pennsylvania.

At the completion of his junior year, in 1889, he came to Montana and entered the service of the Montana Central Railway, and was sent to work on the location of the Neihart branch. In the fall of 1890 he returned to Lehigh and completed his course, graduating the following year, taking the degrees of Bachelor of Science and Mining Engineer. He was fourth in his class, and that entitled him to membership in the honorary society of San Beta Delta of that university. While in college he worked during the vacations and improved every opportunity to obtain remunerative employment, and with the money thus earned paid his way through college. He returned to Helena, Montana, in the summer of 1891, and again entered the employ of the Montana Central Railway. He was with them but a short time when he entered the service of the Drum Lummond Company, at Marysville, under Mr. John Herron, who is well known to the Montana Society of Engineers.

In the fall of 1892 or spring of 1893 he entered the employ of the Boston and Montana C. C. and S. Mfg. Co., at Great Falls.

He occupied various positions while in their employ,—as foreman on the gas producing during the trying days of developing the production of gas from Sand Coulee coals; foreman on the blast furnaces and reverberatories, and general night foreman over the whole smelter.

This position was rather severe on his health, and after several periods of sickness he removed to Butte in February, 1897, and was

mining engineer for the Butte and Boston Con. Mfg. Co. until January, 1900, when he resigned to open up a private office. After a few months' work he again entered the employ of the Boston and Montana C. C. and S. Mfg. Co. as engineer in charge of their interests in the disputed territory that was in litigation between them and the Montana Ore Purchasing Company, and was engaged in this work until the time of his sudden death.

He was of a very enthusiastic temperament, and whatever he undertook to do was vigorously pushed to a successful termination. He was a devoted member of the Protestant Episcopal Church, having been vestryman in the various churches in the cities where he resided. He was always interested in the moral and religious welfare of the community in which he lived, and many are the men that have been assisted in their hour of need by his timely generosity.

He was a devoted son and the trusted support and counsel of his family during the lingering illness of his father in the later years of his life.

In July, 1898, he was married to Daisy Evans, the daughter of Mr. and Mrs. W. J. Evans, of Great Falls.

His domestic life was happy, hospitable and congenial, and his whole ambition was to provide comfort and happiness for those who were dependent upon him. His mother and sister were living with him at the time of his death. By his manly character and genial disposition he made many friends wherever he resided, and his untimely death was deplored by all who had ever known him.

He was always interested in the welfare of the Montana Society of Engineers, having been a member of the Society for several years, and was one of our most respected and promising members. He had made application to become a member of the American Society of Civil Engineers, but died before the final papers were made out.

The following resolutions were adopted:

WHEREAS, The Creator and Ruler of the Universe, in His infinite wisdom, has taken away from the Montana Society of Engineers one of its most devoted members, James S. B. Hollinshead; and

WHEREAS, The high esteem with which he was regarded by his associates in the Society, impels us to express in our records the deep regret we feel over his decease; therefore,

Resolved, That we extend to the wife, the mother and the sister our heartfelt sympathy, and assure them that of him there shall always remain a cherished memory by this Society. In his honesty and zeal he was reaping an ideal return for faithful endeavor when his promising career was ended.

Resolved, That the minutes of the Montana Society of Engineers shall contain the words above written, and that a copy be sent to the relatives of the deceased.

C. H. REPATH,	}	<i>Committee.</i>
C. W. GOODALE,		
C. H. MOORE,		

Henry M. Claflen.

THE Civil Engineers' Club of Cleveland, at the very opening of the new century, is bereft of one of its oldest and most respected members. Mr. Henry M. Claflen passed away after a lingering illness at an early hour New Year's morning, January 1, 1901, in his sixty-sixth year. He was born in 1835 at Attleboro, Mass., was of Scotch and Puritan descent, and in 1852 came to Cleveland with his uncle, Peter Thacher, of the firm of Thacher, Bent & Co., to engage in bridge building, an industry with which his name has remained inseparably connected. Wooden bridges were then in vogue, and the firm acquired a wide reputation in their construction.

During a part of the Civil War Mr. Claflen was employed by the Government as an expert, to superintend the rebuilding of railway bridges destroyed by Confederates in Tennessee and Kentucky; a commission attended with many difficulties and dangers, which, however, he accomplished with success, greatly facilitating the movements of the Union Army.

At the close of the war Mr. Claflen returned to Cleveland, and, organizing the bridge-building firm of McNairy, Claflen & Co., became its president, and conducted for years a large and successful business. The firm built a large number of bridges, of which the iron portion of the Superior Street Viaduct in this city is a monumental example. The concern was also engaged in car building on an extensive scale.

Mr. Claflen afterward organized the Claflen Paving and Construction Co., of which he was president, taking large contracts for the paving of the principal thoroughfares of Cleveland as well as in other cities. These pavements were usually of wood in the first instance, but as the material wore out stone was substituted. Both these companies accumulated large sums of money, though later, through unfortunate contracts, large amounts were lost. Mr. Claflen at one time was reputed to be quite wealthy, yet owing to a series of misfortunes, without fault on his part, he ended his life a poor man. For the last few weeks he was cared for at St. Vincent's Hospital.

It is doubly lamentable that a man of such ability and integrity, and unwearied devotion to business, having reached an age when he might justly expect to settle down in the comfortable enjoyment of his property, should find both property and life forsaking him.

Mr. Claflen was married in 1863 to Miss Alice B. Hall, daughter of John Hall, of Toronto, Canada, who survives him. They had one son, who died young. His brother, Mr. Harvey T. Claflen, constructing engineer at the Variety Iron Works, and his family are the only remaining relatives in Cleveland.

Henry M. Claflen was a charter member of this Club, and always took a deep interest in its welfare, subscribing liberally to its funds and assisting on social occasions. His genial and happy disposition made him a welcome companion, while his upright character and refinement of manner won him the admiration of all.

In closing this sketch your committee would offer the following:

Resolved, That in the death of Henry M. Claflen the Civil Engineers' Club of Cleveland has lost a member who, since its organization, has honored it with his name, his influence and his character.

Resolved, That this memoir be spread upon the minutes of the Club, and published in the JOURNAL.

Resolved, That a copy of the same, with the condolence of the Club, be transmitted to the widow of the deceased.

FRANK C. OSBORN,
WM. H. SEARLES,
Committee.

Editors reprinting articles from this journal are requested to credit not only the JOURNAL, but also the Society before which such articles were read.

ASSOCIATION OF ENGINEERING SOCIETIES.

Organized 1881.

VOL. XXVI.

APRIL, 1901.

No. 4.

This Association is not responsible for the subject-matter contributed by any Society or for the statements or opinions of members of the Societies.

INSTALLATION, OPERATION AND ECONOMY OF STORAGE BATTERIES.

BY ERNEST LUNN, MEMBER DETROIT ENGINEERING SOCIETY.

[Read before the Society, February 28, 1901.*]

WHERE the conditions are such that the demand on the central station is ever fluctuating and reaches a maximum in the winter time of three or four times the average load for only an hour or an hour and a half a day, which is the case in nearly all cities of the size of Detroit, a storage battery plant is a very valuable auxiliary.

This paper will deal with the battery plant of the Edison Illuminating Company, of Detroit, Mich., but before taking up that subject I wish to give a short description of the cell most commonly used in lighting and power stations.

There are several forms of cell, but all in commercial use are of lead plates in dilute sulphuric acid, and depend for their action on the formation of lead peroxide on the so-called positive plate and of sponge lead on the negative when a current is forced through the cell; which formations are reduced again, with production of a current in the reverse direction, as soon as the cell is free to discharge. The typical cell is merely two plates of pure lead in dilute acid. In practice the formations are facilitated by previous mechanical or chemical preparation of the plates. The mechanical preparation may be the slitting or grooving of the plates, to facilitate the electrical action by exposing more of the metal to the acid; but it is more often a careful determination of the plate structure, so as to secure and maintain the mechanical integrity.

*Manuscript received April 4, 1901.—Secretary, Ass'n of Eng. Soes.

The chemical preparations are usually lead oxides or salts as part of the first construction, so that the work remaining to be done by the earlier electrical charges may be a minimum.

It should be noted that there is no electrical storage in a so-called storage battery or accumulator. The storage is of chemical energy, as in any electrical battery cell, and the difference between a common chemical battery and an accumulator is that in the latter the chemicals used permit a reversible cycle, the electric discharge being followed by an electric charge, which restores, with more or less completeness, the chemical energy which gave the discharge.

The chemical actions involved in the process of discharging and charging are very complicated, and have not been positively determined. The commonly accepted theory is that, on discharge, the lead peroxide on the positive plate is reduced to lead sulphate, while at the same time the sponge lead on the negative is sulphated, with the result that the sulphur radical is abstracted from the electrolyte, leaving it more dilute, hence of lower specific gravity.

A reversal of conditions takes place during the charging process. Oxygen and hydrogen are liberated by the electrolytic action of the current, which is forced through the cell in opposite direction to that of the discharging current. Oxygen unites with the sulphate of the positive plate, converting it into lead peroxide and liberating the sulphur radical, which goes back to the electrolyte, increasing its specific gravity. Hydrogen is freed at the negative plate, and decomposes the sulphate of lead on that electrode, reducing it to pure lead. The sulphur returns to the electrolyte, further increasing its specific gravity.

An accumulator cell consists of three parts: the tanks, the plates and the electrolyte surrounding them. The retaining tanks for large batteries are usually of heavy ash, lined on the inside with pure sheet lead; while those used in small cells are of either hard rubber or glass. The Manchester positive* plate, made by the Electric Storage Battery Company, of Philadelphia, has a framework of lead alloy, containing a series of buttons. The framework gives conductivity and strength to the plate, holds the buttons in place and is continuous with the lug to which the bus bar is connected.

The buttons, upon the surface of which is found the active material, are made of lead ribbons about 9 inches long and $\frac{1}{2}$ inch wide, corrugated on one side and rolled up, making them about $\frac{3}{4}$ inch in diameter. These are put into holes in the alloy frame,

*The terms positive and negative apply to the terminals of a battery exactly the same as we apply them to the terminals of a dynamo.

which they just fit, and hydraulic pressure is brought to bear upon them, which, with the subsequent forming process, causes them to swell so that they fit firmly in their positions.

The special advantages of this button construction are that it is free from buckling caused by the unequal expansion of active material, and also that it exposes a very large surface to the action of the electrolyte. Its spiral formation permits the attainment of both these desirable qualities. Other batteries have differently formed plates, but all manufacturers endeavor to make a plate which will expose a large surface of active material to the electrolyte and which will be free from danger of scale and metal short-circuiting the cell internally, and at the same time be durable and free from buckling.

As nearly as may be, the negative plate is of pure lead, but in an allotropic state. Its construction is somewhat different than that of the positive plate, although a few years ago both plates were formed in a similar manner and like the present negative. The essential qualities of a good negative plate are that it shall have good conductivity and a framework strong enough to hold in place the active material which must compose a greater part of the plate. In the chloride plate a compound containing lead chloride is formed into tablets about $\frac{3}{4}$ inch square and $\frac{1}{4}$ inch thick. These squares are placed in a mold, and a grid of nearly pure lead is cast around under hydraulic pressure, leaving them about $\frac{1}{4}$ inch apart. They are intended to be as close together as the mechanical construction of the plate will allow. After casting, the plates are subjected to an electro-chemical reduction process, which removes the chlorine from the tablets and leaves them in the form of spongy lead, chemically pure and very porous.

A good positive plate must have ample surface over which the active material may spread, while it is essential that the negative be porous enough to allow a rapid diffusion or circulation of the acid as it comes in contact with the lead particles, not merely on the surface, but throughout the mass. On this quality depends to a great extent the maximum rate of charge and discharge. If a particle of lead, after being partially sulphated, is surrounded by a dilute solution of sulphuric acid, having a high resistance and low specific gravity, it is practically incapable of adding any energy to the circuit of which it is a part until a stronger (and hence lower resistance) solution of acid has come in contact with it. At any given rate of discharge, the attainment of this state of helplessness on the part of the particles composing the negative plates is the working limit.

A short rest, or a lower rate of discharge, will allow the cell to regain the normal voltage corresponding to the amount of active material left unacted upon in the plates. It will thus be seen that the freedom with which the electrolyte may diffuse in the plates decides the question of the maximum charge and discharge rates of the battery.

An ideal battery would be one which gave up the same number of ampère hours whether discharged at a high or at a low rate. In central station work, where the load is fluctuating, and especially where there is a very decided peak for a short time,—say for one hour,—it is the battery with sufficient capacity to carry that peak that is wanted; and yet in the accumulator of to-day the total capacity at the one-hour rate is only half what it is at the eight-hour rate, and only a few years ago the maximum was very little over the eight-hour rate.

The voltage, on open circuit between the positive and negative plates of a cell, ranges from 2 to 2.2 volts. This variation depends upon the type of cell and upon the state of charge. As soon as discharge begins the pressure drops, and it continues to drop until the limiting point is reached, which is about 1.7 volts. This lower limit coincides with the reduction of all the available active material. The reaching of this limit, as already noted, does not prove that there is no more active material left in the plates, but only that there is none in working contact with the electrolyte. Sometimes a series of cells may have an average voltage less than 1.7, which means that some cells are useless and are being charged by the current forced through them by the others in the series.

The electrolyte is dilute sulphuric acid, 28 per cent. by bulk. Both acid and water must be chemically pure. The impurities most to be avoided are those which affect the chemical reactions in the plates, the metals being particularly objectionable. The acids other than sulphuric which are present in commercial sulphuric acid—*i.e.*, nitric and hydrochloric acid—are likewise to be avoided. There is evaporation of water from the surface of the electrolyte, and there is a loss of fluid by spraying during the latter part of charge. These losses have to be made good by the addition of pure water and new electrolyte. A still for water distillation is a common annex to a large battery. The loss of acid is usually negligible.

Setting Up. In setting up a battery, the positive plates of one cell are connected to a lead bus bar, on the opposite side of which are connected the negatives of the next cell.

Fig. 1 shows the arrangement of plates and bus bar connections. At present the plates occupy only one-half of the available

space in the tanks. The battery will be completed as the demand for service requires increased capacity.

Connection to System. In connecting the battery to the system, three methods may be followed, according to the manner in which the battery is operated.

In railway work, and particularly in suburban lines when the potential of the system is extremely variable, the battery is connected in multiple with the system. It discharges when there is a drop in voltage caused by a heavy demand for current, and receives its charge when the voltage rises above the normal pressure of the




FIG. 1. STORAGE BATTERY TANKS.

system. At all other times it is allowed to float, neither charging nor discharging. A cable connection is usually made to a generator, so that an occasional charge may be given it if necessity demands. No other regulating apparatus is required. A battery connected in this manner is used simply to equalize the pressure on the system, and does not sustain any regular charge and discharge.

In street railway systems, where the battery is used not only to equalize the pressure, but to carry regular peaks, special apparatus for charging and discharging must be provided. The apparatus used for this purpose is called a "booster." A booster is simply a motor-driven generator in series with the battery circuit. When a

charge is given the battery the booster raises the pressure at the terminals of the accumulator sufficiently to force through it the desired amount of charging current. On discharge it has a reverse action, and lowers the pressure over the battery until the desired discharging current is obtained. The booster commonly used in railway operation is a "differential booster," so called because it has a differential winding which permits the charge and discharge to be governed automatically.

In a lighting system, where the pressure must be kept much more constant than in railway work, the regulation is controlled by a series of end-cells connected to end-cell switches, together with a booster. The booster may be used for either charging or discharging, but has no automatic controlling arrangement. It is customary to use the booster only on charge. The discharge is controlled by the end-cell switches.

The so-called "end-cells" are merely a certain number of the terminal cells of the battery, so arranged that any number of them may be successively connected in series with the main battery as the load increases and cut out again as the load drops off.

The number of end-cells, as well as the number in the main battery, depends upon the voltage at which the system is operated. The maximum voltage of the main battery must equal the normal voltage of the system. There must be a sufficient number of end-cells to insure proper regulation under all conditions of charge, and also to provide for the distribution drop of the system. For instance, in a 125-volt system this would mean fifty cells in the main battery and about thirty additional end-cells to give a bus bar voltage of 136 at end of discharge. From the cell bus bars between the end-cells copper leads are run to the end-cell switches, terminating in a series of studs arranged in succession. Parallel to these studs is a copper slide, from which connection is made to the switchboard. A laminated copper brush, making sliding contact with the slide, is moved successively over the studs by means of a screw propelled either by hand or by a motor.

Fig. 2 shows one of the end-cell switches, showing the arrangement of the copper slide and studs.

The operation of the battery is very simple. In the Edison system, for instance, the pressure across the mains is about 120 volts. In order to balance the battery against this pressure it will be necessary to have about 60 cells in series, counting two volts per cell. In this condition it acts as a regulator, or floats; for if there is a rise of pressure on the mains, due to a sudden cessation in the demand for current, the battery will absorb the surplus energy by

suffering a slight charge; while, on the other hand, should the pressure suddenly fall, the battery discharges enough to keep the voltage almost constant in the system.

In street railway work, where the load is much more fluctuating than in lighting, this characteristic of the battery is of great consequence.

As the cells discharge, additional cells have to be added, in series with those already in, in order to keep the pressure constantly 120 volts at the service ends of the mains. This is done by moving the sliding contact brush further along the end-cell switch. As the




FIG. 2. END CELL SWITCH.

load drops off, these cells, previously cut in, have to be cut out again. This is done by moving the brush in the opposite direction. The end-cell switches are operated from the switchboard, so that the operator has complete control of the battery from his position at the board.

Availability. In order that the effect of the Edison battery may be easily understood, I wish to say a word concerning the general plan of the Edison Illuminating Company's underground distribution system. This will be necessary because the battery plant is now a part of that system, and its value can better be

appreciated when the conditions of the field previous to the installation of the battery are understood.

The main station (Station "A," corner of State street and Washington avenue) has been, and is at present, the generating plant for nearly all the current used in the underground system.

Fig. 3 is a diagram showing the relative positions of this station and the centers of distribution of the underground system within the half-mile circle; also the location of the battery station, Station "E."




FIG. 3. PLAN OF COMPANY'S SYSTEM.

Last spring the Edison Illuminating Company was facing the proposition of determining the most economical way to increase the output of the generating station. It was estimated that the holiday season load would run about 4000 or 5000 ampères, or 500 to 600 kilowatts, higher than the year before; and in the previous year the station was loaded to its full capacity. Owing to the already crowded condition of Station A, the cost of installing generating machinery sufficient to supply the demand for the coming year, with some facilities for taking care of the probable increase of load of the following season, would, it was figured, be greater than the cost of an accumulator plant.




FIG. 4. SECTION OF STATION.

Furthermore, it was not only undesirable, but next to impossible, to increase sufficiently the output of Station A.

A converter station, taking power from our alternating system, and situated where the battery, Station E, now is, would have been a possible expedient had it not been for the fact that the peaks, on both the Edison and the alternating stations, take place about the same time. The additional equipment necessary to insure service equal to that given by the battery would have cost more than the battery. The peak, which comes only in the winter months, lasts, all told, not more than 125 hours per year; and to install generating machinery to carry that load for that length of time, and to lie practically idle the remainder of the year, would mean an expenditure of money difficult to realize encouraging dividends on. With a storage battery plant it is different; it takes the high peak in the winter months and furnishes the system with sufficient reserve at all times, while at the same time it allows two-thirds of its capacity to be used at will every day in the year. Whatever the advantages afforded by the battery, they are felt every day. Fewer boilers have to be kept fired up and fewer engines ready to run, and the generating machinery can be worked at the point of greatest economy.

Location. The decision to install a battery led to the investigation of possible sites. A theoretical location could have been easily determined by taking into account the existing conditions and the possible extension of the system had not other conditions introduced very important limiting factors. These factors included the available sites, their comparative cost and the comparative cost of copper necessary to make the best connection to the system, besides the fire risk to which the location of each would subject the battery plant.

Construction of Building. The lot selected gave no excess of space. The sectional elevation of the battery station shows this (see Fig. 4).

To get the battery in place without crowding, and with convenient arrangement of copper, required considerable study. The final copper plan was drawn by the battery company after the dimensions of the room were fixed by us, and the copper and switches were got out according to this approved plan while the building was in progress. Work was begun on the foundation May 1, 1900, and the building was finished in August.

The wall above the opening for the end-cell switches is of brick, clear through to the roof, thus separating the battery room from the rooms in front. There are good reasons for having it

so arranged, the principal one being that it protects the cells from fire originating in the dwelling rooms. Fire is not likely to originate elsewhere. The switchboard and booster room is directly above the end-cell switch room. All the operating is done from this room.

To go back to the construction of the building. It is absolutely necessary that there be a good foundation, for there are 160 tanks, weighing about 2 tons apiece, in a room 30×85 feet. These must be kept in perfect alignment, and any sinking or failing in the foundation would cause serious trouble. The natural foundation




FIG. 5. STATION E.

was found to be of clay. A good system of drainage was put in the ground, so that the tile came under the walks between the tanks, and then a covering of concrete 16 inches thick was spread on, coarse at the bottom and finer at the top. This used up the material of the building found on the lot. Upon this were placed extra heavy paving bricks. It took eight barrels of pitch, between the bricks, to complete the foundation, which, when it was done and dry, was perfectly level and also a good insulator. One fails to detect the slightest sign of a current when standing on the floor and feeling at the same time any of the live conductors. (Those

who are accustomed to getting a poke every time they lay a hand on a wire around a station will appreciate the convenience of having a non-conducting floor.)

The side walls are of red pressed and partially vitrified brick to a height of about 6 feet above the floor, continuing the rest of the way of ordinary building brick. This pressed brick is acid-proof. The front is of gray pressed brick, and so designed as to give the building the appearance of a dwelling house rather than that of an electric lighting station. (See Fig. 5.)

Installing the Battery. The setting of the tanks was an operation requiring great care. On account of their weight, they must be well supported. Insulation, too, is a matter of great importance. Each tank is supported on eight petticoated insulators,




FIG. 6. LOAD CURVE.

Thursday, January 25, 1900. Storage battery not installed.

which rest on vitrified tile $7\frac{1}{2}$ inches wide and $\frac{3}{8}$ inch thick, set to a templet and on sulphur. With the tile set and the porcelain insulators fastened to the bottoms of the tanks by being stuck into their places with hot pitch, the operation of tank setting became both simple and rapid. As soon as a few tanks were put in place, the glass supporting plates were put in, and the battery plates supported on these. In this way a large force of men was kept at work. Different gangs were setting tile and tanks, and cleaning up plates and putting them in place in the tanks at the same time. As soon as it could be done, the work of burning the plates to the lead bus bar was commenced.

Burning is necessary instead of the more convenient soldering, because solder would be promptly attacked by the acid spray.

Perhaps the most interesting of all the work was filling the tanks with the acid. At the rear of the building was placed a tank similar to one of those used for the battery, and about 8 feet above them. Ten rubber tubes (garden hose) were constantly siphoning the acid from the tank to the battery tanks. A gang of men was emptying carboys into the upper tank as fast as they could be handled. A carboy would be tipped upside down over the tank, the box surrounding it supporting it in such a way that its neck extended into the tank about 5 inches. The acid in the tanks could therefore never get above the level of the mouth of the carboy as it was thus inverted. As soon as one was placed on the tank and




FIG. 7. LOAD CURVE.

Tuesday, December 18, 1900. Storage battery installed.

started to empty, it was shoved along to make room for another, and was empty by the time two others had been put on behind it. The process was very rapid, and over 2000 carboys were emptied in about a day and a half. Everything had to be so far completed by the time the acid was in that the first charge could begin immediately afterward, for it injures the plates to allow them to stand in the electrolyte for any length of time in an uncharged condition. The injury is in the formation of an irreducible sulphate.

The first charge was begun immediately and continued for thirty hours, the rate being comparatively low,—500 amperes to start with and increased later to 700 amperes. The cells were over-

charged on the first occasion and on the next few charges, the object being to complete the formation of the active material, which is nearly, but not quite, completed when the plates leave the factory.

Operation. The subject of operation can best be understood by an inspection of the following curves:




FIG. 8.

Sunday, September 23, 1900. Storage battery not installed.

Fig. 6 shows a characteristic load curve previous to the installation of the battery.

Line A, called the engine curve, represents the normal rating of the units running. Line B, called the commercial load curve, represents the amperes supplied to the system.

It will be noticed that the load factor of the engines' run—that is, the ratio of the ordinates of curves B to A—is compara-




FIG. 9. LOAD CURVE.

Sunday, November 25, 1900. Storage battery installed.

tively low. It was necessary to run the engines at this low load factor in order to secure reliable service under all conditions of operation.

Fig. 7 illustrates a characteristic load curve after the battery was installed. The cross-hatched areas represent the operation of the battery. It will be noticed that the load factor has been greatly increased. This is due to the fact that the battery was on the system and supplied a reserve, making it unnecessary to run gen-

erating machinery below the normal rating, as was done before the battery was installed.

Figs. 8 and 9 are characteristic Sunday load curves, before and after the battery was installed respectively. Compare again the load factors in the two cases.

Fig. 10 shows the operation of the battery in emergency cases. On account of a feed-water pipe bursting at the generating station, the plant was shut down for about three-quarters of an hour, while the battery carried the entire district load, giving the engineers sufficient time to get another boiler unit in commission.




FIG. 10. LOAD CURVE.

Wednesday, November 21, 1900. Storage battery installed.

Fig. 11. Curve O O O is the battery capacity curve, made up from data furnished by the Electric Storage Battery Company. The discharge rates are plotted as ordinates; the time and hours as abscissas, the capacity being 2750 ampère hours at the one-hour discharge rate, 3750 at the two and one-half, 4350 at the three and 5440 ampère hours at the eight-hour rate.

Curves A A A, B B B, etc., are curves showing the various discharges in ampère hours, plotted in a similar manner to the capacity curve.

It is well known that the available capacity of a battery increases as the rate of discharge decreases, and it was for the pur-

pose of showing the relation existing between them that the capacity curve was superposed on the discharge curves.

Suppose at any particular time it is known that, say, 2500 ampère hours have been taken from the battery at various rates of discharge, and it is desired to know how long a certain discharge rate, say 2000 ampères, can be carried. Follow up the 2500-ampère discharge curve until it intersects the 2000-ampère rate line. The distance between this point of intersection and the point where the 2000-ampère rate line cuts the capacity curve represents the length of time that 2000 ampères can be carried, which is about




FIG. 11. BATTERY CURVES.

Capacity curve shows capacity of battery at different rates of discharge.

Discharge curves show various discharges in ampère hours and their relation to the capacity curve.

twenty minutes. With the battery in the same condition, 1500 ampères could be carried for about forty-five minutes, as shown by the distance between the points of intersection of the 1500-ampère rate line with the 2500-ampère discharge curve and the capacity curve.

In a similar manner, it can easily be calculated how long any rate can be carried by the battery, or whether it can be carried at all, if the ampère hours previously taken out are known.

It is not customary to work the battery near enough to its limit to make it necessary to consult the curves. It is, however, very

valuable in emergency cases to know how long a certain rate can be carried. The curves have been repeatedly found to be very reliable, and to know just how long the battery can be depended upon to carry a given load, if necessity demands, is a source of no small satisfaction to the operator.

Economy.—The real economy of an accumulator plant is hard to determine, constituting as it does only a small part of a large system, each department of which adds to or detracts from the economic operation of the whole, according to the degree of efficiency with which each branch is run. It would be unfair to expect the number of pounds of coal burned per kilowatt-hour output to be greatly decreased on account of having the battery in operation when it is remembered that only about 8 per cent. of the output is dealt with by the battery. It has been impossible to get accurate data on this point. There has been a falling off in the amount of coal burned for a given output since the battery was installed, but I am not prepared to say that the saving in the coal bills, calculated along that line, is more than enough to pay the operating expenses of the battery station.

I do hold, however, that the cost of operating and maintaining an accumulator plant (the one under consideration in particular) is no greater than that of a complete generating plant of the same capacity, and in the above-mentioned case the cost of installation of such a plant would have been in excess of the first cost of the battery. In such a steam plant we would not have expected any greater reduction in the cost of coal per kilowatt-hour than we have already experienced while using the battery. There are other reasons, however, for believing that the installation of the battery plant was a wise move. Situated as it is, it makes it possible to cover districts which could not be reached directly from Station A. Not only that, but the whole system feels the effect of the better regulation afforded by the battery. It acts as a reservoir, ready at all times to give energy to the system, and forestalling any drop in pressure which could be caused by the failure of any single unit at the generating station. It is customary to keep always enough reserve energy in the battery to carry for about an hour the load dropped by such an accident, giving the engineers plenty of time to get another set of generators or boiler plant in commission. This reserve amounts to about one-third of the capacity of the battery. We are at liberty then to use the other two-thirds in whatever way good operation demands.

So far the battery has given the best of satisfaction. During the summer months we expect to use it to as great an advantage as

during the past winter. Thunder-storm peaks can be taken care of without the necessity of keeping boilers in readiness for such an emergency, and the load factor of the engines run can be raised to the most economical point of operation, reducing by no small amount the number of pounds of coal burned per given output. As a means by which the output of the system could be increased the battery was the cheapest and best; and as for supplying reserve, ready at a moment's notice, it has no equal. Its many other virtues only strengthen an ever-growing respect for it.

CONCRETE CONSTRUCTION.

BY C. R. NEHER

[Read before the Engineers' Society of Western New York, March 5, 1901.]

THE object of the present paper on concrete construction is to give a few practical suggestions based on actual experience. I have no new theories to advance, but am a believer in the use of a wet mixture, of such proportions as to give a maximum of strength under compression, always using Portland cement. Where economy is necessary, I would introduce large stone in the heart of the mass, or cellular construction, but would not cheapen the concrete.

My remarks will be from the standpoint of the purchaser and contractor, as well as the engineer. As engineers, in our desire to secure good work and uniform results, we are apt to introduce unnecessary refinements, resulting in increased cost, retarding the progress of the work and often defeating the end in view.


As concrete is almost always used in compression, I would recognize no test but that of the actual mixture to be used in the work and that under compression. Such a test demonstrates the excellence of all the ingredients and whether they are properly proportioned. Even with excellent ingredients, low results are often obtained by reason of wrong proportions. To illustrate, last summer I had occasion to test the value of copper slag and lake gravel in concrete. The gravel alone, mixed five parts gravel to one of cement, was good for about 60 tons per square foot ultimate compression after seven days. The standard of excellence desired was that obtained by limestone and gravel, mixed 1 cubic foot of cement to $2\frac{3}{4}$ cubic feet limestone (passing a 2-inch ring, pieces $\frac{1}{2}$ inch and under excluded) and $2\frac{1}{4}$ cubic feet of lake gravel, which gave an average ultimate compression in seven days of 135 tons per square foot.

My first tests on the slag mixture gave only about 80 tons per square foot in seven days, and appeared to demonstrate a low value for the slag; but examination of the fracture showed an excess of gravel and a fracture through the spaces where the most gravel existed. A slight diminution in the quantity of the gravel gave results of over 140 tons in seven days. The copper slag is shown by analysis to be free from deleterious chemicals, except lime, and its use in work of four years' standing seems to prove the absence of free lime. The slag can be obtained cheaper per cubic yard than

*Manuscript received April 23, 1901.—Secretary, Ass'n of Eng. Soes.

stone, but, by reason of its great weight (about 3300 pounds per cubic yard for run of crusher, against 2800 pounds for limestone), the cost of transportation and handling is increased. Owing to its weight and abrasive qualities, the duty is harder on the mechanical mixer and tools, and the slag is more apt than limestone to separate itself from the other ingredients when thrown from a height or used with a large amount of water; and its apparent economy is largely offset by the objections mentioned.

The engineer should seek to obtain greatest strength, complete filling of voids and a smooth exterior; all of which can be obtained



UNDER SECTION OF FLOOR, EASTERN ELEVATOR, SHOWING BEAMS AND GIRDERS.
RANSOME CONCRETE CONSTRUCTION.

by simple means. An excess of fine material, while producing a good finish, weakens the concrete; imperfect filling of voids produces rough work, and is also an element of weakness; therefore, to define the exact proportions to be used in any piece of work necessitates an intimate knowledge of the exact materials that will be used by the contractor to whom the work is awarded. As stone from different quarries does not produce the same fracture or the same amount of fine material, it is seldom wise to state the exact proportions, except that of the cement to the rest of the aggregate, the remaining ingredients to be so proportioned as to fill all voids without an excess of fine material, leaving the exact amounts to be

determined by experiment with the actual materials to be used when placed on the work.

Specifications should state the minimum size of broken stone allowed, as well as the maximum, as broken stone is graded in five commercial sizes; and to determine the voids it is necessary to know the sizes included in the coarse aggregate. As a measure of economy, it is well to specify run of crusher, dust removed. This is usually sold at 5 per cent. less than the graded sizes, and contains about 20 per cent. more material, leaving less fine material to be supplied to fill voids, resulting in a saving of 25 per cent., which



THIRTY-SIX-INCH FLOOR, EASTERN ELEVATOR, BUFFALO, N. Y. RANSOME
CONCRETE CONSTRUCTION.


will be offset somewhat by greater cost per cubic yard for transportation.

Thorough ramming should always be specified. The general impression among men employed in placing concrete is that little ramming is required if the mixture is wet. This is a mistake. Large voids will show in the face of the work if not thoroughly tamped; and the fact that wet mixtures are seldom tamped enough is one of the reasons why it sometimes does not show up so well in testing as compared with dry mixing, which must necessarily be thoroughly tamped.

Thorough mixing should also be insisted on, and on all work

where an amount to exceed 40 cubic yards per day is placed mechanical means should be used. In this way greater strength and uniformity can be obtained at less expense than by the addition of cement.

A concrete composed separately of several of the commercial sizes of broken stone, gravel, sand, etc., is always expensive. The coarser size stone, passing a 2½-inch ring, with the voids filled by the addition of the smaller sizes, sand, etc., would take 45 cubic feet to make one cubic yard in place, or a yield of 60 per cent.; besides adding to the expense of the handling and being very diffi-



ARRANGEMENT OF FORMS AND TWISTED STEEL RODS, THIRTY-SIX-INCH FLOOR.
EASTERN ELEVATOR. TOP VIEW.

cult to properly proportion by the ordinary laborer. Equally good results would be obtained by run of crusher, sand and cement, giving only three ingredients to watch, and resulting in a very material saving in expense. As eternal vigilance is the price of success in concrete work, simplifying of methods is desirable. We err when we introduce refinements, which increase the cost and give no corresponding results.

To produce smooth work, the addition of granolithic face or plastered surface is unnecessary. Smooth forms, with concrete well proportioned, will give just as smooth work at much less cost, leaving the whole mass uniform, without a line of separation or

difference of compressive strength. As an illustration of this, the concrete foundation and floor of the Eastern elevator and the foundations of the new Dakota elevator are good examples, and a cordial invitation is extended to all to examine this work. A large portion of this work was placed in midwinter, proving that good work can be done at all times and seasons, although the expense is about 20 per cent. greater.

Another way to produce finish is to joint the concrete to represent masonry, using rough lumber for forms; then bush-hammering the face, which can be done by an ordinary laborer at $1\frac{1}{2}$ cents per



CONCRETE FOUNDATIONS, DAKOTA ELEVATOR, BUFFALO, N. Y.

All made in February, 1901. Thermometer 0° to 40° . Cost 63 cents per cubic yard to heat.

square foot. The amount saved by using rough lumber goes a long way toward paying for the bush-hammering, which removes all impressions from inequality of molds, efflorescence, etc. The front of the Eastern elevator, facing the dock, is so treated.

The preparation of forms calls for considerable ingenuity, and every contract requires special study, to the end that smooth surfaces be left, with unbroken corners, that the swelling of the wood does not rupture the concrete or leave distorted surfaces; and that the forms be so designed as to be used several times, and readily set up and taken down and later on devoted to other uses. As the

charge for forms against the concrete can seldom be kept below 50 cents per cubic yard for heavy work, there is always an opportunity for the ingenuity of the designer, as few rules can be laid down for his guidance.

The use of matched or tongue-and-grooved stuff is not desirable, as concrete fills in the openings and there is no opportunity to expand from moisture. Unmatched boards dry apart and let the water in the concrete leak out, carrying with it some of the cement. Later on they swell and buckle and, if used as interior forms, burst the concrete. The best way devised so far is to bevel one edge of the boards, using narrow stuff, not to exceed 6 inches. The sharp edge of the bevel, lying against the square edge of the adjoining board, allows the edge to crush when swelling and closes up the joint, preventing buckling.

A coat of soft soap, before filling the forms, prevents the concrete from adhering to the forms, which should always be scraped and brushed with a steel-wire brush when taken down.

Square corners should be avoided, as they readily chip off: and where used as interior forms for recesses or cellular construction, a fillet should always be placed in the corners.

Concrete can often be saved by introducing cells in the mass. These are formed either by cheap hemlock boxes, which can be left in the work, or by collapsible boxes which can be withdrawn and used over again. Where weight is desirable, one-man stone can be rammed in the heart of the mass, reducing the cost very materially.

Where, for economy in handling or other reasons, it is desirable to dump the concrete from a considerable height, some precaution should be taken to avoid having the coarse aggregates separate from the rest of the mass. This can be accomplished in several ways,—either by chains loosely stretched at intervals across a chute or by shelves extending part way across the chute at an incline, so as to deposit on a corresponding shelf on the opposite side, so alternating the length of the chute. Either of these methods is a direct benefit, as it more thoroughly mixes the concrete.

Our building laws as a rule show little knowledge of the value of concrete, ordinarily limiting its use to 16 tons or less per square foot, involving a larger factor of safety than is required for any other material. This probably is due to the large amount of poor concrete turned out, and also to a desire to exclude from the building trades a material that can be placed by unskilled labor.

Regarding the introduction of steel or iron in its various forms in concrete to give tensile strength, there is no question as to its

utility if properly used. I claim no special knowledge of any of the systems except the Ransome, which appears to me the best, for the following reasons: It is a perfect system, from which the entire structure, from foundations to roof, can be made without the introduction of I beams or metal framework of any description, except molding in the cold-twisted square steel bars.

The cold-twisting which the square bars receive has many advantages possessed by no other system. The twisting prevents the rod from drawing in the concrete, making the grip on it continuous and uniform, rendering the strains all equal. It further decreases the ductility of the metal, making it act more nearly in harmony with the concrete,—a vital point when the nature of concrete is considered. Incidentally, we also gain a marked increase in tensile strength, which in practice we generally throw in as an extra factor of safety. The application of concrete-metal is in its infancy, and in a short time I predict it will be used in many ways not now thought of. Its application so far has been markedly successful. The floor of the Eastern elevator is, I believe, the boldest application, to date, of concrete-metal construction. The actual load on the floor is 4470 pounds, and the dead weight of the floor is 300 pounds per square foot, taking the load as uniformly distributed. When we consider that the grain load is concentrated on the rim of the tank, and generally taken as two-thirds of the whole load; that the supporting columns, owing to the peculiar layout of the property, have no relation to the position of the tanks, and that in practice some bins are full and others empty, giving eccentric loading, we see that the problem was a difficult one. The efficiency of the construction is still to be demonstrated. Of its success I have no question. The basement floor of this elevator was built for a live load of 75 pounds, but it has been loaded over almost its entire surface with from 300 to 500 pounds per square foot frequently in seven days after being placed, and that in midwinter.

DISCUSSION.

MR. DIEHL.—Mr. Neher, will you give us a description of the work you are doing at the Eastern Elevator, also at the Dakota Elevator?

MR. NEHER.—The property of the Eastern Elevator is angular, being a rhomboid in plan. The new site occupies the same position as the old elevator destroyed by fire in August, 1900. So far as possible the old piles and masonry piers were utilized. The piers were placed 12 feet centers and at right angles to each other and to the long side of the property. The old plans showed 16 piles

per pier, a heavy timber grillage, and well-proportioned stone piers, stepped up in uniform courses, with equal offsets. Excavation revealed the fact that there were only 12 piles per pier, and that the masonry was laid directly on the pile heads. Many of the piers were of the size of the cap stones, all the way down to the footing stone. In 80 per cent. of these piers the bottom courses of stone were badly broken. As 12 piles per pier were considered insufficient, four more were added in each case, making the load on each pile about 20 tons. Where the old piers were left in, 4 piles were driven outside, and the whole was surrounded with concrete, and prevented from cleaving from the stone by twisted steel bars running around the piers. In the cases where the stone was removed, the 4 piles were added. Excavation was extended 3 inches below the pile heads. One-inch twisted steel bars were laid across the pile heads entirely across the width of the pier in both directions, and concrete was then rammed in the forms until it reached a point 24 inches above the rods. Above this, after thoroughly setting, piers with an area sufficient to withstand a load of 35 tons per square foot were molded, to the height of the basement floor, a height over all of about 7 feet. On these piers, columns 9 feet high and 33 inches square were built, and directly on these was placed the heavy floor 36 inches deep, already mentioned.

THE PRESIDENT.—Were the piles driven to the rock?

MR. NEHER.—No, sir. Some few brought up on a hard pan. Most of the piles were driven down from 28 to 35 feet. The hard pan varies at different depths. Some of the piles seemed to be broken in the soil.

MR. KNIGHTON.—How does this concrete construction compare in price with the ordinary construction?

MR. NEHER.—Taking the price of the materials entering into an ordinary wall, I should say the Ransome construction was somewhat more expensive. While this construction is not a substitute for everything, still I think for work such as we are doing at the Eastern Elevator it is much better than the ordinary construction and cheaper than steel.

MR. VANDER HOEK.—What is the twisted iron put in the concrete for?

MR. NEHER.—To take care of the tension. Where there is to be a great load on a floor I do not think there is anything that will stand like the Ransome system. Before it was taken up by our firm, I studied very thoroughly the matter of the different forms of construction, and I came to the conclusion that this

was the best system for heavy loading. For instance, at Bayonne, N. J., there is a borax factory, the floor of which was built to withstand a pressure of 500 pounds per square foot. There are portions of this floor which have been loaded up to 1200 and 1300 pounds per square foot.

MR. VANDER HOEK.—You spoke of the cement briquettes as breaking at 85 tons after seven days. Were these briquettes of the ordinary form?

MR. NEHER.—They were 6-inch cubes, and we used a hydraulic jack. I think in this case it was Atlas cement. We have used both Atlas and Lehigh, and have got about the same results from each. We sent a boy to the mixer, and he picked out a batch just as it came from the mixer. Where we made tests by hand mixture we did not get as good results.

MR. VANDER HOEK.—You used Portland in every case?

MR. NEHER.—Yes, sir.

MR. TUTTON.—What mixer do you use?

MR. NEHER.—The Ransome. We have made some improvements on it.

MR. TUTTON.—We are using one, but we have not made any tests.

MR. NEHER.—The record made by us is 146 yards in 13 hours, with the small mixer. We laid on an average 41 to 42 batches in 10 hours. This could not be done if fed with wheelbarrows. We fed the machine with a rotating derrick and dump buckets.

MR. ROCKWOOD.—Did you use any salt?

MR. NEHER.—We always use salt, a 10 per cent. solution.

MR. ROCKWOOD.—Regardless of the weather?

MR. NEHER.—Yes, sir.

MR. VANDER HOEK.—Did you get the same results in winter as in summer?

MR. NEHER.—We used the same materials in summer as in winter, but I do not think any man can say he got just exactly the same results.

MR. ROCKWOOD.—Do you use hot or cold water?

MR. NEHER.—We use hot water in winter. We find that with a 10 per cent. solution of salt in hot water, the concrete will not freeze for 5 or 6 hours. This gives us time to fill the forms before covering them up and heating with salamanders.

MR. NORTON.—Did any of the concrete freeze?

MR. NEHER.—Yes, some little did freeze on top. This we capped off.

MR. KNIGHTON.—What do you consider the best method to follow in leaving off work where you expect to begin next day?

MR. NEHER.—So far as I am concerned, I do not like to leave one day's work uncompleted; but when we do, we generally insert twisted bars placed vertically, to give us union with the succeeding work.

MR. KNIGHTON.—Have you built any arches?

MR. NEHER.—I have not. Quite a number have been built in the South for railroads.

MR. DIEHL.—I would move you, Mr. President, that a vote of thanks be extended to Mr. Neher for his kindness in addressing us this evening. Seconded by Mr. Tutton. Adopted unanimously by a rising vote.

OBITUARY.**Sherman Emmett Burke.**

MEMBER OF THE ENGINEERS' CLUB OF CINCINNATI.

MR. BURKE was born in Cincinnati, Ohio, February 17, 1872, where he attended the public schools in his youth and later was a student of Mt. Auburn Military School and Franklin Preparatory School.

During the spring and summer of 1890 Mr. Burke was employed on the location and construction of the Middletown and Cincinnati Railroad, of which his father, Major M. D. Burke, was chief engineer. In the latter part of the year Mr. Burke entered the preparatory department of the Ohio State University, and matriculated with the class of 1895 in the course of civil engineering.

In his college career Mr. Burke was a charter member of Beta Nu Chapter of Sigma Nu Fraternity, and captain of Company D of the university battalion, where he distinguished himself by winning the prize sword in 1894.

In June, 1894, Mr. Burke accepted a situation in the engineering department of the Cincinnati, Portsmouth and Virginia Railroad, under the direction of Mr. W. B. Ruggles, chief engineer, where he remained until March, 1895, when he entered the service of the Cincinnati, Lebanon and Northern Railway Company as engineer.

In June, 1895, Mr. Burke entered the service of the Pennsylvania Company, and was assigned to the Newport and Cincinnati bridge corps, under the direction of Mr. George U. Engle. Mr. Burke remained with the Newport and Cincinnati bridge corps until the completion of the substructure, after which he accompanied Mr. Engle to Indiana, where they were engaged in survey work, and later became part of the chief engineer's office force at Pittsburg.

The energy and fidelity displayed by Mr. Burke soon attracted the attention of the officers of the Pennsylvania Company, who evinced their appreciation by making him assistant engineer of maintenance of way of the Richmond division of the Pennsylvania lines July 1, 1897.

On July 1, 1899, Mr. Burke was transferred to the Cleveland, Akron and Columbus Railway, of which he was made engineer of maintenance of way November 1, 1899, remaining in that capacity until his death.

On October 17, 1900, while accompanying the general manager's inspection party, Mr. Burke received accidental injuries

which resulted in his death. Mr. Burke leaves a widow and daughter to mourn their loss, and a host of friends who regret with deep feeling that a promising and useful career was cut short by his untimely death.

J. A. RABBE,

J. A. LILLY.

Editors reprinting articles from this journal are requested to credit not only the JOURNAL, but also the Society before which such articles were read.

ASSOCIATION OF ENGINEERING SOCIETIES.

Organized 1881.

VOL. XXVI.

MAY, 1901.

No. 5.

This Association is not responsible for the subject-matter contributed by any Society or for the statements or opinions of members of the Societies.

THE SOFTENING OF FEED WATER FOR BOILERS.

BY LOUIS BENDIT, MEMBER OF THE ENGINEERS' CLUB OF ST. LOUIS.

[Read before the Club, April 3, 1901.*]

It certainly is unnecessary in this advancing scientific age, and before this society, to prove the facts that nearly all waters that are found either in streams or beneath the surface of the earth are impure or that water purification is essential, whether for dietetic or manufacturing purposes. This is conceded by every engineer.

In this paper we shall consider only the best method for the treatment of feed water for boilers.

All natural water contains two classes of impurities, viz., organic and inorganic, either in suspension or in solution. The organic impurities are of vegetable and animal origin, and are taken up either in flowing over the ground or by direct contamination, such as the addition of sewage from cities or refuse from manufacturing concerns. This evening we shall consider only the soluble inorganic or mineral impurities, for it is these which give trouble and cause expense when the water is used in steam boilers.

The mineral impurities in solution are the lime, magnesia, soda and potash in combination with carbonic, sulphuric or hydrochloric acids, with iron, generally as a bicarbonate, and a small amount of silica.

The soluble lime and magnesia are the impurities which make water hard. The hardness of water is measured in degrees, as parts per thousand, or in grains per gallon. All salts of lime and

*Manuscript received May 27, 1901.—Secretary, Ass'n of Eng. Soes.

magnesia are figured to their chemical equivalent of lime carbonate, and each part per 100,000 is called a degree of hardness. Thus, we say a water has a hardness of 10 or 50, as the case may be, meaning that when all lime and magnesia salts are figured to the lime carbonate, the water contains 10 or 50 parts per 100,000. The hardness of water may be measured in a very simple manner by means of a standard solution of soap in alcohol, the strength of the solution being tested by means of a solution of calcium chloride of known strength. Soap will not lather or form suds with water until all the lime and magnesia are precipitated, for the principal action of soap is that of softening water, and, in making the test, we take advantage of this fact by adding the standard soap solution to known volume of water, until a permanent lather is formed.

A part of the carbonates of lime and magnesia may be removed from water by boiling, also a portion of the lime sulphate, if it is present in considerable amount. The number of degrees of hardness removed by boiling is called temporary hardness; that remaining, permanent hardness. From this it will be readily seen why exhaust steam heaters fail to complete the work, for, at best, they can remove only the temporary hardness, leaving chlorides, nitrates and the greater proportion of the sulphates to pass on into the boiler, where scaling and corrosion take place. Of course it is impossible to use an exhaust steam heater to purify water in condensing plants. When hard water is used in steam boilers, the heat drives off the carbonic acid, precipitating the carbonates of lime and magnesia. This takes place at 212° F. for an interval of two or three hours.

Furthermore, the continual evaporation of water in a boiler concentrates the impurities, until finally a point of saturation is reached. This, combined with the heat of the high-pressure steam, causes a precipitation of the sulphates of lime and magnesia together with some of the more soluble impurities.

These are called the scale-forming impurities, because a crust or scale forms or accumulates wherever the hot water comes in contact with the metal. This scale is built up of thin layers of precipitated lime, magnesia, silica and iron. On the inside of the boilers it covers the tubes and plates, generally being thickest where the circulation of the water is least.

The consequences are generally serious, because the scale is a non-conductor of heat; carbonates of magnesia having a relative value of from 0.67 to 0.76 as non-conducting materials (felt or wood being taken as 1). It is claimed that the conducting power of iron is about thirty times that of saturated scales.

While it is true that the well-known "Tables of Loss of Fuel Due to Scale," printed and circulated by manufacturers of scale preventatives, are very much exaggerated and probably entirely incorrect, still it has been proved by practical experiments that a metal is heated to much higher temperature in boiling water if it is covered with a non-conducting material than if the metal is clean.

If a boiler is heavily incrustated with lime, there is great danger of overheating the metal, because the water is not in immediate contact with the steel and cannot carry off or absorb the heat from the plates. The boiler, being under pressure, the overheating of the metal results in a stretching of the plate, forming a "bag," or the metal may blister and crystallize, and this will very much reduce its tensile strength, rendering the boiler unsafe.

This means that repairs are necessary. Even in cases where the metal does not get hot enough to bag or blister, it expands unequally, destroying the seams and joints between the several parts of the boiler, thus causing leaks, which in time become serious enough to put the boiler out of use.

Even where no disastrous results follow, much labor upon the part of the engineer in charge is necessary to keep the scale from accumulating. The scale is usually very hard, and can be removed only after considerable hard work. The continual hammering and chipping necessary for this is injurious to the metal, and, even if the cleaner's intentions are the best, it is impossible to reach and clean all parts of the return tubular boiler.

HEATERS AND MECHANICAL PURIFIERS.

The boilers are not the only part of the steam-generating plant affected by the impurities of the water. A deposit of a part of the carbonates of lime, magnesia and iron takes place as soon as the temperature begins to rise, which is when the water reaches the exhaust steam heaters. The first heaters built consisted of a coil or a number of pipes enclosed in a metal housing. The water was pumped through the inside of the pipe, and the exhaust steam in the chambers surrounding it heated the water. Used in places where the water contained only a small amount of lime and magnesia carbonates, no trouble was experienced; but when this type of heaters was tried to heat waters containing a large amount of lime carbonates, as do our western waters, these heaters were rendered useless in a very short time. The water passages through the pipe became clogged, and no water could be forced into the boiler.

Because of the fact that the carbonates are partially precipi-

tated by the heat of the exhaust steam, heater manufacturers have called their exhaust steam heaters "purifiers," and have so modified them that they can be readily cleaned.

The same trouble arises in plants using economizers, or heaters through which the water passes after it leaves the exhaust steam heaters and before it reaches the boilers. These get their heat from the waste gases of the furnaces, and it is very important that their surfaces be cleaned and kept so, without involving great labor and expense.

The exhaust steam heater, as purifier," has helped the trouble only in part, because the sulphates, which form the hardest scale, are not precipitated at all at the comparatively low temperature of the water from an exhaust steam heater; for that reason they pass on to the boiler and collect on its surfaces. To remedy this, a second tank, like a boiler, filled full of pans or shelves and heated with live steam from the boiler, is tried.

Into this receptacle all the water passes before it finally reaches the boiler. By carrying this heater at boiler pressure, the water becomes hot enough to start the precipitation of its sulphates. This is not an instantaneous process, but a gradual one, and it continues after the water has reached the boiler. Of course the efficiency, in all mechanical purifiers depending upon heat, is proportional to the length of time during which water is subjected to the heating or purifying process. In practice the water is never thoroughly purified in exhaust or live steam purifiers, because the heater is usually so small that the water passes through it in too short a time to complete the precipitating process.


Sulphate of lime is said to be completely insoluble at temperatures above 300° . This is true, provided there is a certain amount of it in the water.

Analyses of water from the blow-off valves of boilers show that the sulphate of lime in solution is as high as 25 grains per gallon, even when the temperature is far above 300° . From this it is evident that it is due to the concentration as well as the heat that the sulphate of lime precipitates in the boilers, forming scale. Concentration does not take place either in exhaust or in live steam heaters.

The introduction of soda ash into the feed water in an open heater has been tried, and, where the character of the water is not bad, this method has helped somewhat; but where the water contains the average amount of impurities, it is of little or no advantage, and, as far as we can discern, the soda ash might just as well be fed to the boiler direct, for the average heater is so small that it is impossible for the precipitation to be completed then.

To show that this is true, we will take water of an average condition, say 14 grains of carbonate of lime to the gallon, and 1000 horse power boiler plant evaporating 100,000 gallons of water in twenty-four hours for a six-days' run. That means about 7,500,000 grains or 1000 pounds, or 5 barrels, of carbonate of lime. Of course, no 1000 horse power heater ever had that quantity of residue in it at one time, because it cannot get all the lime of the water in that way; and, were the heater allowed to run long enough to accumulate that amount, it would become clogged so that the water could find no egress to the feed pump.

Except in the case of waters low in scale-forming matter, this method is attended with many objections.



WATER-SOFTENING AND PURIFYING PLANT, CLARK'S PROCESS.

At the Crawford, McGregor & Canby Company's Works, Dayton, O.

First. There is the mechanical problem of disposing of the voluminous precipitate which hard waters give up when they are properly treated.

Note the above that even 14 grains of carbonates per gallon mean 1000 pounds at the end of a week's run of a 1000 horse power plant, and this does not include the sulphates or chloride precipitated by the soda ash.

Second. The heater, of course, can be cleaned advantageously only when the plant is shut down. Carbonates precipitated by heat cannot be blown from a pipe, as can those precipitated by a chemical treatment.

Third. The purifiers operate upon the continuous process plan, feeding a soda-ash solution into the raw water; the result is that the feed pump fills with precipitated lime, and this either decreases the supply or shuts it off completely. If larger feed pipes are used, too much ash goes to the boiler, and the water foams. The average engineer has too much to do to nurse the feeds, so that they are out of order about half the time, and no better results are obtained than with a plain exhaust heater.

In the above-mentioned 1000 horse power installation, with the use of a water-softening plant of the intermittent type, the cost of precipitating the carbonate of lime would be less than \$2.50 per week, which certainly is much less than the expense of removing 1000 pounds of lime from an open heater, to say nothing of the important fact that the open heater would fail to accomplish the desideratum, whereas the water-softening plant would accomplish it.

Innumerable other mechanical devices have been tried to overcome this trouble, such as skimmers, surface blow-off, etc. Notwithstanding all these efforts, scale continued to form on the plates and the tubes of boilers. There seemed to be another way, and that was to supply to the hot water in the boiler itself a remedy which would keep the scale from hardening.

BOILER COMPOUNDS.

Mixtures known as "boiler compounds" have been used for years. These are generally composed of soda in combination with some organic acid, such as tannic acid, acetic acid, etc. All of these acids are said to corrode the metal and to be positively injurious to the boiler. Almost everything has, at one time or another, been put into a boiler to keep the scale soft, such as oak bark and shavings, because of the tannic acid they contain; distillery slops, on account of their acetic acid; potatoes, corn, etc., for their starch, leather, slippery elm and manure, for the gelatinous matter; molasses and sugar, because of the saccharates of lime formed. Innumerable other substances have been used without judgment or reason.

Prof. Robt. H. Thurston, in his "Manual of Steam Boilers," page 463, says that logwood, hemlock and other woods are sometime employed, but are apt to injure the iron of the boilers, as may acetic or other acids contained in the various saccharine matters, which also make the lime sulphate scale more troublesome than when clean. Organic matter should never be used.

From a chemical standpoint the most efficient boiler compounds are trisodium phosphate and fluoride of sodium. With these, when the water is heated, both carbonates and sulphates of

lime and magnesia are precipitated as phosphates or fluorides, which do not harden upon the tubes and shell. The principal objection to them is the cost of using them in quantities sufficient to remove enough of the scale-forming matter to be of benefit. There are two reasons why they are expensive. The chemical equivalent of these compounds makes it necessary to use one pound of trisodium phosphate to precipitate either 0.9 pound of carbonate of lime, or 0.77 pound of carbonate of magnesia. One pound of fluoride of sodium is required to precipitate 1.19 pounds of lime carbonates or 1.6 pounds of lime sulphates; and its cost, at present writing (1901), is about two and one-half times as much as that of the trisodium phosphate.

One pound of caustic lime will precipitate 1.78 pounds of lime carbonate, or nearly twice as much as will trisodium phosphate, while its cost per pound is about one-eighteenth as much, or it will remove one and one-half times as much carbonate of lime as will fluoride of sodium, which costs about forty times as much per pound.

Therefore, with the same expenditure of money, caustic lime will precipitate about thirty-six times as much carbonate of lime as will trisodium phosphate, and about sixty times as much as will fluoride of sodium.

Because of the cost, the amount of either trisodium phosphate or fluoride of sodium put in boilers is but a small percentage of the true amount necessary for complete precipitation of the scale-forming matter. That part which is converted into a phosphate or fluoride of lime or magnesia, mixes with the heat-precipitated carbonates, and mechanically prevents them from getting very hard, although they do not or cannot prevent the remainder of the lime carbonates from precipitating by heat.

Another reason why the large amount of these compounds necessary for complete precipitation cannot be used is because too frequent blowing off is required in order to prevent the water in the boilers from becoming saturated with soda by the continual concentration of the impurities and the continual addition of the compound.

The vegetable boiler compounds consist of sugar and tannins mixed with slippery elm or powdered wood pulp to furnish a soluble starchy substance. The tannins convert the carbonates into saccharates, which are blown out. One pound of tannic acid is required to precipitate one-seventh of a pound of carbonate of lime, and one pound of saccharic acid will precipitate about five-eighth of a pound of sulphate of lime.

Comparing these chemical compounds with a proper water-softening treatment, it is readily seen what a large amount of wholly unnecessary foreign matter must be put into a boiler in order to form a small amount of lime sludge which will not harden on the tubes and plates, even if no other objections arose.

It should be clear to anyone why boiler compounds fail to keep a boiler free from scale except in waters containing a very small amount of incrustating solids, such as some surface waters from rivers, lakes, ponds, etc.

Kerosene oil, which is used extensively, is entirely mechanical in its operation. It does not convert any of the scale-forming material into a non-hardening condition, because there is no chemical change; but owing to its light, volatile nature, it penetrates a porous scale and tends to disintegrate it. When the boiler is cold, the rotten scale partially breaks off from the metal, and is removed when the boiler is opened. It is the appearance of the rotten scale which makes it seem as if the boiler must be clean, whereas actually they are quite dirty, for but a small portion of the total amount has been removed. The volatile nature of this material prevents its use in any place where a pure steam is required, and it should never be used where a steam-heating apparatus is employed, because the volatile hydrocarbon distilled causes leaks at joints, fittings and valves.

WATER SOFTENING.

The process known as water softening, based upon the exact quantity and chemical character of the impurities, offers the relief desired. It is a method based upon accurate chemical knowledge, and it does not depend upon the change or imagination of any man to prove its efficiency. A chemical process involves an expense due to the reagents used; therefore, in order to keep down the cost to a minimum, only the cheapest and most efficient reagents can be employed.

The Clark process of precipitating carbonates of lime and magnesia by means of caustic lime is undoubtedly the cheapest chemical method; that, combined with soda-ash treatment for the sulphates and chlorides, makes it possible to get a clear feed water low enough in scale-forming to fulfill all requirements.

True water softening is an exact process. By this is meant that the exact amount of caustic lime must be put into the water to remove all the carbonates of lime and magnesia present; and the exact amount of soda ash used to decompose all the sulphate of lime and chloride of magnesia. No more, no less.

If it is desired to run at the lowest possible cost for operation, the method of treating the water and the apparatus used must be so simple that a man can operate it who has no knowledge of chemistry, and of whom nothing but mechanical work is required.

The apparatus which has been designed to accomplish this may be divided into two classes, viz., the intermittent and the continuous.

The apparatus designed for the continuous process consists usually of a steel settling tank, in which the water, after the addition of lime and soda water, is made to flow through spaces between series of intercepting plates in order to effect a mixture of the reagents with the water, which then passes to the bottom of the tank through a pipe, and thence rises again nearly to the top, where it overflows in a continuous stream.

Exact and uniform treatment is difficult to obtain, especially in our turbid western waters.

First. Because the amount of caustic lime or of soda ash dissolved in a gallon of solution may vary.

Second. Because the change of pressure may vary the amount of raw water supply, changing the whole character of the effluent.

Third. Because it is a difficult matter to keep uniform the amount of the chemical solution flowing through the small orifice into the raw water.

Fourth. The interior pipes or openings are likely to become incrustated, causing a variation which effects the results.

Fifth. Because no machine yet built will regulate the amount of lime and soda in the same proportion as the amount of raw water flowing through the machine, when the demands are irregular. At certain hours of the day (during the peak of the load) the demand for feed water is often triple that of other times.

The intermittent system consists of two or more settling tanks, provided with agitators in order to thoroughly mix the lime and soda with the water in one tank, after which the water is allowed to settle while the water in the other is being treated or being drawn from it. For drawing off the clear water, use is made of a pipe on a movable joint near the bottom of the tank, its other end being supported near the surface by a float. By this means clear water may be drawn by the time the precipitate has settled a few feet. In this machine water can be softened with great accuracy and uniformity.

This plan is the original one, and for certain demands is the cheapest. The principal objection to it is the ground room it occupies. The necessity for using very large tanks has been overcome by using a filter to mechanically remove the floating lime sludge, which does not completely settle in the time allowed in small

tanks. This plan is in no sense an obsolete one, for plants are being installed at the present time in England and in this country among the largest manufacturing concerns, and for use in city water works.

To some the settling tank plant may seem crude in comparison with the more elaborate plants working upon the continuous process. The expensive continuous water-softening plants are not necessary for good softening, and generally they are more difficult for the average man to operate satisfactorily.

On account of the expense of installing the plant, the continuous process is the only method which can be used where very large quantities of water are to be softened; that is, in plants furnishing two million gallons a day or more. In order to get satisfactory results from a continuous process water-softening plant, it should be in charge of a man who is expert in handling such apparatus, or where the services of a chemist are constantly available.

Among the many advantages of the intermittent settling-tank plant are:

First. The absence of automatic chemical feeds.

Second. It can be operated by the engineer or his assistant, without interfering with their regular work.

Third. A constant quantity of raw water is collected, to be treated with a uniform amount of chemical reagents. By this plan an excess or insufficiency of chemicals is avoided, and, therefore, a uniform character of softened water is furnished, while the simplicity of the apparatus enables an unskilled workman to obtain as good results as an expert chemist.


Fourth. The mechanical stirring, resulting in an agitation of raw water with the chemicals, insures an intimate mixture, and very materially hastens and soon completes the chemical reaction.

Fifth. The sludge of previous purification, which has settled to the bottom of the tanks, is mixed with the water by the action of the mechanical stirring device. This insoluble matter, moving in the water, gathers together the new, finely divided precipitate of lime and magnesia. This aids the chemical reaction, and hastens the settling and clarifying of the water.

Sixth. The sludge, collected in the settling tanks, relieves the filter beds, so a filter can be run five or six times as long without cleaning as would be the case were all sludge intercepted by the filters.

Seventh. Inasmuch as these settling tanks do not usually require washing or emptying oftener than once a week, the amount of waste water, required for cleaning or removing of sludge, is a very small percentage of the total amount purified.

Eighth. The water must stand for some time to permit of a complete chemical reaction between the softening agents in the water and the chemicals added to it. If the chemicals are not allowed



WATER SOFTENING PLANT, FAYAWANDY IRON AND STEEL CO., NORTH FAYAWANDY, N. Y.

that no chemical reaction is instantaneous. If iron and magnesia are not completely removed in the purifying processes, they are sure to precipitate in the pipes, heaters and boilers.

Ninth. The perfect quiet of the water gives an opportunity for complete settling, and renders the unfiltered water clearer than that from any other apparatus not using filters, or that from exhaust steam heaters in which crude filters are placed.

Tenth. The operation of this apparatus is the method followed by a chemist in a laboratory, but on a larger scale and with minor modifications to suit conditions.

Eleventh. This arrangement of two settling tanks permits an accurate daily record to be kept of the amount of the water evaporated in the boilers. This feature will be appreciated by careful and economical managers of large steam plants who are watching their coal piles.

The tanks are made of wood, brick or steel plates, and are generally cylindrical. The size of these reservoirs depends upon the quantity of water required per 24 hours, and the condition under which they are operated.

For plants requiring up to 4000 gallons per hour, we advocate two tanks, each having a capacity equal to six hours' supply. In plants with 8000 gallons per hour, we use two tanks, each having four hours' supply, and in all sizes above 8000 gallons hourly capacity, we use two tanks, each having a two hours' supply.

The two-hour tanks require more frequent attention, but these may be placed in charge of a boy, who can operate them, under the supervision of the chief engineer, with as good results as a man.

They are filled alternately with hard water. The chemical reagents are mixed in a small tank placed upon the top of the settling tanks, and are washed into the water while the tank is filling. A mechanical stirring device, consisting of a paddle revolved by suitable gearing, and operated by hand or liquid power, depending upon the size, mixes the hard water and the reagents together, at the same time stirring up from the bottom the lime sludge of the previous purification. This floats in the water, hastening the chemical reaction, and causes the new, finely divided carbonate of lime precipitate to gather into large flocculent or woolly flakes, heavy enough to settle quickly as soon as the water stops moving.

This paddle-stirring device is the simplest and the cheapest in the market. With reasonable care it cannot get out of order; it does not have to be cleaned to keep it in working condition, and does not require a large quantity of high-pressure steam to operate it. It should be run by a belt, carried from a shaft in the building, or by a small, independent steam engine or electric motor.

The power required varies from 1 to 3 horse power, so that the amount of steam consumed for this power is extremely small. By

exhausting the steam from the stirring engine into the coil pipe in the settling tank, the water becomes slightly heated. In cold weather this prevents it from freezing, and at all times hastens the chemical reaction.

The softened water is taken out of the tank by means of a hinged, floating outlet pipe, arranged to rise and fall with the level of the water, so that the clearest water is drawn from the top of the tank. By this arrangement a deep tank has all the advantage of a shallow one as a settling basin, because the water from the top carries the least amount of floating lime sludge into the filter beds, and in that way the filters can run the longest possible time without being cleaned, the time varying from three to seven days.

Inlet connections, through which to fill the tanks and wash the pipe connections, and to wash lime sludge from tanks, are placed in the bottom.

The washing of the settling tanks needs only to be done when the lime sludge becomes deep enough to interfere with the settling. The lime, once precipitated, does not redissolve in water. These tanks are cleaned once in four to six days, depending upon the amount of sludge collected. All that is necessary is to open the wash valve and start the stirring device to mix up the lime sludge, which is soft enough to run readily through pipe.

In small plants the sheet-iron chemical tank is placed on top of the settling reservoirs; in large tanks, at the bottom. In the latter case, a small centrifugal pump is used to pump the chemical solution into the tanks.

By using this simple plan, the chemicals are partially mixed with the hard water. The mixture is completed by the revolving paddles of the stirring device, which is started as soon as the filling of the tanks begins, and runs until the tank is full.

When pressure filters are used, the settling tanks are placed about three feet above the ground, but when open or gravity filters are used, the tanks are elevated about eight feet above the ground, or the filters must be lowered to allow water to flow into them from the settling tanks by gravity.

The instructions given for operating these plants are extremely simple, so that any man of average intelligence has no difficulty in understanding and using them.

When an old boiler is first fed with softened water, it must be opened every week until the old heavy scale is removed, otherwise there is great danger of the loose scale collecting on the fire sheets and burning the iron or causing a bag.

The water does not foam, provided the blow-off cock is used regularly, thus preventing a concentration of those impurities which cannot be removed by any purifying process or apparatus. The water has a less tendency to pit or corrode the metal than hard water, and a very small amount of combined carbonic acid. Its mineral acids, hydrochloric and sulphuric, are combined with soda, for which they have a strong affinity. The water is either slightly alkaline or neutral, but never acid.

This apparatus will render the most turbid waters clear, because the large amount of sediment found in some waters, which is so difficult to filter by a continuous-process plant, is, in this apparatus, the means by which the water is cleared. That is, the mud or sludge of previous purification helps to remove that of the new raw water, and at the same time it does not deposit on the filter beds, and thus necessitate frequent washing.

TESTING THE WATER.

Careful chemical analyses have shown that all waters vary in the amount of mineral impurities at different seasons of the year. This is especially true of surface waters from rivers, lakes, etc., but even upon waters from deep wells, the amount of rainfall has a marked influence.

For this reason, and also because the tanks may be filled to different levels, it is necessary to test the water in order to determine whether the correct amount of caustic lime is added to the hard water. To do this, two chemical solutions are used: one to show when not enough caustic lime has been added; one to show when an excess has been used.

We have proved by experience that there is no difficulty at all in the successful use of these test solutions on the part of any careful and reasonably intelligent man. The change of water is not a daily one, but rather one that takes place from week to week, and, by testing the water once every day or two, it can be kept uniformly satisfactory.

There is no satisfactory test that can be employed outside of a laboratory to determine the correct amount of soda ash, but a slight excess of soda ash is not objectionable, but rather beneficial for water used in steam boilers. Hence, when the water is used for that purpose, it is not necessary to test the water for this soda ash. All that is then required is to use enough.

Should any scale form in the boilers, its appearance and character will indicate, to an observant man, whether it is the sulphate or the carbonate of lime, and from this he should know whether it

is necessary to increase the amount of soda ash, and whether he is using enough of lime.

Equally important, with the selection of an efficient boiler, is the character of the feed water, and its treatment, so as to maintain the original efficiency that modern boilers give when in prime condition. Therefore, when a new boiler plant is installed, and when more than one source of water is available, it will certainly pay, in a majority of cases, to investigate each water, and so determine which is best for boiler use, and which will most readily yield to treatment and thus prove the cheapest.

In the city of St. Louis, where not less than ten cents is paid for each 1000 gallons of water used, and in other cities where a 50 per cent. greater tax is collected, it will, in many cases, pay to sink wells and treat the water thus obtained, which will seldom cost, for treatment and pumping, one-quarter of the price of city water.

COST OF SOFTENING WATER.

All carbonates of lime and magnesia, and iron are removed by caustic lime, which is also precipitated and removed along with the original impurities. By means of soda ash, sulphates of lime and magnesia, or chlorides of lime and magnesia are converted into carbonates of lime and magnesia, and hydrate of magnesia, which are precipitated, while the soda unites with the sulphuric and hydrochloric acids, forming the neutral sulphate of soda and chloride of sodium, which are soluble in water.

The caustic lime used must be as pure a calcium oxide as it is possible to obtain. A "fat" lime is generally of this character. A high percentage of magnesia, oxide of iron or silica, is objectionable.

The cost of treatment of water varies from one-third cents per 1000 gallons up, depending upon the character of the water.

The advantages of this method of feed-water purification are self-evident.

First. The water is softened while cold, and before it enters the boiler room; therefore, the feed pipes, exhaust and steam heaters and economizers are kept practically free from calcareous deposit.

Second. The softened water contains a very small amount of incrustating matter. Therefore the boiler can be operated many times as long without cleaning and does not collect a hard scale.

Third. When it is necessary to wash out a boiler it can be done for about one-third of what it cost before the water-softening plant was put in.

Fourth. The purifying apparatus can be cleaned advantageously while the steam plant is in operation, thus saving Sunday work or overtime.

TABLE SHOWING AMOUNT OF IMPURITIES REMOVED FROM WATER BY CHEMICALS USED IN SOFTENING.

One Pound of the Following Chemical	At Price in Cents per Pound.	Will Remove Following Amount in Pounds:					
		Carbonate of Lime.	Carbonate of Magnesia.	Sulphate of Lime.	Sulphate of Magnesia.	Chloride of Lime.	Chloride of Magnesium.
Caustic lime, 98%	4-13	1.75	1.5
Soda ash, 58%	.88-1.15	1.28	1.13	1.04	0.9

Fifth. The scale-forming matter in the water is reduced to that condition in which it can be gotten rid of, at the least possible expense: a small fraction of the cost of cleaning heaters or boilers.

Sixth. No boiler compound is required.

Seventh. An increased economy resulting from clean boilers.

Eighth. Less water used for cleaning, and less coal used for heating up the cold boiler and brickwork, due to less frequent cleanings.

TABLE OF COST OF PRECIPITATING 1000 GRAINS OF DIFFERENT IMPURITIES WITH DIFFERENT REAGENTS.

Reagent.	Cost of Reagent per Pound.	Carbonate of Lime.	Carbonate of Magnesia.	Sulphate of Lime.	Chloride of Magnesia.
Caustic lime, 98% pure.....	3-10c.	.0255c.	.0296c.
Soda ash, 58%.....	1-12c.167c.	0.243c.
Caustic soda, 74%.....	3c.	.3570c.	.4070c.
Trisodium phosphate.....	5c.	.7850c.	.928c.	.576c.	0.831c.
Fluoride of sodium.....	10c.	1.2000c.	1.430c.	.883c.	1.26c.
Tannic acid.....	5c.	4.5750c.	5.475c.

Ninth. The saving in repairs.

Tenth. The increased safety to life and property by decreasing the danger of explosion, either of boilers or of high-pressure heaters.

Water from which the incrustating solids and mud are removed before it reaches the boilers or heaters, so that not over 1 grain of lime carbonate and $1\frac{1}{2}$ grain of magnesia hydrate are found in a gallon of water, is in such a degree of softness, that not more than a "paper" scale will accumulate on the plates and tubes of steam boilers in six months of constant use, and but a small amount of soft deposit upon the pans of the exhaust steam heaters.

This is the condition to which a hard water can be brought by means of the Clark process. The figures show a plant on this system, erected in the works of the Crawford, McGregor & Canby Co., at Dayton, Ohio.

The following are analyses of well water, before and after softening in this apparatus:

ANALYSES OF WATER, BEFORE AND AFTER SOFTENING BY THE CLARK PROCESS, AT THE LOUISVILLE ELECTRIC LIGHT CO., LOUISVILLE, KY.

IMPURITIES GIVEN IN GRAINS PER U. S. GALLON.

	Raw Water.	Softened Water.
Silica	1.10	.40
Oxide of iron and aluminum30	.10
Carbonate of lime	16.78	.80
Carbonate of magnesia	1.80
Hydrate of magnesia	1.04
Sulphate of magnesia	9.90
Chloride of sodium	8.40	6.09
Sulphate of soda	6.00
Total	34.56	18.33

Take, for example, Michigan Lake water, the cost of softening which is 0.34 cents per 1000 gallons.

For a 100 horse power boiler, operating 12 hours and evaporating 4050 gallons, the cost of softening is 1.4 cents per day; cost per year (350 days), \$4.90.

With Lake Erie water the cost of softening is 0.80 cents per 1000 gallons; cost per day per horse power, 3.25 cents; cost per year, \$11.38.

DEEP WELL WATER FROM SOUTHERN OHIO.

IMPURITIES GIVEN IN GRAINS PER U. S. GALLON.

	Before Softening.	After Softening.
Oxide of iron630
Carbonate of lime	10.768	1.450
Carbonate of magnesia	4.777
Hydrate of magnesia870
Sulphate of lime	1.725
Sulphate of soda	1.862
Chloride of sodium	2.686	2.686

Total residue 19.981 grains. 6.172 grains.
 Hardness (Clark) 17.5 degrees. 3.0 degrees.
 Theoretical soap-destroying power,
 per 1000 gallons of water 26,000 pounds. 4,500 pounds.
 Cost of chemicals to remove temporary and permanent hardness, \$5.02
 per million gallons.
 Cost of chemicals to remove hardness only, \$4.35 per million gallons.

Where formerly it was necessary to open boilers for cleaning once in ten days or two weeks, and then the cleaning consisted in scraping, hammering and chipping the scale from the tubes, by the

use of softened feed water, a boiler will run from twice to four times as long, and nothing but a stream of water from a hose is necessary to clean the soft white sludge from the metal; this requires but a fraction of the time used for cleaning by the old method.

An exhaust steam heater will run about twenty-four times as long before it has an equal deposit on the pans. Where economizers are used, the softened water keeps these clean for the same reason.

When used in boilers heavily scaled, this softened water has a tendency to remove the old crusts, because no new deposit of lime and magnesia forms over the old crusts, thus cementing it to the metal while the boiler is hot. The unequal expansion of the metal and of the non-conducting crust loosens the latter, and it falls from the tubes and plates. The action is practically the same as that noticed when rain water or distilled water is used in boilers.

ECONOMY IN OPERATION OF 2000 H. P. STEAM PLANT, DUE TO USING WATER-SOFTENING PLANT.

COST OF OPERATION WITHOUT WATER-SOFTENING PLANT.

Cleaning five 400 H. P. boilers, each once in 2 weeks, 130 cleanings per year, at \$20.....	\$2,600.00
130 tons of coal, at \$1.30 per ton, to get steam on boilers cooled by cleaning	195.00
Yearly extra repairs on five boilers, due to bad water....	150.00
Boiler compound for five boilers, per year	300.00
	<hr/>
	\$3,245.00

COST OF OPERATING WITH WATER-SOFTENING PLANT.

Yearly cost of chemical reagents to treat 60,000 pounds of water per hour, at 7½ cent per 1000 gallons.....	\$551.88
Yearly interest 8 per cent., and depreciation 10 per cent., on \$4500	720.00
Yearly labor of operating plant, at 90 cents per day.....	328.50
Washing five 400 H. P. boilers, each once per month, or 60 washings per year, at \$8	480.00
60 tons of coal at \$1.50 per ton, to get steam on boilers cooled by washing	90.00
	<hr/>
	2,170.38
Saving by using softened water (about 24 per cent. on \$4500)	\$1,074.62

COAL ECONOMY.

2000 H. P. boilers evaporate 60,000 pounds of water per hour, or 1,440,000 gallons of water per 24 hours. Evaporation without purifier at 10 to 1 equals 144,000 gallons; 72 tons of coal per 24 hours, at \$1.50 per ton, = \$108 per day, or, per year.....	\$39,420.00
If evaporation were increased to 10.10 pounds of water per pound of coal, due to having boilers free from scale, 1,440,000 pounds of water should be evaporated each 24 hours with 71.28 tons of coal, at \$1.50 per ton, a yearly cost of	39,025.8c
	<hr/>
	394.20
Estimated saving about 32.6 per cent. on \$4500 investment	\$1,468.82

If the length of time between boiler washings can be increased eight or ten times over what was necessary before softened water was used and regular blowing down put in practice, and if it is found unnecessary to use scrapers or tube-cleaning machines at all, because no scale accumulates or builds up; if open exhaust steam heaters can be run from six months to one year without cleaning; if no live steam purifiers are required, and no boiler compound used, then by the use of softened water the percentage of idle capital is decreased, and the labor of cleaning boilers, heaters and purifiers is decreased.

A well-known engineer recently remarked: "We are far behind European steam users in taking advantage of the economy possible by keeping the interior of our boilers clean and free from corrosion." However, inasmuch as an increasing number of water-softening plants is being installed and successfully operated, we will soon lose our foreign reputation of being non-progressive in this respect.

But it must be borne in mind that the success of a water-softening plant depends upon the way in which it is operated. Therefore, the element of risk attending this part of its success should be as low as possible, and it has been demonstrated that the operation of the intermittent type is attended with less risk than that of any other.

**ON THE ENGINEERING DIFFICULTIES ATTENDING A
PROPER INSPECTION OF CEMENT.**

BY J. F. COLEMAN, MEMBER, LOUISIANA ENGINEERING SOCIETY.

[Read before the Society, April 8, 1901.*]

IN the various and multiform details which make up the duty of the engineer, a proper and intelligent inspection of the materials which enter into the structures built under his supervision is far from being the least.

In harnessing nature to the service of mankind he makes use of so nearly all of the products of mine, quarry and forest, in natural and in manufactured form, that it would be too much to expect that any one individual member of the profession could be qualified to pass judgment upon all of them except in a most general way, and largely for that reason we have become subdivided into various branch professions; and as the world grows on, and we grow with it, there will naturally follow resubdivisions, so that each class of works and materials, within certain limits, will of necessity have to be in the care of specialists in that class.

However, there are materials so generally used in nearly all classes of engineering work that each man of us all, in whatsoever special branch he may be, should have a working knowledge of them, for the reason that he is compelled from time to time to make use of them under circumstances which frequently preclude the possibility or feasibility of obtaining the judgment of others more experienced than himself. To one of these materials this paper would direct your attention.

Cement is a building material which has been in use for so many centuries that it may almost be said to be older than the engineering profession. With its proper mode of manufacture this paper has nothing to do, nor with its proper use. It would be presumptuous likewise to claim that this paper can throw new light on the testing question. It is intended only to convey to you an idea of the difficulties that have been and are being met by the writer in the testing and inspection of cements, with some few statements of what appear to him to be facts in connection therewith.

At first glance it would appear that concerning a material so old as cement our knowledge should be absolute and our data precise, and the beginner will no doubt think such to be the case until he has gone below the surface into the subject. After that, each step he takes, each new piece of information gained, each experi-

*Manuscript received May 17, 1901.—Secretary, Ass'n of Eng. Soes.

ment he makes, will but serve to make him doubtful of that which he thought was certainty before; and the deeper his research the less sure he will feel of his knowledge and its reliability. At least that is the experience of the writer, who has had more or less to do with cements for some ten or twelve years past, and who has carefully studied everything he could lay his hands on pertaining to this subject for the past five years, to say nothing of some laboratory practice.

Volumes enough to fill a large library have been written on the testing of cements. The various European countries have so-called "standard methods" for making tests, and we of America have also a standard. The subject has received for years past, and is receiving now, the best attention and most earnest study of the brightest minds in our profession in all countries. Nearly all the prominent engineering societies on the globe have standing committees on "cement," which make a special study of all the questions that relate thereto, collect all the writings on the subject and from time to time submit reports of such conclusions as may have been reached. And yet, with all this study and research, with all the literature on the subject from the pens of eminent engineers and others, the more deeply the writer has gone into this subject the less certain has he been of his conclusions or of the reliance to be placed in them, and the more "at sea" has he felt on the subject at large.

It should be understood, of course, if it is not already apparent, that this paper does not purport to be the work of one who lays claim to expert knowledge on the cement question, but is rather an *exposé* of the doubts and tribulations of one whose practice is not specialized in cement works particularly, and who therefore pretends to only an average amount of information on this important subject.

We all know, or can learn in very short order by reference to any one of the numerous text-books, the chemical constituents of the cements of the various classes. We know that the chemical analysis of one brand of cement of a given class varies somewhat from that of another in the same class, and that the analyses of the various classes are sufficiently marked to define them without serious trouble. We all have a general knowledge of how cements are manufactured, and we also know the approximate relative values of the several classes of cements; but there is not one of us who does know or who can absolutely determine the value of any given cement from a chemical analysis and a physical laboratory test occupying a reasonable time. There seems to be *no* test whereby the actual value of a cement may become known except the test of

usage and time, and in this respect each of us is dependent largely on his brother professionals.

If a sample of any unknown cement, no matter how valuable it may ultimately prove, be submitted to any engineer for use in an important structure, he would doubtless decline to admit it, irrespective of its chemical analysis or physical test. There is no question in my mind that he would be wise so to do, because of the dearth of any positive knowledge which would enable him to determine its value from any test that has yet been devised for laboratory use.

This lack of knowledge leads to a certain crudity in our specifications. For example, we require certain "fineness" tests, "tensile" tests, etc., but after these are all met by any sample of cement which may be submitted, we are still uncertain as to the merits of that cement unless we know that it has stood the test of usage and time, and that the laboratory tests of the same cement in the past have about coincided with the current test.

Cements have been manufactured that would pass the usual specification requirements and yet be unfit for use. Our tests not infrequently show better results for an inferior cement than for its superior. Samples taken from the same barrel of cement and sent to a dozen of the most accredited laboratories will show widely varying results. Briquettes made by two different men in the same laboratory, in as nearly the same manner as possible and from the same sample, will show considerable variation; and even those that are made by the same man from the same sample and at the same time have such a range of variation as to be bewildering to the seeker after certain knowledge. Of course it goes without saying that for any proper inspection of cements the engineer must be equipped with a testing machine, sieves, molds, etc., so that he may mold briquettes and break them as set forth in all the articles, papers and books that have treated the subject. The trouble is that after he shall have thus provided himself he has but opened new difficulties and doubts for himself. I know of a case in point: A sample was taken from packages of cement which were proposed for use in a certain piece of work. The engineer in charge was not personally acquainted with the brand, though he had heard of it, and it was well recommended to him by other engineers who had used it to their satisfaction. The cement was what is known as "natural," the specifications for which required, among other things, a tensile strength of 125 pounds, neat on seven-day test. The sample tested to 225 pounds under these conditions; the twenty-eight-day test was parallel, and the other tests set forth in the specifications were as fully met. The cement was admitted to use,

and was incorporated into part of the work under proper and careful inspection. In a short time it gave evidences of failure, and on being exposed showed practically no bond. Shortly afterward, the cement having been continuously used meantime on adjacent work which was under the supervision of another engineer and pronounced satisfactory by him, the gentleman whose experience I cite concluded to go further into the merits of this particular cement, as he had a great deal of confidence in the judgment of several of his brother engineers who had used it and pronounced it satisfactory; so he gathered new samples from a number of packages, divided the samples into several different parcels and sent them to as many different laboratories, requesting each of them to make thorough tests and to report not only the physical results, but the general conclusions arrived at. The laboratories referred to in due time reported most favorably on the cement. The test made anew by my friend on a part of the same sample showed results as nearly similar to his original findings as it was reasonable to expect; but upon again using the cement in question—this time under the most rigid personal inspection and with constant and careful continued testing—no better results were obtained. In this particular case the seeker after knowledge was no nearer the truth than he had been at the beginning, except that he had learned that the brand in question was unsatisfactory to *him*, in spite of the laboratory showing. On this state of affairs a difficulty arises. Here is a cement presumably manufactured and sold in good faith; it fulfills all requirements, in so far as laboratory tests go. That class of cements is a proper class for the work in hand, as evidenced by the fact that another brand of the same class, which does not stand the same laboratory test quite as creditably, is used in place of the rejected brand in the structure in question and does not fail. Other engineers who are without fear and without reproach use the brand and are satisfied with it, and yet it does not in *his* judgment serve its purpose at all. His conscientious judgment dictates its rejection, and yet he feels alone, or nearly so, in his position. He doubts his own conclusions, fears to do injustice to and work hardships on the manufacturer or dealer, and yet cannot conscientiously permit the use of that brand; all the while admitting that it fulfills all the specification requirements.

Now, for what purpose are engineering specifications intended? Is it not a fact that the engineer, by his plans and specifications, should seek to describe as accurately and completely as possible the work they cover in general and in detail, the manner of its execution and the matter with which it must be executed, the classi-

fication of materials, etc.? Does he not seek to describe the materials in such manner that there can be, in the mind of the bidder, no doubt as to what is intended in order that the bidder may intelligently estimate the cost of the work; and, further, that there can be no difference of opinion as to the intent between any two persons who understand such instruments of the engineer or architect as plans and specifications?

Whenever the specifications for any piece of work fail to so describe a given material as not to admit of a doubt as to what grade will be acceptable, they do not serve their purpose; and whenever such description as may be set forth in any specifications will clearly permit the use of a material which is unsatisfactory, that description is faulty.

We are but too willing and too prone to blanket over such imperfections as this last with the phrase "acceptable to the engineer," although in so doing we but stumble into the other fault mentioned; for who but the engineer can say what will be acceptable to him? In those materials concerning which we do have or can obtain absolute knowledge there can be no excuse therefore for such laxity of specifications, but there does seem to be some reason for it when we touch upon cement. Although such practice is far from infrequent, in the judgment of the writer it is not ethical in general to specify the "XYZ cement or equal," inasmuch as it makes a standard of a trade product manufactured by one concern. On the other hand, if we but specify that the cement shall be of a certain fineness, certain tensile strength, neat and sand, in specified time limits and the other usual requirements, without the saving clause "of a brand acceptable to the engineer," we bind ourselves tentatively to accept some new brand of unknown durability and value purely on a laboratory test, which, after all is said, counts for very little. Again, the results of different laboratories on the same sample vary so widely that when a cement is *near* to the requirements, either above or below in your own laboratory it may show far above or far below in some other laboratory; or if two or more be called on to test, one may be considerably above and another as much below your own results.

On one brand, for instance, some eighteen tests, made by four laboratories, on neat cement, seven days, ranged from 186 to 576 pounds. This is a very unusual and extreme case, but a difference of 150 pounds ranging between 350 and 500 pounds is by no means as rare as might be supposed. With such a state of affairs the engineer must bring his best judgment to bear on the cement question in order to get results; he can be bound by no cast-iron rules.

He must sometimes reject cements that fill the requirements of the specifications, and on some other occasions he could safely admit a cement that fails to come within the said requirements. Our specifications, then, are not precise and clear, but are merely a rough guide, and will so continue until such time as we have obtained more absolute knowledge.

For comparison and analysis I have formulated a tabulation showing the chemical analyses of five different cements, to which I would invite your attention:

CONSTITUENTS.	Domestic Portland.			Slag.		Portland.
	1	2	3	4	5	6
Silica.....	20.76	21.80	21.48	28.85	22.80	22.50
Oxide of iron	10.71 {	3.93	2.70	12.05 {	1.55	3.50
Alumina		7.23	7.74		14.10	7.00
Lime.....	63.42	63.12	62.22	51.20	46.10	61.00
Magnesia.....	2.89	1.88	2.95	2.27	3.65	1.25
Sulphuric anhydride.....	1.67	1.17	1.75	1.31	1.40	0.88
Loss on ignition.....	0.55	0.54	0.27	4.05	7.40	2.82

Nos. 1, 2 and 3 are domestic Portland cements; Nos. 4 and 5 are slag cements, and No. 6 is the average formulæ given by Candlot & Spalding for Portland cement. It will be noted that Nos. 1, 2, 3 and 6 do not vary very widely as to chemical constituency, and that the principal chemical difference between them and Nos. 4 and 5, which are slag cements, is that the latter run high on silica and low on lime.

Now let us compare Nos. 2 and 3, both Portland cements. These show very little difference, and that little would hardly seem to account for a difference in physical test. Records of No. 2 show an average tensile strength of 850 pounds neat on seven-day test, while No. 3 only shows 700 pounds. No. 3 is a well-known brand that has been in extensive use for a number of years; No. 2 is comparatively new, having been in use for only a few years. Both are usually acceptable brands, and yet I have been reliably informed within the past week that this No. 2 has recently been rejected by a most painstaking and experienced engineer for the work under his charge for reasons not stated.

It is plain that we cannot all be experts on cement or on any other one material; and if we are not experts, how can we pass intelligently upon the merits or demerits of the material before us?

It is an "old saw" that "a little knowledge is a dangerous thing," and while that saying is always more or less trite, it seems to be particularly so here.

Under present conditions we are likely to reject a good cement and use a poor one, and never learn that we have erred until too late to rectify the error.

As a broad general proposition, it might be stated that the only safe way to act on works of supreme importance would be to admit only brands of high standing that have been well known for years; to assure ourselves of the freshness of that which is used, and to test physically from time to time in order to assure ourselves that the cement has not been tampered with. An objection to this plan is that a virtual monopoly would be effected, since if all engineers followed this line it would not pay to establish new factories and to create new brands. The progress that has been so marked in the character of Portland cement in the past few decades would also be checked, as there would then be no incentive to improve or to seek to improve the present standards.

There is no reason to hesitate in prophesying the course of the profession on this question. We will continue in the future to do as we have done in the past, and occasionally, when circumstances and surroundings justify it, will "take chances" until the happy time arrives when the laboratory experts devise some sure and certain method of classifying cements by their tests so that the relative values may be absolutely gauged, without regard to brand or other trade-mark and without regard to past performances. In the meantime we may all at least hope that such a time is near at hand.

DISCUSSION.

MR. L. W. BROWN (by letter).—The variation of 50 per cent. or more referred to by the author between different laboratory tests of the same artificial cement is, to my mind, due to want of ordinary care on the one hand and to extraordinary care on the other in the manipulation and care of the briquette; and it may be observed that with the greatest care a difference as high as 20 per cent. will result between two laboratories testing the same artificial cement, due to difference in method of manipulation. But the great differences referred to unquestionably result from the improper and careless manipulation of the briquette, which is perhaps the most important part of the test and which is often done by the office boy or janitor.

I am of the opinion that if an engineer wants accurate knowledge of the cement he is using he must personally test it, and an engineer in charge of large and important works should be equipped and required to make these tests so as to nullify the element of carelessness and secure uniformity in manipulation. But such tests are

more for the satisfaction of the engineer than to secure any valuable results.

The value of laboratory tests was most clearly illustrated during the construction of portions of the drainage work in New Orleans, where the Drainage Commission arranged with Professor Creighton, of the Tulane University, to make the tests. As often happens, the results of the test were not made known until after the lot from which samples were taken had been used in the work, and when the results showed deficiency the work suffered; from which conclusions I feel justified in advancing the opinion that the testing of cement as it is used cannot result in any benefit, and may be the cause of serious trouble.

The American Society of Civil Engineers has for several years past endeavored to reach some standard for testing cement, but has as yet reached no definite conclusion; and the subject has received the deep consideration of the best minds in this country and in Europe. The conclusion reached is that the testing of cement embraces conditions wherein the slightest variation in manipulation causes wide difference in results, and the manipulation does not admit of the precision necessary to secure a satisfactory standard, as will be readily observed by the following parts of the manipulation wherein variation occurs:

How are samples obtained, and from what proportion of packages?

How are the samples mixed?

Proportion of samples made into briquettes.

Depth, diameter and size of wire of screen.

Length of time screens of different finenesses should be shaken.

Humidity of atmosphere.

Temperature.

Amount of water, and whether regardless of humidity of atmosphere.

Pressure in forming briquettes.

Fineness and angularity of sand.

Method of mixing.

Length of time the mixing should continue.

Method of filling the briquette frame.

Treatment of briquettes while setting.

Surface on which briquettes are formed.

Finish of briquettes, by trowel or otherwise.

Rate of applying load.

From this it is most apparent that no positive standard for laboratory tests can be made which will give any reasonable

uniformity of results. Hence other measures must be thought over, considered and, if satisfactory, adopted; and I would submit the following,—viz:

Artificial or Portland cement is susceptible of the same class of inspection at the factory as is steel, iron or machinery at the mills, foundry or shop. The proportion of the ingredients can be and are by the factory chemically determined in the slurry before burning, and the fineness is regulated by screens as the finished cement leaves the stones. The proper chemical analysis being determined, as also the fineness for certain results, the factory should sell the cement according to these different and known ingredients, coupled with the fineness, and the price proportioned to the value of the contained ingredients and their fineness. The engineer specifies the class of cement, and in the case of large works he places a competent man at the factory, the same as he does at the rolling mills, foundry or shop. The sack or barrel containing the cement of proper requirements is labeled and sealed, and if the seal is broken before reaching the work the cement is rejected. When the amount of cement required is small, arrangements can be made whereby the dealer, at small additional expense, has the cement inspected, labeled and sealed by any of the several reputable inspecting and testing firms.

The results from such inspection would far exceed in value any laboratory tests, and would remove the main difficulty attending the use of cement. The factory must necessarily give an absolutely true statement of chemical ingredients and fineness for the various strengths of their particular cement.

As to natural cement, it is understood that the product cannot possibly be uniform, and consequently it is not expected. Hence natural cement, no matter how satisfactory a test may be shown, should not be used on work where great stability and longevity are required.

The fluctuating value of cement is very largely occasioned by the manipulation of the mortar on the work where it is used, and is often the cause of failure of good cement: and it is obligatory, in order to secure good results, that the engineer should have means to ascertain positively the manipulation of not only one batch, but of every batch used on the work. The main points to be secured to provide good results in cement masonry or concrete are the angularity, fineness and proper proportions of sand and the proper amount of water. Too much water drowns the cement, and if applied in large quantities or under pressure has a tendency to separate the cement from the sand, so that the proper mixing is not

secured. The chemical analysis of the water should be known, and turbid water, carrying clay in suspension, should not be used. Thorough, complete and uniform mixing of the sand and cement is also very important. In fact, a poor cement properly manipulated will give better results than a good cement improperly manipulated.

EARLY TRANSPORTATION CANALS.

BY J. T. FANNING, MEMBER AMERICAN SOCIETY CIVIL ENGINEERS.

[Synopsis of a paper read before the Engineers' Club of Minneapolis,
April 15, 1901.*]

WE sometimes hear that canals are now obsolete, but at the last sessions of our National Congress there was offered a resolution relating to a proposed canal. That resolution, if passed, might have awakened a thrill among the nations like that of a proclamation of defiance to the world. Recent foreign news items have indicated that the German Government has considered most earnestly the desirability of constructing additional extensive canals, and also that the Russian Government has now in progress a canal intended to connect the Gulf of Riga and the Black Sea, a work not less in magnitude as an engineering work than is her Siberian railway. It is only about two years since Vice-President Roosevelt, then Governor of New York State, desiring to formulate and recommend a canal policy for the State of New York, appointed an eminent commission, and said to them:

"I desire the opinion of a body of experts, who shall include in their number not merely high-class engineers, but men of business, and especially men who have made a study of the problems of transportation; who know the relative advantages and disadvantages of ship canals, barge canals and ordinary shallow canals; who are acquainted with the history of canal transportation as affected by the competition of railroads, and who have the knowledge that will enable us to profit by the experience of other countries in these matters."

These suggestions indicate that the question of useful canals is still a living issue and indicates that the charge of obsolescence applies only to those canals whose usefulness has been outgrown through lack of their capacities. On close examination some of those old canals are found to have been stupendous works, which, for their day, were most creditable to their promoters, and may even now excite our admiration. They are, therefore, of historical interest.

Here followed a concise historical sketch of the *ancient lowland canals* constructed and used by the Chaldees, the hydraulic works of the Egyptians and the colonial hydraulic enterprises of the Romans.

Sluice Chutes.—If we keep in remembrance the fact that the early transportation waterways were without locks, and that sluice

*Manuscript received May 31, 1901.—Secretary, Ass'n of Eng. Soes.

chutes were used as substitutes for locks, we shall see clearly that those waterways could have been only works of the deltas and low countries. The Chinese have not yet modern locks on their grand or other canals, but they are said to pull their boats from one level up to slightly higher levels by the aid of windlasses, and with much expenditure of manual labor. Instead of locks they have guide walls at each chute, narrowing the canal to the width of their widest boats, and they use stop planks or timbers at the downstream end of the changes of canal levels and open the chute when a boat is to pass. This was the method in use in Italy before the idea of a gate at the upper end of the lock was conceived.

Straight-Edge Levels.—The old excavators of canals had not the advantage of a spirit level to aid them in laying out their works. The Romans are said to have used, in leveling, the straight edge of a plank about twenty feet long. At each end of this plank a frame depended, and on each frame a line was made at right angles to the top of the plank. While in use, the plank was so adjusted that plumb lines hung from the top of the plank would cover the vertical lines on the upright frames. The top edge of the plank was then level and could be used for sighting. In the top edge of the plank was a groove which was sometimes filled with water, and when the water was equally near the top edge of the plank at the ends, the plank was sighted along for a level line.

Canal Locks.—The invention of the second or upper gate, in connection with a canal chute, embodied the principles of construction of the modern lock.

This invention is claimed in Italy for two brothers Domenico, in 1481, and the State of Venice has claimed to have been the first to adopt the double gates. It is said that Leonardo da Vinci, famous as painter, architect, philosopher and engineer, adopted the Domenico scheme to connect two canals in Milan, by six locks with a total fall of 34 feet, and he has since often been mentioned as the inventor. He may have first so planned a lock that it became a practical and useful invention.

This lock, with upper and lower gates, marks a distinct advance in canal engineering; for canal boats that had heretofore been of service in the low and nearly level countries might now rise to the higher lands and proceed farther inland, and might even cross ridges of moderate height from stream to stream and from estuaries to elevated inland lakes.

To the Italian philosophers, Galileo, Castelli, Toricelli and their pupils we are indebted for much of the early experimental knowledge relating to the flow of water through orifices and small pipes

and over weirs, and for the early formulas developed from their researches; and, likewise, we are indebted to the Italian engineers for the methods of practical construction of transportation canals, on which boats might ascend from the lower to the upper part of a river valley.

The broad lower valley of the River Po, extending from the foot of the Alps on the north to the foot of the Appennines on the south, was in early times covered with a network of irrigation canals, and this valley became in consequence the fertile garden of Northern Italy. When the true canal lock was invented, the canal system extended up the valley of the Po above the city of Milan, and the Italians became the most skillful canal builders in Europe.

Foreign Canals with Locks.—In 1758 the English Parliament granted to the Duke of Bridgewater an act for the construction of a transportation canal between Manchester and Liverpool, and this canal was constructed under the direction of the eminent engineer Brindley. It is recorded that, in the middle of the last century, the cost of transporting goods by road between Liverpool and Manchester, about thirty miles, was forty shillings per ton, or about thirty-three cents per ton per mile. The Bridgewater canal reduced this rate to six shillings, or about five cents per ton mile. The result gave a tremendous impetus to manufactures and to mining in England, and started England on a period of most remarkable commercial prosperity that placed her in the front rank of manufacturing nations.

Following this beginning of water transportation from the Mersey harbor, England soon developed an extended canal system, opening important lines of internal navigation in various parts of the United Kingdom.

The Royal and Grand Canals in Ireland, ninety-two and eighty-five miles in length respectively, were originally works of much importance. They extended from Dublin, on the east, to Limerick on the west of Ireland.

The prominent industrial advancement of Belgium was largely due to the promotion of cheap water transportation. Belgium has maintained its principal waterways, and still derives great advantage from them. From Brussels, the capital, which is near the center of the state, there is even now a regular line of steamers to London.

Holland was known as the "Land of Dykes and Ditches" before she began to embank her lowlands from the sea. Her ditches still serve as public thoroughfares for navigation in summer

and for sledges and for skaters in the winter. The Haarlem Canal, surrounding the Haarlem Meer, a lake of about seventy square miles area, was originally excavated to facilitate the drainage of the Meer, and to furnish a transportation route to replace navigation upon the lake. The canal surrounding the lake is thirty-eight miles in length. Into this canal the waters of the lake were pumped with an average lift of sixteen feet, and the rainfall is still pumped into the canal. This area of seventy square miles is redeemed from below sea level for the benefit of agriculture and the enrichment of the state.

The canal works of the French engineers present some of the most scientific and substantial hydraulic constructions for transportation purposes of the early as well as of modern times.

The German and Russian engineers have also executed, in their respective countries, some important transportation canals that are worthy of special attention, but our time will not permit reference to them in detail.

Gustavas Vasa, in Sweden, is said to have been not less ambitious for the development of the resources of his state than was Peter the Great for the development of the internal resources of Russia. It was his desire that there should be continuous water transportation from Gothenburg, on the west, to Stockholm, on the east. Along the proposed route are the lakes Wener, Hielmar and Mælar, whose connecting streams have great cataracts. Several successive rulers, after Gustavas, examined anew this navigation project and partial works were undertaken from time to time. In 1806, Thomas Telford, the experienced and famous canal engineer of England, was called to examine and report upon the whole project. Telford's comprehensive plan was adopted and the work commenced. Sixty-five miles of the line required artificial work, and the remaining fifty-five miles were lake navigation. The summit of the canal is 296 feet above tide level. The plan showed 42 feet width of canal at the bottom and 10 feet depth of water. The locks were planned 120 feet long and 24 feet width. This was justly regarded as one of the most important public works in progress in the first decade of the late century, and this canal is still in service.

The Swedish Canal, connecting the Wener and Wetter Lakes, is of nearly equal importance as respects remarkable construction and extent of traffic.

American Canals.—Our own Washington, the surveyor and engineer, when a private citizen of Virginia, exerted a strong influence and gave his best endeavors to inaugurate a comprehensive

system of American internal routes of transportation both of public roads and canals.

As a surveyor, as promoter of the interests of his State, and then, in 1754, as commander of a military expedition, he became familiar with the trails from Chesapeake Bay and James River over the Allegheny Mountains to the Ohio River Valley, and with the portages from the Hudson River along the Mohawk and Oswego Valleys to Lake Ontario. Before 1776, a considerable migration of families from the Atlantic Coast colonies had started toward the fertile lands west of the mountains. The war of Independence then interfered with the advancement of projects for public highways. Soon after the close of the Revolutionary War, Washington is said to have obtained a charter for a water route between the Hudson River and the Great Lakes, and was elected the first president of the company. This was, however, but one of the efforts that later led the State of New York to undertake the greater waterway along a similar route.

At the opening of the new century, the farmers who had migrated from Massachusetts to Vermont were sending their produce to Boston by way of the Merrimac River, and the farmers who had migrated to lands known as Central New York were sending their produce to market by transports down the Delaware and Susquehanna Rivers in frail boats which were not expected to be returned up the rivers.

In 1805 Congress appointed three commissioners to search for the shortest and most desirable route for transportation over the Alleghenies, and, in 1808, Albert Gallatin made an exhaustive report to Congress upon the topography of the United States, and suggested a network of rivers, canals and roads, to be improved by the central government.

The necessity of cheapening transportation was at the same time suggesting private development of waterways by chartered companies.

The American canal-building era began with starting the constructions of the Middlesex Canal in Massachusetts and the Santee Canal in South Carolina in 1802. The Middlesex Canal was completed from the Charles River at Boston to the Merrimac River near Lowell in 1808. The era of the construction of old-style transportation canals continued until about the year 1840, at which date about 4000 miles of canals had been built in the United States, beside the important canal works of Canada.

In the New England States there were 227.69 miles of canal, of which the Middlesex, thirty miles long, and the Blackstone,

forty-five miles long, were most important. These two have gone out of use.

In the remaining Atlantic States there were 2526.77 miles of canals, of which the Erie, 363 miles length, and its branches, 365.75 miles in length, were the most important. The Erie Canal was commenced in 1817 and completed in 1825.

There were also, in the Atlantic States, the Delaware and Hudson Canal, 119.63 miles length; the Raritan, 42 miles; the Morris and Essex, 101.75 miles; the Lehigh, 84.48 miles; the Chesapeake and Ohio, 136 miles; the James River, 175 miles; the Dismal Swamp Canal, 23 miles.

A large part of the canals above enumerated are still useful in the transportation of heavy freights.

In Illinois there is the Illinois and Michigan Canal, on which there is still traffic.

In Indiana there is the Wabash and Erie Canal, 187 miles in length.

In Ohio there is the Ohio and Erie Canal, 307 miles in length; the Hocking, 50 miles; the Miami, 178 miles; the Sandy and Beaver, 76 miles; and the Mahoning, 77 miles in length.

Ohio, Indiana and Illinois have a total of 1086.9 miles, while Alabama and Louisiana have together 151 miles of canals.

The Pennsylvania system, extending from the head of the Chesapeake Bay to Pittsburg, was a combination of canal and railway, and that part between Harrisburg and Pittsburg was substantially adjacent to the route now followed by the Pennsylvania Railroad.

The Schuylkill and Lehigh systems were essentially slack-water navigations, involving many dams in the rivers and locks at the dams.

The Erie Canal and its branches, as first constructed, had generally a surface width of 40 feet and depth of 4 feet, and locks of 90 feet length and 15 feet width, and accommodated boats of 80 tons burden.

The Lehigh had a depth of 5 feet and locks 100 by 20 feet, and accommodated boats of 100 tons.

The Chesapeake and Ohio Canal had a depth of 6 feet and locks 100 by 15 feet, and accommodated boats of 150 tons.

The Illinois and Michigan Canal had a depth of 6 feet, and accommodated boats of 150 tons.

The Erie has been twice enlarged, and the New York State authorities are to-day discussing the proper amount of appropriation, whether \$22,000,000 for another moderate enlargement or

\$62,000,000 for a considerable enlargement of the Erie Canal prism and locks.

In January, 1900, the eminent New York State Commission, already mentioned, reported on two projects of enlargement. One project proposed to deepen the canal prism to 9 feet and adapt its locks to pass boats of 450 tons burden, at a cost of \$21,161,645, and the other project recommended was to deepen the prism to 12 feet and increase the locks so as to pass boats with a cargo capacity of 1000 tons each, at a cost of \$58,894,608.

The commission suggested pneumatic or other mechanical lifts at Cohoes and Lockport, as substitutes for the groups of locks at those sites.

Our limitations as to time permit only brief mention of the Canadian Lachine, Welland and Sault Ste. Marie Canals, because they should be classed among ship canals, and therefore not strictly within our present province. For the same reason we can only mention in general terms the American Sault Ste. Marie Canal, which surpasses all others in dimensions of locks and in amount of traffic.

Slide Gate Locks.—One of the first American examples of rolling lock gates was completed, in 1885, at the Davis Island dam on the Ohio River, five miles below Pittsburg. The lock is 600 feet long and 110 feet wide. Each gate is opened by rolling it into a pocket at one side of the canal. A quadrant gate is proposed for the head gate of the lock on the Mississippi River between Minneapolis and St. Paul. This gate is 80 feet wide, and is to be raised by pressure from the water above the lock, somewhat after the manner of operating bear-trap dams.

Inclined Plane Lifts.—For nearly three hundred years after its invention, in Italy, the two-gate lock was uniformly adopted in new canal constructions. Then inclined planes were introduced in a few high lifts. A conspicuous example in our own country is on the Morris and Essex Canal in New Jersey. This canal extends from the Jersey Flats through Newark and over the hills to the Delaware River at Easton. This canal has 23 inclined planes, with average lift or fall of 58 feet, thus covering 1334 feet of rise and fall, while an additional 223 feet of rise and fall is overcome by locks of low lift. The boats constructed for this canal were 8½ feet wide and 60 to 80 feet long, and of 25 to 30 tons burden, but not exceeding, with maximum load, 50 tons weight.

There were twin-lock chambers at each end of the incline, and a track similar to a railway track extended through the lower locks up the incline and through to the end of the upper locks. A truck,

similar to a railway platform car, but lower, was run into the lock before the boat entered. This truck was nearly as long as the boat, and rested at each end on a group of four flanged wheels. On top of each side of the truck floor was a truss to stiffen the floor. This truss extended a little higher than the gunwale of the boat. After the boat had entered the lock, it floated over the truck and was made fast to it. A chain, securely attached to the frame of the truck at one end, extended over a windlass at the top of the incline and to the twin truck. By aid of power, applied to the windlass, the car and boat were quickly hauled up or lowered down the incline, when the water floated the boat off from the car and the boat proceeded on its regular journey.

On the Chesapeake and Ohio Canal, an inclined plane high lift was constructed to pass boats from and to the Potomac River. This was located about one mile above Georgetown, and was of lift equivalent to the five locks at Georgetown.

The Monckland Canal, near Glasgow, has a conspicuous example of an incline sloping one in ten, and with a vertical lift of 98 feet. Each truck runs on twenty wheels, and its tank is 70 feet long, $13\frac{1}{2}$ feet wide and $2\frac{1}{4}$ feet deep. The weight of each carriage, with water and boat, is about 80 tons, and two are used, counterbalancing each other.

In the overland canal in Germany there are inclined planes on which boats of 50 tons weight are handled.

Another class of canal inclined planes in Germany is known as Greve's Lock. This consists of two inclined channels, side by side, sloping 1 in 10, with very smooth walls and floors. This double channel unites two canal levels, and has gates at the upper level. When a boat is to ascend, it is first floated into the foot of one channel, then a movable valve, mounted on wheels and of the full cross-section of the channel, moves up behind the boat and crowds forward a sufficient mass of water up the inclined plane to float the boat to the upper level. At the same time a floating boat may be similarly lowered in the twin channel. The two valves are connected together by a chain which passes over a windlass at the head of the incline. A small surplus of water on the side of the descending boat overcomes the frictions of the moving valves.

Canal Aqueducts.—The Chirk aqueduct, on the Ellesmere Canal in North Wales, is an excellent example of bold and skillful engineering. This work was planned by Telford, and was completed in 1811. This granite arched aqueduct of 10 spans and its high embankments cross the valley of the Ceriog River where the

valley is 700 feet wide. The water surface in the aqueduct is 70 feet above the level of the river.

The Dee aqueduct, on the same canal, is 1007 feet in length, and consists of an iron trough about 12 feet wide. This iron channel is supported by 19 arches and trusses on masonry piers. The surface of the water in the canal is 121 feet above the surface of the river.

The Seneca River aqueduct of the Erie system has 31 spans of 22 feet clear opening. The waterway is a timber channel 53 feet wide, with 6 feet depth of water. The tow-path is carried on 31 masonry arches.

On the Erie Canal there are two aqueducts over the Mohawk River. One of these is 1188 feet length.

The Genesee aqueduct, at Rochester, is of cut stone masonry. It is 804 feet long and has 11 arches.

The Delaware and Raritan Canal has 12 aqueducts, and the central and western divisions of the Pennsylvania Canal had a total of 49 aqueducts.

Canal Tunnels.—On the Leeds and Liverpool, in England, there is a tunnel 4920 feet long, 18 feet high and 17 feet wide.

On the Birmingham Canal there are several tunnels having an aggregate length of $6\frac{1}{4}$ miles.

There are several short tunnels on the American canals, and the layout of the Chesapeake and Ohio Canal contemplated a summit tunnel $3\frac{1}{4}$ miles long, passing through the crest of the Allegheny Mountains.

Canal Dams.—The Schuylkill River slack navigation involved the construction of 34 dams. The central division of the Pennsylvania Canal required 18 dams, and other American canals and their feeders have required numerous dams, some of them expensive.

Hydraulic Lifts.—Hydraulic lifts are another substitute for locks on transportation canals, and they have proved successful and are especially valuable as savers of lockage water and of time in lockages when there are great differences of level between two sections of the canal. One of the first successful lifts was at Anderton in England, for connecting the river Weaver navigation with the Trent and Mersey Canal.

In this lift there is a pair of metallic tanks, each of proper size to receive a canal boat and the water to float the boat. Each tank is mounted on a long vertical plunger of 3 feet diameter. Beneath the canal bed is sunk a long cylinder into which the plunger enters through a stuffing box, so that the cylinder and plunger constitute

a hydraulic ram or lift which, in this case, can move vertically 49 feet.

When a boat is to pass from a lower to an upper level, one tank is lowered, so that its floor is level with the bed of the canal. Its end is opened and a boat floats into the tank. The end is then closed, and the boat, still floating in the water-filled tank, is lifted 49 feet to the upper level. The gate at the other end of the tank is then opened and the boat floats into the upper level of the canal. At the same time another boat may have been lowered in the twin tank. The tanks are so arranged that the weight of one balances that of the other. There is a group of guide columns at each corner of the double lift and the tops of the columns are connected together by stiffening trusses. A tank girder at the top level for each tank, connects the lift tank with the canal in the earth embankment. A small pumping plant, near the base of the lift, gives the hydraulic pressure equal to 38 atmospheres, which sustains the rams. A small surplus of water in the descending tank overcomes the friction, and this slight difference in weight is secured by drawing a small quantity of water from the tank which is to ascend. This Anderton plant was erected in 1875.

The Les Fontinettes lift, near St. Omer, in France, and the La Louvière lift, on the Canal du Centre, in Belgium, are similar in character to the Anderton, but are larger and have two hydraulic plungers for each tank. There are substantial masonry guide piers at Les Fontinettes.

The lift tanks at Anderton are 77 feet long and 15 feet wide. They have 5 feet depth of water, and lift boats of 100 tons burden.

The lift tanks at Les Fontinettes are 133 feet long and 17 feet wide. They have 6.6 feet depth of water, and lift boats of 300 tons.

The La Louvière lift tanks are 141 feet long and 18.4 feet wide. They have 8.5 feet depth of water, and lift boats of 110 tons.

Their rams are respectively 3 feet, 6.6 feet and 6.6 feet diameter, and their vertical lifts are respectively 49 feet, 43 feet and 55 feet.

In the "Prussman" lock it was proposed to support a lift tank on five or more submerged cylinders under the lock. These cylinders were air-tight and contained sufficient air to support and elevate the tank containing the canal boat to be lifted.

Pneumatic Locks.—The Canal Board of the State of New York proposed to use pneumatic locks in the improvement of the Erie Canal, and designs for such locks were prepared by Chauncey Dutton, C.E., in 1895, for the Cohoes lift of 144 feet, and for the Lockport lift of $57\frac{1}{2}$ feet.

This system proposed also to employ metal tanks in which the boat is floated in water as it is elevated. The floor of the tank will rest on five or more inverted cylinders, like straight-sided bells, which are open at the bottom, but closed at the top by a tight connection with the tank floor.

When the lock tank is down, the hollow cylinders beneath the floor project into the water. When the lock tank is to be raised, air is pumped into all these inverted bells or hollow cylinders, which are so connected by pipes that there will be uniform pressure in all. The locks are in pairs, their pressure pipes are connected so that each may be equally buoyed, and each will sustain its tanks and floated boat. When the tank lifts are to change elevations, a little water is withdrawn from the ascending tank. A complete set of operating pipes is provided, with valves and controlling apparatus and with air and water pumps.

The proposed length of each boat tank is 310 feet, the water width 29 feet, and the water depth 12 feet. Each tank is expected to pass up, at one motion, two boats carrying each 1350 tons, or a total of 2700 tons of cargo, within ten minutes time between arrival and departure of the boats, and to pass down two similar boats at the same time.

Results.—The construction of canals has reduced costs of transportation of agricultural products and of merchandise of the lake districts from \$0.25 per ton mile on earth roads to \$0.00075 per ton mile along the water route which our Northwestern products now take to the Eastern markets.

These canal waters first made possible the full settlement of our lands on the western slope of the Appalachian chain, and then, together with lake navigation, made possible, by cheapening transportation, the settlements and agricultural developments of our Middle and Western States. In process of time they have made possible the sending of the grain and flour of the Northwestern to the Eastern States and to Europe.

These canals present some most admirable examples of skillful engineering. The story of the evolution of these American canals is also, in large part, the story of the evolution of the profession of civil engineering in America, and the record of our predecessors along this line is one to which we may turn with satisfaction, with professional admiration and with pardonable national pride.



Editors reprinting articles from this journal are requested to credit not only the JOURNAL, but also the Society before which such articles were read.

ASSOCIATION OF ENGINEERING SOCIETIES.

Organized 1881.

VOL. XXVI.

JUNE, 1901.

No. 6.

This Association is not responsible for the subject-matter contributed by any Society or for the statements or opinions of members of the Societies.

SUBAQUEOUS TUNNELS FOR GAS CONDUITS.

BY W. W. CUMMINGS, MEMBER, BOSTON SOCIETY OF CIVIL ENGINEERS.

[Read before the Society, April 17, 1901.*]

AT the first of the year 1899, in the distribution of its gas, the Massachusetts Pipe Line Gas Company found itself confronted by the problem of three river crossings: The Mystic River at Malden Bridge, Charlestown near Everett; the Charles River at the new bridge between Charlestown and Boston proper, and the Charles again at the River Street Bridge between Cambridge and Brighton.

The size of the pipe at Malden Bridge was to be 54 inches, that at Charlestown Bridge 42 inches and that at River Street 48 inches. It was necessary to avoid "pockets" in the pipe, which would tend to obstruct the passage of the gas by the collection of water of condensation, and to provide for the removal of this drip-page.

The pressure head in the tunnels, when passing gas, was liable to vary from 3 to 12 inches water column, *i.e.*, the problem was to keep the water out rather than the gas in.

The requirements of the State Board of Harbor and Land Commissioners were as follows: For the Malden Bridge the top of siphon must not be less than 23 feet below mean low water, and the clear width of draw opening must be at least 43 feet; for the Charlestown Bridge the top of siphon must not be less than 28 feet below mean low water, and the clear width of draw opening at least 50 feet; for the River Street Bridge the top of siphon must

*Manuscript received May 20, 1901.—Secretary, Ass'n of Eng. Socs.

not be less than 10 feet below mean low water, and the clear width of draw opening not less than 36 feet.

This gave a minimum cover of 7 feet at the Malden Bridge, and none whatever at the Charlestown Bridge or at the River Street Bridge, so far as the Harbor Commissioners were concerned. As a matter of fact, the legs of the siphons were placed farther apart than these requirements, in order to provide room for fenders and for working of the draw, while the least safe cover was about 8 feet of earth. It was also necessary to avoid obstructing the channel during construction.

It was necessary to take into consideration the future changes in these bridges, since, after once connecting the various gas companies, it would be disastrous to cut the supply.

This latter consideration barred the old Warren Bridge, located just above the new Charlestown Bridge, and rendered the River Street Bridge uncertain, while at that very time steps were being taken toward building, on the Malden Bridge site, a new structure, in which the location of the draw had a wide range of probability. The possible deepening of the channels had also to be taken into account.

At Malden Bridge a siphon in place would cost \$14,000, and the approach on piles (800 feet in length) \$15,000, fenders \$20,000, a total of \$49,000 from bank to bank. Bids were received from Charles Haskin for constructing a tunnel and laying the pipe for \$33 per lineal foot, the material to be furnished by the pipe line company. This made a total of about \$50,000 from bank to bank, as against \$49,000 for the ordinary siphon. This difference in cost was more than balanced by the advantages afforded by the tunnel, which would be practically indestructible, independent of the changes in highway traffic and navigation, and free from liability to accident and need of repairs.

At the Charlestown Bridge two siphons would have been necessary, if constructed in the ordinary way, at a cost of about \$24,000 and \$10,000 for the extra fenders, while the bids for a tunnel under the two draw spans was \$51 per lineal foot for driving the tunnel and \$11 per foot for laying the pipe and concreting, all material to be furnished by the Massachusetts Pipe Line Company as before, making a total of \$36,000, as against \$34,000 for the ordinary siphons. At this time the advantages of a tunnel were so obvious that it was determined to use that construction here also.

About April 1, 1898, the Malden Bridge Tunnel was started with a time limit for completion set at August 1 the same year, and

contracts were made for the completion of the other two a month later, September 1 being the time set for turning gas into the mains. As a matter of fact the Malden and Charlestown Tunnels were completed about December 1, 1899.

Three methods were suggested in the design of the tunnels. In all of these the tubular casing by wooden lagging (a method originated by the contractor, Mr. Charles Haskin, and described later) was considered.

One plan was to line the lagging with brick masonry laid under compressed air, and to lay the pipe or pipes on blocking, free and open to inspection, repair and possible future additions. Had the fluid to be carried been water instead of gas, the convenience undoubtedly would have outweighed the possible extra cost. As it was, the advisability of avoiding anything that might be converted into a gas pocket prevented such constructions, while the rigidity of the structure was best obtained by making it one solid piece, as by filling the space between the pipe and the lagging.

In sinking the shafts it was proposed to use ordinary sheathing until the water should be reached, and from that point to sink a steel tubular casing by means of compressed air.

At the Malden Bridge wash borings were made and compared with those of the Metropolitan Sewerage Commission, which had driven a tunnel a few feet to the east. It might be said here that in all cases these borings, although made by a responsible firm, were chiefly remarkable for their unreliability.

The first shaft was sunk on the Everett side of the Malden Bridge, as near the abutment as the retaining wall would allow. After going about 6 feet, the steel caisson was erected and sunk in the ordinary way (see Plate A, Fig. 3), paving stones being placed on the shelf at *a* and the excavation carried on under the cutting edge *b*. The casing was kept plumb by varying the excavation and also by such guides as might be used at the top. The caisson was extended by removing the air lock and inserting a 10-foot section, caulking the flanged joints when necessary.


This shaft was 46 feet deep 43 feet below high water, at which times, of course, the air pressure was about 23 pounds.

The steel casing, shown also in Plate A, was made of 38-inch boiler plates riveted to a 3-inch angle iron, which, with the corresponding angle iron of the next section, formed a flanged joint that was made up with red lead and caulked where necessary. The inner diameter of the tubing was 7 feet and the length of a section was generally 10 feet, each section weighing about 4000 pounds.

The cutting edge was made on the first section by placing a wide flange 2 feet back from the bottom and staying it with brackets as shown at *a*. On this shelf the paving stones were placed, to balance the upward pressure of the air and to furnish a downward thrust at the cutting edge. Stones, piles, sunken timber, etc., were broken up and taken out through the lock.

When material sufficiently compact to prevent the escape of the air was reached the sinking of the caisson was stopped, and the lagging was carried down the shelf, as shown in Fig. 4, Plate A.

This lagging consisted of circular segments 6 inches wide, sawn from 2-inch plank and having an outer diameter of 7 feet. There were eight of these segments to a ring, and they were



SHIELD USED IN DRIVING MALDEN TUNNEL, MASS. PIPE LINE GAS CO.

placed by spiking to the previous work with 7-inch spikes, each ring breaking joints with the previous one. This construction, which was the same as that used in the tunnel proper, was found to be exceedingly rigid.

A few feet above the point where the tunnel was to be started, the tubular form was changed and the "goose neck" was started. This consisted in constantly lengthening that diameter of the shaft parallel to the axis of the tunnel, on the side from which it was to start, until room enough was obtained to turn a 54-inch pipe, 8 feet long, into the tunnel by a method similar to that shown in Plate B, Fig. 5. In this goose neck the sides were necessarily flat, but, being surrounded by stiff clay at this shaft, they showed no sign of weakness. At the Charlestown tunnel, however, the material was sandy and the side came in.

The shaft was driven 6 feet below what was to be the bottom of the tunnel, and 4 feet of concrete were put in as a foundation of the pipe that was to make the leg of the siphon (see Plate C).

The shaft on the Boston side was then sunk in the same way, and the tunnel started from that end.

In driving the tunnel a shield was used similar to the Great-head design, as shown in Plate D. The excavation was carried about two feet ahead of the shield in good digging, and the latter was pressed forward by the hydraulic jacks *a a* bearing directly against the lagging. This served a double purpose, push-



PLATE G.

ing the shield forward and closing up the joints in the lagging, although, as the lumber was thoroughly dry when placed, it was found that the swelling of the wood made very tight work. The lagging was given a wash of cement after it was placed, and such leaks as showed were caulked with wooden wedges and yarn, and by feeding dry cement into the holes, the escaping air under pressure carrying the cement with it. (See Plate G.)

North of the draw the tunnel ran beneath an ice guard, as shown on the general plan, Plate C, and the bottom of the piles had to be cut off in the heading. This occasioned no great hard-

ships, while the driving was in clay, but about three-quarters of the way across the river a streak of silt and sand was struck, which, being only 7 feet thick between the top of the tunnel and the bottom of the river, followed the piles into the heading and stopped the work.

Poling planks were driven ahead, similar to those shown in Fig. 6, Plate B, and cut so that the ends could be worked back on the cutting edge of the shield. Gunny sacks, filled with horse manure, sawdust, etc., were thrust into the cavities, and, as soon as the holes were plugged, they were quickly plastered with clay. The material ahead was then excavated and the shield pushed forward. The surrounding material was so soft and unstable that the lateral movement of the shield was scarcely controllable, the whole structure moving toward the side that caved in.

As a whole, however, after the soft material was passed and the transit line extended, the headings met within 0.42 inch. The tunnel was allowed to fill with water and to remain filled for a few days, to give the woodwork a chance to swell and to permit the silt to pack about the lagging.

To a great extent this closed the remaining leaks, so that a No. 5 3-inch pulsometer easily kept the water down after the air pressure was removed. After pumping the tunnel out, a cross-section was taken, and this, compared with one taken before, showed that the tunnel had flattened about $\frac{1}{2}$ inch, thus proving that the lagging would not be permanent of itself.

In giving the line of the tunnel the distance between the shafts was triangulated and the direction transferred to the tunnel by means of two wires which passed through holes tapped in the air lock. This gave a base line about 4 feet long, which was produced into the heading by means of nails in the roof of the tunnel.

In this tunnel it was decided to lay pipe 54 inches in diameter, 8 feet long, with turned and bored joints, as shown in Plates E and F. The pipes were lowered in the shaft on the Boston side of the tunnel, turned on a pair of skids in the goose neck, the same as shown in Plate B, Fig. 5, and drawn through by an engine at the other shaft. A piece of timber was fastened to the tunnel, and the joints were forced home by a hydraulic jack which rested against it.

The joints were first smeared with sal-ammoniac, but it was found impossible to get them tight, as the turning was more or less irregular, and what sal-ammoniac was not washed off by the

water, refused to rust as it did on top. Instead of rust, a soft black coating formed on the metal, presumably due to the sulphuretted hydrogen which was present, and when this was wiped off the metal was left clean and smooth.

The leaky joints were caulked with copper wire, dry shingles, jute, cold lead and anything that best suited the particular leak, and the joints were filled flush with Roman Orchard cement. (Plate F.)

Between the pipe and the lagging was a space varying from nothing, where the lagging was cut out to improve the alignment, to 6 inches at a point diametrically opposite. This space it was proposed to fill with grout under pressure.

An expert with "experience" submitted a bid for doing this by forcing a mixture of lime and cement into the cavity. This was




PLATE F.

TAPER JOINTED PIPE USED IN MALDEN TUNNEL, MASS. PIPE LINE GAS CO.

SCALE 1 : 4.

guaranteed to do the work, the lime being "greasy" and acting as a carrier for the cement. Meanwhile the engineers made a series of experiments as to the action of different cements and mixtures under conditions similar to those on the work. In each case grout was made, and poured into a pan containing salt water. All the cements to which lime had been added remained like so much mud; some of the cements with high records caked like dirt, while some of the cheaper low-grade cements took a quick initial set, which, of course, was what was wanted in this case. It was found that one brand of cement, into which steam was turned, became soft and slippery like paste and set very quickly. A jet of steam, acting on the principal of an injector, was accordingly used, the grout being mixed in a trough at the top of the shaft and carried down by 1½-inch pipes. (See Plate C.)

In laying the 54-inch pipes, bulkheads had been built between the pipe and the lagging every 25 feet or more. Each length of this pipe had a hole for a 34-inch pipe tapped in its top, and into these holes the grouting pipes were successively introduced, the progress of the grouting being watched through the holes in the succeeding pipes, and these holes being plugged when the grout began to appear.

The steam jet was in the shaft, and as the reach from it to the introducing hole became greater and the time of changing forward became longer, the injector became plugged with cement and was finally abandoned, the pressure due to the height of the mixing trough being used and the pipe washed out with clean water after each succeeding run. When the distance became too great to get the desired pressure by this method, the grout was mixed in the tunnel and injected by means of a force pump.

From time to time the plugs were withdrawn from the top of the tunnel, and the grout cut through with a drill to determine its set and fill. The best results were obtained when the steam jet was used, the cement seeming to have swollen in setting.

Where the cavity was not entirely filled, the force pump was used to finish the work. In the shafts the pipes were concreted as fast as placed, the steel casing being left in.

In driving the tunnel the water was taken care of by two 4-inch pulsometers, and by two steam ejectors rigged tandem; that is, one at the bottom of the shaft and one halfway up.

On the completion of the tunnel the water of condensation and leakage amounted to $4\frac{1}{2}$ barrels per day.

The tunnel was finished December 1, 1899, and gas was turned on about December 3. The drippage decreases to $2\frac{1}{2}$ barrels a day in summer and increases to $19\frac{1}{2}$ barrels a day in winter.

The Charlestown Tunnel was commenced as soon as the air lock could be spared from the Malden Tunnel. The dimensions and form of this tunnel are shown in Plate H.

The shafts were sunk in midstream from temporary platforms, and did not differ materially from those of the Malden Tunnel.

For convenience in handling the water in working from both shafts at once, the summit was placed between the shafts. This tunnel was driven without a shield, under an air pressure of 28 pounds, the clay being stiff enough to maintain the heading except in one part where gravel was encountered in the roof. Here poling boards, horse manure, etc., were used, as in the Malden Tunnel, except that the poling planks were worked back on the

lagging when cut off, instead of the shield as in that tunnel. (See Plate B, Fig. 6.)

The goose neck was turned in less favorable material in this tunnel, and on removing the bracing the flat side broke in. After ineffectual attempts to patch it, a concrete lining was placed, as thick as would allow the introduction and turning of the pipe. These were common bell and spigot pipe, 12 feet long, and were made up with cement joints.

The pipe was placed in the shaft on the Boston side first, and the concrete was brought up to the top of the steel caisson. The tunnel pipe was then started at that shaft and laid toward the Charlestown side.

A 3-inch pipe, provided with open tees, was suspended in the roof of the tunnel, and each length of 42-inch pipe was concreted as it was placed. The concrete was mixed over the shaft and dropped through a chute to a car that ran inside the pipe already laid, and was then dumped, remixed and rammed by men standing alongside of the pipe. (See Plate I.) Around the joints the concrete was made stronger, and greater care was used to make it impervious to water.

When the pipes were all laid and concreted, the 3-inch pipe in the roof was flushed with grout.

The shafts were protected by circular fenders, and also by outer channel fenders as shown by Plate H.

This tunnel was completed about January 1, 1900. It is the best one of the three, the only objection being the necessity of pumping two drips.

In the River Street Tunnel, Plates J and K, the Brighton shaft was sunk 90 feet, and the Cambridge shaft 60 feet. It was commenced by sinking the Cambridge shaft without the steel caisson and running the tunnel in 80 feet without compressed air. At that point the clay changed to a vein of sand, and the heading came in, filling the tunnel for 40 feet and destroying the cross-section.

The Brighton shaft was then sunk to a depth of 90 feet before enough clay was found to turn a goose neck. The old shield could not be used, because it was not large enough, and on account of the scarcity of steel it would have taken too long to procure a new one. As matters turned out it would have been better to wait for a shield, but the borings seemed propitious and a heading was started.

The enormous head made 36 pounds air pressure necessary and also greatly increased the leakage, as much as 1,000,000 gallons daily being pumped by three Knowles 5-inch pumps.

After going a short way, the roof material changed to sand and continued so to the completion of the tunnel. "Cave-ins" and "breakdowns" were of everyday occurrence, and every incentive was used to keep the men at work.

Negroes were worked in one heading and white men in the other, pitted against each other as to courage and record; extra time was given and shifts shortened, but under the heavy pressure, with the temperature at 105° and the slow laborious methods necessary in the uncertain heading, progress was very slow, and it was only the indomitable courage of the contractor that carried the work to a successful completion.

The general method of procedure was as shown in Plate B, Fig. 5. Poling planks were driven ahead, a couple of feet of the sand was excavated, the surface was smeared with clay to hold the air and a bulkhead was thrown across. The clay bottom was then excavated, the lagging brought forward and a new start made in the sand. Progress was from one to three feet a shift in each heading.

The results in alignment were such that it was necessary to make two offsets of 2 feet each, to keep the transit line in the tunnel. Nevertheless the closing error was less than 0.05 foot.

The lagging was lathed and plastered with cement, and about 6 inches of concrete was placed in the bottom while the air pressure was still on. The air lock was then removed, and six 12-foot lengths of 48-inch pipe, with the drip, were lowered in the Cambridge shaft, the lock was replaced, and these were hauled through to the Brighton shaft (see Plate B, Fig. 5), where two lengths were supported in the shaft while the drip was set and concreted.

These two pipes were then set and concreted, and a 6-inch drain pipe was laid in the concrete connecting the tunnel with that part of the shaft above the pipe. The five other lengths were laid from the drip in the tunnel, and the 6-inch drain pipe was continued beneath them. Owing to the rapid rise in the tunnel, shown in Plate K, this had the effect of materially reducing the head, and when six more pipes were laid in the tunnel in the same way, an attempt was made to proceed without the air pressure.

There was too much leakage, however, for the three pumps in the Brighton shaft, and there was no room for more pumps. Moreover the pumps or their connections were continually breaking down and it was decided to lay the pipe under pressure.

The general methods were about the same as those used in the Charlestown Tunnel, except the plastering of the lagging, the

laying of the 6-inch drain and the handling of the concrete. The concrete was mixed on top, lowered through the air lock in canvas bags, twelve or sixteen at a trip, and wheeled to the point of laying in three or four barrows, four bags filling one barrow. As each man dumped his load, he wheeled his empty barrow into the pipe to make room for the man behind him.

The proportions of the concrete were: 1 cement, $2\frac{1}{2}$ sand, 5 broken stone. In two hours this set sufficiently to permit walking over.

As a rule three 8-hour shifts of 9 men each were employed in driving the tunnel, and progress was about three feet each shift.

In laying and concreting the pipe, there were two 11-hour shifts of from 11 to 13 men, averaging one pipe each shift. There were eight batches of concrete to each length of pipe. The men received 23 cents an hour when working under pressure.

The plant included 3 locomotive boilers, 2 upright boilers, one 5-drill and one 4-drill unjacketed compressor, and one 14-inch and one 10-inch jacketed compressor, one 6-inch and three 5-inch steam pumps at 75 pounds and 110 pounds steam pressure, respectively, three 3-inch pulsometers and two 4-inch ejectors.

As in the other tunnels, all joints on the inside of the pipe were filled flush with cement.

The cost of the Malden Tunnel was \$35.34 per lineal foot for driving the tunnel, \$15.50 per lineal foot for the pipe and \$4.80 per lineal foot for laying the pipe and grouting, or \$55.64 per lineal foot complete.

On the Charlestown tunnel the cost was as follows: Driving and fenders, \$87.45 per foot; pipe, \$4.35 per foot; laying, \$9.60 per foot; total cost, \$101.40 per foot.

The quantities were as follows: Concrete, 420 cubic yards; 42-inch pipe, 85 tons; cement, 260 barrels, at \$2.35 to \$2.75; sand, 200 tons, at 70 cents; stone, 600 tons, at \$1.

At River Street Tunnel the cost was as follows: Driving, \$48.84 per foot; laying, \$45.45 per foot; pipe, \$5.36 per foot; total cost, \$99.65 per foot.

The quantities were: Concrete, 560 yards; stone, 1303 tons, at \$1.10; sand, 97 loads, at \$1.60; 48-inch pipe, 169 tons; cement, 859 barrels, at \$2.35 to \$2.75.

Cost of labor on concrete in tunnel about \$5 per cubic yard. Cost complete of concrete in tunnel about \$9 per cubic yard.

While driving the River Street Tunnel, owing to its uncertain termination, it became necessary to lay a temporary pipe on the River Street Bridge and to sink a small siphon at the draw. A

20-inch pipe was, therefore, laid on the bridge, and a siphon, made from 12-inch threaded wrought iron pipe, was sunk through the bridge by cutting holes 4 feet square for the legs of the siphon, lowering them through and connecting up with the extension piece before sinking them into the water.

The whole work was done and gas was flowing inside of six days from ordering the stock. The little pipe was eminently successful, there being only a head of 1 inch water pressure lost in passing the siphon, and the pipe was easily removed when the tunnel was completed.

The amount of gas passed at that time was 2,500,000 feet per diem, and the pressure was 7 inches to 10 inches water column.

The choice between driving a tunnel and sinking a siphon is naturally governed by the location. Where the requirements of depth and width are great and the obstruction to navigation while sinking the siphon is serious, especially in the case of a double draw, the tunnel is cheapest in any ground. The same may be true of a single draw in good ground. Where the pipe, for any cause, cannot be supported by the bridge, and the approaches are exposed to ice and heavy shipping (a condition requiring strong fenders) and where the earth is propitious, it may be cheaper to tunnel the entire river, as was done at Malden Bridge.

Where the channel may be obstructed by temporary piling, and where the requirements as to preserving the channel are not burdensome, a siphon is undoubtedly the cheapest, as in the crossing of Island End River, now under way. It is needless to say that a tunnel is *always the best*.

In these tunnels it has been demonstrated that in good clay, and in good clay only, a tunnel can be advantageously driven without a shield under compressed air; that the segmental lagging, as used by Mr. Haskin, is an easy, economical and stable method; that breaks, even in bad ground, are neither necessarily dangerous nor prohibitively difficult; that a large tunnel, with concrete between the pipe and the lagging, although more costly than a smaller tunnel grouted, makes much tighter work; that turned and bored joints are a delusion and a snare; that it pays to point up the joints on the inside of the pipe with cement; that cement joints give the best results, and are the cheapest and most convenient; that lathing and plastering the lagging with cement, while under compressed air, is an advantage.

Mr. G. H. Finn is the general manager and Mr. L. J. Hirt was the chief engineer of the Massachusetts Pipe Line Company. W. E. Silsbee had immediate charge of the Malden and Charles-

town Tunnels, while E. C. Hayden had immediate charge of the River Street Tunnel.

DISCUSSION.

MR. HOWARD A. CARSON.—I have been very much interested indeed in the paper which has been read to-night. It recalls the experiences of myself and those associated with me some years ago when I was engineer of the Metropolitan Sewerage System. All that is ancient history now, but I refer to it at the request of the President and Secretary. The author has alluded to the tunnel crossing near the Malden Bridge beside the new gas tunnel. On that there were some interesting experiences. Mr. Haskin was connected with that. During one serious blow-out the men were compelled to leave the tunnel, and the whole tunnel was filled with water in about an hour. This tunnel was at one point so close to the bed of the stream that, among other experiences, was the finding of a human skeleton in the mud at the top of the tunnel.

The engineer of to-day, tunneling under deep beds of water, is very much more fortunately placed than those of a generation ago, before compressed air for tunneling was brought into use. You have all read of the various attempts which were made to build a tunnel under the Thames early in the last century, of the very slow progress and how several of these attempts were given up. A long time was used, seventeen years, in making the first successful Thames tunnel. The engineer now, if he has occasion to go under a stream of moderate depth, can make use of either of several processes.

In the work on the Metropolitan Sewerage System there were six passages built under tidal estuaries, "siphons," we called them; one on the outer end of Deer Island, about eighteen hundred feet into the sea; one under Belle Isle Inlet; one under Shirley Gut; one under the Mystic River, at the point spoken of by the author this evening; one under the Malden River, and one under Chelsea Creek. In two of these cases, Belle Isle Inlet and the Malden River, the cofferdam process was used. At Malden River, the cofferdam was quite successful; that is, there were no serious mishaps of any kind; the trench was flooded once, but there was no serious trouble. At Belle Isle Inlet, however, where the cofferdam was also tried, the process, as carried on, was very unsatisfactory, the trench being flooded many times. It was finally necessary to make use of somewhat novel processes for finishing up the work.

As most of you remember, a novel method was used at the outer end of Deer Island extending into the sea, and in crossing

Shirley Gut, in sinking and connecting large pipes made of brick and concrete. In these two cases, so far as rapidity and economy of the work was concerned, the results were superior to any of the other methods tried. At Shirley Gut the pipes were from 48 to 65 feet long and over 8 feet external diameter. They were made on the shore above high tide and moved down to low tide by means of blocks and rollers, as in moving houses. The ends were stopped up, so as to make the pipes water-tight. They were finally floated to their proper position, and methods taken to place them accurately on the bottom, join them together and afterwards remove the bulkheads.

Some allusion has been made to the East Boston Tunnel. I hope most of the members will visit this tunnel within a few days. The work has now progressed, by the shield, something like 240 feet. The work is temporarily arrested, to put in the air locks. Before the compressed air is used will be an excellent time for the members to view the whole situation. As you will learn all about it then, I will say now but a word for those who cannot go.

The general method employed there is almost precisely the same as that which was used on the subway tunnel on Tremont Street. There are two drifts about 8 feet square, made and timbered by an ordinary tunneling process. These drifts are about 30 feet apart horizontally, outside to outside. In each of these drifts one of the side walls of the tunnel is built. The shield of the tunnel is later moved along, running on top of and resting on these side walls. The arch of the tunnel is built under the tail end of the shield, and, of course, joins with the side walls just mentioned. The invert is put in later. The hydraulic jacks, which push the shield along, react against cast-iron rods imbedded in the masonry of the arch, the same as on Tremont Street.

The main difference between the Tremont Street tunnel and that of East Boston is that, in the latter case, the arch is of concrete, while in the Tremont Street tunnel it was of brick. The cross-section in East Boston is considerably taller. The arch, instead of being very flat, is a semicircle.

MR. C. M. SAVILLE.—The Metropolitan Water Board has just completed a small tunnel between Chelsea and Charlestown. The contractor for the gas tunnels also did the work for the water board, and many of the men were employed on all of the work. The methods employed on our work were substantially the same as the author has so interestingly described. Two water shafts were sunk, one on each side of the channel and about

140 feet apart. These shafts were about 65 feet deep, and connected at their bottoms by a drift under the channel. The net inside diameter of each shaft and drift was 6 feet, and they were lined throughout with a foot of brick masonry laid in Portland cement mortar. The same shield was used as has been described by the author, but it was remodeled to work the heading, which had a gross diameter of about 9 feet. The material encountered was mostly sand containing considerable water. Much difficulty was encountered in keeping the shield on line and to grade, and, after the drift was about three-fourths completed, the shield was removed and the remainder of the work was done with poling boards. After the tunnel was completed, a 24-inch ordinary cast-iron water pipe was laid in it by the maintenance department, and this pipe is now in use.

During the progress of the work, an article appeared in one of the Boston papers purporting to be a description of the methods employed, and among other interesting points brought out was the statement that for every pound of material excavated a pound of air was pumped in to take its place.

MR. ROBERT A. SHAILER.—I do not know that I have anything to say except that I have enjoyed listening to Mr. Cummings's paper on subaqueous tunnels.

I am sure that an ordinary mud digger like myself cannot be expected to have much to say of interest to this society, which certainly contains among its members very prominent engineers, probably the best engineers in the country.

In the paper just read considerable stress was laid upon the use of compressed air for the purpose of keeping out water, and the thought occurred to me that possibly you are not all familiar with the use of compressed air for the purpose of keeping clay from flowing or swelling, as it is usually termed.

We have been working for a number of years at Cleveland, Ohio, constructing a tunnel 9 feet inside diameter, with 12-inch brick walls and 26,000 feet long. The 22,000 feet already completed have been constructed through a very soft, swelling clay; in fact, a material which it would be almost impossible to handle without compressed air. It contains no water to speak of, and if any of you were to go into the tunnel under our usual pressure of 28 to 30 pounds of air, the clay would seem practically dry and quite stiff and hard, and it would be difficult to realize what it would be without the air pressure.

In sinking shaft No. 2, which is composed of cast-iron cylinders extending from above the surface of Lake Erie down nearly

to the top of the arch, which is at about grade minus 94, and then underpinned with brick, we had occasion to take the air pressure off, and where square openings like windows were left for the purpose of breaking out into the drifts, I have seen clay flow in through said openings and drop off in large chunks, while with the air pressure the clay appeared still and stable. Last fall, when one of the air locks in the tunnel got to leaking, so that the pressure was almost entirely lost, the clay flowed into the completed tunnel so as to nearly fill it up solid for some twenty feet.

Mr. Carson has just spoken of our being about to put on the air pressure in the East Boston Tunnel. We anticipate no trouble or danger from water in carrying on this work, but we do expect to have swelling clay, and it is to hold the clay that we are installing the pneumatic plant.

There is another use of air pressure in which we have had some experience, and that is for the dilution of explosive or marsh gas, as it comes into the tunnel.

At Cleveland the whole ground is saturated with this gas, and chemical analysis shows that even with great care we have from $\frac{3}{4}$ to $1\frac{1}{2}$ per cent. of this gas at all times in the air which the men breathe. If our pressure goes down, the percentage of gas becomes greater, so that we are reasonably sure that the use of compressed air tends to keep the gas out. The mixture of 5 or 6 per cent. of gas is exceedingly explosive, while a mixture of 9 to 10 per cent. is not. This may seem paradoxical, but it is true. What I have always feared is that, as the gas must flow into the tunnel practically pure, there must be, somewhere between that and its dilution down to $1\frac{1}{2}$ per cent., a point at which the mixture is dangerous. We therefore watch our electric wire connections, and take all the precaution we can and carry our inlet pipe straight up to the heading, so as to dilute the gas there.

Compressed air has been used to retard the flow of water into tunnels where the head was so great that sufficient pressure could not be maintained to keep the water out entirely. Under these conditions the work of necessity must be carried on very slowly and at great expense.

MR. W. W. CUMMINGS (by letter).—An inverted siphon possibly a little out of the ordinary line was placed in Everett, Mass., May 21. Its characteristics were its economy and its rigidity, notwithstanding its rather unusual length.

The Harbor Commissioners required that a clear waterway 60 feet wide and 18 feet below mean low water should be preserved.

The river bottom at this point is but 4 feet below mean low water, the channel as yet not having been dredged.

As shown by the drawings, the siphon was made up of a 30-inch riveted steel pipe $\frac{3}{8}$ inch thick, the legs being about 32 feet long and the extension piece about 74 feet long on centers; and an inclosing box 3 feet 6 inches square, made up of 6 x 6-inch spruce corner posts, with 3 x 4-inch sticks spiked to them for the nailing of the 2-inch cover planks.





It was designed to make the siphon as light as possible. Therefore the steel pipe was figured to be self-supporting when hung by the two legs, and only sufficient concrete was added to sink the pipe and its inclosing box. The sides of this box formed two trusses, calculated to support the box and the contained concrete when hung by the legs of the siphon, or to have sufficient excess of strength, when submerged and supported at its center, to make up the deficiency in the steel pipe when supported at that point. Particular care to secure an even bottom in the dredging was therefore unnecessary. The angles of the siphon were reinforced by $1\frac{1}{2}$ -inch tie-rods and two 6 x 6-inch struts bearing on pieces of angle iron.

The weight of the siphon complete was about 60 tons, or 900 pounds per lineal foot; and 9 tons, or 125 pounds per lineal foot, when submerged.



The pipe and the extension piece of the box were constructed on shore. These were then placed on temporary piling in the channel by means of a lighter, and concrete, composed of one part Star cement to one part unscreened fine gravel, was added after smearing the joints of the steel pipe with neat cement mortar. The legs of the box were then carried up, the concrete being added as the work progressed, and the whole was allowed to set for six days. Particular care was taken to make the concrete impervious to water. In placing the siphon, three lighters were used, one large one on one leg and two smaller ones on the other. When lifted free from the blocking, the deflection at the center was about $1\frac{1}{2}$ inches. The lowering consumed about two hours. When in place, the pipe was under a maximum head of 26 feet, and remained twenty-four hours without showing any leaks. It was then filled with water and allowed to settle to its bearing.

The whole siphon, with the exception of the 6 x 6-inch and 3 x 4-inch spruce timber, was made from the scrap pile at a cost of \$592.62. The material new would have cost about \$685, making a total new of about \$9 per lineal foot. The dredging cost \$1800, and the placing about \$600.

Without searching the records, it is believed that this is the longest and largest siphon in the vicinity, that of the Boston Water Department at the Warren Bridge being 24 inches in diameter and 55 feet long, and that of the Metropolitan Water Board at Saugus River being 20 inches in diameter and 48 feet 8 inches long. This latter one cost \$23 per lineal foot. It might be added that the siphon was subject to extremely rough usage while being lowered, but it was perfectly rigid and the concrete showed no signs of cracking.

SINGLE AIR LOCK
FIG. 1FIG. 3
SECTION SHOWING LAGGING

LONGITUDINAL SECTION

LONGITUDINAL SECTION OF TUNNEL
FIG. 5


END VIEW

STEEL CASING AND AIR CHAMBER
USED IN MALDEN TUNNEL
MASSACHUSETTS PIPE LINE GAS CO.


SCALE 1:48

METHOD OF CONSTRUCTION
IN THE
ALLSTON TUNNEL
OF THE
MASSACHUSETTS PIPE LINE GAS CO.


SCALE 1:48




GOOSENECK
FIG. 3




Piling planks




HEAD END
FIG. 5







"DRIP" FOR SOUTH SHAFT.




"DRIP" FOR NORTH SHAFT.



HALF PLAN BOTTOM

HALF ELEVATION
WEAR

SECTION ON CD

HALF ELEVATION
FRONT

SECTION ON EF

TOP SECTION FOR SHAFTS. 2 OF.

PLUG




PLAN




FRONT ELEVATION



TOP



SECTION ON AB




"Y" BRANCH.

ELEVATION SPIGOT END



SECTION ON GH



MAINHOLE COVER

SECTION




PLAN



REGULAR PIPE FOR SHAFTS AND TUNNEL.

ELEVATION SPIGOT END




LONGITUDINAL SECTION




BEND.


ELEVATION BELL END




LONGITUDINAL SECTION



HALF ELEVATION BELL END.



SECTION ON JA





SCHEDULE OF REGULAR PIPE

	No.	Length
Soun	3	8'-0"
Shaft	1	6'-0"
Shaft	1	4'-0"
Shaft	1	2'-0"
Shaft	3	8'-0"
Shaft	1	5'-0"
Shaft	1	3'-0"
Shaft	1	6'-0"
Shaft	1	5'-0"
Shaft	1	3'-0"
Shaft	1	2'-0"
Total Pieces	120	


MYSTIC RIVER SIPHON
DETAIL OF CAST IRON PIPE
MASSACHUSETTS PIPE LINE GAS CO.

SCALE 1:36









METHOD OF CARRYING CONCRETE
IN
CHARLESTOWN TUNNEL
MASSACHUSETTS PIPE LINE GAS CO.
SCALE 1:48









PROFILE OF TUNNEL
UNDER CHARLES' RIVER
BETWEEN
ALLSTON AND CAMBRIDGE
MASSACHUSETTS PIPE LINE GAS CO.

SCALES { HORIZONTAL 1:720
VERTICAL 1:180

THE INCREASING ELEVATION OF FLOODS IN THE LOWER MISSISSIPPI RIVER.

BY LINUS W. BROWN, MEMBER LOUISIANA ENGINEERING SOCIETY

[Read before the Society, March 11, 1901.*]

My acquaintance with the Mississippi River began in 1880, twenty-one years ago, and for the past fifteen years I have been directly connected, officially and otherwise, with the levee work at this point, and I cannot fail to appreciate the material changes which have taken place during these two decades, in dimension of levees required to properly protect this section against inundation.

Twenty years ago the levees were of very small dimensions and very low in elevation as compared with those now existing. As I remember, the levees in the third district were but little larger than a well-banked potato row, and were located from 75 to 100 feet from the front street (North Peters), and the elevation of levees along the Commercial front was several feet lower than they exist to-day.

The serious and most important question presented is, what do the facts, as gleaned from the two decades just passed, teach us, and what conclusions are to be drawn? In my opinion, the facts, as presented, most conclusively demonstrate that to secure in the future the same protection against inundation as in the past and at the present time, there will be required a continual raising and enlarging of the levees, and the conclusions to be drawn are that in a very few decades (taking the past two decades as a criterion) the construction of levees to properly secure us against inundation will become a prodigious undertaking, both as an engineering feat and as a revenue consumer, owing to the very large proportions that will be required.

The question, what will be the height of levees for proper future protection against the inundation of the Mississippi Delta? demands immediate attention, and should be given the most careful thought and consideration. The maxim: "He only is free from danger who, even when safe, is on his guard," embodies the sentiment which should pervade every interest throughout the Mississippi Delta, and which should stimulate us to inaugurate at once a careful investigation and to apply such remedies or adopt

*Manuscript received May 20 1901.—Secretary, Ass'n of Eng. Soes.

such methods as will measurably well assure us of a moderate maximum elevation of levees for future protection. It is not too soon to inaugurate the necessary measures for a thorough investigation and secure the co-operation of all interests, and invite the attention of, and secure the necessary assistance from, the Federal Government to meet the issues which are now most apparent of future consummation, unless thwarted.

What are the causes of the constant increase in elevation of floods in the Lower Mississippi, why are the maximum floods sporadic; seldom, if ever, occurring in yearly succession, why should the maximum floods increase in elevation when a corresponding increase of discharge is not, by investigation, apparent, and why did the normal flood of 1898, discharging very considerably less volume than the great flood of 1851 or of 1890, require greater flood elevation? The United States Government gaging of May 2, 1898, shows that the elevation of flood was 16.65 feet on gage, and the discharge 1,084,000 cubic feet per second, whereas on February 26, 1890, the flood elevation was 14.7 feet on gage, and the discharge 1,422,000 cubic feet per second, which shows that the flood of 1890 discharged 338,000 cubic feet per second (or 30 per cent.) more water, and at an elevation of 0.95 feet (or 0.6 of 1 per cent.) less than that of 1898. On March 17, 1851, the gaging as recorded shows a discharge of 1,153,000 cubic feet per second, with a flood elevation of 14.8 feet on gage.

When the causes are ascertained, what are the remedies to be applied or the methods to be adopted to maintain a comparatively uniform elevation of maximum floods?

These are the questions to be solved, and they should receive the immediate and earnest consideration of every interest throughout the Mississippi Valley. And I will predict that the proper solution of these important questions will keep every member of this society of engineers busy for some time to come. The matter is of such paramount importance that it should enlist the very best endeavors of each and every one of us, and we should not be satisfied until we have secured some measurable degree of success.

Before attempting to lay before you an outline of my views of the cause producing the conditions, or the remedy to apply, I would refer to the following statistics and facts to amplify and form base for the conclusions and suggestions I may present.

All elevations used in this paper will refer to the Carrollton gage of the Mississippi River Commission, zero of which is 20.91 feet above Cairo Datum or 0.35 feet below mean ocean level; and all velocities and discharges referred to are those contained in the

reports of the Mississippi River Commission. The distance from the Carrollton gage to mean ocean level in Gulf is, for the calculation of slopes, assumed at 120 miles. The reports of the Mississippi River Commission do not contain statistics as to elevations at the heads of passes or at Fort Jackson, excepting from 1891 to 1898 at the latter point. I also note the incompleteness of the reports as to elevations, discharges and velocity of the river at any point, in that they cover only a few days of the year and often do not cover the maximum conditions. The discussion of the subject at this time may require some deductions to be made, and any conclusions reached will be understood as being susceptible of such modification as more full and correct data may conclusively determine to be correct and proper.

I remember the newspaper reports of the flood of 1874, which flood overtopped the then existing levees, and later I became familiar with the effects of this great flood, which reached the then extraordinary maximum elevation of 15.7 feet on gage, or 15.35 feet above sea level, although the elevation of this flood was only 6 inches higher than that of 1828, forty-six years previous, and was not as high by 0.2 of a foot as the flood of 1862, as recorded in the Government records. The average slope of this flood of 1874 to sea level was 0.128 of a foot per mile, or about 1 foot in 8 miles. The records of velocity and discharge are not embraced in the Government reports, but assuming the gagings of March 14, 1891, when elevation of flood was 15.6, as a comparative estimate of the velocity and discharge for flood of 1874, we have 6.95 feet velocity and 1,202,000 cubic feet discharge per second.

The flood elevation of 1874 was not surpassed until 1890, when it reached an elevation of 16.1 and in 1892 of 17.35 and 1893 of 17.45, and the greatest of all floods occurred in 1897 when the maximum elevation was 19.17 feet or 3.47 feet higher than the extraordinary flood of 1874, twenty-three years previous.

The elevation of flood of 1897 at Carrollton was 18.82 feet above ocean level, and the average slope from Carrollton to ocean was 0.156 of a foot per mile or 1 foot in 6.3 miles, or 22 per cent. greater than the slope of 1874, and while the Government reports do not give the gaging as to velocity and discharge on the day when the greatest elevations were noted,—viz, May 13, they give, for May 18, a velocity of 7.3 feet and a discharge of 1,350,000 cubic feet per second, gage reading 18.7 feet, and this gaging is the greatest, both as to velocity and discharge, of any shown in the reports, which further shows that while the difference in

elevation of the flood of 1897 above the sea level was 22 per cent. more than that of 1874, twenty-three years previous, the discharge was only 12 per cent. greater.

The history of the great floods, as recorded, is as follows:

Dates.	Gage reading.	Height above sea level.	Slope per mile.	Velocity.	Discharge.
1828—April 1	15.20	14.85	0.123	5.90	1,099,000
1849—March 15	15.20	14.85	0.123	5.90	1,099,000
1851—March 27	15.40	15.05	0.125	5.99	1,118,000
1858—May 10	15.10	1,168,000
1859—May 4	15.60	15.25	0.127	6.00	1,156,000
1862	15.90	15.55	0.130	6.68	1,243,000
1874—April 16	15.70	15.35	0.128	6.75	1,175,000
1890—March 13	16.10	15.75	0.131	6.90	1,292,000
1892—June 10	17.35	17.00	0.141	5.87	1,079,000
1893—June 22	17.45	17.10	0.1425	5.82	1,113,000
1897—May 13	19.17	18.72	0.156	7.30	1,350,000
1898—April 25	15.90	15.55	0.130	5.73	1,024,000
1899—April 21	16.00	15.65	0.135	6.81	1,182,000

The velocity and discharge for the years 1851, 1890, 1892, 1893 and 1897 are the results of gaging on these dates as contained in the reports of the Mississippi River Commission, but those for the other years are not given in the reports, and the velocity and discharge for these years are interpolated from the records of other years when gage readings or elevation of floods were the same, thus:

The year	1828	is from records of	March 25,	1851.
" "	1849	" "	" "	28, 1891.
" "	1859	" "	" "	24, 1890.
" "	1862	" "	" "	19, 1890.
" "	1874	" "	" "	18, 1891.
" "	1898	" "	" "	June 9, 1892.
" "	1899	" "	" "	March 16, 1891.

There is recorded no gaging since 1892 for flood elevation of 15.9 and 16 feet for years 1898 and 1899 respectively, and the interpolations made are clearly on the side of very greatest possible maximum velocity and discharge for these years. It is most apparent, from the records, that the discharge for later years is much less than in former years for same elevation of flood, as is shown by the records and gagings of the normal flood of 1898, when the elevations were from 15.5 to 15.65 feet, and the maximum discharge was from 1,049,000 to 1,087,000 cubic feet as compared with that of all the great floods from 1828 to 1890, when the ele-

vation ranged from 15.2 to 15.9 feet and the discharge from 1,099,000 to 1,243,000 cubic feet per second.

The record of the gaging on May 4, 1898, shows that with an elevation of 15.65 feet the discharge was 1,049,000 cubic feet with a velocity of 5.97 feet; and it is perhaps safe to assume that the maximum volume of discharge of future great floods will approximate but not exceed 1,400,000 cubic feet per second; hence the elevation of flood on May 4, 1898, to discharge a maximum flood of 1,400,000 cubic feet at 6 feet velocity, with cross-section of 175,600 feet at elevation of 15.65 feet on gage, and assuming the width of river between levees at 4000 feet, would be 14.4 feet higher, or 30.05 feet on gage, and with increasing velocities would be as follows:

Velocity	6.25—12.1	feet higher	or	27.75	on gage.
"	6.50—9.9	"	"	25.55	" "
"	6.75—7.9	"	"	23.55	" "
"	7.00—6.1	"	"	21.75	" "
"	7.25—4.3	"	"	19.95	" "
"	7.50—3.1	"	"	18.75	" "
"	8.00—0.0	"	"	15.75	" "

Hence, to secure in 1898 an elevation of flood slope not exceeding 16 feet on Carrollton gage, a velocity of 8 feet per second would have been required to pass the maximum flood volume of 1,400,000 cubic feet, and with a velocity of 7.3 feet per second, and a discharge of 1,350,000 cubic feet, as gaged on May 18, 1897, producing a flood elevation of 18.7 feet, the maximum flood elevation of 1898, to pass this volume at this velocity, would have been only 2.3 feet higher or 17.95 on gage, or 0.75 feet 9 inches lower, which clearly demonstrates that the floods with maximum elevations, even with equal volume of discharge, cannot occur in succession, for the reason that the avenues for passage of water are scoured out by the first flood, and the conditions to retard the passage cannot be formed in the interval of time, between two flood periods. The velocities shown above, and which exist in the Lower Mississippi, are very heavy, and even the lowest is not consistent with any reasonable security of bed or banks, as is shown by the following experiments of Bazalgette, in which he found the velocity required to remove materials as follows:

Fine clay	0.25	feet per second.
Sand	0.50	" " "
Coarse sand	0.66	" " "
Fine gravel	1.00	" " "
Pebbles	2.00	" " "
Stones, egg size	3.00	" " "

And the observations of eminent hydraulicians, as referred to by Gauguillet & Kutter, give mean velocities required to abrade river beds and banks as follows:

River mud	0.33 feet per second.
Sand, size of anise seed	0.46 " " "
Clay and loam	0.66 " " "
Sand, size of peas	0.79 " " "
Common river sand	0.92 " " "
Coarse gravel and small cobblestone.....	3.93 " " "
Angular flint stone, egg size	4.23 " " "
Soft slate	6.45 " " "
Stratified rock	7.86 " " "
Hard rock	13.12 " " "

From which it is not surprising that with a current having a velocity of from 5 to 7.3 feet per second the alluvial banks of the Mississippi River are abraded.

The facts, as presented above, make prominent the further very pertinent question, what will be the rate of increase of future maximum flood elevations? Referring to the above list of great floods, we find that from 1828 to 1874, a period of forty-six years, the increase was only 0.5 of a foot, or at a rate of 0.011 of a foot per year or 1 foot in ninety years, while the flood of 1897 was 3.47 feet higher than the flood of 1874, or a rise of 3.47 feet in twenty-three years, or at a rate of 0.15 of a foot per year or 1 foot in six and one-half years. It will be noted, further, that in 1890 the elevation of maximum flood was 16.1 or 0.4 of a foot higher than that of 1874, or 0.4 of a foot increase in sixteen years, or at rate of 0.025 foot per year or 1 foot in forty years; while the flood of 1890 was 3.07 feet below that of 1897, or an increase of maximum flood elevation of 3.07 feet in seven years, or at rate of 0.44 foot per year, or a foot in about two and one-half years. It is also interesting and instructive to note that the maximum elevation of floods since 1897, while they have been considered as normal, were all considerably higher than those of the great flood periods prior to 1890.

A careful consideration of the facts above presented, showing the increase of elevation of maximum floods, would determine, as conservative, a rate of increase in future of 1 foot in five years, and it is to be feared, and may be expected, that this increase will be exceeded. Hence, unless means are adopted to thwart the gradual increase of maximum elevation of floods, the levees in 1950 will be 10 feet higher than at present, under which condition the whole delta will be confiscated for levee protection, and commerce on the Lower Mississippi will be rendered wholly impracticable.

Mr. Chas. Ellet, who represented the United States Government in connection with river investigation in the year 1851, was sufficiently bold to assert that, to sustain a flood of the intensity of that of 1851, the levees must be made 2 feet higher than they then existed, from Red River to New Orleans; for which assertion he was, in 1861, severely criticised by the United States Government's representatives in charge of river matters. As a matter of fact, the floods of 1851 were no doubt as intense as those of 1897, and while the maximum discharge at Carrollton, as gaged, was 1,186,000 cubic feet per second, and that of 1897 1,350,000 cubic feet per second, the volume passing from the river into the sea between the Red River and New Orleans, was equal to or greater than the difference between the measured discharge; and the prophecy of Mr. Ellet has been more than realized, as in lieu of 2 feet, levees to properly protect the alluvial lands are now fully 5 feet higher than they existed in 1851.

The estimate made by the Government engineers in 1861 for the proper and absolute protection of the alluvial lands along the Mississippi River, from Cairo to the Gulf, in addition to the value of levees then existing, was \$17,000,000, and the value of then existing levees was placed at \$9,000,000, making the total value of the ultimate and complete levee system \$26,000,000. Since 1861 up to the present time, there have been expended upward of \$50,000,000, and the levees are yet incomplete; and to properly protect the alluvial lands against inundation in the future, as far as 1950, the levee system alone, if built at once of proper proportions, will cost upward of \$100,000,000, but a very much greater amount will be expended by reason of the work of raising and enlarging the levees. This will necessarily be required to be done gradually and oftentimes as an emergency, and at no time will the alluvial lands be absolutely free from danger of inundation, unless the increase of flood elevations is restrained.

The facts above presented, and the conclusion to be drawn, are most thoroughly convincing that the elevation of the surface of normal and extraordinary floods in the Lower Mississippi are increasing, which conclusion presents, in contemplation, most undesirable future conditions and invites our most serious attention.

The methods adopted in the treatment of rivers in Europe, traversing alluvial territory, such as the Rhine, Vistula, Danube and others, cannot be adopted, as these methods have utterly failed in restraining an increase of the elevation of their floods; and, again, these rivers are very small in comparison with the Mississippi; and such measures as would increase, almost imperceptibly, the eleva-

tion of floods in these small rivers would make the increase in the Mississippi River most apparent.

When the "all-levee system" was inaugurated and urged, between the years 1860 and 1880, no marked increase in the elevation of floods was apparent; in fact, the records show an increase of only 0.9 of a foot from 1828 to 1890, a period of sixty-two years; while from 1890 to 1897, the records show an increase of 3.07 in seven years; and the engineering profession, more particularly the Government engineers, in recommending the "all-levee system," did not take into consideration the consequent and serious effect of increasing the elevation of floods, the extent to which this elevation would reach or the disastrous effects resulting therefrom. That this reasoning is correct is established by the fact that in 1861 Captain Humphreys recommended the construction of a levee system as being all that was essential, and estimated that the ultimate cost of protecting the 29,000 square miles of alluvial territory against inundation would be \$17,000,000, whereas we have already spent upward of \$50,000,000, and, as above noted, will require not less than \$100,000,000 within the next forty years, unless the flood elevation can be reduced or maintained at an elevation not exceeding 18 feet on the Carrollton gage.

That the "all-levee system" is a necessity no one can possibly deny; but, as is shown, a levee system without other equally important works will in a few years prove a disastrous failure. It is a matter of universal record that the advocates of the "all-levee system" have persistently condemned all suggestions which would effect, by reducing, the elevation of floods, even when made by prominent, accomplished, brilliant and learned members of the engineering profession; and it is now most apparent that these views must be modified, and such measures considered and adopted as will assist in the matter of reducing the elevation of floods of the Mississippi River.

To refer briefly to the causes producing these high elevations of floods in the Lower Mississippi, it would be pertinent to remark that the power and force embodied in the Mississippi River at high floods are such as to be beyond human hands or brains to combat. The only measures that mankind can adopt, with any degree of success, are those which are in line with nature's laws, and to find the cause it is proper to make comparison between the river, with the "all-levee system" only, as now existing, and alluvial rivers having no levees, and see wherein they differ.

Were the Mississippi River not leveed in, and were no artificial works constructed along its banks, it would, when rising

above its normal bank, overflow, and deposit its sediment on the adjacent banks and the surrounding country. As it gradually elevated its banks and the surrounding country, and gradually withheld the water from overflowing, it would scour a channel of the desired width and depth to convey the volume to the sea level at such velocity as the bed would allow; the elevation of the flood height would be a purely natural one, coinciding with the distance and volume, and the elevation would gradually increase as the river extended into the Gulf, which, under present conditions, is less than 200 feet per year, and in 1000 years would be about 40 miles, or sufficient to raise the flood elevation at Carrollton about 1 foot. According to Government statistics it would take something like 720 years to raise the 29,000 square miles of alluvial territory one foot; so that, if the Mississippi River were left alone, the time would be very remote when the elevation of floods would increase 3.47 feet, as has taken place in twenty-three years, or between 1874 and 1897.

One of the main causes of the increase of flood elevations is the construction of the levees on lines not calculated to maintain a constant cross-section of the river, or especially of that portion of volume which flows above the natural bank; such construction affords an opportunity for the volume to lose its velocity at points where levees are placed comparatively far apart, and thus requires an artificial head to cause the volume to resume its flow through a more confined portion of the river. This elevation of the volumes in the wide portions further reduces the slope and velocity of river above, and, hence, affects the whole river and interferes with any uniform velocity; and, further, the low velocity thus produced at points is sufficient to form deposits and decrease cross-section. This, in turn, causes further elevation of flood surface and produces at other points such intense velocity as to abrade the bed and banks, and oftentimes materially increases the length of the main channel. This is also true of points where the river itself and levees are wide, as compared with other points where the river and levees are narrow, producing relatively low and relatively high velocities, rendering impossible any uniform velocity. Again, there are places where the river is entirely too narrow to properly pass the floods, and some of these narrow points are highly improved, as at New Orleans.

Another cause for the increase of elevation of floods, and fluctuations in elevations for equal volume of discharge, is the changing of the bed of the river and the moving back of levees around bends. This materially increases the distance to ocean

level, and thus reduces the slope and the average velocity, and is further assisted by the great inequalities in the width between levees, providing the conditions above outlined.

Another cause may be found in the accretions which form on the bottom and sides of the channel on the apex sides of bends, without a corresponding amount of abrasion on the concave side, during seasons of normal floods. This condition may increase for a year or two, when a flood with a very high elevation ensues, due less to a greater volume than to the choked or diminished cross-section of river channel.

The combination of all of these causes produces a constant stop and start; retardation and acceleration of velocity, causing excessive accretions at one point, and excessive abrasion at another, cutting out a channel through a choked cross-section at one place and depositing it in a cross-section of superabundant area at another place until it in time becomes choked, and thus the elevation of the floods is constantly varying and steadily increasing, *due to the increase of resistance for channel to clear itself of deposits*. The yearly extension of the river into the Gulf, as affecting the slope, is insignificant and requires no consideration as affecting the elevation of floods, excepting for periods of time as marked by centuries.

That the elevation of great floods is increased by reason of greater volume cannot be conclusively determined in the affirmative. Were the elevation of normal floods not increasing in practically the same ratio as the elevation of the great floods, more consideration could be given to the great increase in the volume of one great flood over that of another.

The careful consideration of the records of great floods for the past seventy years would clearly indicate that the volume is not increasing, and there is every reason why the maximum volume should not increase with the settling up and improvement of the country over that of the great floods which occurred, when the whole country tributary to the Mississippi was wholly unimproved. The opening up and improving of the country has very largely increased the percolation and retention of water on the lands, and the installation of industrial enterprises retains large quantities which formerly were precipitated to the Mississippi immediately the warm season opened. With the further development of the country, this volume, which will be retained and allowed to run off gradually, will greatly decrease the maximum volume of future floods, and even with the worst combinations and most undesirable conditions as to the breaking up of seasons of cold weather, the

maximum volume of future floods should not exceed the maximum volume of the great floods of the past. It is, however, possible, and even probable, that very great future advantage will be secured to the Lower Mississippi by the construction of further works having for their object the further retention of water for irrigation, or other purposes of the territory tributary to the Mississippi, and thus entail a double benefit.

The suggestions as to the methods to adopt in order to secure the very lowest possible permanent maximum flood elevation for the Lower Mississippi (16 feet or less at Carrollton) are replete with material for discussion and consideration.

The first steps toward securing satisfactory results would be to provide a firm base or foundation for such conclusion as may be reached, by the inauguration of measures to secure full and complete data and information of all the conditions now existing which have a bearing on the subject, and to this end it would be necessary to correlate, and place in such shape as can be utilized, all the data secured by the United States Government and the Mississippi River Commission, and all the reliable data which can be furnished by levee boards, levee engineers or other parties, and fill in with the best possible judgment, by interpolation or otherwise, the data covering past conditions which are not attainable, and then proceed to arrange for the securing of accurate data of all the conditions, as to cross-section of channel throughout the whole length of the Lower Mississippi; make complete investigation as to direction and intensity of currents, and of all abrasion and accretion of banks; secure all data necessary to determine positively the cause for any and all of the varied actions of the river, such as accelerated and retarded velocities, shoaling and scouring of bed, accretion and abrasion of banks; also note all the conditions necessary to determine the practicability of the adoption of such remedy as may be determined upon. Make full investigation and survey of all low alluvial lands, note all the conditions necessary to determine as to the practicability of their utilization as relief avenues for the floods, and at the same time assist in making these low lands suitable for future agricultural enterprises; in fact, make the whole investigation as nearly complete as possible, and thus enable the whole subject to be studied and considered in all its phases. This might perhaps result in the adoption of methods, quite inexpensive and most efficient, not thought of now, for the securing of the object sought to be obtained, and at the same time provide very great advantages to industrial and commercial enterprises.

In the absence of full and complete data and information on all points bearing on the subject, or rather in the light of such information as is now before us, it would appear that, to provide proper protection of the Mississippi Delta against inundation, there must be provided, in addition to levee building, a reasonably uniform cross-section of river, especially for the volume flowing above top of natural ground, that the levees should be located to provide this requisite and that future location of levees should be determined by the calculation for volume and velocity of river at any point, for the purpose of providing proper cross-section, rather than by such physical condition as may exist, as is the present practice.

Measures must also be adopted by which the extensive caving, by reason of constant and heavy abrasion of banks in bends, will be measurably retarded. To accomplish this end, the heretofore condemned suggestion looking to the removal of accretions on bends or points can no doubt be practiced with great benefit. The desired requisite to be secured, to maintain a low and uniform elevation of floods, is a channel which is of such cross-section as to flow, with a reasonable velocity, the volumes received. A careful investigation of the channel, after each high water, will give the data necessary to determine by calculation what work will be required in removing accretioning banks, bars or other obstructions to secure the proper channel for the ensuing season.

Should the investigation disclose the fact, which in all probability it will, that at places the river is too narrow and the levees too close, the latter must be removed, and conditions provided by which the river will cut a channel of the requisite cross-section; where choked cross-sections exist at points where valuable improvements are located on the adjacent banks, as at New Orleans, the additional channel area required may be secured by a spill-way extending from a point just above the city and connecting the river at the English Turn; the ends of this spill-way to be located at an elevation of say 13 feet Carrollton gage, or such elevation as may be determined as coincident with the volume, section and velocity safe to pass New Orleans; and the ends of the spill-way to be made of masonry, impermeable to action of water, and thus secure control of the volume it will convey. This spill-way will assist in maintaining a velocity in the main channel past New Orleans such as will not cause the heavy abrasion now sustained by reason of the high velocity required to pass flood volume.

I am of the opinion that the suggestion made by Brigadier-General B. S. Roberts, of the United States Army, to reclaim

waste swamps along the Lower Mississippi by utilizing the delta-making material of the surplus water of the river, will, with some modification, prove most beneficial to all interests, especially the agricultural and sanitary interests of Louisiana; and I am convinced that such measures will also form a most important factor in maintaining a correspondingly low and permanent elevation of floods, will render unnecessary large future expenditure for levee construction and will provide the greatest possible security against inundation, notwithstanding the fact that the Government engineers in charge of the Mississippi River improvements condemned and criticised the suggestion of General Roberts as having no merit.

The measures I would suggest, as modifications of the plan presented by General Roberts, would be such as not only affect the flood slope of the river and vastly improve the lowlands, both from a financial and sanitary point of view, but would further provide an invaluable supply of water for irrigating the land during the low-water season, which is not infrequently accompanied by a long season of drouth. To this end, there would be located, at such points as the survey and investigation would best determine, a spill-way of such construction as to be positively free from danger of washing out, the sill of which to be at such elevation as conditions would determine. This spill-way would be connected, by levees across the high ground adjacent to the river, with a large reservoir or basin constructed directly in the low ground or swamps. The size of this basin would be such as conditions may determine, for illustration, say 10 miles long and 5 miles wide, embracing an area of 50 square miles. This reservoir would be constructed by dredges from the inside and the proper levees would be formed around it to such height as may be determined,—say of sufficient height to maintain the surface of water at an elevation of 5 feet above the high land adjacent to river where the spill-way has ceased to run. At such point as may be desired, in the levee forming the reservoir, will be constructed a spill-way to allow the water from the river to pass directly to the swamps, after filling the reservoir. The surface of the swamps will be gradually raised by the deposits from the river water, and any territory desired can be elevated by construction of small levees to direct the flow after the water leaves the reservoir. Thus, at small expense, the whole territory adjacent to the reservoir will be elevated in a few years. In the course of time, say twenty-five or thirty years, or when sufficient filling has taken place, the spill-way and reservoir could be abandoned and new ones constructed at other points, and thus the alluvial

territory along the river would be constantly elevated, co-extensive with, and perhaps at a greater rate than the increase of elevation of floods from natural causes. The reservoir of the dimensions above referred to, holding 5 feet of water, would contain 6,969,600,000 cubic feet of water when flood in the river recedes below elevation of sill of spill-way; and this volume of water could by gravity be used to irrigate the adjacent lands during a dry season. On the assumption of there being required for proper irrigation an acre foot or a depth of 12 inches of water over the whole territory to be irrigated, the volume would irrigate 160,000 acres of land, and a low estimate of the value of such irrigation would be \$5 per acre, which would aggregate an advantage amounting to \$800,000 per annum or 10 per cent. on a capitalization of \$8,000,000, not including the advantages accruing from the elevating of these lands, making them productive, and at the same time removing extensive malarial breeding areas and improving the sanitary condition of the territory.

The dimensions of the spill-ways and reservoirs would be such as would be determined by the survey and full consideration of the location selected. Approximately, the spill-way would be 5000 feet long and would have a maximum capacity of 60,000 cubic feet per second, and it would be judicious that a sufficient number be constructed to have an aggregate maximum discharge of 400,000 cubic feet per second, or say eight in number, located at such points as to cover the low ground to best advantage and make the connecting levees as short as possible. In the main, these large spill-ways and reservoirs should be located on the right bank, as larger areas of lowland lie on this side of the river and the connection with the sea is more direct; although several small spill-ways and large reservoirs could be located to great advantage on the left bank.

Closer investigation and experience will determine the volume which can be, with best advantage, passed from the river to the spill-way, but for economic interest the volume allowed to flow over the lowlands, as proposed, should be as large as possible, and perhaps it may be wise to exceed the volume of 400,000 cubic feet per second above referred to. This may be done without decreasing the velocity in the river sufficiently to form deposits. The volume in the river, when it recedes to the sill of the spill-way, may be most advantageously fixed at such volume as will produce a velocity not exceeding 5 feet per second, or with maximum discharge of about 800,000 cubic feet per second.

As above represented, the annual value of spill-way and reservoir for irrigation would approximate \$800,000 for each spill-way having a capacity of 60,000 cubic feet per second and reservoir embracing 50 square miles, which, for eight, or sufficient to discharge 400,000 cubic feet per second, with corresponding reservoir capacity, would amount to \$6,400,000 per annum, or 10 per cent. on a capitalization of \$64,000,000. The cost of the spill-ways and reservoirs would depend on location, but approximately the cost of each would not exceed \$600,000, not including the value of the land occupied.

The foregoing, however, does not represent all of the direct advantages which would be secured. The elevating and reclaiming of the lowland will, in time, produce an advantage of enormous value. Land now worth \$1.25 per acre will become the most fertile and productive in the Union, and the crops grown will yield a revenue equal to 10 per cent. on a capitalization of from \$50 to \$150 per acre.

The suggestion, as will be observed, contemplates the delivery of water on to the lowlands at such velocity and in such manner as will admit of deposits forming adjacent to the reservoir, or at any point desired, by the construction of a small supplemental levee, and obviate entirely the high velocities and the heavy abrasion of land, and uncontrollable points of deposit which are secured by a sill and side levee to the lowland, which is practically a leveed crevasse; and further secure the irrigating reservoirs. It would be pertinent to remark that the irrigation of our lands is a progression which in the very near future will be most fully appreciated, and will be adopted wherever an opportunity offers. For the purpose of irrigation, large reservoirs with small spill-ways could be placed along the Upper Mississippi.

Allowing that 400,000 cubic feet per second is passed by eight spill-ways and allowed to deposit on low ground for an average period of 120 days each year, and that the water contains, of solids, 1 part in 1500 parts, the deposit per year would be 5 inches deep over an area of 250,000 acres, or 5 feet deep in 12 years, or on an average it would fill 63,470 acres 1 foot deep each year, and in 100 years it would fill 6,347,000 acres 1 foot deep.

Recapitulating the calculations: 400,000 cubic feet per second for 120 days would deliver on the lowlands 4,147,200,000,000 cubic feet of water, and on basis of 1 part solid in 1500 parts, the amount of deposit would be 2,764,800,000 cubic feet of earth, or 102,400,000 cubic yards, or 153,600,000 tons, or 5,120,000 carloads of 30 tons each, and allowing 30 feet to the car would make a

train 29,130 miles long, and if this train traveled at the rate of 30 miles per hour, it would take over 40 days to pass one point.

This illustrates the enormous amount of earth carried by the Mississippi each year and deposited in the Gulf of Mexico. Did not nature intend that the Mississippi River should drain the territory embracing thirty-two states, two territories and a portion of the British possessions, on the principle that the section which was injured or jeopardized, and which required work of protection, would be recompensed at the expense of the territory that sustained benefits with no corresponding injury? And did nature intend the millions of tons of fertile earth carried by the Mississippi to be wasted in the waters of the Gulf of Mexico?

I believe it was intended by nature that the Mississippi River should be the source of very great benefit to mankind, but stipulated that if mankind would receive the full benefit of this river he must use intelligence and exertion, as is shown by similar works of nature. And I further believe that mankind is endowed with all the necessary intelligence to positively avoid danger of inundation of the alluvial lands of the Lower Mississippi, and realize all the benefits of the rich material carried in suspension, by filling in the low places and enriching the whole territory as desired, as also improving the sanitary condition of this section, and the consummation of these most desirable conditions depends entirely on the energy of mankind. Have we energy to help ourselves?

DISCUSSION.

MR. H. B. RICHARDSON.—This paper announces conclusions as to the height of future floods in the Lower Mississippi River, and the consequent dangers impending, which, if correct, must be regarded as appalling, and may well cause us to join with the author in asking, "Have we the energy to help ourselves?"

When it appears that a "consideration of the facts . . . would determine as conservative a rate of increase in the future of one foot in five years," so that the levees required to restrain the flood "in 1950 will be ten feet higher than at present,"—and presumably twenty feet higher in the year 2000. With an equal increase each succeeding century, we may think the wisest application of our energies to be toward the removal of ourselves and our belongings to regions of greater altitude.

It is some comfort, however, to find the author remarking that "any conclusions reached will be understood as being susceptible of such modification as more full and correct data may conclusively determine to be correct and proper."

And it may afford further relief to examine more carefully the table constructed by the author "to amplify and form a base for the conclusions" presented.

This table, in which we are informed "the history of the great floods is recorded," contains six columns of figures, referring to the gage height, slope, velocity and discharge at Carrollton, of thirteen floods during the period of seventy-one years between 1828 and 1899. The two last columns ("Velocity" and "Discharge") contain twenty-five items, thirteen—that is, 50 per cent.—of which "are interpolated from the records of other years," according to a system of the author's own devising,—namely, by finding, in the reports of the Mississippi River Commission, a gaging of discharge and velocity made at Carrollton at any time when the stage was the same as the highest of the year given in the first column of the table, and filling in the last two columns with the discharge and velocity so found. For instance, as shown in the second table, the author takes from the records of March 25, 1851,—when the gage reading at Carrollton was 15.2,—the velocity and discharge as then gaged, and "interpolates" them for the year 1828, when he says the flood stage, on April 1, was the same. Why the gaging of March 25, 1851, should have been selected for "interpolation" in preference to that of March 22, when the stage was the same, but the velocity and discharge considerably greater, is not apparent. Nor why the "interpolations" for April 25, 1898, should have been taken from the records of June, 1892, instead of March, 1891, when the stage was the same and the observed velocity and discharge decidedly larger. The "slope per mile" given in the fourth column is also "interpolated" from assumed data; so that, after all, the only column of the table that purports to give any real "history of the great floods" is the second,—*i.e.*, "gage reading,"—the third column being simply a variant of the second, produced by the subtraction of a constant difference (0.35) between zero of the gage and mean Gulf level.

From the table so constructed the author proceeds to show the "rate of increase of future maximum flood elevations." For forty-six years of the period included in his table he finds it only a foot in ninety years, while in the next twenty-three years it goes up to the alarming rate of a foot in six and one half years, the last seven years of which period has rushed on at the fearful rate of a foot in about two and one-half years.

He fails, however, to note that during the last two years included in the table there has actually been a *decrease* at the rate of almost a foot in seven and a half months.

Nor does he mention the fact, shown by the table, that the increase from the beginning to the end of the period covered, is only a foot in eighty-eight and three-fourths years, or about the same as that given for the first forty-six years.

And yet the author, after a "careful consideration of the facts presented" in the table, concludes it to be a thing that "may be expected" that an increase of future flood elevations at Carrollton will continue indefinitely at the rate of one foot in each five years.

This can be compared only to the conclusions of another experienced observer—Mr. S. L. Clemens—in which he shows, from the rate at which the river is being shortened by cut-offs, that the corporate limits of New Orleans and Cairo must overlap each other at some future date, not now recalled by this writer, but probably about the same time that the levees here are built ten feet higher than at present.

The author's local experience and observation has covered a period of twenty-one years, and his conclusions are entitled to serious consideration.

But it should be remembered that the investigations of Humphreys and Abbot, reported in their "Physics and Hydraulics of the Mississippi River," covered a period of ten years between 1850 and 1861; and that the Mississippi River Commission has been diligently studying the same problem for over twenty years—or since 1879; both with ample means for surveys and numerous assistants, and that the scope of their operations has included not only all that was to be learned from the surveys and observations at Carrollton and New Orleans, but also throughout the entire river.

The Humphreys and Abbot report gave certain elevations at numerous points along the river, which they considered as probably the highest likely to be reached by any flood confined between levees, not greater in volume than those previously recorded. After the flood of 1874, the Commission appointed by the President to report on the flood of that year, practically adopted the same conclusions regarding the probable flood-elevations. And, finally, the Mississippi River Commission, after some seventeen years of surveys, investigations and studies, adopted a provisional standard of probable flood heights, not greatly differing from the conclusions of its predecessor, though somewhat higher at Carrollton.

No flood has yet come within more than a foot of reaching the latter standard at Carrollton, and only one has reached the mark set by Humphreys and Abbot forty years ago.

Considering the relative opportunities enjoyed by the several investigators for collecting full data and for comprehensive discussion of the whole subject, the present writer is inclined to accept the more moderate conclusions of Humphreys and Abbot and the Mississippi River Commission, rather than the startling predictions of the author.

MR. B. M. HARROD.—In the paper under discussion the title, "Lower Mississippi," is limited to that part of the river below the mouth of the Red River. It has usually been understood as extending over all parts flowing through the alluvial valley, or wherever its geology and physics are the same.

The phenomena of any one part are explainable only by a comparative study of all parts where similar conditions prevail.

Gage heights are transmitted with substantial regularity from one station to another over any length of the river which is not affected by tributaries or outlets. If either of these disturbing influences intervene between two gages the relation of one to the other is disturbed, and no flood estimate can be based on the lower one without estimating the effect of the intervening disturbance.

Probably the law of the uniform relation of successive gages would, for obvious reasons, be more closely applicable to that part of the Mississippi below Red River than to any other whenever the discharge passing that station reaches the sea, or at least the Fort Jackson gage, without loss. But this has not been the case in any year of large or even of moderate floods until recently. The loss of discharge by crevasses between Red River and Carrollton has always disturbed their high-water gage relation. On several occasions the escape through crevasses amounted to one-third or more of the discharge passing the former station. Under such conditions no conclusion concerning the increase or decrease of floods can be reached by an examination of recorded gage heights at Carrollton without a study of the effect of the crevasses.

The fallacy of any such method of reasoning is shown by an examination of the relative heights of the gages at Red River and at Carrollton during the time that these stations have been carefully maintained and regularly recorded, or since the high water of 1871, a period of thirty years.

The discharge at Red River gage station is the sum of the discharges of the main trunk of the Mississippi, of the Red River and of the overflow, if any, through the Tensas Basin, less the discharge of the Atchafalaya. A certain gage reading at Red River will give, approximately, a certain gage reading at Carrollton, provided there are no crevasses between. The discharge of the Lafourche

is so small, even at flood stage, that it may be neglected in so crude a discussion as this.

In any examination of gage heights, to determine the tendency of floods to increase or diminish, the writer prefers the method of dividing the total period of available records into groups and comparing the averages, rather than picking out arbitrarily the maximum heights in two flood years and assuming that the difference between them indicates the rate of change, without a consideration of modifying condition.

The following are the averages of the three groups of flood heights of ten years each, at Red River and at Carrollton, from 1872 to the present time:

Station.	1872-1881.	1882-1891.	1892-1901.
Red River	41.43	43.77	41.00
Carrollton	12.50	14.57	14.95

It will be observed that the second decade shows an increase over the first at Red River of 2.34 feet, or $5\frac{1}{2}$ per cent.; and at Carrollton of 2.07 feet, or $16\frac{1}{2}$ per cent. The third decade compared with the second shows at Red River a decrease of 2.77 feet, or $6\frac{1}{2}$ per cent.; and at Carrollton an increase of 0.37 feet, or $2\frac{1}{2}$ per cent. The third decade, compared with the first, shows at Red River a decrease of 0.43 feet, or 1 per cent.; and at Carrollton an increase of 2.45 feet, or $19\frac{1}{2}$ per cent.

These figures, including all that are sufficiently complete and reliable for use, indicate no progressive change of importance at Red River, and a considerable but irregular increase at Carrollton. The former gage records the discharge of the valley across the thirty-second parallel, modified only by the distribution of discharge down the main trunk and through the Tensas Basin, while the Carrollton gage has been largely controlled by intervening crevasses.

This exhibit directly connects the increase of high waters at Carrollton, with the improvement of the levee system which followed the organization of the State levee boards and the first extension of Government aid early in the second decade, from 1882 to 1891, and with the continued and increasing vigor with which the work has been pushed, both by the States and general Government, since 1892.

In this connection, it may be interesting to give the record at Cairo, near the head of the valley, as it has been used at Red River and Carrollton. During the second decade the average of high waters was $10\frac{3}{4}$ per cent. higher than in the first; in the third it was

9 per cent. lower than in the second, and substantially the same as in the first decade.

The evidence of any present change in flood heights other than that accounted for by building of levees is entirely inconclusive. The author is of the opinion that the floods of the future will not increase, but may decrease. The reasons given, connected with the breaking up of ground for cultivation and the extension of irrigation, are probably good, as far as they go, for the western tributaries. But it is hard to believe that the extensive deforesting of the western slopes of the Alleghenies can fail to increase the rapidity and thoroughness of the run-off from these mountains, making the high water higher and the low water lower.

The building of levees commenced from small beginnings nearly two centuries ago, and since then has been the only method employed for the reclamation and protection of the alluvial lands of the valley. Since 1850 the levee system has received thorough study and full discussion. Humphreys and Abbot reached a conclusion in favor of a combined system of levees and outlets, but failed to find any suitable location for the latter. Abbot demonstrated the futility of attempting to grade up the lower lands of the valley by deposit from overflow. Barnard, Bailey, Forshey, Eads and many others advocated levees. The discussion occupied many engineers and entered both houses of Congress and their committees. While it raged the people who wanted to live and plant in the river States went on strengthening and extending the levees. It is now the adopted system because it is proved theoretically right and practically useful. Levees have caused no elevation of the bed of the river and no phenomena that were not anticipated, and have developed no insurmountable difficulties. They have at all times been, and they are now, worth every dollar they have cost. So well are those who live behind them satisfied of this that there is no relaxation of effort to complete the system.

Reservoirs may, in certain localities, serve as useful adjuncts for the regulation of high and low water discharge, for irrigation or perhaps for sedimentation, but their use will be limited by the want of suitable physical conditions and their great cost.

General Barnard, who was not only one of the ablest advocates of the reclamation of the alluvial valley by levees, but also the first and for a long time the only United States engineer who advised the improvement of Southpass by jetties, thus expressed himself in a criticism of General Ellet's plan of outlets:

"The idea that levees have any tendency to cause a rising of the bed is so simply absurd, so destitute of a single reason to justify

it, that it hardly seems necessary to allude to it. It is the want of levees, and that alone, which can cause such a rising, and in proportion as the water is let out from its confinement by levees, by means of crevasses or 'outlets,' will the bed of the Mississippi River be elevated.

"There is but one protection to Louisiana, and that is levees; outlets or lateral vents of any kind may be discussed, adopted by State authorities, perhaps attempted. If so, they will certainly deluge the unfortunate district through which their discharge is carried, while they utterly fail to relieve the river; producing, on the other hand, deposits in its bed, which they will eventually raise, and with it the surface.

"In brief, to take waters from the river channel and to throw them into the lateral basins, lakes and bayous is to take them from the channel by which they can, with the most ease and safety, be carried to the sea to put them into basins unsuited by their slope to carry off the floods thrown upon them."

MR. WILLIAM JOSEPH HARDEE.—Before entering into a discussion of the paper before us, the writer desires to apologize to the members of this Society for imposing on their time, and to beg their indulgence if what he has to say upon the subject is as extended or more extended than the original paper. The subject is a most vital one to the inhabitants of the alluvial valley traversed by the Mississippi River, and should not be lightly dealt with. To reach intelligent conclusions in the matter of flood heights necessarily involves the investigation of a very large field.

The harsh impeachment has been breathed that those engaged in the works of river improvement are perforce, for self-protection, banded together in supporting with great unanimity the methods being employed through apprehension that they might, like Othello, find themselves with their occupation gone. Such charge cannot be made in the case of the writer, as he is not now and may never again be identified with Mississippi River improvements. He feels, however, that his long connection with those works and his experience of many years spent in working on the river entitle his opinion to some weight without question as to his motives.

There is so much fallacious reasoning in the paper before us, appealing strongly as it does not only to the layman, but to the inexperienced engineer as well, that the writer feels it a duty he owes to the community in which he lives to exercise his best effort to defeat the circulation and acceptance of such unsound doctrines.

There are to-day but few, if any, subjects more perplexing to American engineers than the one of economically controlling the Mississippi River with respect to maintaining adequate depths for low-water navigation; providing against the destruction, by caving

banks, of valuable improvements situated in close proximity to its shores, and protecting against overflow the lowlands in the valley through which it flows.

The subject is, unfortunately, one in which not a large number of engineers are directly interested, and it has therefore challenged the attention of not many and the close and devoted study of but few.

No reliable conclusions concerning that part of the subject relating to increasing flood heights can be deduced from a study of the river at any one particular point, or of a very short length of it. The investigation should properly cover the entire length of the river from Cairo to the Gulf, for the purpose of disposing of matters of general bearing and influence; and then there should be considered a stretch of river, ranging from 100 to 200 miles in length, throughout which the levee line is continuous on both banks and no tributary streams occur to exert an extraneous influence. Consideration of a long length of river is essential to eliminate local vagaries and afford net results.

He who undertakes to study the Mississippi River intelligently soon finds himself in such a maze of ramifying data, many of which are apparently inconsistent or seemingly contradictory, that unless he be patient and persistent he will soon abandon his investigation.

After a careful consideration of the paper before us, the writer is forced to the conviction that its author undertook to discuss his subject with a preconceived *theory*, and in an endeavor to establish the correctness of that theory he has either failed to make proper research to inform himself fully or else he has ingeniously avoided reference to and consideration of such data as are properly germane to the subject, reviewing and employing only such data as he believed would support his theory. As far as employing data is concerned, he fails to go beyond the Carrollton gage, using only some controvertible data acquired at that gage upon which to base his theory. Where he does venture beyond the Carrollton gage his conclusions are mere opinions, unsupported by even apparently trustworthy data. The writer has already stated that reliable conclusions cannot be arrived at by a consideration of the river at one point only, as he will later on endeavor to demonstrate. He is so impressed with that belief that, on such account alone, he would disregard the conclusions reached by the author, no matter how well such conclusions appear to be supported by apparent facts. The author, fortified with specially selected data, endeavors by fallacious argument to prove that his "theory" is a "condition," predicated his conclusions principally on a comparison of dis-

charge observations measured at the Carrollton, La., station, propped up by some alleged but unproven facts, and some admitted facts so unimportant in effect as not to possess appreciable bearing on the subject. And, having satisfied himself and ostensibly his readers, that dire calamity threatens the Mississippi River Valley in the near future, he exhorts us to employ our best endeavors to discover some avenue which promises relief in a measurable degree, describing a general plan by which he believes adequate relief may be secured.

As the writer cannot admit that a calamity threatens, he will not indulge in a discussion of relief measures, but will confine his attention to a disproof of the conclusions reached by the author.

It may not be out of place, at this time, to remark that the question of utilizing the sediment carried by the waters of the Mississippi River for the upbuilding of the lowlands in the alluvial valley is one which is not altogether without merit, but the writer feels that it is a matter which time and circumstance will develop. The cost of the work incident to such an accomplishment would at this time so far exceed the value of the lands reclaimed as undoubtedly to render the project impracticable. The population of Holland averages 401 persons to the square mile, and such density of population enhances the value of land to a degree which justifies the large amount of money invested in dikes, extensive drainage canals and gigantic pumping stations to reclaim the land and protect it against inundation.

In Louisiana, the fifteen riparian parishes in the alluvial valley, the parish of Orleans included, average 71 persons to the square mile. In some of the parishes containing the largest areas of very low lands, the population per square mile is as small as 7 to 19 persons. Considering the present small value of lowlands in the alluvial belt, and the large tracts of cheap land available there for cultivation, it may be readily appreciated that our country has not yet reached a stage in its existence at which the expenditure of large sums of money is justified in reclaiming low, ill-drained lands. When such time arrives, some method, perhaps along the lines suggested by the author, will be employed to render lowlands available for agricultural pursuits.

From the writer's knowledge of how discharge measurements are conducted, gained from personal observation, he is confident that not even approximate reliance can be placed on the results obtained. Discharge measurements should be disregarded for purposes other than general approximations. They should never be employed to govern conclusions based on differences shown by a

comparison of results obtained at different periods for the same station or close analogy of results obtained at different stations. There are so many opportunities for accidental error which cannot be easily detected, that error of result is likely to range as high as 25 per cent. This opinion is shared by many of the officers of the United States Engineer Corps, under whose direction discharges of the Mississippi River are measured, as the writer knows from their personal expressions to him.

To illustrate the unreliability of the discharge records quoted by the author, and incidentally for the information of those members of the Society who may not be familiar with the detail work embraced in measuring those discharges, the high-water depths of the river being as great as 180 feet, the following description of the crude method commonly employed in the past is furnished:

Depths of water were measured with a cotton rope line weighted with a 7 to 20-pound weight of lead, depending on depth of water and velocity of current; velocities were measured with a Price self-registering current meter. In the early days, before a current meter was invented, velocities were determined by means of surface floats floating over a fixed base line. Both the soundings and velocities were measured from a steam launch of small size, which could be rapidly maneuvered.

The point at which the discharge is measured is usually designated as a "discharge station." At the station, a cross-section of the river is established on a line projected as nearly as practicable at right angles to the general axis of the current. The contour of the submerged portion of the cross-section is developed by a number of soundings taken from a steam launch moving backward and forward across the river a number of times. Sub-stations on the cross-section are then established at points marking the angles in the wetted perimeter. To minimize error, in the instance of long planes in the wetted perimeter, the sub-stations are established not further apart than 200 feet.

The depth of the river and the velocity are measured at each sub-station. The depths and mean velocity at adjacent sub-stations are averaged, and then multiplied by the distance between the sub-stations, thus determining the discharge, for any desired unit of time, for that particular division of the cross-section; the several sub-divisions are afterward summed up, and the total discharge for the station thus determined.

On the line of cross-section, on both banks of the river, there are placed, several hundred feet apart, two prominent targets, furnishing a range to guide the boat in taking position on the cross-

section. Sub-targets are located along the bank of the river on the upper side of the discharge station, two of which form a range, and so placed, as to position, that a projected line through them intersects the cross-section line at a sub-station. The targets, of course, are marked differently, so as to be readily distinguished by the observer on the boat.

The boat is moved to a point slightly above the sub-station to be measured; and, when it starts floating with the current, the lead is heaved and the boat either worked ahead or backed, as may be necessary to keep the lead line in vertical position and alongside of the boat. As it is difficult, after the lead has once touched the bottom, to maintain it plumb for any length of time because of deep water and strong current, it is important that it shall be cast just far enough above the line of cross-section to assure its reaching plumb just as the sub-station is reached.

It will be observed that there are two rather difficult points involved in determining correct depths. To begin with, the boat must be skillfully handled, and great care must be taken that it crosses the sub-station at its proper location, which circumstance can be determined only by the boatman through the intersection of the sub-range line and the main cross-section line. This is not easy to accomplish when it is remembered how easily a small light craft may be influenced by wind and current. The boatman must also take into account the depth of water and the velocity, to guide him in determining just how far above the station to go, and what position to take with respect thereto, to get his boat in shape for casting the lead, in order that the boat may cross the sub-station just about the time the lead line becomes plumb.

Each day, before sounding is commenced, the lead line is soaked for half an hour or so in water, then taken out, stretched and verified. It is always long or short, and the difference must be determined for different depths and applied as a correction to the depths measured.

On many occasions the writer has personally directed soundings of the Mississippi River, and on some occasions has himself handled the lead line. From his observations and personal experience he is certain that in depths ranging from 100 to 160 feet of water, flowing at a velocity of from 5 to 7 feet per second, it is impossible to secure a plumb lead line. There is always a considerable amount of swag throughout the center of the line; just how much cannot be determined, but certainly of sufficient amount to affect the correctness of the sounding.

Before commencing a series of discharge observations, the current meter is rated. This is accomplished in slack water by dragging the meter with a boat a number of times over a fixed base. The mean of a number of observations is taken as the fixed relation between a revolution of the meter wheel and a lineal foot. As it would be impossible, with the use of one boat and one meter during the day (the time in which a discharge must be measured) to measure the velocity at a number of depths on each sub-station, which should properly be done in order to secure close results, the inventor, Mr. W. G. Price, then United States assistant engineer, personally directing the discharge observations at the Carrollton station, after much study and innumerable observations, fixed, for depths of less than 20 feet, 0.4 of the depth below the surface as a point at which the mean velocity occurs, and, for depths in excess of 20 feet, 0.6 of the depth below the surface as the point at which the mean velocity occurs.

To one having knowledge of the Mississippi River, who will pause to consider the general turbulence of the flow of its waters, the number of cross-currents, boils, eddies, etc., it does not seem reasonable that the mean velocity should really occur at the depths above described. In the opinion of the writer, this arbitrary use of a fixed percentage of depth, without allowance for local conditions, at which to measure mean velocities, contains considerable element of error.

In measuring a discharge, the first thing done, after checking the lead line, is to make one sounding at each of the sub-stations. If the sounding corresponds closely with the depth found on the preceding day, the boat passes on to the next sub-station; but if any considerable difference be found, a number of additional casts of the lead line are made, in order to verify the sounding and make certain that some change of depth has taken place since the preceding day.

The writer is informed by assistant engineers, who have measured discharges at the Carrollton station, that differences as high as 4 feet have been noted from day to day at a sub-station. Since depths are measured at the sub-stations only, no determination is made of changes, if any, between sub-stations. It will be observed that in this respect there is opportunity for considerable error in the area of that sub-division of the cross-section.

When the depths throughout the discharge section have been determined, the boat takes position in turn at each sub-station. The machinery is worked ahead, just sufficiently strong to overcome the current and maintain the boat in a fixed position; the

meter is then lowered to proper depth, and usually is operated for three minutes. The total number of revolutions is registered on a gage on the deck of the boat, the observer closely watching the gage to see that the meter is running evenly. By reducing the total number of revolutions to the equivalent per second and applying the meter rating, the velocity of that sub-station is determined. The opportunities for accidental error in this part of the work of measuring the discharge are not small. The observer must trust to his boatman to keep the boat steady and in proper position, and, as has been stated, it is doubtful that the depth used is the point at which the mean velocity really occurs. Further, the meter is rated but once during a season; its mechanism is delicate, and likely, at any time, to become deranged, affecting all reductions based upon the original rating. It must also be stated that the position of sub-stations is not altered from time to time to meet occurring changes in the bottom of the river.

It would seem almost certain that, with such great opportunities for error, considerable error does occur. The writer is aware that in the past some of the observers have been almost criminally careless in the performance of their duties. He knows of one observer, whose work forms part of the records of the Mississippi River Commission, who, through an entire series of discharge measurements never had a lead line cast after the contour of the cross-section was first developed; he contented himself with merely applying the change of gage height to the original depths. A canvass of the records and the inconsistencies found, alone proved that the discharge measurements are not reliable within close limits.

In 1880, June 12 and June 16, Carrollton gage registered 7.6 feet; in the former instance the discharge was 581,000 cubic feet per second, whereas it was only 553,000 cubic feet per second in the latter instance.

Again in 1851, July 2 and July 19, Carrollton gage registered 12.2 feet; in the former instance the discharge was 805,000 cubic feet per second, whereas it was 856,000 cubic feet per second in the latter instance.

Again in 1883, April 28 and May 1, Carrollton gage registered 14.2 feet; in the former instance the discharge was 972,000 cubic feet per second, whereas it was only 941,000 cubic feet per second in the latter instance.

Again in 1890, March 6 and 7, Carrollton gage registered 15.2 feet; in the former instance the discharge was 1,175,000 cubic feet per second, whereas it was only 1,128,000 cubic feet per second in the latter instance.

The difference in the discharges for the same gage reading may be due to error of measurement or they may be due to natural changes in the cross-sectional area caused by a rising or a falling river. It does not matter to which cause the difference is chargeable, the fact remains that a discharge determined at a gage reading on a particular day cannot be relied upon as being the same for a similar gage reading at some distant date, a fluctuation of gage height having occurred in the interim.

It will be noted that the author of the paper under discussion rests his case almost entirely on conclusions reached through a comparison of discharge measurements. The writer believes that in doing so he has committed a grave error, because not only are the records in that respect faulty, but if they were absolutely correct his case would still remain unproven, since a change in the carrying capacity of the river cannot be established by observations taken at one point only. The discharge is controlled not by the gage height only, but also by the slope existing at the time and place of measurement.

It is a law of hydraulics that, if, during a given period and over a given length of river, there has been no net loss of cross-section, and if the elevation of water at the upper end should be increased while at the lower end it remains constant, there will follow increased slope, producing increased velocity, and consequently increased discharge.

The writer, therefore, believes that the author, in seeking to determine whether less discharge occurs at the same or greater gage heights, should have altogether disregarded a comparison of discharges measured at one point only, and should have given his attention to a determination of the changes that have taken place in the carrying capacity of the river.

One of the peculiarities of the Mississippi River is the rapidity with which the area of a given cross-section will vary under the influence of changes in the axis and velocity of the current caused by a rise or fall in the river and a variation in the amount of sediment it is carrying. The records abound with corroboration of that statement.

On a given cross-section the bottom will, to-day, scour in places and shoal in others. Within the short interval of a few days that result will be found to have been reversed, the abrasions having disappeared and accretions beyond the original elevation having occurred, and *vice versa*. At times a net increase and at other times a net decrease of cross-sectional area will be noted.

An increase or decrease of cross-sectional area at one point may be compensated by a corresponding change in the cross-sectional area at a point a short distance below.

It may also occur that there will be either a net increase or a net decrease of cross-sectional area throughout a short length of river, so that, to determine what change in the carrying capacity of the river, if any, has taken place, a long length of river must be considered, and its experiences gathered at about the same gage heights noted, to eliminate local vagaries; in such an instance the net result may be accepted as conclusive evidence whether or not the carrying capacity of the river has remained the same, or whether it has increased or decreased.

The author of the paper under discussion alleges that the carrying capacity of the river is steadily decreasing, which, in his opinion, forces any given volume of water to attain a higher elevation in passing a given point. A similar allegation has many times been made by many persons.

The Mississippi River Commission, in search of light and truth on the subject, and for its information and guidance, had an investigation made by its principal assistant engineer, Mr. J. A. Ockerson, of the 202.7 miles of river extending from Riverton to Vicksburg. Within that distance 554 cross-sections, which were measured during low water in 1881-1882, were measured during low water in 1894 for purposes of comparison. Mr. Ockerson's report, entitled "Comparisons of Cross-section Elements of the Mississippi River," was published by the Mississippi River Commission, from whom a copy may be obtained, and members will find it very interesting. Referring therein to his investigation, Mr. Ockerson says:

"In order to separate the results for pools and crossings, the river has been divided into a series of sections in such a way that the results for the pool sections and bar sections have been summed separately. This is done to detect, if possible, any difference in movement of bed under the two conditions of pool and bar."

After a most careful analysis and review of the subject in a report covering twenty-nine pages of closely printed matter, Mr. Ockerson expresses the following conclusions:

1. The channel capacity in 1894 was greater than in 1881-1882, due to changes above the low-water line.
2. The crests of the shoal bars in 1894 were, on the whole, lower than in 1881-1882. This refers to the actual elevation of the bottom and not to the top of water on the bars.

3. The maximum depth of pools was generally less in 1894 than in 1881-1882.

4. The thalweg depths were, on the whole, less in 1894 than in 1881-1882. That is, a little more than one-half of the length of the river under consideration, and also the average of the sections, shows an elevation of the thalweg or raising of the bottom. A large percentage of this raising occurs in the pools.

5. The high-water bars lying between the medium and bank-full stages have been cut down an average of something over one foot.

6. The general tendency seems to be toward a channel more uniform in depth and of greater capacity.

The author of the paper under discussion charges diminution in the carrying capacity of the river to the three following principal causes:

1. Construction of levees on lines not calculated to maintain a constant cross-section of that part of the river above the natural bank.

2. Moving back of levees around caving bends, thereby materially increasing the distance to ocean level.

3. Diminution of channel by accretions on the sides and bottom of the river on the apex side of bends without corresponding abrasion on the opposite side.

Referring to reasons 1 and 2, it may be stated that, by actual measurement at the office of the United States engineers in this city, from Baton Rouge to Carrollton, the average distance the levee line is removed from the natural bank on the west side of the river is 358.68 feet and 340.26 feet on the east side, making an aggregate of 698.94 feet of batture, or foreshore, between the natural bank and the levee line.

It is a well-known fact that the flow of the river over the battures or foreshores is largely obstructed by eddies, spur levees, vegetation, and other obstacles. If, however, we apply, to this width of say 700 feet, an extreme depth of 5 feet and an extreme velocity of 4 feet per second, we shall have the small amount of 14,000 cubic feet of water flowing above and beyond the natural banks. The amount is an inconsiderable part of a discharge so large as a million or more cubic feet per second. In fact, the flow over the battures is rarely measured and included in the discharge recorded for a station.

It will scarcely be denied that, in the three respects cited by the author of the paper before us, the length of river, from Riverton to Vicksburg, possesses more favorable elements for proving the cor-

rectness of the author's arguments than does the river from Baton Rouge to Carrollton, a length of 125 miles, which is as great a length above Carrollton as can be reasonably counted on as exerting an influence on the gage at that place.

Between Riverton and Vicksburg the river is made up of a succession of deep bends, with little or no length of straight river between the bends; the levees are anywhere from a few hundred feet to five miles or more from the natural bank, since, when rebuilt to meet the demands made by destructive caving banks, they are retired to a distant location. That length of the river is very variable. The bars build up rapidly, and middle ground bars form, splitting the channel and tending to obstruct the flow of the river.

On the other hand, the river between Carrollton and Baton Rouge is fairly straight; there are but few sharp bends and many long lengths of straight river. The levees are quite uniformly removed from the natural bank, there being but one point, Bonnet Carre, at which local conditions force an unusual retirement for a length of about a mile, and the retirement there does not exceed 2600 feet. Levees which must be retired because of caving banks are rebuilt on locations but a few hundred feet distant. The length of the river is almost constant. The bars do not build up rapidly, and serious middle ground bars obstructing the flow of the river are rare and never extensive. If, in a length of river where all things combine to favor the author's theory, that theory fails, does it not stand to reason that it must fail when the circumstances are less favorable?

The writer at least believes so, and he is further convinced of the soundness of his opinion, that the carrying capacity of that part of the river which might exert an influence on the Carrollton gage has not diminished, by a consideration of the conclusions reached, after careful investigation and analysis, by Major Geo. McC. Derby, Corps of Engineers United States Army, in charge of the work of improving the Mississippi River.

The writer had the pleasure of assisting in that investigation, which eventuated in a report dated March 16, 1900, addressed to the Mississippi River Commission, from which the following excerpts are taken:

"In general it may be said that any study of the relations of gage heights, while exceedingly interesting, is apt to be on the whole rather unsatisfactory; the number of variables in the problem is so very great that the mind is baffled in its efforts to keep track of them, and at the end remains unsatisfied as to the soundness of the conclusions reached. It fortunately so happens, however, that there is one long stretch of the Mississippi River, where, through

natural causes many of the variables of this perplexing problem have been eliminated; this tempting field for investigation is of course the stretch of 200 miles lying between the mouth of Red River and New Orleans. At the next gage below New Orleans the flood heights are so low and the mouth of the river is so near, that the tides of the Gulf, small as they are, are sufficient to introduce perplexing complications; while above Red River, outlets and tributaries combine with all the other uncertainties to make the problem as difficult as it well can be. Between Red River and New Orleans there are practically no tributaries, and but one small outlet; the length of the river is about constant; the levee system is less variable than elsewhere; and the effect of the tide at the Carrollton gage is so slight that the height of the river may be assumed to be controlled entirely by the stream of water coming from above, unaffected by variations of level having their origin below.

"During the flood of 1897, which broke the high-water record at every gage in the Fourth District, I was a good deal surprised and impressed by the fact that the first gage to exceed its previous record was the lowest one,—namely, the gage at Fort Jackson, the next was the Carrollton gage, and so on up the river to Red River Landing, where the gage did not exceed its previous record until sixteen days after the Carrollton gage had done so.

"What was scarcely less surprising was the fact that when the Carrollton gage reached its former maximum (17.45) the gage at Red River Landing still lacked 1.6 feet of the height which in 1893 had produced that maximum.

"Both of these remarkable facts point *at first sight* to the much-looked-for raising of the bed of the lower river, with the consequent increase of flood height, which so many have claimed to be the ultimate effect of levee building.

"Before attempting to seek the cause of these phenomena it will be well to ascertain first whether they represent merely curious anomalies peculiar to the flood of 1897, or whether they indicate any well-established tendency to a change in the regimen of the river."

Tables are submitted showing the ratio between the Red River Landing and Carrollton gages for all the flood waves that passed the former place at stages of about 45.2, 43.6 and 39.3 respectively.

Continuing, Major Derby says:

"More evidence to the same effect could be adduced, but the above seems to be sufficient to establish clearly the proposition that the striking feature of the flood of 1897 under discussion, was not something abnormal, but that, on the contrary, such a change in the regimen of the river has actually taken place that we must now expect that any flood wave passing Red River Landing at a high stage will cause a flood wave at Carrollton a foot or more higher than a flood of the same height at Red River Landing would have caused fifteen or twenty years ago.

"Now, if this is actually a fact, it must be due to one or more of the three following causes:

"1. A raising of the bed of the river below Carrollton, causing a decrease in the carrying capacity of that portion of the river.

"2. The effect of crevasses and their closure.

"3. An increase of the carrying capacity of the river between Carrollton and Red River Landing.

"I will consider each of these possible causes in turn.

"1. Has the bed of the river risen?

"If the apparent increase in the flood height at Carrollton is due to the filling up of the bed of the river below, it is manifest that such an effect would be proportionately more noticeable in the case of a low flood wave than it would be in great floods.

"I accordingly submit tables showing the gage readings for many small flood waves which passed both gages well within the banks of the river, a type of waves which usually receives but little attention, but which is in some respect more instructive than the greater waves.

"An examination of these tables not only shows that the apparent increase of flood height at Carrollton is not more noticeable at low stages than at high ones, but it reveals, on the contrary, no trace whatever of any such apparent increase.

"I conclude that whatever else the apparent increase of flood height at high stages may be due to, it is certainly *not* caused by a rise of the bed of the river below Carrollton."

Major Derby also shows that the results observed are not due to crevasses, and, continuing, says:

"If we are right in the conclusion that the apparent increase in the relative height of the Carrollton gage is not due to the filling up of the bed of the river below, nor to the effects of crevasses above or below, there must have been an increase in the carrying capacity of the river above Carrollton, the following tables, with the others already given, show that this increase in carrying capacity must have taken place at such a height in the bed of the river as to manifest itself only at stages above 27.0 on the Red River Landing gage (highest gage record 50.2).

"In the annual report of the Mississippi River Commission for 1899 the surveys made between Red River Landing and Donaldsonville are discussed with results which are corroborative of the above discussion of the gage readings, the conclusion having been reached that the comparison of the results of all the surveys seems to show conclusively that there had been a general tendency to the permanent enlargement of the stream *above the low water line*, and the capacity of the river to discharge its flood waters has been more than maintained.

"The practical effect of this increase of the carrying capacity of the river between Carrollton and Red River Landing is to diminish the high-water slope, so that a flood wave producing a given height at the Carrollton gage would pass Red River Landing to-day at a level several feet lower than would have been the case fifteen or twenty years ago. In other words, since the crevasses have been closed and the levee line maintained with few

or no breaks, there has been a notable decrease of flood height at Red River Landing, amounting apparently to 3 feet or more."

Observe that Major Derby conclusively demonstrates that the carrying capacity of the river has decreased neither above nor below Carrollton; that, on the contrary, there has been a well-defined tendency toward enlargement.

The writer had plattings made of the only five cross-sections of the river, at the Carrollton discharge station for which reliable records are accessible, and the areas below the zero of the gage computed, with the following result:

Year.	Gage height.	Area below zero of gage
1883	15.4	137.178 square feet.
1891	14.8	144.153 " "
1893	17.2	151.881 " "
1895	2.0	143.750 " "
1896	6.1	143.785 " "

This table certainly shows no evidence of a progressive decrease in the cross-sectional area, but rather the reverse, as we have, in 1895 and 1896, at a low stage, a greater area than we had in 1883 at a high stage. But, as has been stated earlier in this paper, the elevation of the bed of the river at any given cross-section varies from day to day, as the river rises or falls; and, whether or not the carrying capacity is increasing or decreasing, can be ascertained only by determining the net change in a long length of river.

One of the most remarkable of the statements in the paper under discussion is that the development and improvement of the watersheds of the Mississippi River and its tributary streams will decrease the maximum volume of future floods. The writer has always believed—in fact, has never before known the proposition to be challenged—that the deforestation in the great watersheds and the improved drainage of lands there, must necessarily cause retention of less of the rainfall by the soil, but will affect its more rapid delivery to the main drainage arteries, resulting in not only greater volume in the Mississippi, but temporary increased height, because of the rapid assemblage of waters in that stream.

The author of the paper under discussion finds great comfort for himself, and support for his theory that the levees must be raised not less than 10 feet higher than at present by the year 1950 in what he designates as the bold assertion of Mr. Chas. Ellet, made in 1851, to the effect that the levees would have to be raised 2 feet higher than they then were to restrain successfully such a flood as occurred in that year. There is no evidence to show that Mr. Ellet reached that conclusion through the reasons assigned by the author. It is

more likely that he had a more intimate knowledge of the Mississippi River than did his associates, and that he was wise enough to realize that 2 feet additional height of levees was a fair estimate of the requirements to retain between the levees such a flood as that of 1851 and to care for such volume of water until such time as the energy of that flood, augmented by the energy of others to follow, would increase the carrying capacity of the river.

Had Ellet known that the immense low-lying basins in the alluvial belt would be rapidly leveed at some comparatively early date, he would doubtless have expressed the opinion that the levees would have to be raised five or more feet instead of two to successfully carry between them to the sea such floods as that of 1851.

The author of the paper before us says that the Government engineers, in recommending the "all-levee system," did not take into consideration the serious effect of increasing the elevation of floods, etc. In this he is mistaken. In 1880, when the Mississippi River Commission first came into existence, it was without anything like complete and reliable data upon which to base its future operations, nor was it equipped with funds for levee work. From time to time, as far as its funds would permit, it joined the local levee organizations in the general work of restoring and maintaining the continuity of the levee line to a grade one foot higher than the highest previously known water. It was fully recognized, at that time and since then, as the transactions of the commission will show, that the grade used was forced by economy. It was deemed advisable, since the levee system would be no more efficient than its weakest lengths, to restore the entire system to some practicable grade, rather than to have gaps in the line and some lengths of such comparatively extraordinary height as not to render maximum service for years to come. As soon as the continuity of the levee line was re-established and there were funds with which to improve the existing system, the commission adopted a provisional grade as the next practicable step to which to advance the height of the levee line. About that time the extension of the levee system along the fronts of previously unleveed immense alluvial basins was undertaken, and has since been continued. This extension of the levee system produced a change of flood conditions, which made it very difficult to answer with precision the question of a grade competent to care for future floods. The problem would have been more easily solved if only the retention of flood waters between the then existing levees had to be dealt with, but the introduction of the new factor, the leveeing of new basins, made the problem more perplexing.

Future flood heights and ultimate levee grades were the subject of much discussion by the members of the Mississippi River Commission and eminent levee engineers, Captain Townsend, of the Army Engineer Corps, and the late Major Wm. Starling, of Greenville, Miss., contributing valuable papers, which will be found in the Transactions of the American Society of Civil Engineers.

When the levee line had been nearly uniformly raised to the first provisional grade and the system had been considerably extended, the greatest flood of record, 1897, occurred. From the observations derived from that flood, a new grade was adopted, which it is confidently believed will meet all future requirements, except probably a most extraordinary coincidence of maximum rainfall in the valley of the Mississippi River and its tributary streams.

The author of the paper under discussion appears ignorant of the facts just related, and overlooks the effect exerted on flood heights in the lower river by increased flood heights in the upper river, which were anticipated and produced by causes easily comprehended.

One of the good arguments advanced in support of levees lowering flood heights by increasing the carrying capacity of the river, is contained in the following paragraph in the paper under discussion :

"Were the Mississippi River not leveed in or no artificial works constructed along its banks, it would, when rising above its normal banks, overflow and deposit its sediment on the adjacent banks and the surrounding country, and as it gradually elevated its banks and the surrounding country, and gradually withheld the waters from overflowing, it would scour a channel of the desired width and depth to convey the volume to the sea level."

If the river will do, naturally and by slow degrees, what the author says it will do, why should it not do so just as effectively, yet more rapidly, with the assistance of artificially elevated banks?

The writer is firmly convinced that the levee system is a success; that it is performing its mission well, and will continue to do so; that it will in time prove the means of increasing the carrying capacity of the river; and, that floods of a given volume will pass to sea level at lower elevation than formerly.

MR. SIDNEY F. LEWIS.—In the study and solution of the problems of the Mississippi River, the engineer has to depend more upon facts, and the relations they bear to one another, than upon any fundamental principles to guide his work.

He must analyze and classify all the reliable data on the subject in order to obtain these relations of fact before he can ven-

ture to build a theory. We recognize the value of the three principal mechanical laws as applied in hydrodynamics, the A, B, C, as it were, of the subject, which make up the theory of flow, as expressed in the formula, "Velocity of flow in a stream varies directly as the square root of the product of its hydraulic radius (the ratio between the sectional area of the part of the bed it occupies, and the frictional or resisting surfaces bounding it, known as the wetted perimeter) by its slope (the ratio between its fall and length)" as of prime importance to the engineer who lays a pipe or builds a conduit, for by this formula he can determine the form and set the slope, and the resulting flow will be the one thing that he wants to know; but the flow in a sedimentary stream, like the Mississippi River, makes its own form, and that a very irregular one, and so distributes its slope that it may be almost all concentrated at a certain point at one stage, with little or none there at a different stage. Here there is not much use in trying to express the velocity by $V = C\sqrt{RS}$, for R and S are more difficult to measure than V.

Those of us who are more familiar with the vagaries of this river, and who are employed daily in its observations and operations, know that the "guess and allow," the "average judgment" and the "personal equation" figure immensely in the determination of C, the experimental coefficient.

The author of this paper by his ingenious methods of interpolation and interpretation from his point of view of the relation of certain gage readings, velocity, slope and discharge observations in some thirteen high water years, all of which he calls great floods, builds up a theory and arrives at conclusions, which, to say the least, are appalling, and well worthy of all our energies to thwart and prevent. We live, however, in that consolation which the author metes out to us, when he informs us that this dire calamity, at a rate of one foot increase of elevation to the levees every five years, will take place in 1950. The writer would suggest to the younger members of this Society, who will have passed the age of three score and ten allotted to man, that when that momentous day arrives, they gather all the literature on the Mississippi River, instruments and other paraphernalia, and go to the then existing mountains on the New Orleans front, and offer them in sacrifice to the deity of the "Father of Waters," and further invoke the Almighty, of whom it is written that He created this universe in six days, and that after resting on the seventh, in the contemplation of His great work, He concluded that all was well with one excep-

tion,—He had failed to complete the Mississippi River. To man, made in His own image, He has relegated this task, and if it be beyond the brains and ability of man to master it, why let us pray to Him for a second "Appalachian Revolution," so that He can correct His first mistake, and turn the flow of this great river up stream toward the North Pole instead of the Equator, for it is the shortest distance by that route to the center of the earth.

The writer is inclined to be optimistic in his views. He believes that the universe, being the work of an infinitely perfect being, is the best that could be created; and with regard to levees, they were not built out of theory, but are an evolution from a matter of necessity.

Those "well-banked potato rows" which the author speaks of in the introduction of his paper as existing in the Third District some twenty years ago, the writer, as a boy forty years ago, knew to be levees of a fair size and section. They were first located and built upon the banks of a bend, known generally as the crescent of this city, and, from time to time, as caving developed, they were moved back to circumvallate the caves, and, at every recession, owing to the natural slope or lay of the bend, their dimensions necessarily had to be increased. A few years previous to our great high water of 1897, a few of the stretches of levees in this bend passed through an evolution of woodwork construction; the requisite section of earth was superseded by plank, posts and tie rods, and braced to the stone gutter curbs of the Front street. They were called "boxed levees." They were the source of a great deal of worry and uneasiness during the high water of 1897, but by a great deal of work done upon them, principally in rebracing, they withstood the pressure of that high water.

To-day, by the author's advice and recommendation, these stretches of levee have been removed riverward with increased dimensions, part of the section of earthwork is built out on a prepared base of piles 70 to 80 feet long, driven at uniform distances apart, and abutting a water tight sheet pile bulkhead on the front, with the expectation of replacing this pile bulkhead revetment later on, with a river slope of solid earth, to be supported on a pile foundation,—another stage of evolution. The writer lives in hope that the pile wharf revetment protection work to the bend of the river along the Third District front, the design and execution of the author, will keep these levees from caving off into the river in the next decade or two.

As to the levees on the commercial front in 1717, when they were first built by De La Tour, they were probably "well-banked potato rows," and served the purpose of the limited area they then protected from inundation. To-day a greater part of the commercial front, outside of the original levee line, has been reclaimed to the city by accretions. In this fact we recognize that while the "Father of Waters" is inclined to be bold and bad in many of his ways, giving us a ducking occasionally, and an unkind cut here and there in the bends, yet there is much to be said to his credit, in which the commercial front of New Orleans will bear him out.

From these beginnings in 1717 has evolved the "all-levee system" as it exists to-day, and the writer believes that the portion of it in the delta section of the Lower Mississippi will stand on its own basis and merit. The immediate and most potent motive of its advocates is the reclamation and protection of the alluvial lands of the State bordering on that stream, and the efforts in this direction will not cease until the purpose is accomplished.

MR. L. W. BROWN.—The impression seems to prevail that my paper refers to the Lower Mississippi, as embracing only that portion from the Red River to the Gulf. The arguments relative to increasing floods, their cause and the remedy, as advanced, embrace the river from Cairo to the Gulf; and, as verbally explained to Major Harrod at a previous meeting, the construction of reservoirs, as relief avenues for floods, refers more particularly to that portion from Red River to the Gulf where avenues of escape to sea can be most readily secured. The paper refers to the construction of reservoirs above the Red River, but rather for irrigation than as a relief measure.

The paper records the statement that I am not opposed to levees; and I desire to emphasize the statement so as to positively remove any impression to the contrary, by advising that I consider the levees absolutely necessary; but, as stated in my paper, I consider that levee building, on the lines now adopted, and without the execution of other equally important work in connection therewith, will in a few decades entail disaster to all interests in the alluvial sections, notwithstanding the united opinions of the savants of river and levee matters to the contrary.

I would observe that both Major Richardson and Major Harrod have, in their discussion, studiously avoided any reference to the absolute fact that the levees are enormously higher to-day than two decades ago; and I would further observe that

the levees in 1897 were only by great exertion made to answer their purpose, and that the high and substantial levees which existed in 1897, as compared with the low and weak levees of 1882, offered no greater security against inundation; and as history never fails to repeat, when mankind is inactive, it is not improbable that in 1905, or earlier, the existing levees, which are mountains as compared with those of 1882 or 1897, will be found small and weak, and that protection will require more labor to reinforce and supplement than was required on the levees of 1897, the total cost of which will never be known; but the cost of reinforcement and losses from all causes will probably exceed \$100,000,000.

Major Harrod makes use of the following expression:

"The phenomena of any one part are explainable only by a comparative study of all parts where similar conditions prevail."

How could this maxim be applied to the Mississippi River in 1897, when all the parts embraced such phenomenal conditions as produced most disastrous effects, and when there existed no condition by which a comparison of any one part could be made. Hence, there being no means to define the cause of the phenomena of 1897 by comparison of one part of the river with another, the cause is sought to be secured by an inquiry into the effects which the work done by the Mississippi River Commission has produced on the river, by a comparison of the same parts of the river, or of the whole river as refers to some important fundamental element of the river, such as slope, velocity, cross-section, etc., or, if no work had been performed in attempting to improve the river, the same investigation would be necessary to determine what was producing the disturbance, and, when found, to determine to what extent mankind could assist in providing against reoccurrence; and I propose to show, replying to Major Harrod's discussion, that the improvements now being made on the Mississippi River are causing serious interference with one of the fundamental elements of the river,—viz, the slope. With a view of fortifying my conclusions, I will quote a portion of the fourth section of the act of Congress, approved August 29, 1879 (twenty-two years ago), which gave life to the Mississippi River Commission, and which reads as follows:

"SEC. 4. It shall be the duty of said commission to take into consideration and mature such plan or plans and estimates as will correct, permanently locate and deepen the channel and protect the banks of the Mississippi River; improve and give safety and ease to

the navigation thereof; prevent destructive floods, promote and facilitate commerce, trade and the postal service, and when so prepared and matured, to submit to the Secretary of War a full and detailed report of their proceedings and actions, and of such plans, with estimates of the cost thereof, for the purpose aforesaid, to be by him transmitted to Congress."

I refer to the above to show that Congress positively directed that the plans of the commission should embrace the protection of the country against destructive floods, and the instructions are in the most emphatic terms, "It shall be the duty of said commission to mature such plans as will prevent destructive floods." In passing this act, Congress unquestionably realized the importance of the floods of the Mississippi, and that the work of the commission appointed in 1874 to investigate the river, as contained in their report to the Forty-third Congress, second session, embraced the necessary investigation and consideration by eminent hydraulicians to enable the commission appointed in 1879 to proceed with absolute certainty of results; and it is interesting to observe the language of the two acts. The act of 1874 directs that a report shall be made of best methods to protect the alluvial lands against inundation; whereas, the act of 1879 is a positive order to "prevent destructive overflow."

The direct questions may be asked, have the results of the work done by the commission during the past twenty-two years, embracing an expenditure of \$35,000,000, carried into effect the direct order of Congress, as issued in 1879? As a matter of fact, has not the expense entailed on the various States, parishes and individuals depending on levees for protection, increased tremendously since 1880, or since the plans of the Mississippi River commission were adopted and partially executed; and does not the rate of increase of cost and height of levees, between 1880 and 1901, very largely exceed the rate for any period of twenty-two years from 1828 to 1880; and have the alluvial districts of the Mississippi been more secure against inundation during the past twenty-two years than they have for any like period prior to 1882; and during the past twenty-two years have not the actual losses from inundation far exceeded those of any like period prior to 1880?

I propose to establish, by the writings, theories and actions of the Mississippi River Commission, that the slope is decreased in proportion as the height of floods are by their own works increased, and will use the recorded and published observations of the commission for evidence.

The following is a quotation from the original report of the Mississippi River Commission to Congress in 1880:

"The bad navigation of the river is produced by the caving and erosion of its banks and the excessive widths with the bars and shoals resulting directly therefrom. It has been observed in the Mississippi River, and is indeed true of all silt-bearing streams flowing through alluvial deposits, that the more nearly the high-river width, or width between the banks, approaches to uniformity, the more nearly uniform will be the channel depth, the less will be the variations of velocity and the less the rate of caving to be expected in concave bends.

"This would seem to be so in the very nature of things, because uniformity of width secured by contraction will produce increased velocity, and therefore increased erosion of the bed at the shoal places, accompanied by corresponding deposit of silt at the deep places.

"Uniform depth, joined to uniform width, that is to say, uniformity of effective cross-section, implies uniform velocity, and this means that there will be no violent eddies and cross-currents, and no great and sudden fluctuations in the silt-transporting power of the current. There will, therefore, be less erosion from oblique currents and eddies, and no formation of shoals and bars produced by silt taken up from one part of the channel and dropped in another.

"As the friction of the bed retards the flow of the water, any diminution of the friction will promote the discharge of the floods. The frictional surface is greater in proportion to volume of discharge where the river is wide and shoal than where it is narrow and deep. It follows, therefore, that after the wide shoal places are suitably narrowed, and the normal sectional area is restored by deepening the channel, the friction will be less than it was before. This will result in a more easy and rapid discharge of the flowing water, and consequently in a lowering of the flood-surface. It would seem, therefore, that the plan of improvement must comprise, as its essential features, the contraction of the waterway of the river to a comparatively uniform width; and the protection of the caving banks.

"INITIAL WORK.

"Under the authority conferred in Section 5 of the act, estimates of cost of certain initial works, constituting a component part of the general system of works contemplated, as submitted.

"These works of channel contraction and bank protection, which in the judgment of this commission, may be advantageously undertaken during the coming fiscal year or as soon as Congress supplies the means, are confined to an aggregate length of 200 miles of the shoalest water below Cairo, embracing the following localities,—namely, New Madrid, Plum Point, Memphis, Helena, Chocataw Bend and Lake Providence."

For good reason, no doubt, although the public is not informed as to that reason, the general plan of contraction of channel and

providing uniform width between banks, uniform cross-section and velocity, as originally determined upon, seems to have been abandoned, and, perhaps for the welfare of our section, it is fortunate that the original plan was not carried out.

It is interesting to note the conclusions of the commission when the inauguration of the work was recommended in 1880. The reports say that the first work "is confined to an aggregate length of 200 miles . . . embracing the following localities,—viz, New Madrid, Helena," etc. All this initial work recommended is located from 600 to 800 miles from the outlet of the river; and all the money expended by the commission for twenty-two years, except some small and spasmodic levee building and useless mattress planting, has been spent in endeavoring to protect the work done by the commission in the upper reaches, in violation of nature's laws, and which would perhaps have been found unnecessary, as the bad conditions in these upper reaches would have corrected themselves had the necessary assistance been provided by improving the outfall; hence a maxim: "To improve the flow or discharge in any stream, improve the outfall and thus increase the slope."

The work done on the Mississippi River during the past twenty-two years is illustrated by a municipality which has a proper and well-proportioned sewerage or drainage system, and in which, as the city grows, considerable expenditure is made in the enlarging and extension of the laterals without any improvement of the main outlet, and experts are called to demonstrate why the system is defective. The main trunk of the Mississippi, between Vicksburg and the sea, is defective, and requires such improvement that the slope will be increased in proportion as the elevation of surface of floods is increased by greater volumes.

The report of the commission, in 1880, contains the following:

"It follows, therefore, that after the wide shoal places are suitably narrowed, and the normal section area is restored . . . this will result in a more rapid discharge of the flowing water and consequently in a lowering of the flood surface."

The above is precisely in line with the recommendation made in my paper; and I contend that the line of levees must be constructed on lines to give the velocity determined as proper in that portion of the river in which they are located; but the inauguration of the work must be at the outfall, and the determination of required velocity at different parts of the river must be decided by the observation and consideration of the conditions secured by the work from the outfall upwards.

Has the commission executed any work, according to the strict interpretation of the first quotation above from their report of 1880? Are they building levees, or recommending them to be built, on the lines suggested by their report? Are they holding caving banks or attempting in any way to maintain the concave sides of bends, which is necessary to carry out their recommendation to secure uniform width, cross-section, velocity, etc.? And does a glance at their reports, or does actual observation, show either that their works of bank protection are stable or that they satisfactorily answer their requirements? As a matter of fact, does the value of the bank protection works which have not washed out and which are now serving any purpose, amount to 10 per cent. of the money expended for their construction? Is it not evident that all the work done by the Mississippi River Commission during the past twenty-two years has been on lines contrary to known hydraulic laws, and is there any reason why the work should not fail? Was it not the proper plan to inaugurate work at the outlet of the Mississippi River and improve the discharge to the sea before attempting to improve the upper trunk and laterals?

The decreasing of slope with increasing flood elevations conclusively proves that hydraulic laws have been violated in connection with the river improvements.

The theory of the plans of the Mississippi River Commission, as generally understood, are that an increased velocity and reduced flood elevations will result from confining the volume, and that any outlet, whether a natural bayou, crevasse or waste weir, would not decrease the flood elevation, except within a few thousand feet of the opening, and would, further, absolutely increase the height of flood slope throughout the river. That the theory, as practiced by the Mississippi River Commission, is an absolute violation of hydraulic laws is shown by the fact that any increase of flood elevation at Cairo or Memphis occasions a flood elevation at Red River and Carrollton, which is very much higher in proportion than such a conclusion would determine proper; in fact, the actual heights, at the several points, above those of preceding seasons of high water, are about the same, or, perhaps, more at the lower end of slope; whereas, with a rise of say 3 feet at Memphis or Helena, the proportional height would be only a few inches at Red River and Carrollton, which proves that the slope is decreased as flood heights increase.

The surface of water of the flood of 1897 was above the surface of water of flood of 1890, at the several points in the river, as follows: Carrollton, 3.07 feet; Red River, 3.53 feet; Vicks-

burg, 3.43 feet; Helena, 4.03 feet; Memphis, 2.06 feet; Cairo, 2.82 feet; which shows that the elevations of floods of 1897, in the lower end of the slope, were much higher above the elevation of flood of 1890 than they were at the upper end, which condition is seen to be reversed from Vicksburg to the sea by comparing the floods of 1890 with the floods of 1874. The height of the floods of 1890, above those of 1874, at the several points on the river, were as follows,—viz, Carrollton, 0.4 foot; Red River, 0.38 foot below; Vicksburg, 3.35 feet; Helena, 1.90 feet; Memphis, 1.60 feet; Cairo, 1.43 feet.

A consideration of the latter table shows that the river is congested between the sea and Vicksburg; while the first table shows that the congested condition extended to Helena, *i.e.*, the water came into these reaches faster than it could be discharged to the sea.

In absence of full slope data, I propose to consider that the gage readings of the Mississippi River Commission supply all requirements for present purposes, and that they are susceptible of reliable deductions as to intensity and variability of slope of floods between points on the river; as, according to the theory of the Mississippi River Commission, the gage readings are not affected by crevasses or other small and local conditions, although Major Harrod, in his discussion, has thought fit to express an opposite view. I will assume that the flood wave extended over a period sufficient to absolutely fill the whole river, as it did in 1897 and in other flood years, and will use the highest gage readings throughout the river for securing a comparative table of slope for different conditions.

The use of gage readings, as I propose, is generally considered proper, and I quote "Seddon on River Hydraulics," where he refers to gages, as follows:

"The gage relations on the Mississippi are not only especially stable, but they are also, in general, especially well-defined single lines; and, in that case, every variation which shows in the surface levels of the same discharge at one of the gages must show in the given ratio and the given period at the other. Changes of plane are transferred as well as discharge curves, and, as far as the gage relations below Arkansas City, each shows a single line for both of these periods, this change of plane is necessarily an identity all the way down."

In the following table Column X is elevation of maximum gage readings above *o. C. D.*; Column Y the slope between the several points on the river, expressed, in order to avoid fractions, in millimeters per mile. This table embraces the record of ten

seasons between 1874 and 1898, five of which were years of normal floods,—1878, 1885, 1889, 1896, 1898, and the other five are years of high floods,—1874, 1882, 1890, 1893, 1897.

For calculation of slopes, distances are taken as follows:

Cairo to Memphis	230 miles.
Memphis to Helena	76 "
Helena to Greenville	172 "
Greenville to Vicksburg	121 "
Vicksburg to Red River	106 "
Red River to Carrollton	192 "
Carrollton to the Sea	120 "

YEARS OF HIGH FLOODS.

	Cairo		Memphis		Helena		Greenville		Vicksburg		Red River		Carrollton		Sea	
	X	Y	X	Y	X	Y	X	Y	X	Y	X	Y	X	Y	X	Y
1874	338.21	237.07	133	207.80	121	149.20	104	114.74	98	70.90	78	36.61	55	21.26	39	
1882	341.74	230.12	135	200.18	120	149.68	105	114.79	88	72.35	78	38.86	58	21.26	37	
1890	341.64	230.57	135	200.70	119	151.45	103	115.09	92	72.52	78	37.10	56	21.26	40	
1893	340.17	230.17	133	200.60	117	152.30	102	114.34	97	71.87	79	38.36	53	21.26	41	
1897	342.46	241.63	132	213.73	117	154.75	101	118.52	91	74.05	81	40.08	34	21.26	48	

YEARS OF NORMAL FLOODS.

	Cairo		Memphis		Helena		Greenville		Vicksburg		Red River		Carrollton		Sea	
	X	Y	X	Y	X	Y	X	Y	X	Y	X	Y	X	Y	X	Y
1878	327.88	233.07	126	200.73	130	146.05	97	109.99	98	63.27	80	32.21	46	21.26	28	
1885	329.24	233.22	128	202.68	123	146.05	101	108.34	96	65.81	78	34.46	50	21.26	34	
1889	228.37	230.57	126	196.08	138	139.85	97	160.80	98	57.85	79	32.81	40	21.26	29	
1896	330.04	232.37	129	200.40	128	142.60	103	105.04	96	61.25	80	34.61	43	21.26	34	
1898	340.62	241.56	131	211.09	122	154.16	103	115.44	97	68.15	87	36.81	50	21.26	39	

As will be observed, a study of this table is very instructive. The slope from Cairo to Memphis is, in comparison, quite regular, with the several elevations, varying from 126 mm. per mile at elevation 327.88 feet at Cairo in 1878 to 135 mm. at 341.64 feet in 1890, which shows that this stretch of river has a fairly uniform section and that its condition, for discharge of floods, is superior to any of the other sections. It will, however, be noted that the slope in 1897 was 132 mm. per mile and was less than that of any of the other flood years with lower elevations, which would indicate an increasing retrogression of the value of the channel for delivery of floods.

The slope in the stretch between Memphis and Helena has, for floods, gradually decreased from 121 mm. per mile at elevation of 237.97 feet at Memphis in 1874 to 117 mm. per mile with elevation of 241.63 feet in 1897, which shows clearly a decreasing slope with increasing elevation, and that this stretch cannot discharge any large flood with safety. It will be further noted that the slope in this stretch is very much greater under normal floods than in high

floods, the slope in 1878, at elevation of 233.07 feet, being 130 mm. per mile and decreasing with considerable uniformity to 122 mm. per mile at elevation of 241.56 in 1898. It will also be observed that the slope is rapidly decreasing with time for both normal and high floods, which proves that the flow conditions are being interfered with.

The same condition of decreasing slopes with increasing flood elevation is shown to exist in the stretch between Helena and Greenville, where the slope, in 1874, was 104 mm. per mile with elevation of 207.8 at Helena, and it was 104 mm. per mile in 1897 with elevation of 213.73 feet.

In the stretch between Greenville and Vicksburg, the slope in 1897 was only 91 mm. per mile at elevation of 154.75 feet at Greenville, while in 1874 it was 95 mm. per mile at elevation of 149.2 feet, showing a large decrease in slope with increase of elevation of flood surface.

The stretch between Vicksburg and Red River shows a small increase in slope, but not commensurate with the increase in head or flood surface, and between Red River and Carrollton the slope is less in 1897 with elevation of 74.05 at Red River, than in 1874 with elevation of only 70.9 feet, showing a congested condition, retarding velocity and flow.

It is interesting to study the slope from Vicksburg to the sea for the years of 1896, 1897 and 1898, and note the great increase of slope in 1898 over that of 1896, which corroborates my views as expressed in my paper, as follows:

"Why are maximum floods sporadic, seldom, if ever, occurring in yearly succession . . . which clearly demonstrates that the floods with maximum elevations, even with equal volume of discharge, cannot occur in succession, for the reason that the avenues for passage of water are scoured out by the first flood, and the conditions to retard the passage cannot be formed in the interval of time between two flood periods."

And the table above clearly proves that the increasing height of floods is "*due to the increase of resistance for channel to clear itself.*"

I fail to understand how the Mississippi River Commission can proceed on the lines now adopted for improving the river. There is so much evidence at hand and so many facts established to prove not only the utter futility of the work, but that it must result in unsatisfactory and disastrous results.

I have proved that increasing floods are decreasing the slope. It is impossible to calculate the ratio, but, assuming that it will

be the same as shown by comparison of 1897 and 1874, the additional height of levee required at Carrollton to contain the floods when the St. Francis Basin is leveed, will be not less than 5 feet.

Seddon, in "Reservoirs and the Control of the Lower Mississippi," refers to the St. Francis Basin as follows:

"Altogether, then, from the evidence of this 1897 flood, there is little doubt that to shut off the outflow completely from all these great basins is to raise the high water stages of such floods from six to eight feet above the level at which the natural reservoir system of this river would have carried them; and even in the interests of a real flood protection alone, it would certainly be wise to consider whether some less dangerous step into the unknown might not be substituted for it."

Starling, on the "Mississippi River," says:

"The St. Francis was closed since 1893 to a distance measured along the river of 120 miles and a gap of 100 miles still remains. It is to the building of these levees and to the maintenance of the lines previously existing that the unparalleled stages attained by the water has been due."

And as for the highly improved alluvial lands below the Red River, the writing of Prof. Lewis M. Haupt is sufficiently suggestive: "The last stage of that property will be worse than the first."

The investigations I have made of the methods now in hand for the improvement of the Mississippi River suggest, as a comparison, an illustration wherein the Mississippi River, from Vicksburg to the sea, represents an old beer keg with the head knocked out, set on end and provided with a rusty, worn-out choked faucet, the key of which has long since been lost; while the river above Vicksburg is represented by a brand new and thoroughly banded whisky barrel set above and arranged to discharge into the old beer keg by two, new highly-polished, non-choking, keyless faucets, and the proprietor of all this outfit is guaranteed by the designer and constructor that, by maintaining the whisky barrel full, the old beer keg might be filled, but would never overflow.

It would appear that, to secure proper and satisfactory results, the work of improving this river must be inaugurated at the sea, the first step being to provide a proper outlet for the ultimate confined volume, and gradually extend the improvement to reach the whole length and breadth of the stream. I am convinced that no levee work, outlet work or jetty work singly will answer the purpose, and that the work must be a combination of several dis-

inct methods. In this opinion I am fortified by eminent hydraulicians, and will quote as follows:

Herman Haupt on "The Problem of the Mississippi," published in the "Journal of the Franklin Institute," April, 1899, says:

"In May, 1897, the writer published several articles in the New York "Sun" on the Mississippi River problem, the aim of which was to show that of the systems proposed, neither the levee, the outlet, the reservoir, nor any other, singly, would secure protection from overflow, but that a combination of several and an intelligent application of certain recognized principles, with a careful study of local conditions was essential to a practical solution of the problem presented."

This statement indorses the recommendations of my paper. Professor Haupt further says, referring to the known and established variation of slope:

"These variations of slope would necessarily produce variations of velocity, and unless the sediment had been previously deposited every reduction in velocity would cause new deposits in the bed, and every increase in velocity from contraction of the cross-section by levees or otherwise would suspend such deposits, or, in some cases, might even depress the bottom by producing a scour.

"As there are variations of slope and constant contraction and expansion of sectional area, there must necessarily be frequent changes of velocity, and, as a matter of course, there will be deposits in some portions of the bed and none in others, with occasional scour tending to the formation of holes."

This statement is justified by the known results which have their cause verified by the fact that the slope decreases with the increase of elevation of flood; and, referring to the ultimate closing of all the outlets from Cairo to the sea, he has the following to say:

"If the partial closing of the levees in front of some of the basins has resulted in such an enormous increase of flood height that the most elevated levees would have been overtopped and submerged but for the relief afforded by crevasses, what results may be expected when the whole river is confined by continuous levees on both sides? If the volume of water that is poured into the upper portion of the Mississippi is twice as great as is now discharged at its mouth, what must be the elevation of the crest lines of the flood when the volume is doubled? The idea that an increase of velocity will result from the increased volume and, that in consequence, a scour will be produced that will increase depth sufficiently to compensate for increased height of flood has been shown to be fallacious. If there was a continuous scour the material must be deposited somewhere, and the only conceivable place

of deposit would then be at the Gulf, reinforced by all the material brought in from the tributaries and from erosion of the banks, in which case the amount would be so enormous that it would be almost impossible to maintain navigation and New Orleans might become an inland city. Heretofore, relief has been afforded by crevasses and cut-offs, by which it is said that half the volume in flood stages has found its way to the Gulf through swamps, bayous and secondary streams, and was not discharged through the passes. When these avenues of escape are cut off there must necessarily be a great increase in the flood height unless some other mode of relief can be provided.

"The evidence presented should be conclusive that parallel levees of any ordinary height, continuous on both sides of the streams, with outlets all closed, compelling the river to carry and discharge into the Gulf double the former volume of flood water will not, with certainty, secure the country permanently against overflow, but when the limit of the capacity for protection has been attained the danger from crevasses, if they should occur, will be vastly increased."

Prof. J. B. Johnson, before the American Association for the Advancement of Science, in 1884, gave expression to his views, as follows:

"It would seem, therefore, that in the river's present condition, there is no evidence that a confined flood will scour out its bed so as to facilitate the discharge, and there is considerable evidence against it. If the river flowed between straight parallel banks, such as Captain Eads has constructed at the mouth of the river, there then could be no such thing as discontinuous transportation of sediment, and hence no alternate scour and fill. Then concentration of volume would be beneficial and would ultimately lower the river bed. But this condition of things can never be reached on the Mississippi River, and hence the concentration of flood volume will be harmful rather than beneficial."

Seddon, in "Reservoirs and the Control of the Lower Mississippi," invents a very appropriate maxim when he says:

"The idea is a fundamental one that the ills of the river in the main lie in the variations of its flow."

And the question may be asked, has any improvement been made in this main evil during the past twenty-two years? A truthful answer would be that not only has no improvement been made, but that the evil has increased.

The same writer, referring to the partial leveeing of the St. Francis Basin, says:

"This line, as first built, was much too low to withstand the increased flood heights that followed the restricted overflow, and the great flood of 1897, the first that has come against it, broke through the levee in a number of places before it had reached its

extreme by several feet. But it, nevertheless, gave the last and the best indication of what flood heights may be expected when the overflow into this natural reservoir system is entirely closed out."

Major Harrod has seen proper to state that the high water at Carrollton is directly connected with the levee system, and attempts, by a series of averages, to prove that the constantly increasing height of flood waters are merely a natural conclusion and were not unexpected, neither are they higher than was anticipated. These conclusions open up a wide and interesting field for discussion, but for the time, I will refer to them only to make the suggestion that the integrity of levees can be gaged only by that of the weakest part. In this respect the levee is precisely similar to a chain, the weakest link of which represents the maximum strength of the chain; hence, a levee of sufficient integrity to sustain the flood of average elevation would be of no value whatever to sustain the sporadic maximum floods; and, as asked in the former part of this paper, who can foretell, with absolute certainty, what is the future maximum elevation of the floods of the Lower Mississippi? From a careful consideration of the improvements now being made on the river and the results, covering a period of twenty-two years, are we not justified in anticipating that the floods of 1897 will be largely exceeded?

Referring to the question of increased run-off from watersheds from the deforesting of the western slopes of the Alleghenies, it seems to be unsettled, although a preponderance of opinion concludes that the future run-off will not exceed that of the past.

Humphreys and Abbot, on page 437 of their report of 1861, referring to forest, state:

"The removal of the matted undergrowth and the softening of the earth cause a greater quantity of rain to be absorbed, and the exposure to sun increases evaporation."

Seddon makes the following observation:

"Cutting down forests, draining lands, reclaiming swamps, with all the climatic changes that are assumed to go with such development of a country, are each and all given a place in these deductions, and that some of them actually have a place in the flood regimens is possible; but what this is, and what its magnitude, and, indeed, even whether in a given case it would increase or decrease the flood extremes, is in general beyond the range of our present knowledge of the subject."

Referring again to Major Harrod's discussion, we find that he says:

"Abbot demonstrated the futility of attempting to grade up the lower lands of the valley by deposit and overflow."

In the first place, Humphreys and Abbot's deductions and conclusions, while they are generally considered as being very valuable and excellently suited to the conditions of forty years ago, are not to be followed to-day without deep consideration. As a matter of parallel, the rules and deductions governing the use of steam and other engineering specialties, which were considered absolutely perfect forty years ago, are now absolutely obsolete; and it is interesting to note the extreme height of perfection to which all branches of engineering have attained, as compared with forty years ago, excepting only the engineering work in connection with the Mississippi River, which has for forty years made no positive and solid advancement toward providing benefits, either commercially or sanitarily, to the immensely valuable territory tributary thereto; and I do not consider that it is impracticable or impossible to adopt measures which will vastly benefit all interests along the Mississippi River, notwithstanding that Captain Abbot, some forty years ago, concluded otherwise. I further believe that the high attainments of the engineering profession in this country will not allow the Mississippi River to become a bugbear of engineering inconsistencies, reprisals and criticisms, but will insist on the adoption of such enlightened engineering works as will produce results which will be the wonder of the current century.

Major Harrod, in his discussion, says:

"The levee system has received thorough study and full discussion."

I ask, has an opportunity ever been afforded during the past twenty-two years for a discussion of the river matter, and of what use, in the light of the present experience and knowledge, are the discussions of Humphreys and Abbot, and others of forty years ago? Further, is it not a recognized fact that an attempt on the part of any engineer to question the methods now adopted is considered a breach of professional etiquette; and, again, what positive conclusion has the Mississippi River Commission reached on the subject that is accessible to the public? And again I ask, would Barnard, Bailey, Forshey and Eads, were they living to-day, hold the opinion they expressed forty years ago? A quotation from Emerson eminently fits the foregoing:

"With consistency a great soul has nothing to do Speak what you think to-day in words as hard as cannon balls, and to-morrow speak what to-morrow thinks, in hard words again, though it contradicts everything you said to-day."

With candor and satisfaction, worthy of a less interesting and important subject, Major Harrod, in his discussion, says:

" . . . the people who wanted to live and plant in the river States went on strengthening and extending the levees. It is now the adopted system because it is proved thoroughly right and practically useful. Levees have caused no elevation of the bed of the river, no phenomena that were not anticipated, and have developed no insurmountable difficulties. They have at all times been, and they are now, worth every dollar they have cost. So well have those who live behind them been satisfied of this, that there is no relaxation of effort to complete the system."

Each word of the above provides a text, and an instructive and interesting book could be written from this paragraph and entitled "The Candor and Satisfaction of the Mississippi River Commission." I will refer to only a few of the many points this paragraph suggests.

Has the Mississippi River Commission such knowledge, and has it made such investigations as are necessary to determine, with such positiveness as is contained in Major Harrod's language, that the bed of the river is not being elevated? If they have, why is it that this most valuable information is not made public? If the flood elevations are increased, as past experience teaches us they have been, and if they have occasioned a decrease in the slope of the whole river, as is shown to be the case, although not published by the Mississippi River Commission, by what hydraulic laws would the deduction be made that the bed is not fouling? If no phenomenon has occurred which was not anticipated, the Mississippi River Commission is responsible for the losses this country sustained in 1897, amounting to upward of \$100,000,000, by not adopting, in 1894, a grade for levees 4 feet above the high water of 1897, instead of adopting this tremendous elevation in 1898; and with the same reasoning, the Mississippi River Commission should at once give us the proper elevation for levees in 1905, so that we can construct them economically.

As to the statement that the people who live behind the levees are satisfied and that they have not relaxed their efforts to raise and enlarge the levees, as necessity demanded, it is most apparent that with them it is "root, hog, or die." Ruin would follow their inactivity; and their wonderful energy in enlarging levees and in fighting the inevitable can be compared only with the achievements of the most enlightened people that occupy the globe to-day.

A casual intruding observation presents itself in the shape of a query as to how much the alluvial lands of the Mississippi

would be improved and enhanced in value to-day if only one-tenth of the money spent on levees during the past twenty-two years had been spent on the improvement of navigation of waterways, roadways, etc.

Major Harrod's remarks relative to reservoirs and the utilization of river sediment for the benefit of mankind are the echo from forty years ago, and will not withstand the intense searchlight investigation of the engineering profession of to-day. The value of the industrial enterprises throughout the alluvial territory is becoming so enormous that we can no longer rest satisfied with antiquated opinions or be governed by laws long known to be obsolete; and the engineering profession, in the very near future, will provide a way to secure to mankind the benefits which nature intended should be imparted through the medium of the greatest drain in the world, in like manner as this same profession has unlocked nature's storehouse of coal, iron and other commodities now so necessary for our existence.

Referring to Major Richardson's discussion, I must content myself with referring to only the last two paragraphs, as the introduction of Mark Twain as a competent river expert, and quoting him as an authority, places the subject beyond my ability to discuss it.

Considering the intense moment of the subject under discussion, the immense interests involved and the prominent position occupied by Major Richardson, together with his favorably known characteristics, and the extent of his experience, I am greatly surprised that he should choose to consider the matter in so careless a light and treat it with so much irony and levity.

Major Richardson, in concluding his discussion, makes a statement which is entitled to be classed as famous, which in substance is that the elevations for grade of levees, as fixed by Humphreys and Abbot forty years ago, was practically approved and adopted by the commission in 1874, and by the Mississippi River Commission, that no flood had come within 1 foot of some mysterious grade fixed by the Mississippi River Commission at Carrollton, and that only one flood has reached the mark set by Humphreys and Abbot, forty years ago.

Referring to page 441 of Humphreys and Abbot's report, we find the following, relative to proper heights for levees:

"To secure this end in the most economical manner, the operations of this survey indicate that levees should be constructed. Near the mouth of the Ohio, they should be made about 3 feet above the actual high-water level of 1858 . . . Between that

locality and Baton Rouge, it should be kept uniformly about 4 feet, and below Baton Rouge about 3 feet. If the water-mark of 1858 be unknown at any locality, it may be reduced to any well-determined local mark by the table in Chapter II . . . It should be remarked that these heights are based upon the supposition of *absolute security*."

Now understand, clearly, that these heights refer to the top of levee above the surface of the high water of 1858, to provide "*absolute security*" against inundation. The elevation of the high water at Cairo in 1858 was 49.56 feet and the top of levees, as recommended, 52.56 feet. The high water of February, 1883, was 52.17 feet, which made the top of levees as recommended by Humphreys and Abbot only 6 inches out of the water. The surface of the high water at Carrollton in 1858 was 15.1 feet, and the top of levees, as recommended, 18.1 feet. The high water of 1897 was 19.17 foot, or 1.07 foot above the top of such levee.

Supplementing with facts from recent history, I would state that, succeeding the high water of 1874, the City Council, who then had charge of the levees throughout this city, fixed the elevation of the top of levees 3 feet above the high water of 1874, or at 18.7 feet. In 1890 Major B. M. Harrod, member of the Mississippi River Commission, then city engineer and consulting engineer of the Orleans Levee Board, fixed a grade for the construction of wharves and landings along the city front at 18.6 feet, and no doubt recommended that this elevation would satisfy all future needs. Succeeding the flood of 1897, the Orleans Levee Board fixed the grade of levees throughout the Parish of Orleans, excepting the commercial front, at 4 feet above the high water of 1897, or at 22.17 feet at Carrollton, which is 5.07 feet higher than the elevation of the top of levee as fixed by Humphreys and Abbot, forty years ago.

Referring to the concluding paragraph of Major Richardson's discussion, wherein he expresses satisfaction with the deductions and conclusions of the investigation made by Humphreys and Abbott, forty years ago, and those of the Mississippi River Commission, I can but express my astonishment, considering the experience of the past ten years, that an engineer of his attainment and his experience would be satisfied with any past conclusions, and that he is not among the first to advocate measures looking toward relieving a people who have the record of being the highest taxed and the poorest protected of any people in America, and whose ability to exist is accounted for only by the enormous fertility of the country.

That the engineering profession makes not only wealthy individuals, corporations and nations is no canard, although the public fails to recognize such distinction; and this fact has been very gracefully presented to the world by the address of Past President Wallace at the meeting of the American Society of Civil Engineers at London, England, in July, 1900, as also by Past President Malochée of the Louisville Engineering Society. With such a merited honor, and with such responsibilities, can the profession allow the Mississippi River to be continually menacing, with disaster and destruction, a most valuable country, which is susceptible of extraordinary growth, resulting in great wealth, and is it not incumbent on the Louisiana Engineering Society, whose members, owing to their location, are most in touch with the interests to be served, to inaugurate and pursue a vigorous and unbending policy until success is achieved, and thus maintain the prestige of the profession, receive the encomium of a grateful people and secure the satisfaction of having accomplished that which well served our time and generation?

OBITUARY.

David Walker Hardenbrook.

MEMBER, MONTANA SOCIETY OF ENGINEERS.

IN the death of David Walker Hardenbrook, the Montana Society of Engineers lost a member of whom it may be said that he was truly a product of Montana, as he was born in the town of Deer Lodge, on March 1, 1869, and received his education and spent the greater part of his life within the boundaries of the State. Most of his earlier years were spent upon the ranch, and his education necessarily started in the country school-house.

In 1885 he began the preparatory course in the College of Montana, at Deer Lodge, Mont. He entered the freshman year of the course in mining engineering in the fall of 1887, and received his degree in June, 1892.

He began his life's work under Mr. F. W. C. Whyte, a member of this Society, and at that time chief engineer of the Butte, Anaconda and Pacific Railway, then in process of construction. His service with this company extended through many of the branches of the work. He was draftsman in the chief engineer's office for some time, and later he took up the field work in various branches as topographer, level-man, transit-man and finally as engineer in charge of construction.

Three years were spent in the employ of this company, and the following two years in miscellaneous engineering work throughout the State, mostly in public land surveying under Mr. H. B. Davis, of Deer Lodge, and later with Messrs. Sizer & Keerl, of Helena.

Later he became associated with Mr. Chester B. Davis, the eminent hydraulic engineer, during the time that gentleman was gathering data concerning the water supply in the vicinity of Anaconda, Mont.

About this time, during the summer of the year 1897, he was asked to go to Mexico, as assistant engineer for the American Mining Company, at El Oro, under a contract for two years, and his acceptance of this invitation marked a turning point in his life, as the hardships he there endured laid the foundation for the disease which finally resulted in his death.

He took up his work in Mexico under trying conditions, being put in charge of a party on railroad location, all of whom were native peons, and only one of whom could speak English and had been on work of that kind before.

The fact that Mr. Hardenbrook did not know a word of Spanish was also against him, but he went at the job with de-

termination; and with the aid of the assistant whom I have mentioned, he mastered a little Spanish and successfully carried on his work.

About this time he was stricken with typhoid fever and spent two months in a hospital in the City of Mexico.

Upon his recovery he returned to his work, but in a short time was obliged to go into the hospital again, owing to a throat trouble, probably an after-effect of his first illness.

Two months were spent in an effort to get well, and though he worked the balance of his time, his health was much broken.

His two years being up, he returned to Montana in June, 1899, coming by way of Vera Cruz, sailing thence to Havana, Cuba, and on to New York, and returning thence by rail to Montana, visiting many of the larger cities on the way.

He became an employe of Messrs. Harper & Macdonald, civil and mining engineers, at Butte, Mont., and later was with the Montana Ore Purchasing Company, in the engineering department.

He finally accepted a position under Mr. F. S. Jones, chief engineer, B. A. & P. Ry., as resident engineer, located at Anaconda, Mont. His health was failing rapidly at this time, and after a few months in this last position he was compelled to resign, and upon the advice of friends went to California in search of renewal of his former vigor and strength. But it was not to be, and, after lingering some time, he passed away on February 24, 1901.

David Walker Hardenbrook was somewhat backward in his demeanor, and perhaps slow in gathering friends, but he never lost a friend once made.

As a tribute to his worth as a man, and to his ability as an engineer, Mr. F. S. Sizer, the President of this Society, at present sojourning in Mexico recently writes: "I have just learned of the death of Walker Hardenbrook and wish to join you and other friends in mourning his loss. I know that those members of our Society who enjoyed his personal acquaintance will feel as I do, that the highest tribute of praise to his character and life cannot do more than simple justice to his worth. He was singularly upright and honest and of more than average ability, being especially adaptable to difficult conditions as they arose in his professional work. During one summer, I think about six years ago, he was in my employ, and a more faithful assistant I never knew. Since then I have come in contact with him in Butte, and predicted for him a notable career."

ASSOCIATION OF ENGINEERING SOCIETIES.

VOL. XXVI.

JUNE, 1901.

No. 6

PROCEEDINGS.

Engineers' Club of St. Louis.

528TH MEETING, JUNE 5, 1901.—Held at 1606 Locust street; Vice-President Kinealy presiding.

Attendance, twenty-four members and ten visitors.

Upon motion being duly carried, the reading of the minutes of the 527th meeting was dispensed with, as the same had been printed and circulated among the members.

The doings of the 311th meeting of the executive committee were reported.

The application for membership of Mr. John I. Boggs was read. Messrs. Hans C. Toensfeldt and Arthur Tappan North were elected to membership.

The subject of the evening was a paper by Mr. A. H. Blaisdell, entitled "The Western River Steamboat."

Mr. Blaisdell exhibited about fifty lantern slides prepared by himself from photographs of boats and drawings, detailed some tests of steamboat performances, illustrated the path of the paddle wheel and its slip, gave examples of speed calculations and outlined the method of designing a steel hull, with calculations of stability, strength, etc.

The discussion was participated in by Messrs. Flad, Bryan and others.

Adjourned to library room where justice was done to a light lunch provided by the entertainment committee.

Adjourned until September 18, when Mr. J. A. Ockerson will present a paper entitled "The Mississippi River: Physical Characteristics and Methods of Improvement."

W. G. BRENEKE, *Secretary*.

Technical Society of the Pacific Coast.

REGULAR MEETING, JUNE 7, 1901.—Called to order at 8.30 P.M. by the President, Prof. C. D. Marx.

The minutes of the last regular meeting were read and approved.

Mr. Harry A. Noble, with Board of Public Works, San Francisco, who had been proposed at the last meeting by F. C. Herrmann, Hermann Kower, C. E. Grunsky and Luther Wagoner, was declared duly elected a resident member of the Society upon count of ballots.

The proposition of Mr. James Spiers, Jr., to become a member, indorsed by Luther Wagoner, C. D. Marx, E. F. Haas and Adolf Lietz, was ordered to ballot, it having been duly approved by the Board of Directors.

ASSOCIATION OF ENGINEERING SOCIETIES.

VOL. XXVI.

JANUARY, 1901.

No. 1.

PROCEEDINGS.

Engineers' Club of St. Louis.

516TH MEETING, DECEMBER 5, 1900.—The meeting was called to order at 8 o'clock; with President Chaplin in the chair. Thirty-five members and six visitors were present. The minutes of the 515th meeting were read and approved. The minutes of the 300th meeting of the Executive Committee were read.

The applications for membership of Messrs. Wilbur Hayes Thompson and George Dyer Johnson were presented to the Club.

The annual reports of the Executive Committee and Secretary were read, and on motions duly seconded were received and filed. The Treasurer's report was read and referred to the Executive Committee. The report of the Board of Managers was received and filed. It contained detailed statistics of the Association of Engineering Societies prepared by the General Secretary, Mr. John C. Trautwine, Jr. The local board recommended the adoption of resolutions by which it might be possible to secure advertisements for the JOURNAL OF THE ASSOCIATION OF ENGINEERING SOCIETIES, and in this way increase the general fund of the Club. The commissions for securing such advertisements were to be paid from the general fund as provided for in the plans submitted by the Board of Managers. Upon being amended the resolutions were duly seconded and carried. The amendment provides that after the plan devised by the local Board of Managers is submitted to the Executive Committee for approval and passed, it be also presented to the Club for final action.

The report of the Entertainment Committee was received and filed.

The Librarian's report was read and filed. The library during the past year had received considerable attention, a large number of books having been added and a most convenient card-index system adopted.

It was moved and seconded, and the motion carried, that the arrangements for the annual dinner be left to the Executive Committee.

The Nominating Committee made its report with the following nominations:

For President—E. J. Spencer.

For Vice-President—J. Pitzman.

For Secretary—William G. Brenneke.

For Treasurer—George I. Bouton.

Librarian—J. L. Van Ornum.

Directors—A. H. Blaisdell, E. E. Wall.

Board of Managers—W. A. Layman, S. E. Freeman.

Additional nominations were made for office of Vice-President,—viz, William Bouton and J. H. Kinealy.

Mr. William Bouton read a short paper on the "Probable Error per Tape Length in Surveyor's Field Work." A discussion was given of the errors arising from measurements in surveyors' field work, a distinction being made between the error per tape length and that per unit length. The discussion was participated in by Messrs. Pitzman, J. L. Van Ornum, B. H. Colby, Robert Moore and E. A. Hermann.

Adjourned to adjoining room, where a light lunch was served.

F. E. BAUSCH, *Secretary*.

517TH MEETING, DECEMBER 19, 1900.—The annual dinner of the Club was held at the St. Nicholas Hotel at 7.30 P.M.; with President W. S. Chaplin in the chair at the head of the table. Thirty-nine members and one visitor were present. After the dinner was over the result of the letter ballot for officers for the new year was announced as follows:

President—E. J. Spencer.

Vice-President—No election; none of the three candidates receiving a majority.

Secretary—William G. Brenneke.

Treasurer—George I. Bouton.

Directors—A. H. Blaisdell, E. E. Wall.

Members of Board of Managers—W. A. Layman, S. E. Freeman.

As Mr. Pitzman requested the withdrawal of his name as candidate for election to Vice-Presidency, the contest for office lay between the two remaining nominees. A new ballot was taken, resulting in the election of J. H. Kinealy.

Mr. Chaplin, as retiring president, offered some timely suggestions. The engineer, due to his superior education, should take a greater interest in the guidance of public affairs. He should be regarded as authority on all matters pertaining to public improvements.

Mr. Chaplin surrendered the chair to Mr. E. J. Spencer, who presided the rest of the evening. Mr. Spencer alluded to the high character of the Engineers' Club, and its important work in general.

Mr. A. L. Johnson spoke on "What Are We Here For?" He was of the opinion that the Club as a unit might exert its influence on subjects of public importance. In reply to this, one of the members referred to the action of the Club on the filtration question, the results of which are fresh in the minds of all Club members.

Mr. Robert E. McMath spoke on "Little Given, but Much Required." He alluded to the great work of city improvements carried on with practically no funds at hand. His remarks were of great interest, as they dealt with home institutions.

In the absence of Mr. H. H. Humphrey, who was sick, the Chair invited Prof. F. Spalding, of the State University, Columbia, Mo., to make a few remarks. He spoke on the "practical and impractical" side of engineering. Reference was made to the advantages of belonging to an engineers' club, where the practical ideas of engineers are discussed.

Prof. J. L. Van Ornum spoke entertainingly on "Solar Walks of Engineering."

Following the above, short speeches were made by Messrs. Nipher and Ockerson.

A motion was made and duly carried that a vote of thanks be tendered the past officers. A unanimous vote was cast, members rising.

Meeting adjourned.

F. E. BAUSCH, *Secretary*.

518TH MEETING.—Held at 1600 Lucas Place, January 2, 1901, 8.15 P.M.; Col. E. J. Spencer presiding. Twenty-two members and seven visitors were present.

The Secretary reported the minutes of the 516th and 517th meetings were not ready for presentation to the Club, and requested that reading of them be postponed until the next meeting. The request was granted.

Minutes of the 301st and 302d meetings of the Executive Committee were read, but no action was taken upon them, as they had not been approved by the Executive Committee.

The following candidates for membership were balloted on and declared unanimously elected, viz: Wilbur Hayes Thompson, George Dyer Johnson.

The application for membership of Edward C. Dicke and William C. Zelle were read and referred to the Executive Committee.

A communication was read announcing the death, on May 29, 1900, of Mr. A. J. Sypher, non-resident member, of Millerstown, Pa.

The announced subject for the evening was a paper by Prof. J. L. Van Ornum, on "Purification of Sewage by the Septic Process."

As the Club was honored by the presence of Prof. Emery S. Johnson, Professor of Commerce and Transportation, University of Pennsylvania, and member of the United States Isthmian Canal Commission, a departure from the announced subject of the evening was made, and Professor Johnson was invited to speak on the work of the Isthmian Canal Commission. The speaker is chairman of the committee appointed to investigate the commercial features of the Isthmian Canal, but did not discuss those features, his remarks being limited to the engineering problems only. The speaker's talk was informal, but he presented in a quite brief but very instructive and entertaining manner the results of the work of the commission in investigating the subjects of the construction of the Isthmian Canal, by and under the control of the United States Government, across Central America.

The speaker began with a short historical review of previous investigations and attempts at a solution of the problem, and then explained that three routes had received the chief study of the commission:

- (1) A possible route across the Isthmus of Darien.
- (2) The route through the State of Panama, traversing Lake Bohio, recommended and adopted by the French, and
- (3) The route through the States of Nicaragua and Costa Rica, traversing Lake Nicaragua, and known as the Nicaragua route.

From the purely engineering standpoint, the Darien route seemed inferior to both others, owing to the fact that in order to construct a tide level canal a great tunnel would have to be constructed, and for a high level canal it did not lend itself as readily as the other routes. The commission considered a tunnel in a canal more objectionable than one or more locks.

Of the remaining two routes, the Panama seemed the more practicable as regards engineering features, but the undesirability of the concessions it was considered possible to secure led the commission to recommend the Nicaragua route.

The latter route will require the construction of a large masonry dam across the San Juan River, the construction of a harbor at each end of the canal, the building of a number of miles of artificial canal and the improvement of existing waterways. The controlling factor in the time required to construct the canal is the construction of the dam. It has been estimated this would require about eight years' time (possibly only six), and that the entire canal could be finished in this time without unnecessary duplication of plant.

The estimated cost of the canal is about \$200,000,000.

A discussion then followed, bringing out a number of interesting points. The discussion was participated in by Messrs. Pitzman, Bryan, Colby and Grimm.

The President, on behalf of the Club, then thanked Professor Johnson for his very interesting talk.

The Chair then asked the late Committee on Entertainment to provide a lunch for the next meeting.

Adjourned at 10 P.M.

W. G. BRENNKE, *Secretary*.

519TH MEETING JANUARY 16, 1901.—Held at 1600 Lucas Place, 8.30 P.M.; President Spencer presiding.

Minutes of the 516th, 517th and 518th meetings were read and were approved with corrections.

Minutes of the 301st, 302d and 303d meetings of the Executive Committee were read.

The Secretary, who had been appointed by the Executive Committee to act in conjunction with the Treasurer, in auditing the accounts of the retiring Treasurer, reported the accounts correct.

The Committee on Annual Dinner reported a deficit of \$18, and motion was carried to appropriate this amount from the Club's funds to cancel the indebtedness.

Notice was given that those members desiring the report of the Nicaragua Canal Commission (not the Isthmian Canal Commission) could obtain the same by communicating with Rear-Admiral Walker, Washington, D. C.

Letters were read from the President of the Society of Civil Engineers of France to the President, and to Mr. J. A. Ockerson, the Club's representative at the convention of the French Society last summer. These letters conveyed an expression of sympathy and an assurance of the continuation of the friendly relations now existing between the two societies.

A pamphlet containing the reports of the receptions given by the French Society during the period of the Paris Exposition of 1900, in which the Club's delegate, Mr. Ockerson, participated, was received.

Mr. Ockerson donated to the Club a book on the manufacture and use of cements, which is a prospectus of the "Societe Ginirala et Unique des Ciments de la Porte e France."

The death of Mr. J. M. Desloge on September 17, 1900, was announced.

Mr. Edward C. Dicke and Mr. William C. Zelle were unanimously elected to membership.

The subject of the evening was a paper by Prof. J. L. Van Ornum, entitled "The Purification of Sewage by the Septic Process." Professor Van Ornum first reviewed the development of the septic process, in practice and in theory, and then discussed the problems needing further study and how such investigations might be made. He considered the system beyond the experimental stage and that it had been thoroughly tried and proven a success. The author expected that as the application of established principles is perfected and further investigations are made its efficiency will become still greater and its field of application be extended.

Discussion of the paper was participated in by Messrs. Russell and A. L. Johnson.

The Chair asked for report from the Committee on Monument to James B. Eads. Mr. Ockerson reported that as far as he knew no meeting had been held by the committee during the past year.

There was no report from the Committee on Smoke Prevention, all of the members of that committee being absent.

The Chair announced the appointment of the following Entertainment Committee: H. H. Humphrey, Chairman; D. W. Roper, W. H. Reeves.

Adjourned to another room, where lunch was served.

W. G. BRENNEKE, *Secretary*.

Engineers' Society of Western New York.

REGULAR MEETING, JANUARY 2, 1901.—Meeting called to order by the President at 8.30 P.M. The following members present: Messrs. Haven, Norton, Vanderhoek, Knapp, Roberts, C. F. Morse and Weston; also visitor H. C. Booz.

The minutes of the last regular meeting were approved as printed.

The President said, "By your ballots you have elected, as members, Jasper S. Youngs, John T. Herron, John J. Clahan, Charles S. Boardman, Henry Clark, Harry Bartlett Alverson, Frank L. Bapst, and as associates, Emmett W. Huntington, Charles Mosier, Louis Marburg." Applications for membership from David A. Decrow and Horace C. Booz as members, James Franklin, George E. Marsh, Mathew S. Gardiner and Raymond J. Ryan as juniors, Samuel J. Dark, Albert William Caines and William Franklin, Jr., as associates, were received, approved and ordered to letter ballot.

A letter from Mr. T. Guilford Smith, Director of the Society since its organization, relating to fuller information being necessary on letter ballots was read, and the attention of all Committees on Membership was called to the matter, and they were requested to see to it that fuller information was given in the applications.

The President called the attention of the Society to the necessity of the members attending the meetings and talking on subjects of current interest relating to their professions in Western New York. He remarked that it made no difference what measures should be adopted by the Executive Board or the officers so long as the members did not appear at the meetings and talk on these subjects, and that many engineers are disappointed that their profession is not recognized as a force in the community the same as the lawyers and other professional men, but this is very much owing to themselves in that they keep their knowledge hid under their own craniums.

Until they come to the meetings and talk on subjects of current interest to the public of Western New York, and have such discussions published, they cannot expect to be recognized as having any knowledge of value to the public. During the last six months two docks have failed from overloading, in both cases involving loss of human life, and yet not one word has appeared in the public newspapers from the engineers of Buffalo in regard to the cause of these disasters, nor any suggestion that they know how to construct a proper dock. Attention was called to several other public works about which the members of this Society have been silent.

On motion of Mr. Vanderhoek, seconded by Mr. Norton, it was voted that the President and the Executive Board be authorized to appoint committees to furnish topics for discussion on any subject that may be suggested.

The President then asked the members present to suggest topics, and the names of the men for such committees. The President then appointed committees of the Society as follows:

Past-President George A. Ricker, on Docks.

John T. Herron, on Gas.

Thomas W. Wilson, on Modern Street Railroads.

Edward B. Guthrie, on the Engineering Exhibit at the Paris Exposition.

Major Thomas W. Symons, on Niagara River Regulation.

George H. Norton, on Buffalo River Cut-offs.

The President was requested to write to several other gentlemen not now members of the Society, asking them to address the Society on several subjects,—namely, "Concrete Construction," "Goat Island Bridge," "Engineering Features of the Steel Plant."

Meeting adjourned at 10 P.M.

G. C. DIEHL, *Secretary*.

Technical Society of the Pacific Coast.

REGULAR MEETING, JANUARY 4, 1901.—Called to order at 8.30 P.M. by Vice-President Falkenau, who announced officially the death of the honored President of the Society, Mr. George W. Percy, and in a few words spoke of the many virtues of the man who for the past two years had been the head of the organization, and whose sudden loss came as a great shock to those who had been constantly in contact with him.

The members rose in honor to the memory of the late President.

The minutes of the last regular meeting were read and approved. The following gentlemen were elected to membership in the Society, having received the requisite number of votes: Members, Norman B. Livermore, civil engineer, San Francisco; Harris D. Connick, civil engineer, San Francisco; John J. Hollister, civil engineer, Santa Barbara; Charles M. Kurtz, civil engineer, San Francisco; Perry F. Brown, civil engineer, San Francisco.

The Nominating Committee, through its Chairman, Mr. C. E. Grunsky, made a report, placing in nomination the following members to fill the offices of the Society for the year 1901:

For President—Prof. C. D. Marx.

For Vice-President—D. C. Henny.

For Secretary—Otto von Geldern.

For Treasurer—Edward T. Schild.

For Directors—Edward F. Haas, Samuel C. Irving, Adolf Lietz, Paul W. Prutzman, Luther Wagoner.

The report was ordered received, and the Secretary instructed to prepare the ballots for the annual election, to be held January 18, the Chair appointing as tellers for the occasion Charles M. Kurtz and Perry F. Brown.

A memoir in honor of the late President G. W. Percy was read by Mr. G. A. Wright, who had been appointed for this duty by the Vice-President at the previous directors' meeting.

The memoir was ordered received and spread in full upon the minutes; also to be published in the JOURNAL OF THE ASSOCIATION, with an additional number of extra copies to be printed for the family and friends of the deceased.

Major Charles E. L. B. Davis read a paper in discussion of the subject placed before the Society at the meeting of December by Mr. George W. Dickie, entitled "The Need of Education of the Judgment in Dealing with Technical Matters."

Major Davis's statements led to further discussion of the interesting subject, which was participated in by Messrs. Vischer, Wright, Wagoner and others.

Adjourned.

OTTO VON GELDERN, *Secretary*.

DIRECTORS' MEETING, JANUARY 26, 1901.—Called to order at 4 P.M. by President Marx. Present, Directors Marx, Prutzman, Lietz, Schild and von Geldern.

The Chair appointed the following Committees: Executive—Messrs. Wagoner, Prutzman and Haas. Finance—Messrs. Lietz, Irving and Schild. Members on the Board of Management, Association of Engineering Societies—D. C. Heny and Otto von Geldern.

After approving the proposition of the Secretary to invite Mr. Charles Burckhalter to deliver an address before the Society on his results of photographing the solar corona at Siloam, in May, 1900, the meeting adjourned.

OTTO VON GELDERN, *Secretary*.

Engineers' Club of Cincinnati.

13TH ANNUAL MEETING, CINCINNATI, OHIO, DECEMBER 20, 1900.—Dinner was served at 6.30 P.M. The regular meeting was called to order at 8 P.M.; President Punshon in the chair. Twenty members present.

Minutes of the meeting of November 15 were read and approved.

Applications for membership were presented as follows:

Guy M. Gest, general contractor, 90 Perin Building, Cincinnati, for associate membership.

R. J. Bevenish, assistant engineer, Board of Trustees, Commissioners of Water Works, California, for active membership.

John P. Brooks, Professor of Civil Engineering, State College of Kentucky, Lexington, Ky., for active membership.

On ballot being taken Mr. James C. Hobart was elected an active member.

The letter from Professor Diemer, presented at the last meeting, in reference to the establishment of a Department of Mechanical Engineering at the

University of Cincinnati, was taken up, and after some discussion was referred to Messrs. Bogen and Baldwin for report as to the advisability of the Club taking any action in the matter.

The reports of the Secretary and Treasurer for the year 1900 were presented, ordered received and filed and printed, together with a revised list of members for distribution.

The report of the Secretary shows that the attendance has fallen off from 18 in 1899 to 16.3 in 1900; that the membership has also fallen off from 97 at the end of 1899 to 88 at the end of 1900. There were 5 new members elected during the year, 1 death, 9 resignations and 4 members dropped for non-payment of dues.

The Treasurer's report shows receipts amounting to \$662.50, disbursements \$614.85 and a balance on hand of \$343.60.

Officers for the year 1901 were elected as follows:

President—William C. Jewett.

Vice-President—Louis E. Bogen.

Directors—A. O. Elzner, C. N. Miller, H. E. Warrington.

Secretary and Treasurer—J. F. Wilson.

The following question was found in the question box: "What do you consider the maximum resistance per square foot for ordinary clay soils such as are found in the vicinity of Cincinnati, when designing foundations for bridges and buildings? Why?"

This was discussed at some length, it being the general opinion that while the soils at different localities would sustain different weights, one to two tons was about right, although in cases more than that had been allowed.

Upon the newly-elected President taking the chair the retiring President read the paper for the evening, as has been the custom, taking for his topic the question of parks for Cincinnati, which he treated in a very able manner.

On motion, the Club adjourned after extending to the retiring President a vote of thanks for his paper, and for the interest and work in behalf of the Club during the past year.

J. F. WILSON, *Secretary*.

Louisiana Engineering Society.

NEW ORLEANS, JANUARY 12, 1901.—The annual meeting of the Louisiana Engineering Society was called to order this date at 8 o'clock P.M. by President Malochée; twenty-five members and four guests being present.

The minutes of the meeting, held December 10, and the adjourned meeting, held December 17, were read and approved. Also, the minutes of the Board of Directors' meetings held on December 29, January 5 and January 15, respectively, were read for the information of the members present.

The annual report of the Board of Direction transmitting the reports of the Secretary, Treasurer and the three standing committees was read and approved.

A communication from Mr. John P. Coffin, Vice-President of the Southern Industrial Association, was read, which invited the Louisiana Engineering Society to join the association as a corporation. This was indorsed by the Board of Direction with the recommendation that the Society join said In-

dustrial Association. The communication was received, and it was decided by vote that the Society would join, and the Secretary was instructed to issue warrant for \$10, being the amount required for the annual dues.

The ballots for officers of the Society for the year 1901 were opened; Messrs. Duval, Wright and Lombard being appointed by the President as tellers. After a short recess, during which the votes were being counted, the Chair announced that fifty-one votes were cast, and the following gentlemen were elected to the several offices:

President—F. M. Kerr.

Vice-President—J. F. Coleman.

Secretary—John F. Richardson.

Treasurer—Walter H. Hoffman.

Director—Alfred Raymond.

Member Board of Administrators of the Association of Engineering Societies—H. J. Malochée.

An able and eloquent address was then delivered by Mr. H. J. Malochée, the retiring President. His subject was a review of the important office the modern engineer is performing in the economy of the world, and the duties and the importance of the position occupied by the engineering societies as factors in keeping up and raising the code of professional ethics among engineers.

A vote of hearty thanks for the preparation of his masterly paper and for the conscientious and successful manner in which he and his brother officers had conducted the affairs of the Society during the past year was given to Mr. Malochée.

Mr. F. M. Kerr, the new President, was installed in the chair, and made a brief speech of acceptance.

It was announced that the next regular meeting would be held on Monday, February 11.

The meeting adjourned at 10.05 P.M.

GERVAIS LOMBARD, *Secretary*.

ASSOCIATION OF ENGINEERING SOCIETIES.

VOL. XXVI.

FEBRUARY, 1901.

No. 2.

PROCEEDINGS.

Engineers' Club of St. Louis.

520TH MEETING, FEBRUARY 6, 1901.—Held at 1600 Lucas Place, 8.30 P.M.; President Spencer presiding. Thirty members and fourteen visitors were present.

Minutes of the 519th meeting were read and approved.

Minutes of the 314th meeting of the Executive Committee were read.

The applications for membership of Messrs. W. H. Henby and Truman M. Post were read.

President Spencer presented a draft of an "Act prohibiting the discharge of dense black smoke from any premises within the limits of all cities of the State of Missouri having a population of three hundred thousand inhabitants." This, together with a memorial to the General Assembly, was offered by the Chairman of the Committee on Smoke Prevention, with the suggestion that the members of the Club sign the same.

Upon discussion, it developed that Mr. Moore, Chairman of the Smoke Prevention Committee, preferred to have the memorial signed in the name of the Club by its officers. Upon motion made and duly seconded, it was ordered that the President sign and the Secretary attest the memorial.

Mr. D. W. Roper, who had taken up matter of repairing lantern, reported that same had been repaired and the lantern was in shape to exhibit, although it was far from perfect.

Motion made and carried, the Chairman appointed committee of three to report to the Club on lantern, stating what steps must be taken to secure a lantern which will give the best results. The committee appointed was Mr. Flad, Chairman, Mr. Roper and Mr. Maltby. This committee was also ordered to look up the matter of obtaining a good reading lamp for service in the meeting room.

The subject for the evening was an informal address by Mr. Arthur Thacher, president of the Central Lead Company and the Renault Lead Company, on "Lead Mines in Missouri." The speaker discussed, in a very interesting manner, but in a general way only, the geological features of the three lead districts of this State, taking up separately the Southwest

Missouri district, the Central Missouri district and the Southeast Missouri district.

Particular attention was given to the mines of the latter district, as they produce by far the greater proportion of the lead of the State. The speaker explained, in a brief but clear and interesting manner, the various steps followed in the production of lead in this district, beginning with prospecting for the mineral and following the movement of the rock in its course through the mill, whose product is the concentrate; then following the concentrate through the roasters and smelters, ending with the purified pigs of lead. A number of interesting views of mining properties and specimens of ore-bearing rock were shown. The speaker extended a very cordial invitation to all members to visit the mines of the Central Lead Company in order to better acquaint themselves with the nature of the very valuable and extensive lead deposits in this district.

Discussion was participated in by Mr. C. G. Reel and others.

The Chair announced as the subject of the paper for the next meeting, February 20, "A Historical Description of the Bridges over the Mississippi," illustrated by lantern slides, by Mr. F. B. Maltby.

It was decided that this meeting be an open one, and that members be requested to bring their friends, and make special effort to have a large attendance of ladies.

Adjourned to an adjoining room, where lunch was served.

W. G. BRENNEKE, *Secretary*.

521ST MEETING, ST. LOUIS, FEBRUARY 20, 1901.—Held at 1600 Lucas Place, 8.15 P.M.; President Spencer presiding.

Thirty-six members and eighteen visitors, including ladies, were present.

As the minutes of the 520th meeting had been printed on the announcement circular, and mailed to each member of the Club, it was moved and seconded that the reading of these minutes be dispensed with, and that they stand approved as printed.

The minutes of the 315th meeting of the Executive Committee were read.

The application for membership of Mr. Louis Bendit was read and referred to the Executive Committee.

President Spencer announced that as there had been no meeting of the Executive Committee this week, no action had been taken on the applications for membership of Messrs. W. H. Henby and T. M. Post, but their applications would be considered at the next meeting.

Mr. Flad, Chairman of the Committee on Lantern, reported that the committee had selected a new lantern on trial and that the lantern selected would be used in illustrating the paper of the evening. Its cost is between \$17 and \$18, and the cost of operating it is about 11 cents an hour. A new reading lamp was also provided.

The subject of the evening was a paper by Mr. F. B. Maltby, entitled "A Historical Description of the Bridges over the Mississippi River." Taking the bridges in the order of their occurrence, from the falls of Saint Anthony down the river, the speaker gave a description of each bridge, stating the authority for building, the general dimensions of all spans and approaches, the types of trusses, the classes of material in piers and superstructures and such other prominent points as were worthy of mention. The speaker made no attempt to go into engineering details, but confined his paper to a brief

statement of facts of general information. The paper was completely illustrated by lantern slides, views of nearly every bridge on the river being shown.

As there was no discussion after the completion of the paper, adjournment was made to the library rooms, where the Entertainment Committee had made special arrangements to serve a light lunch.

E. B. FAY, *Secretary pro tem.*

Boston Society of Civil Engineers.

JANUARY 23, 1901.—A regular meeting of the Boston Society of Civil Engineers was held at Chipman Hall, Tremont Temple, Boston, at 7.50 o'clock P.M.; President Alexis H. French in the chair; one hundred and forty-two members and visitors present, including ladies.

On motion of Mr. Howland, the reading of the record of the last meeting was postponed until the next meeting.

On motion of Mr. F. O. Whitney, it was voted that the Chairman be requested to appoint a committee of three to report to the meeting the names of five members to serve as committee to nominate officers. The Chairman appointed Messrs. F. O. Whitney, H. D. Woods and C. T. Main as the committee. Later in the meeting this committee reported, as a Nominating Committee, Messrs. F. W. Hodgdon, Dwight Porter, Henry Manley, R. S. Hale and C. R. Cutter, and they were chosen by the Society as its committee to nominate officers for the ensuing year.

On motion of Mr. Sherman, the thanks of the Society were voted to the Derby Desk Company for courtesies shown the members on the occasion of the visit to its manufactory this afternoon.

On motion, Mr. Henry Manley was appointed a committee to make arrangements for the annual dinner, and it was voted to make the usual appropriation for the incidental expense of the same.

Mr. Manley called attention to the death of Queen Victoria, which occurred since our last meeting, and told of the very gracious manner in which she received the American engineers on the occasion of their visit to Windsor Castle last June. In concluding he offered the following resolution:

Resolved, That this meeting desires to give expression to its feelings of sorrow and its sense of loss in the recent death of Queen Victoria; that it desires to do honor to her memory, remembering that amidst the multitude of events of the first importance in the world's history which have transpired during her long reign, she has always been quick to acknowledge the services of modern engineering, and to honor its representatives.

The resolution was adopted by a unanimous vote.

The literary exercises consisted of an entirely informal, but very interesting and instructive, talk by Dr. Desmond Fitzgerald, describing the palaces on the Grand Canal in Venice. The talk was very fully illustrated by lantern views.

Adjourned.

S. E. TINKHAM, *Secretary.*

FEBRUARY 20, 1901.—A regular meeting of the Boston Society of Civil Engineers was held at Chipman Hall, Tremont Temple, Boston, at 7.50 o'clock P.M.; Vice-President F. W. Hodgdon in the chair; seventy-six members and visitors present.

The records of the December and January meetings were read and approved.

Mr. Fred. Rufus Davis was elected a member of the Society.

On motion of Mr. Brooks, the thanks of the Society were voted to the United States Steel Company for courtesies extended this afternoon to the members of the Society who visited its works at West Everett.

Mr. Caleb Mills Saville read the paper of the evening, entitled, "Submerged Pipe Crossings on the Metropolitan Water Works." The paper was illustrated by numerous lantern views of the work. At the conclusion of the short discussion which followed the reading of the paper, Mr. Dexter Brackett had thrown on the screen a number of views of some of the recent work of the Metropolitan Water Board.

Adjourned.

S. E. TINKHAM, *Secretary*.

Engineers' Club of Cincinnati.

120TH REGULAR MEETING, CINCINNATI, OHIO, JANUARY 17, 1901.—Dinner was served at 6.30 P.M.

The regular meeting was called to order at 8 P.M.; with Vice-President Bogen in the chair.

There were twenty-one members present: Messrs. Bert. L. Baldwin, Ward Baldwin, Bogen, Carlisle, Carpenter, Coney, Elzner, Fritsch, Gordon, Gray, Hauck, Hobart, Innes, Kittredge, Nicholson, Osborn, Punshon, Read, Warrington, Rabbe and Wilson.

There was also present, by invitation, M. Philippe Bauna-Varilla, the French engineer, who was for several years connected with the construction of the Panama Canal, and who came to this city on invitation of the Commercial Club, before which organization he appeared last evening and spoke on the subject of the various proposed routes for an isthmian water connection between the Atlantic and Pacific Oceans.

The regular business was, on motion, waived, and the reading of the paper for the evening, by Mr. A. L. Hauck, on the subject "Economies and Economical Appliances Used in the Manufacture of Coal Gas," proceeded with, after which M. Bauna-Varilla favored the Club with a very interesting talk on the relative merits, advantages and feasibility of the Panama and Nicaragua routes for a ship canal, his comparison showing the former to be the better.

A vote of thanks was tendered him for his interesting and timely lecture, and also to Mr. Hauck for his paper.

On motion, the Club adjourned.

J. F. WILSON, *Secretary*.

Civil Engineers' Society of St. Paul.

REGULAR MONTHLY MEETING, FEBRUARY 4, 1901.—Deferred election of officers for ensuing year resulted in the election of:

President—A. O. Powell, Asst. Eng. U. S.

Vice-President—A. W. Munster, Bridge Eng. C. G. W. Ry.

Secretary—G. S. Edmondstone, City Bridge Engineer.

Treasurer—A. H. Hogeland, Res. Eng. G. N. Ry.

Librarian—C. A. Winslow, City Eng.'s office, St. Paul

Representative on Board of Managers for Association of Engineering Societies—Geo. L. Wilson, Asst. City Eng., St. Paul.

Percy E. Barber and Otto Luserke were elected members. The Secretary's report was read and placed on file. The Treasurer's report showed the Society to be free from debt, and a comfortable figure upon the credit side of ledger.

Constitution and By-laws amended changing meeting night from first to second Monday in each and every month.

Mr. H. J. Gillie, Superintendent Edison Electric Light Company, described terminal station within the limits of the city of St. Paul of the electric current generated of power house at St. Croix River Power Company at dam upon Apple River. Afterward members personally inspected the terminal station. Adjourned.

G. S. EDMONDSTONE, *Secretary*.

Technical Society of the Pacific Coast.

REGULAR MEETING, FEBRUARY 1, 1901.—Called to order at 8.30 P.M. by President Marx.

The reading of the minutes dispensed with by order of the Chair.

Mr. Charles Burekhalter addressed the Society on the subject of photographing the solar corona by the aid of a rotating comma-shaped disk attached to a slide, invented by the lecturer, by which certain unequal exposures are obtained to suit the degree of brightness of the field to be photographed. Mr. Burekhalter exhibited, by means of lantern slides, a number of beautiful results of his observations of the last solar eclipse at Siloam, Ga., in May, 1900, and explained at length the mechanism that had made it possible to achieve these remarkable results in astronomical photography.

A vote of thanks was passed for the author, expressing the appreciation of the Society. Adjourned.

OTTO VON GELDERN, *Secretary*.

Engineers' Society of Western New York.

REGULAR MEETING, FEBRUARY 5, 1901.—Meeting called to order at 8 P.M.; the President being in the chair. The following members present: Messrs. Haven, Diehl, Tutton, Knapp, Knighton, Speyer, Norton, C. M. Morse, Geo. F. Morse, Sikes, Weston, Ricker, Kielland, Buttolph and Babcock.

It was voted that the minutes of the last regular meeting be approved as printed.

The Executive Board reported that they had considered the matter of rent. At the meeting just after the annual meeting a Committee on Rooms was appointed to consider the matter of rooms, and they have reported that they think we had better stay where we are. Since then notice has been received that after the first of May the rent of the room in Elliott Square will be increased 15 per cent. Mr. Norton, Vice-President, was appointed a committee of one to further consider the matter, in order to find out what we had better do after the first of next May.

The Executive Board also reported that the Society had received applications from the following gentlemen: Edward Dennison Hooker and Stanley W. Hayes as members, and Leslie J. Bennett and Warren Rodney as associates. The applications were taken up separately, and on motion it was voted that they be referred to letter ballot.

The Executive Board also reported that the Society had elected the following gentlemen: Horace Corey Booz and David Augustus Decrow as members, James Franklin and Mathew S. Gardiner as juniors and Albert W. Caines, Samuel J. Dark and William Franklin, Jr., as associates.

THE PRESIDENT.—The Executive Board sent a marked copy of the printed minutes to the gentlemen who were appointed as committees to read papers before the Society, and to several other gentlemen, and have receive replies as follows:

From Mr. S. W. Hayes, who was requested to read a paper on "The Proper Construction of Docks," asking to be relieved until after the coming summer.

From Mr. C. D. Watson, who said, on account of assignment to work in the South, he would be unable to read a paper at present.

From Mr. David Cuthbertson, who stated that he would be pleased to read a paper on "The Workings of the Weather Bureau" at the meeting of the Society in March.

From Mr. C. R. Neher, who said he would read a paper on "Concrete Construction" at the March meeting.

The Librarian made a brief report.

Mr. Ricker, who had been appointed by the President as a committee of one on Docks, addressed the Society as follows:

MR. PRESIDENT AND GENTLEMEN.—All of you will perhaps remember the collapse of the two ore docks in Buffalo,—one at the Union Furnaces, the other belonging to the West Shore Railroad Company. I am now rebuilding the Furnace Company's dock, and will tell you what I am doing, but before outlining the plan, for the information of those who are not familiar with the conditions, will explain the failure as far as I can. At the foot of Hamburg street, on the east bank of the river, are located the furnaces of the Union Furnace Company, a combination of the three old companies. Here was built a pile and timber dock of the ordinary type of construction, and back of this dock was stored a great many tons of ore. A Brown hoist was erected on the dock, and the ore carried back on a traveler and dropped, but no part resting on the timber structure itself. Immediately back of the dock was a car track. The piles for a distance of 50 feet back were pretty staunchly anchored with 2-inch tie rods, the rods being looped over a rail, which was coupled up with fish plates in front of the inner row of piles, so that the dock was pretty well tied in. The penetration of the piles was from 4 to 5 feet only, and this fact, in addition to the nature of the soil itself, was the cause of the dock failing. Of course, in a pile and timber dock there is little resisting power to lateral outthrust, and an overload of ore simply pushed the whole dock out. After its failure there was but little left of the dock, as the whole structure moved out into the river from 20 to 35 feet. The tie rods being fastened in near the top the footing gave way before the rods broke. Some rods snapped off, in other cases pulled through the anchor bolts, and many piles were broken off. The rock underlying is practically level, there being a slight dip to the east, so that what in-

elination there was against the thrust of the ore. The rock is perfectly smooth and there was nothing to hold the feet of the piles, which slipped along as naturally as could be, and the ore, of course, went to the bottom. It was afterward dredged out with a clam shell dredge and taken back and stored in the yard.

With a dredge the old piles were drawn out and the earth dredged back 30 feet wide down to the rock. We are putting in cribs of 12 x 12 hemlock that are 26 feet wide with two bays of 13 feet each, and are loaded with stone. The cribs reach to a height of about 22 feet. On the top and front of these cribs it is proposed to form a concrete facing of truncated triangular form, 8 feet on the bottom and about 4 feet on top, with the slope on the inner side. The rock filling will be brought up over the entire width of the crib to the top of the concrete. The space made by dredging the earth at the natural slope back of the cribs will be packed full of slag, so that a large part of the treacherous earth back of the dock will be replaced by this slag filling, and so much of the thrust as was due to the earth will be taken away by using this more substantial material for back filling. The new dock will be 550 feet long. That portion of the unharmed pile dock immediately south of the cribs will be allowed to remain, but will not be used for the storage of ore.

THE PRESIDENT.—Is this the first dock or wharf that has been built in Buffalo with a concrete face?

MR. RICKER.—So far as I know, it is. In regard to facing the concrete, we will protect this from bruising by oak timber waling strips and a heavy cap of same material.

MR. DIEHL.—The underlying rock is level?

MR. RICKER.—Almost level. At the south end of the dock the water is 24 feet deep, at the north end it is probably not over 18 feet,—possibly 19 feet.

MR. DIEHL.—How was the width of the crib determined—what formula did you use?

MR. RICKER.—The usual formulas for retaining walls. My sole object was, of course, to get enough stone in the cribs to resist the thrust of the ore piles that would be imposed on the earth immediately back of the dock. And as a further precaution against possible movement of the cribs we shall bore into the rock and drop car axles into these holes vertically, each hole being 3 feet deep, the axles 6 feet long.

MR. KIELAND.—How deep is the water in front of the cribs?

MR. RICKER.—Eighteen feet.

MR. SIKES.—Was there any floor under the ore piles?

MR. RICKER.—Yes. Plank laid on sleepers on the ground. When we considered the cost of a pile and timber dock, we found that the piles must be 5 feet centers, and the caps would have to be 30 inches deep, and a corresponding floor system.

MR. NORTON.—I am somewhat acquainted with the geology of that section, having taken soundings for the rock dredging which the city has done from Ohio to Hamburg streets recently. The rock is worn smooth by glacial action, showing scratches, being mainly very smooth. Immediately above this is a layer of hard pan, containing much of the bed rock in various sized fragments. I believe it to consist largely of the broken and pulverized underlying rock. It was found difficult to drive steel rods through a few feet of this to determine the depth of the rock.

I should like to ask Mr. Ricker if he removes this hard pan with a dredge so as to place the cribs on the rock? And, also, if he thinks that the piles of the dock which failed were driven into this hard pan or through it? I hardly think it possible to drive an unshod pile through it.

MR. RICKER.—I think it extremely doubtful if the original piles penetrated this hard pan, as some were found broken at the point. We were able to remove the hard pan with dredges.

MR. NORTON.—I believe this formation underlies most of the Buffalo River Valley. It is found near its mouth, and also in Cheektowaga. In 1890 I sounded the rock in the river at the Watson elevator. Vessels grounded on what appeared to be rock bottom. A few drivings showed rock to be from 1 to 3 feet below bottom. Borings showed this layer of hard pan which the smaller dredges then in use were unable to strip off. Mr. Stewart, who is building the sub-structure for the D. L. and W. R. R. swing bridge on Water street over the Evans Slip, told me he expected to found the concrete abutments on rock. I told him it was doubtful if the dredge he had would remove the hard pan. He has since told me that it was not removed, but the concrete laid on top of the two feet of hard pan overlying the rock. I do not know whether they found it impossible to do so, or considered it as good as the concrete with which it would be replaced. At the high points of the bed rock the hard pan is often missing. In making some sketch plans for excursion docks, when the matter was recently under discussion, I provided for a construction quite similar to that used by Mr. Ricker at the furnace dock.

THE PRESIDENT.—Mr. Speyer, you found the same formation at Clinton street, did you not?

MR. SPEYER.—Yes, sir. Also at Smith-Seneca streets. There was about 3 feet of this hard pan on top of the rock.

THE PRESIDENT.—On which the retaining walls now rest?

MR. SPEYER.—Yes, sir.

MR. SIKES.—The same formation was found under the U. S. Break-water.

MR. KIELLAND.—When we built the coal trestle at Cheektowaga for the Lehigh Valley Railroad we stripped about an acre of the rock, which showed the same glacial markings, and the boulders which must have made the markings on the rock. The rock was polished in many places, and can be seen there to-day. We found the same formation that you find everywhere else. In some places we found the hard pan overlying the rock, in other places the rock was clean. The hard pan was from 3 to 4 feet thick, and filled with these boulders.

MR. TUTTON.—I would like to extend the remarks, which may be of interest to some of the members. I built a dock south of the Union Iron Works. We drove test piles from 80 to 90 feet before we brought up on the rock. That is, we *think* we brought up on the rock, we are not positive. There seemed to be an estuary running through South Buffalo, crossing the city line about where the Abbott road crosses. There seemed to be gravel at about 25 to 30 feet. This we passed through and drove our piles 20 or 30 feet farther; when we passed through this our piles dropped through. This dock was designed to carry from 200 to 400 pounds per square foot, of ordinary construction. As near as I can remember the dock was 40 feet wide on top. The piles, I think, were 7½ feet centers. The dock gave way in a different manner than the one

being replaced by Mr. Ricker. The ore sank down in the earth and the dock was lifted in the air 10 or 12 feet. This dock was replaced by Mr. Kielland, I having left the road in the meanwhile.

At the time the canals were cut across the Tift farm the foremen of the dredges ran a race to see which could take out the most material, and I think they cut through this layer of hard pan, and this probably accounts for the failure of this dock.

MR. KIELLAND.—I was Division Engineer of the Lehigh when this dock failed. A Brown hoist was constructed on the dock, resting on a pile foundation. The ore was piled from 25 to 30 feet high, the toe of the pile being from 50 to 60 feet from the front of the dock. Very suddenly the pile of ore sank and the dock rose in the air. I came out shortly after the accident. We took soundings in front of the dock and commenced immediately to reconstruct it. We cut off the piles. The Brown hoist was in good shape, only the joints were sprung. We cut off the piles which had been driven out of shape and drove other ones. We got the ore out and placed it farther back. It cost but little to repair the dock, and it is in use to-day.

Mr. Geo. F. Morse, Asst. Engineer L. V. R. R., said that the company had instructed him to make an investigation as to the proper load, etc. He had investigated the matter and had recommended to keep the toe of ore piles 70 (seventy) feet away from front of dock, to dump the ore in conical piles and not in ridges or to limit the load not to exceed more than 1500 to 2000 pounds per square foot of surface.

MR. RICKER.—Do you suppose the ore sank down to this layer of hard pan and rested on it?

MR. KIELLAND.—I think it did. It rested in a pocket. The Lehigh has the biggest dock in Buffalo, and they have not done anything especial to construct a dock to care for this ore. The only precaution is to keep ore piles far enough back from front of dock.

MR. RICKER.—All these failures seem to indicate that pile docks in this soil will fail with a load of about $1\frac{1}{2}$ tons to the foot, about the load which has produced the failure in every case.

MR. SIKES.—This hard pan shows at the Ridge road. There the rock is only about 25 feet below the surface, at Tift street 70 to 80 feet. This hard pan is about 18 feet from the surface at the city line and 31 feet at Tift street.

MR. TUTTON.—They find the same thing at the steel plant, and at Smokes Creek.

MR. KIELLAND.—I want to tell another thing in regard to docks on the Tift farm. The Lackawanna when they built their dock only drove their piles to this sand or hard pan. Just south of the Buffalo Creek bridge the hard pan is about 30 to 35 below water. This dock has been loaded very heavily as a rail and iron dock. It has kept its general elevation well.

The President thanked Mr. Ricker in behalf of the Society for his very interesting talk by means of which the Society has had a most instructive session.

The matter of sending out invitations to the different Societies in North and South America was taken up, and on motion of Mr. Ricker, seconded by Mr. Knapp, it was unanimously voted that the subject matter be referred to the Executive Board with power.

Meeting adjourned at 11 P.M.

G. C. DIEHL, *Secretary*.

MEMBERS ARE ADVISED . .
THAT THEY CAN OBTAIN

Reprints or Extra Copies of their Papers

AT THE FOLLOWING RATES:

			4 pages or less	5 to 8 pages	9 to 16 pages	17 to 24 pages	Covers extra.
100 Copies	.	.	\$2.25	\$4.00	\$5.50	\$9.25	\$2.25
250 "	.	.	2.75	5.00	6.50	11.25	2.75
500 "	.	.	3.50	6.50	8.75	15.00	3.50
1000 "	.	.	4.50	8.75	12.50	21.00	4.50

An extra charge will be made for printing and inserting such illustrations as are not printed on the same pages as the text, and for enameled paper, when this is used, but it is of course impossible to name rates for this in advance.

When reprints are wanted, notice of the fact, stating how many are desired and whether they are to be furnished with covers, should accompany the paper when it is sent to the Secretary of the Association.

If the paper has been discussed, please state whether it is desired that the reprint shall contain the discussion.

JOHN C. TRAUTWINE, Jr., Secretary,
257 SOUTH FOURTH STREET,
PHILADELPHIA.

ASSOCIATION OF ENGINEERING SOCIETIES.

VOL. XXVI.

MARCH, 1901.

No. 3.

PROCEEDINGS.

Proceedings of the Fourteenth Annual Meeting Held in Butte, Montana, January 10 to 12, 1901.

THE fourteenth annual meeting of the Montana Society of Engineers was held in Butte, Mont., from January 10 to 12, 1901. On the evening of the 10th the Society held a "smoker" in their headquarters, Rooms 16 and 17, Tuttle Building. Light refreshments were served and the evening was spent in a very enjoyable social gathering.

January 11 was devoted to visiting points of engineering interest in and about Butte. In the morning the party met at the Society headquarters, and made a trip over the Butte Street Railway to Walkerville; arriving at the new reservoir of the Butte City Water Company, they were escorted by the chief engineer, Mr. Eugene Carroll. They then paid a visit to the Montana State School of Mines, where they were welcomed by Prof. N. R. Leonard, and shown the many points of interest in the new institution. In the afternoon the members separated into smaller parties and visited the various mines and smelters, some going underground to view the riches of mother earth, some to the smelters to study the various methods of treating ore, and others to inspect the splendid machinery of the various hoisting plants used at the different mines, points of interest in which Butte can equal if not excel any city in the world.

At 8.30 P.M. Mr. H. V. Winchell, chief geologist for the Anaconda Copper Mining Company, delivered a very interesting lecture, illustrated with stereopticon views, on "The Iron Mines of Minnesota," in the Council Chamber of the City Hall.

The annual business meeting was held at the Council Chamber, City Hall, Butte, Mont., January 12, 1901.

The meeting was called to order at 10 o'clock A.M. by the President, Mr. Blackford, in the chair.

The Secretary called the roll of members present, as follows:

Geo. T. Wickes, F. L. Sizer, R. R. Vail, Albert Koberle, W. J. Flood, Eugene Carroll, B. D. Whitten, S. H. Crookes, W. H. Williams, J. H.

Harper, R. A. McArthur, Carlisle Mason, C. W. Goodale, G. W. Tower, Jr., C. D. Vail, E. C. Kinney, Wm. Zasliske, A. W. Catlin, C. H. Bowman, C. H. Moore, C. W. Paine, N. R. Leonard, Eugene Sickles, August Christian and C. V. Page.

The Secretary read the minutes of the meeting held December 8, 1900.

The minutes were approved as read.

The Secretary presented applications for membership as follows:

Nathan R. Leonard, President of the Montana State School of Mines.

Reno H. Sales, assistant engineer for the Boston and Montana Company, at Butte.

Charles Warner Paine, engineer in charge of the new works for Butte City Water Company.

Sam. Edward Davis, head surveyor for the Boston and Montana Company, Butte.

Rudolph Joseph Decker, mechanical engineer of the Montana Ore Purchasing Company, Butte.

William White, architect, Butte.

Edgar James Strasburger, civil engineer, Butte.

Frederick John Rowlands, salesman of mining machinery, Butte.

Stephen Pearl Wright, proprietor of the Western Mining Supply Company, Butte.

Charles John Adami, mining engineer for the Butte and Boston Mining Consolidated Company.

On motion of Mr. Sizer the applications were referred to the Trustees.

The Secretary presented further applications as follows, which were similarly referred:

Burt Adams Tower, mining engineer with the Montana Ore Purchasing Company, Butte.

Alfred Frank, mining engineer with the Montana Ore Purchasing Company, Butte.

Richard Austin Lacey, engineer with the Montana Ore Purchasing Company, Butte.

Messrs. Whitten and Koberle and Professor Williams were appointed tellers to canvass ballots for officers.

The Secretary read his report, as follows, which, upon motion, was ordered filed:

REPORT OF SECRETARY AND LIBRARIAN FOR THE YEAR ENDING JANUARY 12, 1901.

BUTTE, MONT., January 12, 1901.

To the President and Members Montana Society of Engineers.

GENTLEMEN:—I beg leave to submit the following as my report for the year ending January 12, 1901:

FINANCIAL STATEMENT.

RECEIPTS.

Cash in Treasury, January 13, 1900	\$355.11
Dues collected	821.50
From sale of old furniture	30.00
Total	<u>\$1,206.61</u>

DISBURSEMENTS.

To expense 13th annual meeting	\$97.05
To Association of Engineering Societies	222.95
To rent of headquarters and janitor's services.....	261.00
To furnishing of headquarters	256.88
To printing and stationery, including 250 copies Constitution, By-Laws, etc.	148.75
To Secretary's salary	100.00
To stamps, envelopes, express charges, telegraphing, hauling, P. O. box and sundries, as shown in vouchers attached to Secretary's bills	46.59
Total	\$1,133.22
Leaving a balance on hand January 12, 1901 ..	73.39
	<hr/> \$1,206.61

All the bills against the Society have been paid up to date excepting the bill for printing the proceedings of the thirteenth annual meeting, which has been held pending correction.

MEMBERSHIP.

The following table shows the membership of the Society of all grades at the beginning and end of fiscal year:

	Jan. 13, 1900.	Jan. 12, 1901.
Honorary members	4	4
Active members	117	110
Associate members	21	28

During the year one member resigned, fourteen members were dropped for non-payment of dues and not conforming to requirements of membership, and seven members, through removal from the State, were removed from active to associate list. Sixteen new members were elected during the year.

The Society lost one member by death during the year, the same being Mr. J. S. B. Hollinshead, of Butte, whose sudden death took place at his home on July 19, 1900.

Four papers were read and two discussions were had at the various meetings during the year. Two hundred and fifty copies of the Constitution and By-Laws, containing in addition the list of officers and members, were published, and distributed to the members of the Society. Two hundred and fifty copies of the proceedings of the thirteenth annual meeting were published. The same included also a synopsis of the meetings of the year 1899, and all the papers read before the Society during that year, and the list of officers and members.

Library. The books of the Society have been shelved in new Werneke bookcases, but no provision has yet been made for properly taking care of the various smaller pamphlets and transactions of various Engineering Societies.

The following magazines are regularly received: *Engineering and Mining Journal*, *Engineering Record*, *Construction News*, *Railway Age*, *Indian Engineering*, *Railway and Engineering Review*, *Irrigation Age*, *Modern Machinery*, *Railway Master Mechanic*, *Journal of the Western Society of Engineers* and the JOURNAL OF THE ASSOCIATION OF ENGINEERING SOCIETIES.

Many smaller books, pamphlets and transactions of various Societies have been received and proper acknowledgment made.

Respectfully submitted,

R. A. McARTHUR, *Secretary*.

A REGULAR meeting of the Montana Society of Engineers was held March 9 in their headquarters, Rooms 16 and 17, Tuttle Building, Butte, Mont., with nineteen members and two visitors present; Vice-President August Christian in the chair.

Applications of Al Arthur Abbott and Albert James Flood were read and accepted for balloting. Messrs. Adami and Tower were appointed tellers to canvass ballots for membership, and reported Messrs. Richard Austin Lacy, Steven P. Wright and Fred. T. Greene elected as members.

Report of Annual Meeting Committee was read and accepted and committee discharged.

The committee appointed to revise the Constitution to create a junior membership submitted the following report:

PROPOSED AMENDMENT TO THE CONSTITUTION.

ARTICLE II.

MEMBERS.

SECTION 1. The membership of this Society shall be designated as Active Members, Associate Members, Corresponding Members, Junior Members and Honorary Members.

SEC. 2. An active member shall be a civil, mechanical, mining, electrical or other professional engineer; an architect, geologist, metallurgist or analytical chemist. He shall have been in active practice of his professional work for at least four years, or in responsible charge of professional work for at least two years, and shall be qualified to design and direct engineering work, or capable of carrying on the work of his profession. Credits from a school of recognized reputation in the above profession shall be considered as equivalent to one-half the time they represent as active practice. The performance of the duties of a teacher in schools of high grade in the above professions shall be accepted as equivalent to an equal number of years of responsible charge of professional work.

SEC. 3. An associate member shall be a person who by scientific acquirements or practical experience has attained a position in his special pursuit qualifying him to co-operate with engineers in the advance of engineering knowledge or practice.

SEC. 4. A corresponding member must have his residence outside of the State of Montana, and must be competent to contribute valuable information on engineering questions. This grade will also include members of the Society who have removed from the State and wish to temporarily withdraw from active participation in the affairs of the Society.

SEC. 5. A junior member shall have had active practice in his branch of engineering for at least two years, or the equivalent of the same as stated in Section 2 of this Article. A junior member shall be transferred to active membership as soon as he becomes eligible therefor.

SEC. 6. An honorary member shall be a person of acknowledged eminence in one of the professions enumerated in Section 2 of this Article.

SEC. 7. Active members, associate members and junior members shall be designated at resident and non-resident members. Those living within thirty miles of the court house in Butte shall be classed as resident members.

SEC. 8. Any member of the Society who removes from the State and wishes to temporarily withdraw from active participation in the affairs of the Society may do so on filing with the Secretary a written declaration of his intentions and paying to the Secretary all accumulated fees or other indebted-

ness due the Society. He will then be classed as a corresponding member, and will be subject to no dues or assessments. He may return to membership by giving written notice to the Secretary and paying to him all assessments and dues for the current year.

SEC. 9. Any member of any other Society in the Association of Engineering Societies, in good standing, may become a member of this Society, when duly elected as described in Article IV of the By-Laws, without paying the initiation fee, and with a release from the annual dues for such period, not over one year, as he may show by certificate he has paid in advance in the Society from which he comes.

ARTICLE IV.

SECTION 1. Active members alone shall have the privilege of voting and holding office. Associate members are entitled to vote, but are not eligible to hold office.

Substitute in Articles III, IV and V of the Constitution the words "Active and Associate Member" in place of "Member" where it refers to voting and "Active Member" where it refers to holding office.

PROPOSED AMENDMENT TO THE BY-LAWS.

ARTICLE IV.

ADMISSION TO THE SOCIETY.

SECTION 1. All candidates for admission to the Society shall make application in writing, etc.

SEC. 6. The annual dues of all resident active members and associate members shall be \$8; resident junior members and non-resident active members and associate members \$6; non-resident junior members \$4. Honorary and corresponding members shall be subject to no dues or assessments. All dues shall be paid to the Secretary on or before the first regular meeting in February of each year.

Substitute in the By-Laws the words "Active and Associate Member" in place of "Member" where it refers to voting and "Active Member" where it refers to holding office.

A motion was passed requesting the report of the committee be printed and sent to the members of the Society inviting a written discussion to be presented at the next regular meeting.

Mr. McArthur presented the following resolutions, which were unanimously adopted:

WHEREAS, A Divine Providence has seen fit to remove from our earthly associations another member of this Society; be it

Resolved, That in the death of David Walker Hardenbrook we recognize the loss of a member whose kindly disposition and gentle manner have won the esteem of his entire acquaintance, and whose quiet and faithful performance of his engineering duties has commanded the respect and confidence of all his professional associates.

Resolved, That this sentiment be spread upon the minutes of this meeting, our sympathy be extended to his friends and relatives and a copy of this action be forwarded to his bereaved family.

A motion was passed requesting Mr McArthur to prepare a biography of the deceased to be presented at the next regular meeting. Messrs. Moore, Harper and Weed were appointed on a committee to select a design for a badge of the Society.

Mr. Walter H. Weed, United States Geographical Survey, entertained the Society with an interesting talk of the mines recently visited by him in Mexico. The geological conditions around Chihuahua and Parral, together

with many interesting features of the country, were described in a very entertaining manner.

NOTICE.—The attention of the members is especially called to the report of the Committee on Revision of the Constitution presented above, and any desirable changes or suggestions should be sent in at once to the Secretary.

This will be presented at the next regular meeting, at which time the matter will be further considered.

RICHARD R. VAIL, *Secretary*.

THE PRESIDENT.—Gentlemen, you have heard the report of the Secretary. What is your pleasure?

It was moved and seconded that the report be placed on file, and upon being put to vote was duly carried.

THE PRESIDENT.—The next order of business is the report of the Treasurer.

MR. HARPER.—I would say that my report is hardly complete. I am expecting two or three further items that I intended to embrace in the report. Mr. McArthur and myself, however, have checked this morning, and have reached a practical agreement. There is at the present time \$73.39 in the Treasury, as he states in his report.

THE PRESIDENT.—When will you promise us your formal written report, Mr. Treasurer?

MR. HARPER.—It will be filed some time during the afternoon, probably by two o'clock.

THE SECRETARY.—If permitted, I will say in that connection, that the items to which Mr. Harper refers are three orders, which were issued January 8, and they are now in the hands of Mr. Moulthrop, who is one of the trustees, and I telephoned him this morning to see if I could get them, and I have been expecting them here. That is the reason that we could not incorporate them in that report.

THE PRESIDENT.—Gentlemen, you have heard the report of the Treasurer. What is your pleasure?

MR. GOODALE.—I move that the Treasurer be given further time to make his report.

The motion was seconded, and upon being put to vote was declared carried.

THE PRESIDENT.—The Secretary will please read the report of the committee that canvassed the ballots for the election of officers.

THE SECRETARY.—The report reads as follows:

“MR. PRESIDENT:—Your committee, appointed to canvass the ballot for officers for the year 1901, desire to report as follows: There have been forty-six ballots cast, of which Frank L. Sizer received forty-six for President; August Christian forty-six for First Vice-President; George T. Wickes forty-six for Second Vice-President; Richard R. Vail forty-six for Secretary and Librarian; Joseph H. Harper forty-six for Treasurer and member of the Board of Managers of the Association of Engineering Societies, and Bertram H. Dunshee forty-six for Trustee for three years.

“Respectfully submitted,

“ALBERT KOBERLE,

“W. H. WILLIAMS,

“B. D. WHITTEN,

“Committee.”

THE PRESIDENT.—Gentlemen, you have heard the report of the committee who have canvassed the ballots. The report shows that the candidates for officers were all elected unanimously.

You have elected for President of the Society for the ensuing year one of the charter members of the Society, an engineer very widely and favorably known throughout the State and elsewhere, and one who will conduct the affairs of the Society with dignity and ability.

I will appoint Mr. Kinney and Mr. Tower to escort the newly-elected President to the chair.

(The committee performed its office.)

I take pleasure in introducing Mr. Frank L. Sizer as President of the Society. (Applause.)

The newly-elected President took his seat in the President's chair, and addressed the Society as follows:

THE PRESIDENT.—Gentlemen of the Society, it is with mingled feelings of pain and pleasure that I stand before you to-day,—pleasure because I regard it an honor to be selected as your President, and pain because I have always looked upon this office as one belonging to the older men of the Society, and I realize now, when this honor is thrust upon me, that I can no longer count myself one of the young men. I admit being a charter member of the Society, and in that sense an old man, but it seems only a few short years ago that I labored under the disadvantage of being thought too young to take charge of any important engineering work. But that is a disability we can all outgrow, and I feel that the only thing of moment is to know whether a man can do his work thoroughly well.

I am growing to take more and more pride in the accomplishment of one piece of work in our beloved profession, and I feel that I shall be thoroughly satisfied with my life if I can succeed in rearing one monument that will be lasting. In this respect I feel that the civil engineer and the architect have the advantage, for it has truly been said of the mining engineer that his province is to tear down rather than to build up,—in other words, "to tear the insides out of the earth" seems to be a particular delight of that branch of the profession to which I have the honor of belonging.

I have always taken great pride in this Society. While I have done much less than many others to build it up and strengthen it, I have yet tried to do my part in those years in the past, when, with our good President Haven,—the only one who ever had the audacity to demand a "third term,"—I assisted in putting hats on chairs to represent a quorum at some of our monthly meetings. But the Society has outgrown the age of tottling, and I feel it is thoroughly able to stand alone.

I am very much gratified with the growth of the Society. In four years we have just doubled our membership, and it seems to me that although our grand young treasure State has developed wonderfully in this same period, our Society can say truly that it has more than justified the fondest hopes of its most sanguine members. It is certainly a gratification to know that in our membership is now contained nearly all of the most prominent members of the professions which are eligible to election in the Society throughout the State, and I feel that there is great need of still further push for the increase of our membership, and gathering in the younger men in the profession. The province of this Society is broad, the scope of it is large, and yet the work to be done is still larger; the opportunities for advancement of

the members of this Society in every direction are very much greater than most of us realize. When I look over the list of members I can hardly justify the choice of your Nominating Committee as regards myself, but with the assistance of the worthy Vice-Presidents and each and every member of the Society, I shall endeavor to merit your approbation in the years to come. (Applause.)

Mr. Wickes, second Vice-President, addressed the Society as follows:

GENTLEMEN:—I was not aware that the Vice-President was to be called upon to take a prominent position in the chair beside the President. I am very much obliged to you for the honor you have conferred upon me, which was entirely unexpected. Although I am one of the charter members, I have not taken very active part, in fact no part at all, in the meetings, but that has been largely due to the fact that my work has been so out of the way, even when the Society held its meetings in Helena, and while my family was there I was away most of the time, and at the times of the meetings it has not been possible for me to go to them. I have, however, always taken a great interest in the doings of the Society, and have always been glad to know that the engineers were combining and would work together. I think that is a feature, generally, that the engineers have not heretofore pulled together as much as they should, as much as many other organizations in the professions do pull together and support each other; but there is no way in which they will pull together or bring about that result better than to be in an organization of this character, and I hope that it will continue to grow and become stronger; and as our President has said that an effort will be made to make the Society a larger and a stronger organization. I thank you for the honor conferred.

Mr. Vail, the newly-elected Secretary, thanked the Society for the honor conferred upon him by his election, and expressed the hope that he might be enabled to perform his duties creditably.

Mr. Tower, Chairman of Committee of Arrangements for Annual Meeting, requested that the members of this Society contribute to the treasury of the committee \$3.50 each for the purpose of defraying expenses.

On behalf of Mr. H. W. Turner, Chairman of Committee on Transportation, Mr. McArthur reported that Mr. Turner had fulfilled the duties imposed upon him and had secured rates from all the railway companies concerned.

The meeting then adjourned until 2 P.M.

AFTERNOON SESSION.

The Society was called to order at 2 o'clock P.M. by the President F. L. Sizer in the chair.

THE PRESIDENT.—We finished Order of Business No. 6, with the exception of some letters which were received by the Society, and I will ask Mr. McArthur to read those letters.

The Secretary read letters of regret from William Appleton Haven and E. H. Beckler, Honorary Members of the Society, upon their inability to be present.

The Secretary was directed by the President to respond to the letters.

THE PRESIDENT.—It will be proper at this time to hear the report of the Treasurer.

The Treasurer, Mr. Harper, submitted his report to the Society.

MONTANA SOCIETY OF ENGINEERS IN ACCOUNT WITH
JOSEPH H. HARPER, TREASURER.

By amount received from Forrest J. Smith, ex-Treasurer.....	\$227.11
“ “ “ “ R. A. McArthur, Secretary.....	851.50
“ “ “ “ A. S. Hovey	128.00
	<hr/>
	\$1,206.61
To expenditures (orders Nos. 1 to 35) as per vouchers....	\$1,133.22
Balance in treasury	73.39
	<hr/>
	\$1,206.61

THE TREASURER.—The vouchers referred to are herewith tendered. They are complete with one exception. The last order, or the last draft that I sent to Mr. Trautwine, Secretary of the Association, has not yet been returned. I will make it a personal matter and see that that is properly attached when it does arrive.

The Treasurer's report was ordered referred to the Trustees. On motion of Mr. Carroll, the Secretary was directed to write letters of thanks to railroad companies and others for courtesies extended to the Society.

On motion of Mr. Wickes, the visiting members expressed their thanks for the hospitality extended to them by the resident members.

On request of the President, the Secretary read Section 3 of Article II as follows: "Candidates for admission to the Society, as members, must have been engaged for at least five years in some branch of engineering or architecture, or have been graduated as engineer or a manager of a railroad, canal or other public work; a geologist, chemist or mathematician; a manager of a mine or metallurgical works; or one who from his scientific acquirements or practical experience has obtained eminence in his special pursuit, qualifying him to co-operate with engineers in the advancement of professional knowledge, but may not himself be practicing as an engineer."

Mr. Goodale urged the advisability of establishing a class of associate members, and asked for discussion of the subject.

Mr. Blackford called attention to provisions of Section 5, Article II, as follows:

"Any member of the Society who removes from the State and wishes to temporarily withdraw from active participation in the affairs of the Society may do so on filing with the Secretary a written declaration of his intentions and paying to the Secretary all accumulated fees or other indebtedness due the Society. He will then be classed as an Associate, and will be subject to no dues or assessments. He may return to membership by giving written notice to the Secretary and paying to him all assessments and dues for the current year."

Then Mr. Harper suggested the title "Junior Members," and on motion of Mr. C. D. Vail, a committee of three was appointed to propose an amendment to the Constitution regarding the matter of membership, and to provide for Associate and Junior Memberships.

The Chair appointed Messrs. Goodale, Charles D. Vail and Blackford as members of the Committee on Revision of the Constitution. On request of Mr. Blackford, he was excused from service on the committee, and Mr. McArthur appointed to fill the vacancy.

Mr. Christian, First Vice-President, expressed his thanks for the honor conferred in his election.

The Secretary read a letter from Mr. Charles H. Repath, giving an account of the death of Mr. Hollinshead and a short sketch of his life's history.

Mr. Carroll voiced the regret of the Society respecting the death of Mr. Hollinshead, and dwelt upon the enthusiasm with which he took part in every movement for the benefit of the Society.

On motion of Mr. Carroll, seconded by Mr. Blackford, the Secretary was instructed to prepare a memorial of Mr. Hollinshead for publication in the JOURNAL OF THE ASSOCIATION OF ENGINEERING SOCIETIES. The President appointed Messrs. Moore, Goodale and Repath members of the committee to prepare this memorial.

On motion of Mr. McArthur, the Secretary was instructed to have 250 copies of the proceedings of this meeting published and distributed to the members of the Society.

Mr. Carroll urged that the publication of these proceedings be expedited.

Mr. Harper mentioned the annoyance caused by the omission on the part of the printers to supply the illustrations accompanying his paper on the Big Hole Dam, in the reprints furnished the Society.

On motion of Mr. Carroll, the motion was amended so as to instruct the Society to procure from the Secretary of the Association of Engineering Societies a reprint of the proceedings of the annual meeting, including the papers presented, and the motion as amended was carried.

Mr. F. W. Blackford, retiring President, presented his annual address and expressed his thanks to the members for the courtesy extended to him during his term of office.

The President complimented Mr. Blackford upon his instructive and entertaining address.

The Society then adjourned.

The banquet held at the McDermott Hotel commenced at 9 o'clock. The following members were present: F. W. Blackford, Eugene Carroll, A. W. Catlin, August Christian, S. H. Crookes, B. H. Dunshee, W. J. Flood, C. W. Goodale, F. P. Gutelius, J. H. Harper, A. E. Hobart, E. C. Kenney, Albert Koberle, M. L. Macdonald, Carlisle Mason, R. A. McArthur, E. R. McNeill, C. V. Page, B. R. Putnam, Eugene Sickles, F. L. Sizer, G. W. Tower, Jr., H. W. Turner, C. D. Vail, R. R. Vail, B. D. Whitten, F. W. C. Whyte, G. T. Wickes, W. H. Williams, E. H. Wilson, H. V. Winchell, C. H. Bowman and Wm. Zschke. Also the following guests: B. A. Tower, Alfred Frank, R. H. Sales, C. J. Adami, S. P. Wright, E. J. Strasburger, R. J. Decker, C. W. Paine, Harry Gallwey, J. E. Dawson, C. C. Rueger.

Mr. Eugene Carroll acted as toastmaster, and following toasts were replied to:

"The President of the United States," by C. H. Moore.

"The Montana Society of Engineers," by F. L. Sizer.

"The Educational Institutions of Montana," by W. H. Williams.

"The Geologist," by H. V. Winchell.

"The Mining Engineer," by Geo. T. Wickes.

"Our former President, W. A. Haven," by C. W. Goodale.

"The Irrigation Engineer," by E. C. Kenney.

"The Ladies," by Geo. W. Tower, Jr.

"The Civil Engineer in British Columbia," by Fred. Gutelius.

Besides various stories and short talks by Messrs. Koberle, Wright, Dawson, Christian, Wilson and others.

Boston Society of Civil Engineers.

BOSTON, MARCH 20, 1901.—The annual meeting of the Boston Society of Civil Engineers was held at Chipman Hall, Tremont Temple, at 7.35 o'clock P.M.; President Alexis H. French in the chair. Ninety-two members and visitors present.

The record of the last meeting was read and approved.

Messrs. William C. Ogden, John K. Perkins, Lewis D. Thorpe and Andrew W. Woodman were elected members of the Society.

The Secretary read his annual report, which was accepted.

The Treasurer read his annual report, which was accepted and ordered to be placed on file.

Mr. Corthell presented and read the annual report of the Committee on Excursions, which was accepted.

The Librarian presented and read the annual report of the Committee on the Library, which was accepted.

Professor Allen presented and read the annual report of the Committee on Quarters, which was accepted.

The Secretary read the annual report of the Board of Government, which was also accepted.

On motion of Professor Swain, it was voted to adopt the recommendation of the Board of Government, that the incoming board be directed to petition the General Court at its next session for authority to enable the Society to hold a larger amount of personal and real estate.

The recommendation that the sum of \$75 be appropriated for the purchase of standard engineering books, was also adopted.

On motion of Mr. Stearns, it was voted to refer to the Board of Government, with full powers, the question of continuing the several special committees of the Society, and the selection of the members thereof.

Messrs. Henry D. Woods and Henry A. Varney, the tellers of the election, submitted the result of the letter ballot for officers.

In accordance with their report the President announced the election of the following officers:

President—Lawson B. Bidwell.

Vice-President (for 2 years)—X. Henry Goodnough.

Secretary—S. Everett Tinkham.

Treasurer—Edward W. Howe.

Librarian—Louis F. Cutter.

Director (for two years)—William M. Brown, Jr.

The President then introduced Mr. J. A. Ockerson, of St. Louis, a member of the Mississippi River Commission, who read the paper of the evening, entitled, "The Mississippi River; Some of Its Physical Characteristics, and Measures Employed for the Regulation and Control of the Stream." The paper was fully illustrated by stereopticon views.

On motion of Professor Swain, the thanks of the Society were voted to Mr. Ockerson for his kindness in reading his valuable paper before the Society.

Before declaring the meeting adjourned the President introduced the President-elect, Mr. Bidwell, who thanked the members for the honor which they had conferred upon him.

Adjourned.

S. E. TINKHAM, *Secretary*.

ANNUAL REPORT OF THE BOARD OF GOVERNMENT FOR THE YEAR 1900-01.

BOSTON, March 20, 1901.

To the Members of the Boston Society of Civil Engineers:

In compliance with the provisions of the Constitution, the Board of Government submits its report for the year ending March 20, 1901.

At the last annual meeting the total membership of the Society was 490, of which 482 were members, 2 honorary members and 6 associates. During the past year we have lost 9 members; 2 by death, 5 by resignation and 2 by forfeiture of membership for non-payment of dues.

There have been added to the Society during the year 19 members, 17 of these have been new members and 2 former members have been reinstated.

Our present membership consists of 2 honorary members, 6 associates and 492 members; a total of 500.

The record of the deaths during the year is: John C. Haskell, died June 12, 1900; Moses W. Oliver, died September 8, 1900.

Ten regular meetings and one special meeting of the Society have been held during the year, and the nineteenth annual dinner was given at the Hotel Vendome on March 5, 1901.

The average attendance at the regular and special meetings was 74, the largest being 142 and the smallest 45. The attendance at the annual dinner was 149.

The following papers have been read at the several meetings:

March 21, 1900.—“The Outlook for Engineers,” by President C. Frank Allen.

April 4, 1900.—“The Evolution of the Modern Sky-scrapers,” by Clarence H. Blackall. (Illustrated.)

April 18, 1900.—“Difficulties Encountered in Building the Concord, Mass., Sewerage System,” by Leonard Metcalf. (Illustrated.)

May 16, 1900.—“Automobile Vehicles,” by Prof. Louis Derr. (Illustrated.)

June 20, 1900.—“Filtration Experiments made at Pittsburg,” by Morris Knowles. (Illustrated.)

September 19, 1900.—An account of matters of interest to engineers seen in Europe during the past summer, by Henry Manley, Edward Sawyer, F. W. Hodgdon, H. D. Woods and Desmond FitzGerald.

October 17, 1900.—“A Successful Siphon,” by R. S. Hale. “Experiments on Brick and Concrete Arches,” by W. D. Bullock. “Tests of a Rapp Floor and a Gustavino Arch,” by F. H. Fay. “Expanded Metal in Connection with Concrete Construction,” by W. M. Bailey. “Ransome System of Concrete Work,” by M. C. Tuttle. “The Roebling System,” by A. W. Woodman. (Illustrated.) Memoir of John H. Blake.

November 21, 1900.—“The Use of Water Power by Direct Air Compression,” by W. O. Webber. (Illustrated.)

December 19, 1900.—“Stone Arch Bridges Recently Constructed on the Fitchburg Railroad,” by A. S. Cheever. “Arch Centers,” by J. W. Rollins, Jr. (Illustrated.)

January 23, 1901.—“Palaces on the Grand Canal,” by Desmond FitzGerald. (Illustrated.)

February 20, 1901.—“Submerged Pipe Crossings, on the Metropolitan Water Works,” by C. M. Saville. (Illustrated.)

Five informal meetings have been held in the Society's library during the past year. The subjects discussed at these meetings have been as follows:

March 28, 1900.—"A Year in Alaska," by Laurence B. Manley.

April 11, 1900.—"Improvement of Feeder to Middlesex Canal," by Arthur T. Safford.

December 5, 1900.—"Street Construction as seen in the Streets of London, Paris and other European Cities," by Henry Manley. Also, "Description of the Pitch Lake in Trinidad," by H. T. Manley.

January 2, 1901.—"Methods of Mixing Concrete," by Sanford E. Thomson.

January 9, 1901.—"Some Impressions of Manila," by J. C. S. Taber.

The board desires to congratulate the Society upon its growth in strength, both numerically and financially, and to call its attention to the fact that our charter only allows us to hold real and personal estate to the amount of \$20,000, while at the present moment the property of the Society is worth not far from \$15,000.

In order to meet the contingencies of a bequest, or a movement in the direction of securing permanent quarters and of the possible delays in obtaining the necessary legislation to hold a larger amount, the retiring board recommends that the incoming one be authorized and directed to make application to the next session of the General Court for the right to hold real and personal estate to the amount of \$100,000, or such other amount as that board shall deem advisable.

The growth of our Society is nowhere more apparent than in the congested condition of our Library, which needs much additional wall and floor space for the material we have, and at the same time should be greatly strengthened in standard engineering literature. To make room for the new books it would seem best to send away for storage, until we have more room, or otherwise dispose of such material, which can be very nearly, if not quite as well consulted at the public libraries.

Two years since the Society adopted the policy of appropriating \$50 annually for the purchase of standard engineering books. It now being apparent that that step was a judicious one, and it being also clear that \$50 annually is not sufficient to provide the new books which we should have,—and many of the older ones which we have not as yet been financially able to get, but cannot afford to be without,—the board recommends that the appropriation for this purpose be increased to \$75 for the coming year.

We desire to call to the favorable attention of the Society the practice the past year, adopted by the Excursion Committee, of causing to be printed upon the notices of the monthly meetings information relating to engineering work in progress in this part of the country, and to express the opinion that it should be continued.

Respectfully submitted to the Board of Government,

ALEXIS H. FRENCH, *President*.

ABSTRACT OF THE TREASURER'S AND SECRETARY'S REPORTS FOR THE YEAR
1900-01.

Receipts:

CURRENT FUND.

Dues from new members	\$95.00	
Dues for year 1899-1900	13.00	
Dues for year 1900-01	3,389.00	
Dues for year 1901-02	29.00	
Sales of JOURNALS	2.10	
Rent of rooms	900.00	
Interest on deposits	23.77	
Balance on hand, March 22, 1900.....	1,910.43	
		<hr/> \$6,362.30

Expenditures:

Rent	\$1,665.00	
Association of Engineering Societies.....	1,004.50	
Transferred to Permanent Fund	2,017.50	
Printing, postage and stationery.....	469.04	
Secretary salary	400.00	
Furniture and repairs	117.63	
Periodicals and binding	96.70	
Incidentals	97.17	
Annual dinner	85.50	
Books	49.60	
Stereopticon at meetings	80.00	
Lighting rooms	26.34	
Clerical work for Librarian	21.49	
Reporting meeting	5.00	
		<hr/> \$6,135.47
Balance on hand		\$226.83

Receipts:

PERMANENT FUND.

Seventeen entrance fees	\$170.00	
Current fund	2,017.50	
Shares Merchants' Co-operative Bank.....	1,147.18	
Interest	225.30	
Subscription to Building Fund	100.00	
Balance on hand, March 22, 1900	165.54	
		<hr/> \$3,825.52

Expenditures:

Deposit in Franklin Savings Bank	\$1,017.50	
Deposit in Provident Institution for Savings	37.35	
Deposited in Boston Five-cents Savings Bank	39.74	
Deposit in Eliot Five-cents Savings Bank	1,053.41	
Deposit in Warren Institution for Savings	31.16	
Deposit in Institution for Savings in Roxbury	27.64	
Shares in Merchants' Co-operative Bank	586.71	
Dues on shares, Merchants' Co-operative Bank	308.00	
Dues on shares Workingmen's Co-operative Bank	300.00	
Dues on shares Volunteer Co-operative Bank	300.00	
		<hr/> \$3,701.51
Balance on hand		\$124.01

PROPERTY BELONGING TO THE PERMANENT FUND, MARCH 20, 1901.

One Republican Valley R. R. bond (par value).....	\$600.00
25 shares Merchants' Co-operative Bank	1,541.40
25 shares Workingmen's Co-operative Bank	2,048.00
25 shares Volunteer Co-operative Bank	1,002.00
Deposited in Provident Institution for Savings	1,177.60
Deposited in Boston Five-cents Savings Bank	1,165.00
Deposited in Eliot Five-cents Savings Bank	1,053.41
Deposited in Warren Institution for Savings	1,039.91
Deposited in Institution for Savings in Roxbury	1,027.64
Deposited in Franklin Savings Bank	1,017.50
Deposited in Old Colony Trust Company	124.01
	<hr/>
	\$12,787.55
Amount belonging to Permanent Fund March 21, 1900.....	10,010.38
	<hr/>
Increase during the year	\$2,777.17

TOTAL PROPERTY OF THE SOCIETY IN THE POSSESSION OF THE TREASURER.

Permanent Fund	\$12,787.55
Current Fund	226.83
	<hr/>
	\$13,014.38
Total amount March 21, 1900	11,020.81
	<hr/>
Total increase during the year	\$1,993.57

REPORT OF THE COMMITTEE ON EXCURSIONS.

BOSTON, MASS., March 20, 1901.

To the Members of the Boston Society of Civil Engineers:

Your Committee on Excursions presents the following report for the year 1900-1901:

Twelve excursions have been made during the year.

April 18, 1900.—To the Charlestown Bridge, and to inspect the Pneumatic Carrier System between the Union Station and the Post Office, Boston. Attendance, 25.

May 16, 1900.—To the Boston Navy Yard, and the Hoosac Tunnel Docks, both at Charlestown. Attendance, 140.

June 20, 1900.—To the work of Abolition of Grade Crossings at Congress street; the Commonwealth Dock; and the Metropolitan Coal Company's coal handling plant, all in Boston. Attendance, 22.

July 18, 1900.—To the Fore River Engine Works, Weymouth. Attendance, 103.

August 22, 1900.—To the sources of supply, New Bedford and Taunton Water Works, Lakeville, Mass. Attendance, 25.

September 19, 1900.—To the Cape Ann Quarries and Breakwaters, Rockport, Mass. Attendance, 35.

October 17, 1900.—To the Wachusett Dam and Reservoirs, Metropolitan Water Works, Clinton, Mass. Attendance, 47.

November 21, 1900.—To the Boston Elevated Railway. Attendance, 80.

December 6, 1900.—To the Cunard steamship "Saxonia." Attendance, 62.

December 19, 1900.—To the New England Electric Vehicle Transportation Company's plant, Boston. Attendance, 22.

January 23, 1901.—To the factory of the Derby Desk Company, Somerville. Attendance, 4.

February 20, 1901.—To the plant of the United States Steel Company, West Everett. Attendance, 30.

Total attendance, 595; average, 50.

This total attendance of 595 compares very favorably with the record of 550 for the preceding year, and 600 for the year before that, the latter being the highest figure ever attained.

Besides the regular work of planning and conducting excursions, your committee has begun the publication of a monthly "Bulletin of New Engineering Work," with the idea of furnishing the necessary information to enable individual members to visit work in which they may be particularly interested. Seven issues of the Bulletin have been published, besides one special bulletin.

There is a cash balance of \$22.54 in the hands of the committee.

Respectfully submitted,

A. B. CORTHELL,

CHARLES W. SHERMAN,

D. L. TURNER,

JOHN R. BURKE,

Committee on Excursions.

REPORT OF THE LIBRARY COMMITTEE.

BOSTON, MASS., March 20, 1901.

To the Members of the Boston Society of Civil Engineers:

The Committee on the Library makes the following report for the year 1900-1901: 217 volumes and a number of pamphlets have been added to the library. The highest accession number is 4529. This number, however, does not correctly represent the number of volumes in the library, as, in past years, pamphlets have sometimes been entered in the accessions book.

The following engineering text-books, having been approved for purchase by the Board of Government, were bought at an expense of \$49.60. Those marked with a star were approved by the Board of Government of the preceding year, but were not then purchased on account of the insufficiency of the appropriation.

LIST OF TEXT-BOOKS BOUGHT, 1900-01.

Herschel: "Frontinus and the Water Supply of the City of Rome."

Wegmann: "Design and Construction of Dams."

Christie: "Chimney Design."

**Engineering News*: General Index, 1890-99.

Wolff: "Windmill as a Prime Mover."

Goodell: "Water Works for Small Cities and Towns."

*Ganguillet & Kutter: "Flow of Water in Channels," tr. Trautwine.

Tillson: "Street Pavements and Paving Materials."

Wilson: "Topographic Surveying."

Wait: "Law of Operations Preliminary to Construction."

*Pryde: "Chambers's Tables."

Woodhead: "Bacteria and their Products."

Howe: "Retaining Walls."

*Kent: "Mechanical Engineer's Pocket Book."

*Campbell: Manufacture and Properties of Structural Steel."

Howe: "Arches."

Engineering News: "Piles and Pile Driving."

Early in the year the Board of Government requested from the Library Committee a report on the question of "What ought to be the general policy of the library in the acquisition of books, especially in the purchase of reference and text-books?" and "What additional periodicals, if any, ought to be subscribed for?" Reports on these questions were submitted in the course of the year, and are recorded in the minutes of the Board of Government. The recommendations are in substance as follows: The general policy of the library ought to continue as hitherto, a specialty being made of State and Municipal reports that are of engineering interest, but more attention ought to be given to engineering text and reference books. An annual expenditure of about \$75 for such books was advised.

On the question of additional periodicals a list was presented, all but two of which were subsequently approved by the Board of Government, and were added to our table. The following periodicals and society publications are now regularly received and placed on our table. Those marked with a star are not preserved and bound.

American Architect.

**American Gas-Light Journal.*

American Institute of Electrical Engineers, transactions.

American Institute of Mining Engineers, transactions.

American Society of Civil Engineers, transactions.

American Society of Mechanical Engineers, transactions.

**American Trade.*

Association of Engineering Societies, journal.

Canadian Society of Civil Engineers, transactions.

Cassier's Magazine.

Deutsch-Amerikanischen Techniker-Verband, Mitteilungen.

Electrical World.

Engineer (London).

Engineering (London).

Engineering and Mining Journal.

Engineering Magazine.

Engineering News.

Engineering Record.

Engineers' Association of the South, proceedings.

Engineers' Club of Philadelphia, proceedings.

Engineers' Society of Western Pennsylvania, proceedings.

Forester.

Franklin Institute, journal.

Indian Engineer.

Institute of Mechanical Engineers (London), proceedings.

Institution of Civil Engineers (London), proceedings.

**Iron Age.*

**Irrigation Age.*

Liverpool Engineering Society, transactions.

**Marine Engineering.*

- Master Car Builders' Association*, proceedings.
 **Municipal Engineering*.
New England Water Works Association, journal.
Nova Scotia Institute of Science, proceedings and transactions.
Ponts et chaussées, Annales des.
Railroad Gazette.
Société des Ingénieurs Civils, memoires.
Street Railway Review.
Technology Quarterly.
Technology Review.
United States Naval Institute, proceedings.
 **United States Patent Office Gazette*.
University of Wisconsin, bulletin.
Verein deutscher Ingenieure, Zeitschrift.
Western Society of Engineers, journal.
Worcester Polytechnic Institute, journal.

Besides the usual accessions of government, state and city reports, several notable accessions by gift have been received. The Massachusetts Topographical Survey Commission has made our library one of the places of deposit for the atlases of the Town Boundary Survey, and 35 atlases have been received. From M. Eiffel have come two sumptuous volumes, a description and illustrations of the Tower of 300 Meters. From our Past President, Desmond FitzGerald, we have 7 volumes of *London Engineering* and 8 volumes of Spon's Engineering Dictionary. Mr. FitzGerald's gifts arrived too late to be accessioned before the annual meeting, and are not included in the 217 volumes mentioned at the beginning of this report, nor are the 50 volumes of the *Zeitschrift für Bauwesen*, the gift of our Past President Clemens Herschel. These were given under the condition that they should be kept together and marked with the donor's name, and not borrowed from the library. These conditions were accepted by the Board of Government on March 16.

Towards the end of 1900, practically the whole of our shelf room was filled, leaving no space for the expansion of our library or for that of our sub-tenants, the Water Works Association, and it became necessary to provide additional room. A new bookcase was constructed at a cost of about \$75, against the west wall, beside and over the little window. This gives about 76 lineal feet of additional shelving. To make this available for the expansion of each of the ten sections of the library, it was necessary to rearrange nearly all the books. This was done, and after giving up about 37 lineal feet of shelving for the use of our tenants we have left for ourselves (by putting a number of the less used books in the rear rank), sufficient room for the normal growth of about three years.

Shelf lists of certain of the municipal reports have been made by Mr. Bryant, and shelf lists of the State reports have been begun by Mr. Flinn and the Librarian.

Throughout the year a large number of duplicate copies of periodicals have encumbered the room. Negotiations have been in progress for a storage within the building, but so far no satisfactory arrangement has been arrived at. If no convenient storage place can be found, it will become a question whether it would not be better to dispose of all the bulky duplicates. While this store of duplicates is an occasional convenience to our members, so

that \$4.10 worth have been sold in the course of the past year, yet the encumbrance and disfigurement of the library is a high price to pay for this occasional service. The present periodical rack is not convenient. It cuts off the light from the further side of the table, and it is not easy to keep in order. We recommend to our successors that they study means for the more convenient storage of the current periodicals. Another question which we bequeath to our successors is that of certain reports that contain but little matter of engineering interest. In view of the lack of room, it seems doubtful whether it is wise to continue to receive such reports, or even to keep on the shelves those volumes that we already have.

Respectfully submitted,

LOUIS F. CUTTER, *Chairman*,
FREDERIC H. FAY,
FRANK P. MCKIBBEN,
of the Committee on the Library.

REPORT OF THE COMMITTEE ON QUARTERS.

BOSTON, March 20, 1901.

To the Boston Society of Civil Engineers:

The Committee on Quarters have examined several pieces of property during the past year, with reference to purchase, but have been unable to find a lot which will not involve the expenditure of a large amount of money to adapt it to the needs of the Society.

As the lease for the present quarters in Tremont Temple expires on May 1, 1902, and our library is already crowded, it seems to your committee that some steps should be taken during the present year towards securing a house for the Society. This will probably involve the expenditure of about \$80,000. From the report of the Treasurer, it appears that we now have \$12,787.55 in the treasury.

There are several societies in Boston which, like our own, are looking for permanent quarters. The most feasible scheme for building, without encumbering the Society with a heavy debt, seems to be to unite with several other societies, if such can be found, and erect a building to be used in common.

If a movement in this direction appears to be desirable, your committee intend to make at once an effort towards securing the co-operation of some other societies.

Respectfully submitted,

DESMOND FITZGERALD, *Chairman.*

Civil Engineers' Club of Cleveland.

ANNUAL ADDRESS OF THE PRESIDENT.

THE work of a scientific or technical society is, I take it, of a three-fold nature: to keep alive the idea of the professional life; to establish cordial relations between the several members of the different professions represented; and to furnish a means for the spreading of the results of the latest researches amongst the members.

Without having planned to arrange the work of the year under these heads, it may be fairly described under some such classification.

With great earnestness on the part of the Membership Committee of the year just closing, and of the same committee of the year preceding,

the men of the city in the different professions represented have been sought out and invited to affiliate themselves with our Society. The idea has been to band together in one society having proper central headquarters all men associated in several lines of work. It has been hoped that by persistent work nearly every man so engaged could be induced to feel that the professional aspect of his work could best be fostered by being with us in the work we have set ourselves to do. So many men on leaving college find, in due time, their proper sphere of usefulness and, before they know it, are in a rut. They do their day's work and go home. They may take one technical journal and even go so far as to conscientiously read it. But from the fact that their daily work is so constant, and perhaps fatiguing, they straightway forget (so it often seems as you observe them) that they are technically educated; that they are professional men as opposed to business men; that they have to do with creative technical problems rather than the sale, manufacture or transfer of some commodity. Soon they drop out of the Alumni Club of their college, take little interest in the theoretical part of their life work, and plod along, doing the best they can in the environments more or less unideal which surround us all in our daily work.

To belong to a profession is a privilege. It may or may not be as remunerative as many lines of business. That is neither here nor there. The man should feel that he would rather follow it than engage in any other work—money or no money. In a sense the engineer should be made from the man who is good for nothing else; or, putting it the reverse, he should be good for engineering or architecture and for nothing else. To such an one the daily work is only a part of the pleasure of being of the profession he represents. To take pride in the great works and achievements of others laboring in the same field, which represent not so much money earned by the engineer as great mental power and genius,—this is one of the emoluments of the profession. To keep in touch with great feats of the mind, great conquering of mind over matter, and to feel that *we* are a part of the same profession, contributing our conscientious daily labor toward the progress of the world,—all this should be one of the distinct aims of any man, I believe, in following a chosen technical line. In some measure this can be accomplished by the individual working and thinking alone. But we believe that being a member of our Society, and receiving our journal and attending our meetings, tends to keep warm in a man's heart the thought that he had when as a student at college,—he warmed toward the other fellow, because he was of *his* course, studying *his* special studies, bright in *his* own lines of thought, full of the same aspirations in life. We are here of one mind. We believe in the work of others greater than ourselves, and in this we find comfort. We are proud of our vocation, and we encourage each other in this idea that in the professional life we have some ideals and thoughts not common to the business life.

Through the endeavors of the Membership Committee the Club has increased its roll by thirty-eight new names during the past year, thus making the largest advance in the Club's history.

The second division under which I would speak of the work of the year is that of establishing and cultivating cordial relations between the men allied to each other directly or indirectly, and whose names are upon our rolls.

This is certainly a very worthy work. I fancy that technical men become reserved in manner more often than the men of what we might term the talking professions, such as law, medicine and the ministry. While it probably is not fair to say that the engineer does more thinking than the lawyer or the minister, he certainly does do less talking. To acquire a habit of much thinking and little talking is, I think, on the Darwinian theory, to render the individual less prone to talk easily and freely and more and more likely to confine himself more and more closely to the daily task,—letting his relations with his fellow practitioners grow less and less cordial, until he finds himself almost alone in his work. Companionship of the right sort of men in the same line is uplifting. It is encouraging. It is sweetening. Nothing so dispels the professional jealousies as this companionship in a cordial society. The rivalries of life tend to separate men. In the business life it is what is termed competition, meaning generally a war over price. In the technical professional life it is a mental comparison more often—a silent battle of mind against minds, which is none the less acute because the men are reserved. Our club life has for one of its main objects the breaking down of all these barriers. It aims to have its men frankly know each other better, and as they learn how free from bitterness and even envy and conceit the other is, they feel kindlier toward all and more hopeful. I believe the saying, "Come with us and we will do you good," is a truthful remark and represents at least our best wishes toward the men devoted to the technical professions in Cleveland. An especial effort has been made this year to make the meetings attractive from the social point of view. When we were in the Case Building we had to adjourn to a restaurant in order to have a social gathering after the literary part of the program. With our new rooms it has been possible to have a delightful lunch served immediately after the meeting itself, during which time we have had rare opportunities to become acquainted and to welcome visitors and strangers. I am sure we have enjoyed those meetings. The new member has found it much easier to know and be known by the men attending. I trust that in the new year this social feature will be introduced where feasible.

A third division of the work, and really one of the greatest importance, is the furnishing the means of spreading the results of the latest researches amongst the members. The business man withholds the secrets of his business to a great degree from his competitors. The professional man considers it in a great measure unprofessional to keep to himself advance work in his own line of study. And is not this one of the great distinctions between the business and professional life? And does it not indicate a breadth of thought, a sweet giving to others the results of many years it may be of careful work. It is a matter of which the medical profession should be proud, that, no sooner does a surgeon or physician discover a new method or treatment than straightway he publishes it. His gain is professional honor and recognition. His financial reward is only indirect.

And I believe that the professional man so guiding his career is *himself* more the gainer than he is the loser. It is generous to give freely; but in the giving one becomes, I believe, more sensitively appreciative of the results of others' study. It is not an ill bargain one makes with the world to thus give. I think those who have thus given to our Club of

their best thought and experience feel as I do. We should foster this spirit. Fine rooms are splendid accessories, but they are *only* accessories. The *real* thing is the work of the brains represented. Even the social life is second to that. As professional men, we are professional thinkers and incidentally doers. But the doing is easier than the thinking in most cases, and in all cases the thinking is the result of the finer quality of the mind.

To encourage fine technical thinking is a worthy object. And our Club is certainly doing much to fulfill its mission if it shall encourage to the utmost all advanced thinkers. It furnishes a place where they can deliver their views and, through the use of its journal, spread the subject matter before men of many cities. This work has been in the hands of a Program Committee, of which Mr. Green is chairman, which has had entire charge of the literary part of the year's work. I will not refer in detail to their work. It has seemed admirable, and I wish publicly to thank them for thus upholding the officers of the year in so signal a manner. There is much missionary work which might be done still, and especially amongst the new members. With the larger membership comes a larger field for the Program Committee. The literary part of the Civil Engineers' Club, I therefore prophesy, is to grow better and broader from year to year.

The having of fine rooms has made it possible to entertain the ladies in our rooms. This might properly be made a feature of the work. To an extent of which the outside public are hardly aware, the wife of a technical man knows and feels more or less of the daily work of the husband. To invite the ladies to occasionally listen to our papers would, it seems to me, be the means of assisting them to more fully appreciate their husbands' work. When we think of Mr. Roebling's wife assisting him in his great undertaking at his bedside, we realize what, in extreme cases, the wife might do. At least to encourage their coming, and, coming, too, at stated times, to hear of engineering matters, is a matter I should like to see tried. If, at such a time, we all made it a point to bring our wives, I am sure they would vote the evening a success. We held one such meeting at Christmas time, and it was a success from every point of view. I wish we might decide at least to have a ladies' night at the holidays and make it a feature of the year.

One more matter I shall speak of, and then I am done. The library of the Club has been brought over to our rooms and an extra room rented and the libraries of all the societies housed there together. This is a most important advanced step and, I trust, will be the means of the books being more used than they have been. A new step has been taken also in this connection, and by one of our own members,—Mr. Searles. He has very generously donated a valuable collection of technical books to the Club.

Would it not be possible to get the several members of our Society to give a book now and then to the Club's library? I mean, a book from their own private shelves. A book perhaps well worn (that will prove its value); perhaps with side notations or its pages indicating that its owner was alive and thinking. I think that each year quite a number of books could thus be added and would prove invaluable. And especially might it be practical to urge that the men about to retire ever have in mind that

our library is a better place for technical books than some garret or upstairs hall, as is the fate of so many professional books,—whether on engineering, architecture, medicine, law or religious subjects.

In connection with the library, one other thought comes to me: Would it not be possible to make it a circulating library and thus make the books do a much larger work? Of course, only one copy of a work is on our shelves, and it therefore might be out when called for. But when we consider how seldom *any* book is called for under the present system, it would not seem to be taking very great chances. Of all the library rules which work hardship in both of our public libraries, that which forces the patrons to stay in the rooms in order to use the reference books is the greatest. It may be necessary, although I should doubt it; but certainly very, very few ever use the reference books as a result. It would be better to lose a book now and then, and feel that the rest were filling a great want, than to debar so many from their use. A tired man is a poor one to go several miles after dinner to a reference library unless he is obliged to, and who of us can take the time in daylight to spend there? In our own little library, would it be sacrilege to allow our books to go out under some simple system? Say for a week only, with power to renew for one week if no card is deposited for it? I believe it would in this way fill in a want which the two great libraries seem unable to meet.

I cannot think but that our members would appreciate it and would soon consider it as one of the good things about our Club. I would respectfully suggest that this matter be brought up by the new board and Librarian and ways be provided to bring it about.

Gentlemen, the task of the officers you elected a year ago is done. For your kindness and forbearance during the year we thank you. For your support we shall ever be grateful. And we trust that, as the years pass on, the Civil Engineers' Club of Cleveland will grow stronger and stronger, more and more honorable and efficient, until our Club will be counted one of the strong, wholesome, uplifting institutions of our beautiful Forest City.

SECRETARY'S REPORT.

During the year the Club has held ten regular meetings, eight semi-monthly and three receptions.

The average attendance for the regular meetings has been 24 members and 9 visitors; for the semi-monthly meetings 19 members and 7 visitors.

The membership on March 1, 1900, consisted of 5 honorary members, 22 corresponding members, 20 associate members and 133 active members, a total of 180.

During the year we have lost by death Messrs. Roswell H. St. John, Henry M. Claflin and Joseph T. Talbot, all active members.

Eight members, four corresponding, three active and one associate, have resigned and one active has been dropped.

Forty-seven active members, one associate member and one corresponding member have been elected. These changes during the year left, on March 1, 1901, 5 honorary members, 19 corresponding members, 20 associate members and 174 active members, a total of 218, showing a net gain of 38 members over the list of March 1, 1900.

FINANCIAL STATEMENT.

BALANCES ON MARCH 1, 1900.

Permanent Fund.....	\$915.55
General Fund.....	311.84
Library Fund.....	173.74
	<hr/>
	\$1,401.13

RECEIPTS, MARCH 1, 1900, TO MARCH 1, 1901.

Dues	\$1,728.00
Fees	240.00
Library Subscriptions.....	15.00
Refunded Postage60
Western Cement Co. (Journal)	3.00
Advertising Commission	70.20
Interest	39.58
	<hr/>
	\$2,096.38

EXPENSES.

Periodicals	\$30.65
Printing	174.72
Salaries	100.00
Postage and Express	61.70
Stationery, etc	17.68
Books	59.27
JOURNAL	387.75
Rent	692.00
Certificates	12.00
Social Account	328.16
Case Library	75.00
Furniture	23.25
Flowers	10.00
	<hr/>
	\$2,072.18
Net receipts	<hr/>
	\$24.20

BALANCES ON HAND MARCH 1, 1901.

Permanent Fund	\$1,195.13
General Fund	100.73
Library Fund	129.47
	<hr/>
	\$1,425.33

ARTHUR A. SKEELS, *Secretary*.

REPORT OF THE LIBRARIAN.

Your Librarian regrets that, owing to his absence from the city during nearly the whole year, he has been unable to devote as much time to the library as he would gladly have done, and at the same time he wishes to express his gratitude for the valuable assistance of our former Librarian, Mr. A. Lincoln Hyde, who has acted in the writer's place during his absence. Through Mr. Hyde, arrangements were made for the transfer of the Club's library from its old quarters in Case Library

to our new rooms in the Associated Technical Clubs, the matter having been duly proposed at a meeting of the Club and authorized by its vote.

Cases for the library were ordered several months ago, but, owing to delay in their completion and shipment, they have only just been received, and within the last week the greater portion of the books comprising our library have been put in place in them. The cases which were gotten for these books were purchased with money appropriated from the general treasury of the Club, and not from the special library fund, in order that the latter might be kept intact for the special purpose for which it was given. One reason which made it desirable to transfer the library at this time was that the subscriptions which were inaugurated five years ago to this fund have just been completed, and further, the agreement between the Case Library and ourselves, by which they were, during this same period, to appropriate for the purchase of engineering works an equal amount of money to that expended by the Civil Engineers' Club, has also terminated. Regarding this private subscription, while there are still some who are not as yet amenable to the persuasion of your Library Committee and are still in arrears as to their last payment, yet there is but a comparatively small sum outstanding as coming from those of whom we can expect payment, and the original list has been considerably depleted by death or removal from the city. In fact, it was the observation of your Committee that those who most earnestly and generously contributed to this fund, judging as one may from outward appearances, could hardly be classed among the members *best* able to carry this burden; and your Committee would therefore respectfully recommend, in view of the termination of these subscriptions and under the present good financial standing of the Club, that an appropriation for the library be made from the general treasury, so that the burden may come more evenly on the whole membership than has heretofore been the case.

Through the generosity of one of the members of the Club, who always has had its interest at heart, we have been brought into the possession of some two hundred engineering volumes of great interest, and in behalf of the Club your Committee would again gratefully acknowledge this gift from Mr. W. H. Searles, past president of the Club. Besides important civil engineering works, there will be found among the books given by him valuable contributions on the subject of the Great Pyramid, Transactions of the Antimetric Society, etc. Mr. Eiffel, the famous engineer and promoter of the great tower which bears his name on the Champ de Mars in Paris, has presented to the Club three most valuable works, covering a complete history of the design and erection of that great triumph of engineering work.

Your Committee believes that the transactions of the various technical societies in which the members of our Club are interested are of special value to our library, since, in these transactions, the engineering topics of the day are best discussed from year to year, and since such transactions are not as easily found or procured by those who are possessed of private libraries as are the individual treatises on these same subjects, and it therefore gives us pleasure to state that we have, on our shelves, complete to 1893 and 1896, the Transactions of the American Society of Civil Engineers, the Transactions of the American Society of Mechanical Engineers nearly complete, and it is needless to say that we

would be greatly indebted to any of the members of our Club who may be members of either of these societies, and who might feel disposed to give us the few remaining numbers.

For some time we have been favored with the reports of the Chief Signal Officer, the War Department, the Secretary of War, etc., so that the Club now has 245 volumes of these reports. At the present time there is not enough room in our library to give them place, and they have therefore been stored away where they can be gotten at more or less readily, and, if considered important and if our quarters will permit, arrangement will be made later for still more easy access to them.

The Club has subscribed for a number of periodicals of literary interest for the reading room of the Associated Technical Clubs, but these periodicals have been paid for from the funds of the Club and not from the library fund.

In anticipation of the change from the Case Library to our present quarters, and in view of the fact that we had, while there, the advantage of so many engineering works which are not the property of our Club, your librarian deemed it advisable to allow part of the money collected to remain with the treasurer unspent, so that it might be used at such a time as the present for purchasing books similar to those now in the possession of the Case Library, and the end of this fiscal year therefore finds us with somewhat over \$129.47 which can be used for this purpose.

Your Committee would gratefully acknowledge the kind interest of Dr. Howe, member of the Library House Committee, as well as Mr. A. Lincoln Hyde for valuable assistance in our work. We believe that the removal of the library to its present quarters will be of great advantage to the Club and that the prospects for the coming year are brighter than ever for those who are interested in our technical library.

Respectfully submitted,

WM. E. REED, *Librarian*.

The papers during the past year have been more than usually interesting and instructive and of such variety of subjects as to interest all.

Although two papers per month were prepared for the spring and early summer of 1900, it was not expected to hold regularly two meetings per month. In October, however, it was decided that two meetings would be desirable, and from that time the Club has met and listened to a paper twice each month.

The stereopticon has been freely used during the year and has proved a valuable feature and a great aid. Of the sixteen papers presented, eight have been illustrated by slides.

During the summer months of July and August, 1900, no meetings were held, but an outing at Beach Park on July 21 was thoroughly enjoyed by a large number.

The second meeting in December, occurring regularly on Christmas evening, was postponed until the evening of December 28 and a special Christmas entertainment prepared. These special gatherings of a social nature should be encouraged. One of the greatest needs of our Club is a closer social relationship and a wider acquaintance among the members, and there can be no better way to promote this than by occasional good times together. The regular meetings do not seem to cultivate this social spirit to a sufficient degree.

It was suggested a year ago that a question box be established, wherein questions for discussion by members of the Club could be placed by any member. No material box was provided, but it was announced that any questions addressed to the Club through its Secretary or through the Program Committee would be promptly brought before the Club for discussion. The members have not availed themselves of this feature to any alarming degree. In fact, two questions, propounded by the same interrogator, have been the sole fruit during the year.

It was also suggested that possibly papers would be more varied in interest, and might be easier of preparation if they were made shorter, and two subjects were taken up at each meeting. The fact seems to be, however, that any one preparing upon any topic finds, when he has gathered his data, that the difficulty is in concentrating it to a sufficient degree, and the necessity seldom arises for increasing the length or scope of a paper or topic.

Respectfully submitted,

BERNARD L. GREEN, *Chairman.*

TREASURER'S REPORT.

RECEIPTS.

Cash on hand March 1, 1900:

Permanent Fund	\$915.55	
General Fund	311.84	
Library Fund	173.74	
		\$1,401.13
Received from Secretary on account of Permanent Fund	\$279.58	
" " " " " " General Fund...	1,801.89	
" " " " " " Library Fund...	15.00	
		2,096.38
		<u>\$3,497.51</u>

DISBURSED.

Secretary's vouchers on account of General Fund, Nos.		
101 to 156, inclusive	\$2,012.91	
Secretary's vouchers on account of Library Fund, Nos.		
22 to 32, inclusive	59.27	
		2,072.18

CASH ON HAND FEBRUARY 28, 1901.

Permanent Fund	\$1,195.13	
General Fund	100.73	
Library Fund	129.47	
		1,425.33
		<u>\$3,497.51</u>

JOHN N. COFFIN, *Treasurer.*

Engineers' Club of St. Louis.

522D MEETING, MARCH 6, 1901.—Held at 1600 Lucas Place at 8.15 P.M.; Vice-President Kinealy presiding.

Attendance, twenty-five members and nine visitors.

Minutes of the 521st meeting were read and approved with corrections.

Minutes of the 306th meeting of the Executive Committee were read.

A communication from the Finance Committee of the Public Welfare Commission, requesting a subscription by the Club of \$100 toward the ex-

pense of the commission, was read. The Executive Committee, having considered the matter, recommended that the objects of the Club did not warrant the Club to make an appropriation of this character, but that it would be well for the members of the Club to give the commission their assistance as citizens. Motion was passed to adopt the recommendation of the Executive Committee.

The members of the Board of Managers having reported to the Executive Committee a plan whereby advertisements for the *JOURNAL* and *Bulletin* would be solicited by an agent to be employed on a commission basis, the Executive Committee recommended that the Club give the members of the Board of Managers full power to put said plan into operation. Motion was passed to adopt the recommendation of the Executive Committee.

Messrs. W. H. Henby, Truman M. Post and Louis Bendit were elected to membership.

The subject of the evening was an informal address on "The Development of the Steam Engine," by Prof. J. H. Kinealy. The speaker gave a very interesting talk, fully illustrated by lantern slides, and he reviewed the various forms of engines from the earliest known down to the latest developments.

Discussion was participated in by Messrs. Ockerson, Bryan, Van Ornum, Borden and Humphrey.

Mr. Maltby, for the Committee on Lantern, reported they had bought a reading lamp for the meeting room, and a new lamp for the lantern, and had contracted for the necessary direct current for the lamp.

Motion was carried to ratify the action of the Committee on Lantern.

For the next meeting announcement was made of a paper by Mr. S. Bent Russell, principal assistant engineer, water works extension, on "Bank Revetment Work at the Chain of Rocks Pumping Station," illustrated by lantern slides.

Adjourned to an adjoining room, where lunch was served.

W. G. BRENNKE, *Secretary*.

523D MEETING, MARCH 20, 1901.—Held at 1600 Lucas Place at 8.20 p.m.; President Spencer presiding.

Twenty-four members and four visitors were present.

The minutes of the 522d meeting were read and approved.

Mr. Flad, Chairman of the Committee on Lantern, submitted the formal report of the committee to the Club. As the committee had reported at the previous meeting and a motion carried to ratify the action of the committee, no action was taken at this meeting on the report.

Professor Van Ornum was then requested to take the chair, and President Spencer addressed the Club in behalf of the Public Welfare Commission, explaining in detail the objects and needs of the commission, its relation to the Engineers' Club, and the work it had so far accomplished. After President Spencer resumed the chair, Professor Van Ornum moved, and it was duly seconded, that the Executive Committee be empowered to take action looking toward the subscription, by the Club as individual members, to the amount desired by the commission. Mr. Flad moved as a substitute that the Executive Committee be directed to pay the \$100 assessed against the Engineers' Club out of

the Entertainment Fund. Mr. Bouton objected, as this was a trust fund, and he thought its use was restricted. Mr. Wheeler stated that the American Society of Mechanical Engineers turned this fund over to the Club in trust without any restrictions. After considerable discussion, Mr. Flad's motion was voted upon and carried.

The subject of the evening was an informal address by Mr. S. Bent Russell on "Revetment of River Bank at the Chain of Rocks by the St. Louis Water Department." Maps and general plans were exhibited showing the conditions and scheme of construction. Lantern slides were also exhibited, showing the progress of the work at different times, the plant used in the work, etc. The work is estimated to cost when complete about \$80,000, and has extended over a period of about four years. The bank protected is about 6000 feet long and from 25 to 30 feet in vertical height. The points of greatest interest are the use of gravel concrete in the place of the usual rip-rap on the upper bank, and the method used to prevent the revetment being undermined at the toe of the slope where the work rested on soft material. These methods include rip-rap dikes, brush mattresses, and aprons made of sawed lumber bound together with wire cable and sunk with rip-rap. Another point of interest is the treatment of the bank where it showed a disposition to slide or slough off.

Discussion followed by Messrs. Maltby and Turner.

For the next meeting announcement was made of a paper by Mr. Louis Bendit on "Treatment of Feed Water for Boilers."

Adjourned to library room, where lunch was served.

E. B. FAY, *Secretary pro tem.*

Technical Society of the Pacific Coast.

REGULAR MEETING, MARCH 1, 1901.—Called to order at 8.30 P.M. by President Marx.

The minutes of the last regular meeting were read and approved.

Mr. Chas. M. Kurtz read a carefully prepared paper before the Society, embodying a "Review of the Various Methods of Concrete and Iron Construction used during the Last Decade," which subject was discussed at length by Messrs. Keating, Wing, Prutzman, Wagoner and others.

Meeting thereupon adjourned.

OTTO VON GELDERN, *Secretary.*

REGULAR MEETING, SAN FRANCISCO, CAL., APRIL 5, 1901.—Called to order at 8.30 P.M. by President Marx. The minutes of the last regular meeting were read and approved.

The following names were added to the membership upon regular count of ballots:

Member—Chas. Albert de St. Maurice, civil engineer, of Eldridge, Cal.

Junior Member—James D. Mortimer, instructor in electrical engineering, University of California.

Associate Member—Milo Hoadley, of San Francisco.

The following name was proposed:

A. S. Riffe, civil engineer, of San Francisco, by D. C. Henny, Otto von Geldern and Adolf Lietz.

Professor Elwood Mead, of the University of California, then addressed the Society on the subject of "Irrigation in California," which was discussed by many members present.

The President suggested that the Technical Society act in conjunction with the Water and Forest Association, and that steps be taken to perfect some action of this character.

A motion was made by Mr. Henny that the Chair appoint a committee to confer with the Water and Forest Association in the work now carried on in this State, and that the President be an *ex-officio* member of such committee, consisting of five members. Motion was carried, and the Chairman announced that he would appoint this committee at the next Director's meeting.

On motion, a vote of thanks was passed by the Society, expressing the full appreciation of its members to Professor Elwood Mead for his courtesy in lecturing on the important subject of "Irrigation in California."

Adjourned.

OTTO VON GELDERN, *Secretary*.

Engineers' Club of Cincinnati.

121ST REGULAR MEETING, CINCINNATI, OHIO, FEBRUARY 21, 1901.—Dinner was served at 6.15 P.M.

The regular meeting was called to order at 7.15 P.M. Vice-President Bogen in the chair.

There were eighteen members present.

Minutes of the meeting of January 17 were read and approved.

Application for active membership was presented by Mr. A. N. Miller.

On ballots being taken, Messrs. R. J. Devenish and John P. Brooks were elected active members and Mr. Guy M. Gest was elected an associate member.

The committee appointed to prepare memoir of Sherman E. Burke, presented the same, which was ordered received and spread on the minutes of the Club.

Mr. Frank L. Fales read the paper for the evening, on "Water Purification and Sewage Disposal at the Lawrence Experiment Station."

After a short discussion of the subject and a vote of thanks to Mr. Fales for his paper, the Club adjourned.

J. F. WILSON, *Secretary*.

Engineers' Society of Western New York.

REGULAR MEETING, MARCH 5, 1901.—Meeting called to order at 8 P.M.; the President in the chair. The following members present: Messrs. Haven, Knighton, Knapp, Booz, Fell, Frnauff, Bardol, Tutton, Whitford, Tresise, Rogers, Babcock, Rockwood, Roberts, Weston, Diehl, Kielland, Norton, Buttolph, Vander Hoek, McKeown, Morse and several visitors.

Applications for associate were read from the following: William Franklin and John Feist. It was voted that the applications be approved and letter ballot ordered.

It was moved by Mr. Knighton, and seconded by Mr. Diehl that Mr. Ricker be requested to rewrite his paper on Docks and resubmit it to the Society, and that the paper and discussion be published in the JOURNAL OF THE ASSOCIATION OF ENGINEERING SOCIETIES. Carried.

The Executive Board reported that they would send out the following letter to various Engineers, Societies, etc.:

ENGINEERS' SOCIETY OF WESTERN NEW YORK,
975 ELLICOTT SQUARE,

BUFFALO, N. Y., March 12, 1901.

The Pan-American Exposition to be held in this city the present year will offer much of interest to Engineers.

We regret that the plan proposed for a separate engineering exhibit has been found impracticable.

The Engineers' Society of Western New York desires to extend to visiting Engineers every possible courtesy. Its rooms are most centrally located in the Ellicott Square Building. The headquarters of the Exposition, telegraph office, telephone station, restaurant, etc., are in the building.

During the Exposition our rooms will be open during the day, and we extend a most cordial invitation to the members of your Society and all visiting engineers to make use of them while in Buffalo.

Your mail addressed care of "Engineers' Society of Western New York, No. 975 Ellicott Square," will be cared for, and information gladly furnished regarding the Exposition and other points of interest to engineers in the city and vicinity.

A stenographer will be in attendance, whose services may be procured by visiting engineers.

Meetings of the Society are held the first Tuesday in each month, at which all visiting engineers will be most heartily welcomed.

Yours respectfully,

WILLIAM A. HAVEN,
Pres. Engrs.' Soc. W. N. Y.

The Executive Board reported the election of the following gentlemen: As members, Stanley W. Hayes and Edward Denison Hooker; as associates, Leslie J. Bennett and Warren Rodney.

It was moved by Mr. Knighton and seconded by Mr. Norton that a special invitation be sent to the new members, and some little extra exertion made to become acquainted with and to entertain them. Carried.

Mr. Neher read a paper on concrete construction.

Mr. Neher's paper was discussed by Messrs. Diehl, Haven, Knighton, Vander Hoek, Tutton, Rockwood and Norton, and the author.

Meeting adjourned at 10.30 P.M.

G. C. DIEHL, *Secretary*.

Engineers' Club of Minneapolis.

141ST MEETING, FEBRUARY 18, 1901.—The meeting was held in connection with a dinner at the Commercial Club.

The Club listened to reports and addresses by the outgoing officers: Geo. W. Sublette, President; W. W. Redfield, Librarian; H. E. Smith, Secretary-Treasurer; Geo. D. Shepardson, member Board of Managers of

Association of Engineering Societies. Also addresses by incoming officers: W. W. Redfield, President; C. L. Pillsbury, Vice-President; J. E. Carroll, Librarian; Edward P. Burch, Secretary-Treasurer; Wm. R. Hoag, member Board of Managers of Association of Engineering Societies.

Col. J. T. Fanning, who was present as a guest of the Society, gave an interesting address on "Engineering in the Last Century." Past Vice-President Irving E. Howe and others also spoke informally.

Mr. Fanning was unanimously elected an honorary member of the Club.

142D MEETING, MARCH 18, 1901.—The meeting was held in connection with a dinner at the Guaranty Restaurant.

The following new members were unanimously elected: Messrs. C. H. Chalmers, Edwin R. Williams, P. P. Crafts, James Gillman, F. B. Slocum. The following names were proposed for membership: Frank H. Nutter, Wm. Robertson, Frank E. Reidhead.

Mr. W. S. Pardee presented a lecture on "Methods in Scientific Study," which proved to be of great interest to the Society.

Bills before the Legislature for State Aid for Good Roads and for Licensing of Bicycles were called to the attention of the Club by the President. A committee was appointed to act with a committee from the Civil Engineers' Society of St. Paul, and to take such action as seemed necessary to push certain worthy bills through the Legislature. Prof. Wm. R. Hoag, Geo. W. Sublette and W. S. Pardee are on this committee.

EDWARD P. BURCH, *Secretary*.

ASSOCIATION OF ENGINEERING SOCIETIES.

VOL. XXVI.

APRIL, 1901.

No. 4

PROCEEDINGS.

Engineers' Society of Western New York.

REGULAR MEETING, APRIL 2, 1901.—The meeting was called to order at 8.30 P.M., the President in the chair. The following members present: Messrs. Haven, Tutton, Buttolph, Knapp, Vander Hoek, Booz, Boardman, Hooker, Ricker, Babcock, March, Fruaff, Knighton, Diehl, Norton, Rogers, Bardol, Weston and Caines. Visitor, Mr. Holmes, of the Engineers' Society of Western Pennsylvania.

It was voted that the minutes of the last regular meeting be approved as printed.

Mr. Tutton, member of the Board of Managers, made a report.

Application for membership was received from Mr. James Leland Averill, and it was voted that the same be accepted and submitted to letter ballot.

The Secretary reported that the Society had elected as Associates, Messrs. John Feist and William Franklin.

The President said that there seemed to have been some misunderstanding how to vote on the new form of ballot which was used for the first time in January. It was unanimously voted by the Society to temporarily suspend so much of the By-laws as relates to the reapplications of persons not elected on letter ballots canvassed January 2, 1901, and that the Secretary be instructed to send out letter ballots for Horace P. Chamberlain and Eugene C. Hanavan.

Mr. March, the Committee appointed on the matter of the Society joining the International Association for Testing Materials, made a report, which was briefly discussed by Messrs. Ricker, Tutton, Knighton and Diehl. It was then voted to accept the report and discharge the Committee. It was also voted that the subject matter be left to the discretion of the Librarian, with power.

The President reported that the Secretary had sent out a large number of the "Pan-American Circulars" to engineering societies in North and South America, and to some parts of Europe. The Secretary read several letters which had been received in response thereto, all of which

thanked the Society for their courtesy, and said they would avail themselves thereof.

The President then said it would be necessary to have a large Committee on Reception of Visiting Engineers. Thereupon it was unanimously voted that the President should appoint a Committee of seventeen or more members as a Reception Committee.

The President appointed the following as such Committee:

George A. Ricker, Past President; Wallace C. Johnson, Past President; Thomas W. Symons, Honorary Member; Harry B. Alverson, F. V. E. Bardol, George B. Bassett, W. A. Brackenridge, Newcomb Carlton, David A. Decrow, Samuel J. Fields, William Franklin, E. F. Gaskin, Marvine Gorham, Edward B. Guthrie, Richard Hammond, William C. Houck, S. M. Kielland, Clarence C. Lewis, Harry J. March, Dr. Truman J. Martin, Charles M. Morse, Charles Mosier, Maurice B. Patch, J. Vander Hoek, J. F. Witmer, and all the members of the Executive Board without special appointment.

Discussion was then had upon Mr. Ricker's paper on "Docks."

The President welcomed Mr. Holmes, of the Engineering Society of Western Pennsylvania, who replied: In coming to the meeting of the Society to-night I did not expect to be called upon to make a speech. I appreciate the honor of being invited, and congratulate you on the manner in which I have been received. If you treat every visitor the same as you have treated me, they will surely come again. I have the honor of belonging to the Western Pennsylvania Society of Engineers and we have four hundred members in Pittsburg. We have a house, the first floor of which is rented. We have our rooms on the second and third floors, which contain the reception room, a library, a large hall for meetings and other rooms. We would like to have a better house, and are trying to get it. We have meetings every month, and in summer have a trip by boat, and in the winter a banquet. We had a banquet in February last, at which time we probably had 300 or 400 members with their friends. Our membership is made of engineers from the Carnegie, Jones & Laughlin, the Westinghouse interests and manufactories in the city. We number among our members such men as William Metcalfe, Thomas F. Johnson, of the Pennsylvania lines, etc. Our former Secretary was Reginald D. Fessenden, who had charge of the Wireless Telegraphy experiments for the Government.

I notice on your walls a number of photographs of Pittsburg. Among them the skeleton of the Carnegie Building. Mr. Frick is building an office building of about the same size. Back of this building is the Fifth Avenue Hill. We hope in time to have this hump cut down, when they will have two additional stories. On the lot there used to stand an old stone church, built a great many years ago. The church was taken down, each stone marked and put up in the same manner as in the original building.

If any of the members of this Society come to Pittsburg we would be glad to have you make use of our rooms.

THE PRESIDENT.—What is the population of Pittsburg?

MR. HOLMES.—Pittsburg and Allegheny, 400,000. We should take in more territory. We should take in McKeesport, Braddock, Wilkens and East Pittsburg, when the population would be very much larger. Allegheny, just across the river, should be in Pittsburg.

THE PRESIDENT.—How long has the Society been organized?

MR. HOLMES.—About twenty-one years at the last annual meeting, I think.

THE PRESIDENT.—You say you have 400 or 500 members?

MR. HOLMES.—I am not sure of the exact number, but I think it is between these figures.

MR. NORTON.—I think at the January meeting, the President incidentally said that we have no quicksand in Buffalo. Test borings were taken by Mr. Caines for the purpose of finding out the soil to be encountered in building the abutments for a bridge on South Michigan street. We found what could be called quicksand. This sand I dried out and have tried it on a No. 50 sieve, and there was no perceptible amount retained. On a No. 100 sieve there was $\frac{1}{2}$ of 1 per cent. retained and on a No. 200 sieve there was only about 25 per cent. retained, making that sand, on a sieve test, finer than the tests for Portland cement. It was a pure quartz sand if that would be called quicksand. Is quicksand composed simply of quartz?

MR. TUTTON.—A great deal of information on this subject is contained in a discussion which took place before the American Society on Mr. Landreth's paper on the Erie Canal, and there was a great variety of opinion—one member claiming there was no quicksand unless it possessed that peculiar property of "quaking," etc. The decision arrived at was that quicksand was pure quartz sand in which the particles were worn round, the actual fineness of the sand had nothing to do with it. I am not sure that I am quoting these conclusions right, and would refer you to that paper, giving the best information on quicksand outside of McAlpine's writings on it.

Boston Society of Civil Engineers.

BOSTON, MASS., APRIL 17, 1901.—A regular meeting of the Boston Society of Civil Engineers was held at Chipman Hall, Tremont Temple, at 7.50 P.M.; President Lawson B. Bidwell in the chair. Fifty-five members and visitors present.

The record of the annual meeting of March 20, 1901, was read and approved.

Messrs. Charles M. Spofford, Herbert R. Stearns and Frank W. Upham were elected members of the Society.

The Secretary reported for the Board of Government that it had voted to continue the same special committees of the Society as last year, and that the membership thereof had been selected as follows:

Committee on Quarters—Desmond FitzGerald, E. W. Howe, C. Frank Allen, E. W. Bowditch and H. Bissell.

Committee on the Library—L. F. Cutter, F. P. McKibben, F. H. Fay, A. D. Flinn and H. F. Bryant.

Committee on Excursions—J. R. Burke, Theodore Horton, J. Albert Holmes, H. K. Higgins and H. D. Woods.

Members of the Board of Government, Association of Engineering Societies—S. E. Tinkham, J. R. Freeman, Henry Manley, Fred. Brooks and Dexter Brackett.

A committee, consisting of L. F. Rice, Desmond FitzGerald and Henry Manley, was also appointed to petition the General Court for authority to hold real and personal estate in excess of \$20,000.

A communication was read from the Engineers' Society of Western New York, extending a cordial invitation to the members of this Society to make use of the rooms of the Engineers' Society of Western New York during the Pan-American Exposition. The Secretary was directed to acknowledge the receipt of the invitation and to express the appreciation of the Society.

Mr. W. W. Cummings read the paper of the evening entitled, "Subaqueous Tunnels for Gas Conduits." The paper was illustrated by stereopticon views. In the discussion which followed, Mr. Carson spoke briefly of the tunnels built for the Metropolitan Sewerage Works, and of the work which had been accomplished on the East Boston Tunnel, and Mr. Saville of the tunnel recently completed for the Metropolitan Water Board under Mystic River at Chelsea North Bridge.

Mr. Robert A. Shailer, President of the Boston Tunnel Construction Company, the contractors for the East Boston tunnel, gave some interesting experiences of the use of compressed air in tunnel work, speaking particularly of the work at Cleveland, Ohio.

Adjourned.

S. E. TINKHAM, *Secretary*.

Engineers' Club of Minneapolis.

THE 143d regular meeting of the Club was held at 8 P.M., on April 15, at its permanent quarters in the County Commissioner's rooms in the County Court House.

Thirteen members and eight visitors present.

After the usual order of business was disposed of, a paper was presented by Col. J. T. Fanning, entitled "Canals and Canal Devices."

A second paper was presented by Mr. E. H. Tromanhauser, on "Grain Elevator Construction."

These papers were of great interest to the members. The first was historical in nature; the second was on up-to-date steel elevator design construction,—a subject of great local interest.

The discussion of the papers was deferred one month.

EDWARD P. BURCH, *Secretary*.

Engineers' Club of Cincinnati.

122D REGULAR MEETING, CINCINNATI, OHIO, MARCH 21, 1901.—Dinner was served at 6.15 P.M.

The regular meeting was called to order at 8 P.M., Mr. A. O. Elzner in the chair, and fifteen members present.

Minutes of the meeting of February 21 were read and approved.

On ballot being taken, Mr. Alex. H. Miller was elected an Active Member.

The following question was presented:—

What kind of explosives do you prefer for blasting in the following kinds of material?

Solid rock, quarried for building.

Solid rock, for removing only.
 Loose rock and shale.
 Hard pan and cemented gravel.
 Loose sand and gravel.

On motion, the same was ordered announced for discussion at the next meeting.

Mr. E. E. Russell Tratman, Resident Editor *Engineering News*, at Chicago, who was visiting the city in the interest of his paper, and who had been invited to attend the meeting, favored the Club with a few remarks, principally on the subject of water works, as he had visited during the day the work being done at California for the new plant for the Cincinnati water supply.

The paper for the evening was read by Mr. M. D. Burke, on "Inland Transportation in the Mississippi Valley."

J. F. WILSON, *Secretary*.

Engineers' Club of St. Louis.

524TH MEETING, APRIL 3, 1901.—Held at 1600 Locust street, at 8.20 P.M., Vice-President Kinealy presiding.

The minutes of the 523d meeting were read and approved.

Motion was made and carried to reconsider the action of the Club at the last meeting, in which it was decided that the Executive Committee be directed to pay the \$100 assessed against the Engineers' Club by the Public Welfare Commission, same to be paid out of the Entertainment Fund. After considerable discussion of the matter, it was finally decided, upon motion being carried, to lay the matter on the table.

The application for membership of Mr. Rudolph Howard Klander was read.

The subject of the evening was a paper by Mr. Louis Bendit, entitled "Treatment of Feed Water for Boilers." Mr. Bendit paid particular attention to the various methods of treating hard waters for use in boilers, and presented considerable data upon the same.

Discussion was participated in by Messrs. Wheeler, Bryan, Freeman and Professor Keiser, Professor of Chemistry at Washington University. Adjourned to Library room, where lunch was served.

W. G. BRENNKE, *Secretary*.

525TH MEETING, APRIL 17, 1901.—Held at 1600 Locust street, at 8.20 P.M., President Spencer presiding.

Twenty-five members and five visitors were present.

The minutes of the 524th meeting were read and approved, the doings of the 308th meeting of the Executive Committee were reported.

Mr. Rudolph Howard Klander was duly elected to membership.

The matter of the assessment of \$100 against the Club by the Public Welfare Commission then came up.

Moved by Professor Van Ornum and seconded by Mr. Flad, "that the matter be referred to the Executive Committee with power to act."

Mr. Wheeler spoke against the motion and advocated delaying action until a better representation of members could be secured.

Mr. Reber spoke in favor of definite action at once, and was in favor of making the appropriation.

Mr. Flad then withdrew his second to Professor Van Ornum's motion.

Mr. Reber then moved "that the St. Louis Engineers' Club contribute \$100 to the Public Welfare Commission."

Mr. Flad seconded the motion.

President Spencer, the Club's representative on the Public Welfare Commission, then spoke on the subject. He explained that Professor Chaplin, when President, had appointed him as the club's representative on the Commission, and how other representatives were appointed. He also said it was thought at that time that the various members of the Commission would need do nothing more than contribute their labor in behalf of the Commission. In the meantime, it has been found that considerable expense has accrued, and it is necessary to meet the same. At the same time, he explained, the Club was not bound in any way to pay the assessment made, but that he knew that three of the organizations appealed to had contributed, and most of the others had probably done so.

Mr. Reber then withdrew his motion.

Professor Van Ornum then moved "the Club ask for the money, the same to be paid in such manner as the Executive Committee may decide."

Seconded by Mr. Bryan.

Amended by Mr. Flad "to refer the whole matter to the Executive Committee."

The following letter was then read by the Secretary:

ST. JOSEPH, MO., April 15.

Mr. W. G. Brenneke, Secretary Engineers' Club, Fullerton Building, St. Louis, Mo.

DEAR SIR: I have your notice of the 13th, with regard to the next meeting of the Club, to be held on Wednesday evening, and regret exceedingly that I will not be able to be present to record my vote against the diversion of any portion of the entertainment fund as a subscription to aid the Public Welfare Commission in their work.

As I have not been present at any of the recent meetings of the Club, I don't know anything about the Public Welfare Commission, nor its purposes; they may be the best in the world, and it may be that it might be well for the Club to subscribe to help out the work, though I am inclined to think that the Executive Committee's recommendation that the objects of the Club did not warrant their making an appropriation of this character, is the correct view to take of the case, especially if the Commission is, as I suppose, of a political character; of this, however, I am not certain.

So far as the entertainment fund is concerned, this was set apart by the Club when I was an active member, and I think when I was a member of the Executive Committee, for a definite purpose; and my recollection is that the bulk of the fund as it is now constituted, was a special gift to the Club for the purpose of entertainment of distinguished engineers visiting the city, and the Club certainly has no right to divert this gift to any other use.

I will be very much obliged, if the matter comes up at the next meeting and is discussed, if you will read my letter, or have it read, as a part of the discussion, and as expressing the views of one of the Past Presidents of the Club.

Yours truly,

BEN. L. CROSBY.

Amendment seconded and carried.

The subject of the evening was, "Some Notes on Roofs and Roofing Materials."

Mr. Wheeler divided roofing into four great classes,—viz., Felts, Woods, Metals and Silicates. The felts were divided into tarred felts, gravel, ready rock and ruberoid. The woods were divided into boards, slabs and shingles. The metals into corrugated iron, tin, lead and copper. The silicates were divided into mud, slate and tiles.

The advantages and disadvantages of each kind, when laid in flat or pitch roofs or both, together with costs and weights per square, and durability, were discussed. The costs given did not include that of supporting material.

There were also presented a number of samples of shingle and interlocking tiles, and a number of illustrations showing tile roofs.

The Chair announced his resignation, for business reasons, as a member of the Committee on Filtration, and also announced the appointment of Professor W. S. Chaplin as his successor.

Adjourned to Library room, where lunch was served.

W. G. BRENNEKE, *Secretary*.

EVERY MEMBER OF THE

Association of Engineering Societies

should have and use

THE ENGINEERING INDEX.

Originally started by Prof. J. B. Johnson in the Journal of the Association of Engineering Societies, this great work has been continued since 1895 solely by

THE ENGINEERING MAGAZINE.

Prof. Johnson says :—"The work has been far better performed by The Engineering Magazine, both in scope and thoroughness, than I was ever able to do."

The Engineering Index is published as a part of each number of The Engineering Magazine and also as a separate publication. In the latter form it is printed on only one side of the paper for the use of those who wish to cut it up for card index purposes. The subscription price of either publication alone is \$3.00 a year; but both publications will be sent to one address for \$4.00 a year. Send for sample copies.

THE ENGINEERING MAGAZINE,

120-122 LIBERTY STREET,

LONDON OFFICE:
222-225 STRAND, W. C.

NEW YORK.

ASSOCIATION OF ENGINEERING SOCIETIES.

VOL. XXVI.

MAY, 1901.

No. 5.

PROCEEDINGS.

Engineers' Club of St. Louis.

526TH MEETING, MAY 1, 1901.—Held at 1600 Locust street, at 8.20 P.M.; Vice-President Kinealy presiding.

Twenty members and five visitors present.

The minutes of the 525th meeting were read and approved, the minutes of the 309th meeting of the Executive Committee were reported.

The application of Mr. Ernest C. F. Koken was read and referred to the Executive Committee.

The subject of the evening was an account by Mr. Flad of his recent trip to Europe, illustrated by lantern slides of kodak snap shots taken by him during the trip. Among the views shown were many of the different filtration plants which he visited, some of these plants being in successful operation and some in process of construction, all of which were described in more or less detail.

The following Committee on Prizes was announced: B. H. Colby, chairman; J. A. Ockerson, Carl Gayler, W. A. Layman, E. R. Fish.

The Chair announced as the subject of the next meeting a paper by Mr. Duncan F. Cameron on "Coal Supply of St. Louis and Adjacent Territory."

Adjourned to Library room, where refreshments were served.

E. B. FAY, *Secretary pro tem.*

527TH MEETING, MAY 15, 1901.—Held at 1600 Locust street; President Spencer presiding.

Present, twenty-six members and six visitors.

The minutes of the 526th meeting were read and approved. The minutes of the 310th meeting of the Executive Committee were reported.

The applications for membership of Messrs. Hans Carl Toensfeldt and Arthur Tappan North were read.

Mr. Ernest C. F. Koken was elected to membership.

There being no miscellaneous business, attention was paid to the paper of the evening, entitled "The Coal Supply of St. Louis and Adjacent Territory," by Mr. Duncan F. Cameron, superintendent of mines for Donk Bros. Coal and Coke Co.

Mr. Cameron took up in a general way the extent of coal territory tributary to St. Louis, giving areas of these coal measures, also their total annual production and the consumption of bituminous coal by the city of St. Louis.

He then discussed in detail what had been done in the way of washing coal at the mines, the result of which is the elimination of the slate and iron pyrites. The construction of a modern coal-washing plant was explained, the same being illustrated on the screen. Mr. Cameron stated tests have been made in office building steam plants in St. Louis and at other places showing a saving of 20 per cent. to 28 per cent. of fuel bills by using washed coal instead of unwashed coal.

It was also stated that a very fair quality of coke had been made from washed Illinois coal in ovens which were not altogether of modern type.

Experiments, the object of which are to produce a good foundry coke from Illinois coal, are being continued with considerable promise of success.

The discussion was participated in by Messrs. Bryan, Kinealy, Blaisdell, Philip Moore and others.

Adjourned to Library room, where light refreshments were served.

W. G. BRENNKE, *Secretary*.

Engineers' Club of Cincinnati.

123D REGULAR MEETING, CINCINNATI, OHIO, APRIL 18, 1901.—Dinner was served at 6.20 P.M.

The regular meeting was called to order at 7.30 P.M., with President Jewett in the chair and thirteen members present.

Minutes of the meeting of March 21 were read and approved.

The question, presented at the last meeting for discussion, was taken up and discussed by Messrs. Lilly, Nicholson, Jewett and others, giving their experience and practice in the use of explosives for blasting for the removal of different materials.

The following question was presented: What can be done to increase the usefulness of the Cincinnati Engineers' Club? This was considered very apropos and the Secretary was directed to announce it for discussion at the next meeting.

Mr. Ward Baldwin read the paper for the evening, mostly extempore, on the subject, "Present Practice in Specific Loading for Railroad Bridges," being a comparison and discussion of the loads called for by the specifications of a large number of prominent railroads at the present time and of the great increase in most of them over what was specific in the year 1894, when he made a similar examination and comparison.

The subject was discussed by Messrs. Nicholson, Wulff, Read, Lilly, Bogen, Jewett and others.

After a vote of thanks to Mr. Baldwin for his paper, the meeting adjourned.

J. F. WILSON, *Secretary*.

Technical Society of the Pacific Coast.

REGULAR MEETING, SAN FRANCISCO, MAY 3, 1901.—Called to order at 8.30 P.M. by President Marx. The minutes of the last regular meeting were read and approved.

Mr. A. S. Riffle, a civil engineer, was elected to membership upon a regular count of ballots.

A posthumous paper by the late President, Geo. W. Percy, entitled "Reflections of Vitruvius," was read by Mr. G. A. Wright.

Adjourned.

OTTO VON GELDERN, *Secretary*.

Boston Society of Civil Engineers.

BOSTON, MASS., MAY 15, 1901.—A regular meeting of the Boston Society of Civil Engineers was held at Chipman Hall, Tremont Temple, at 7:50 o'clock P.M.; President Lawson B. Bidwell in the chair. Total number present, members and guests, including ladies, one hundred and nineteen.

The record of the last meeting was read and approved.

The Secretary read a communication from the Secretary of the International Engineering Congress, to be held in Glasgow, in September next, inviting this Society to select a delegate to attend the congress as an honorary member.

On motion of Mr. Henry Manley, the communication was referred to the Board of Government with authority to select a delegate if the board deems it expedient.

On motion of Mr. Holmes, the thanks of the Society were voted to Mr. Thomas W. Lawson for courtesies extended on the occasion of the visit to his new yacht "Independence" at the Atlantic Works, East Boston; also to the Boston Transit Commission and to Mr. Robert A. Shailer, President of the Boston Tunnel Construction Company, for courtesies extended at visit to the works of the East Boston Tunnel on May 4, 1901.

On motion of Mr. Higgins, the thanks of the Society were voted to the Boston Elevated Railway Co. for courtesies extended this afternoon on the occasion of the trip over the elevated lines of that company in Charlestown and to its terminal station at Dudley street, Roxbury.

Mr. Frank W. Skinner, of the *Engineering Record*, was then introduced and gave a very interesting lecture, entitled "Some Difficult and Curious Foundations." The lecture was profusely illustrated by lantern slides.

On motion of Professor Swain, the thanks of the Society were voted to Mr. Skinner for his entertaining and instructive lecture.

Adjourned.

S. E. TINKHAM, *Secretary*.

EVERY MEMBER OF THE

Association of Engineering Societies

should have and use

THE ENGINEERING INDEX.

Originally started by Prof. J. B. Johnson in the Journal of the Association of Engineering Societies, this great work has been continued since 1895 solely by

THE ENGINEERING MAGAZINE.

Prof. Johnson says:—"The work has been far better performed by The Engineering Magazine, both in scope and thoroughness, than I was ever able to do."

The Engineering Index is published as a part of each number of The Engineering Magazine and also as a separate publication. In the latter form it is printed on only one side of the paper for the use of those who wish to cut it up for card index purposes. The subscription price of either publication alone is \$3.00 a year; but both publications will be sent to one address for \$4.00 a year. Send for sample copies.

THE ENGINEERING MAGAZINE,

120-122 LIBERTY STREET,

LONDON OFFICE:
222-225 STRAND, W. C.

NEW YORK.

Mr. W. H. Smyth, consulting engineer of San Francisco and Mr. Franklin Riddle, civil engineer of San Francisco, were reinstated to full membership in the Society, upon due approval by the directors.

The death of Mr. B. T. Lacy, member Technical Society, was announced, and the following committee notified through the Board of Directors to draw up a suitable resolution in memory of the deceased member: Mr. John Richards, Mr. Geo. W. Dickie and Mr. Geo. E. Dow.

Mr. John Richards then read the paper of the evening, entitled "Industries of the Upper Rhine," based upon personal observations made during a recent European visit.

The subject was discussed by Mr. Geo. W. Dickie.

Meeting adjourned.

OTTO VOX GELDERN, *Secretary*.

Engineers' Club of Cincinnati.

124TH REGULAR MEETING (POSTPONED), CINCINNATI, OHIO, MAY 23, 1901.
—Dinner was served at 6.15 P.M.

The regular meeting was called to order at 7.15 P.M. with President Jewett in the chair, and eleven members present.

Minutes of the meeting of April 18 were read and approved.

The question announced for discussion, "What Can be Done to Increase the Usefulness of the Cincinnati Engineers' Club?" was taken up, several members making suggestions that the members themselves take more interest in the affairs of the Club, by a more regular attendance at the meetings, and by the preparation of papers and questions for discussion, inviting engineers not members to attend the meetings and join the Club; that the Club interest itself in public matters of an engineering nature, by expressing itself when questions of engineering construction or the employment of engineering talent on public works are proposed.

In this connection the Secretary read a letter addressed to the President from Mr. John C. Trautwine, Jr., Secretary of the Association of Engineering Societies, offering to assist in any way that he could to advance the usefulness or increase the attendance and membership of the Club.

The President announced the death, which occurred on May 14, of Alfred Petry, one of the charter members of the Club, and one who always took an active interest in its affairs. On motion that the President appoint a committee to prepare a suitable memoir, the following were announced as such committee: Messrs. Jewett, Devenish and Wilson.

Mr. James A. Stewart read the paper for the evening, on the subject, "A Plan to Utilize Unemployed Labor," being a suggestion for a plan by which men in the various trades with scant employment during the dull winter months, as well as dealers in materials, were to be employed in the construction of buildings, etc., under an arrangement by which they were to give their labor and materials, receiving therefor a certain proportion of its value and retaining an interest for the balance in an organization somewhat on the plan of a Building Association. Discussion by Messrs. Wulff, Devenish, Jewett, Fritsch, Pfister, Bogen, McAvoy (visitor) and Punshon.

On motion, a vote of thanks was extended to Mr. Stewart for his paper.
Adjourned.

J. F. WILSON, *Secretary*.

EVERY MEMBER OF THE

Association of Engineering Societies

should have and use

THE ENGINEERING INDEX.

Originally started by Prof. J. B. Johnson in the Journal of the Association of Engineering Societies, this great work has been continued since 1895 solely by

THE ENGINEERING MAGAZINE.

Prof. Johnson says :—" The work has been far better performed by The Engineering Magazine, both in scope and thoroughness, than I was ever able to do."

The Engineering Index is published as a part of each number of The Engineering Magazine and also as a separate publication. In the latter form it is printed on only one side of the paper for the use of those who wish to cut it up for card index purposes. The subscription price of either publication alone is \$3.00 a year; but both publications will be sent to one address for \$4.00 a year. Send for sample copies.

THE ENGINEERING MAGAZINE,

120-122 LIBERTY STREET,

LONDON OFFICE:
222-225 STRAND, W. C.

NEW YORK.

LISTS OF MEMBERS

OF THE SOCIETIES COMPOSING THE

Association of Engineering Societies.

DECEMBER 31, 1900.

	MEMBERS.	PAGE.
BOSTON SOCIETY OF CIVIL ENGINEERS.....	501	1
CIVIL ENGINEERS' CLUB OF CLEVELAND.....	216	26
ENGINEERS' CLUB OF ST. LOUIS.....	210	37
CIVIL ENGINEERS' SOCIETY OF ST. PAUL.....	55	48
ENGINEERS' CLUB OF MINNEAPOLIS.....	20	51
MONTANA SOCIETY OF ENGINEERS.....	150	52
TECHNICAL SOCIETY OF THE PACIFIC COAST.....	145	59
DETROIT ENGINEERING SOCIETY.....	106	66
ENGINEERS' SOCIETY OF WESTERN NEW YORK.....	78	72
LOUISIANA ENGINEERING SOCIETY.....	76	76
ENGINEERS' CLUB OF CINCINNATI.....	84	80
TOTAL	1041	

Lists of Members of the Associated Societies.

Abbreviations for designating membership:

FOR HONORARY MEMBER.....HON. MEM.
 FOR MEMBER.....MEM.
 FOR ASSOCIATE MEMBER.....ASSOC. MEM.
 FOR JUNIOR MEMBER.....JUN. MEM.

Boston Society of Civil Engineers.

- ADAMS, EDWARD P., Mem.,
 Landscape Architect and Civil Engineer,
 53 State street, Room 1104, Boston, Mass.
- ADAMS, HENRY S., Mem.,
 Civil Engineer, 53 State street, Room 542, Boston, Mass.
- ADDICKS, WALTER R., Mem.,
 Chief Engineer, Boston, Bay State and other local gas companies,
 24 West street, Boston, Mass.
- AIKEN, CHARLES W., Mem.,
 Consulting and Contracting Engineer,
 82 Washington street, New York, N. Y.
- AIKEN, ROY C., Mem.,
 Civil Engineer, 1059 Washington street, Boston, Mass.
- ALLARD, THOMAS T., Mem.,
 Civil Engineer, Fort Caswell, N. C.
- ALLEN, C. FRANK, Mem.,
 Professor of Railroad Engineering, Mass. Inst. of Technology,
 Boston, Mass.
- ALLEN, CHARLES A., Mem.,
 Consulting Engineer, 44 Front street, Worcester, Mass.
- ANDREWS, DAVID H., Mem.,
 Proprietor Boston Bridge Works, 70 Kilby street, Boston, Mass.
- APPLETON, THOMAS, Mem.,
 Civil Engineer, United States Life Saving Service,
 17 State street, New York, N. Y.
- ARMSTRONG, SAMUEL G., Mem.,
 Civil Engineer,
 Amalinda, Upper Buitenkant street, Cape Town, South Africa.
- ASPINWALL, THOMAS, Mem.,
 Aspinwall & Lincoln, Civil Engineers,
 120 Tremont street, Room 606, Boston, Mass.
- ATWOOD, JOSHUA, 3d, Mem.,
 Civil Engineer, 158 Foster street, Brighton, Boston, Mass.

- ATWOOD, THOMAS C., Mem.,
Civil Engineer, 362 Cross street, Malden, Mass.
- BADGER, FRANK S., Mem.,
Assistant Engineer, Continental Filter Co.,
35 Wall street, Room 24, New York, N. Y.
- BAILEY, ERNEST W., Mem.,
City Engineer, City Hall, Somerville, Mass.
- BAILEY, FRANK S., Mem.,
Assistant in Engineering Department, Massachusetts State Board
of Health, 140 State House, Boston, Mass.
- BAILEY, WILLIAM M., Mem.,
Engineer, Eastern Expanded Metal Co.,
20 Pemberton Square, Boston, Mass.
- BAKER, WILLIAM E., Mem.,
General Superintendent Manhattan Ry. Co.,
10 Dey street, New York, N. Y.
- BALDWIN, LOAMMI F., Mem.,
Civil Engineer, 31 Milk street, Boston, Mass.
- BANCROFT, LEWIS M., Mem.,
Superintendent of Water Works, Reading, Mass.
- BARBOUR, FRANK A., Mem.,
Snow & Barbour, Civil and Sanitary Engineers,
1120 Tremont Bldg., Boston, Mass.
- BARNES, ROWLAND H., Mem.,
Pierce & Barnes, Civil Engineers, 7 Water street, Boston, Mass.
- BARNES, T. HOWARD, Mem.,
Civil and Municipal Engineer, 7 Water street, Boston, Mass.
- BARNES, WILLIAM T., Mem.,
Resident Engineer, Baltimore and Ohio Southwestern Ry.,
Washington, Ind.
- BARROWS, HAROLD K., Mem.,
With Metropolitan Water Board, 1 Ashburton Place, Boston, Mass.
- BARRUS, GEORGE H., Mem.,
Expert and Consulting Steam Engineer,
20 Pemberton Square, Boston, Mass.
- BARTLETT, ARTHUR, Mem.,
Assistant in City Engineer's Office, City Hall, Lowell, Mass.
- BARTLETT, CHARLES H., Mem.,
Bartlett & Gay, Civil and Hydraulic Engineers, 852 Elm street,
Manchester, N. H., and 9 Concord Square, Boston, Mass.
- BARTRAM, GEORGE C., Mem.,
With Boston Bridge Works, 70 Kilby street, Boston, Mass.
- BATEMAN, FREDERIC W., Mem.,
Parker & Bateman, Civil Engineers, Clinton, Mass.
- BATEMAN, LUTHER H., Mem.,
Assistant to Engineer, Harbor and Land Commissioners,
131 State House, Boston, Mass.
- BAYLEY, FRANK A., Mem.,
Civil Engineer, 133 Austin street, Cambridgeport, Mass.
- BEMENT, ROBERT B. C., Mem.,
Civil Engineer and President Board of Water Commissioners,
St. Paul, Minn.

- BETTON, JAMES M., Mem.,
Henry R. Worthington Hydraulic Works, Brooklyn, N. Y.
- BIDWELL, LAWSON B., Mem.,
Assistant Engineer, Eastern District, N. Y., N. H. and H. R. R.,
South Union Station, Boston, Mass.
- BIGELOW, JAMES F., Mem.,
City Engineer, City Hall, Marlboro, Mass.
- BISSELL, H., Mem.,
Chief Engineer, Boston and Maine Railroad, Boston, Mass.
- BLAKE, FRANCIS, Mem.,
Auburndale, Mass.
- BLAKE, PERCY M., Mem.,
Civil and Hydraulic Engineer, Bowers street, Newtonville, Mass.
- BLODGETT, GEORGE W., Mem.,
Electrical Engineer, B. and A. R. R., Boston, Mass.
Residence, Auburndale, Mass.
- BLOOD, JOHN BALCH, Mem.,
Blood & Hale, Consulting and Designing Engineers, Equitable
Bldg., Boston, Mass.
- BLOSSOM, WILLIAM L., Mem.,
Surveyor and Draftsman, 355 Washington street, Brookline, Mass.
- BOLTON, EDWARD D., Mem.,
Landscape Architect and Engineer,
224 W. Seventy-ninth street, New York, N. Y.
- BORDEN, PHILIP D., Mem.,
City Engineer, P. O. Box 248, Fall River, Mass.
- BOTSFORD, HARRY G., Mem.,
Assistant Engineer, Engineering Department, Boston.
Residence, 10 Nightingale street, Dorchester, Mass.
- BOURNE, FRANK B., Mem.,
Assistant Engineer in charge of Park Department,
City Engineer's Office, Providence, R. I.
- BOWDITCH, ERNEST W., Mem.,
Landscape Gardener and Engineer,
60 Devonshire street, Boston, Mass.
- BOWERS, GEORGE, Mem.,
City Engineer, City Hall, Lowell, Mass.
- BOYD, JAMES T., Mem.,
Consulting Engineer, 60 State street, Boston, Mass.
- BRACKETT, DEXTER, Mem.,
Engineer, Distribution Department, Metropolitan Water Board,
1 Ashburton Place, Boston, Mass.
- BRACKETT, WALLACE C., Mem.,
Assistant Engineer, Boston Elevated Ry. Co.,
101 Milk street, Room 1001, Boston, Mass.
- BRADFORD, LAURENCE, Mem.,
Civil Engineer, Millbrook, Mass.
- BRADLEY, HARRY C., Mem.,
Instructor, Massachusetts Institute of Technology, Boston, Mass.
- BRADLEY, WILLIAM H., Mem.,
Civil Engineer, 642 Exchange Bldg., Boston, Mass.
- BRANCH, ERNEST W., Mem.,
Engineer, Sewerage Commissioners, Adams Bldg., Quincy, Mass.

- BRAY, CHARLES D., Mem.,
Professor of Civil and Mechanical Engineering, Tufts College,
College Hill, Mass.
- BREED, CHARLES B., Mem.,
Instructor at Massachusetts Institute of Technology.
Residence, 12 George street, Lynn, Mass.
- BREWER, BERTRAM, Mem.,
City Engineer, Waltham, Mass.
- BROCK, NATHAN S., Mem.,
Civil Engineer, 39 Parsons street, Brighton, Mass.
- BROOKS, FREDERICK, Mem.,
Civil Engineer, 31 Milk street, Boston, Mass.
- BROWN, WILLIAM M., JR., Mem.,
Chief Engineer and Superintendent, Metropolitan Sewerage Works,
20 Pemberton Square, Boston, Mass.
- BRYANT, HENRY F., Mem.,
French & Bryant, Civil Engineers,
334 Washington street, Brookline, and 4 State street, Boston, Mass.
- BUCK, WALDO E., Mem.,
President and Treasurer, Worcester Manfs. Mut. Ins. Co.,
53 William street, Worcester, Mass.
- BULLOCK, WILLIAM D., Mem.,
Engineer in charge of Bridges and Harbor,
City Hall, Providence, R. I.
- BURKE, JOHN R., Mem.,
Assistant to Engineer, Harbor and Land Commissioners,
131 State House, Boston, Mass.
- BURLEY, HARRY B., Mem.,
Civil Engineer and Inspector, Associated Factory Mut. Ins. Cos.,
31 Milk street, Boston, Mass.
- BURR, THOMAS S., Mem.,
Civil Engineer, 53 State street, Boston. Residence, Melrose, Mass.
- BURTON, ALFRED E., Mem.,
Professor of Topographical Engineering, Massachusetts Institute
of Technology, Boston, Mass.
- BUTTOLPH, BENJAMIN G., Mem.,
Engineer, State Enterprise and American Mut. Fire Ins. Cos.,
819 Banigan Bldg., Providence, R. I.
- CALDWELL, FREDERIC A., Mem.,
First Assistant, City Engineer's Office, Woonsocket, R. I.
- CARNEY, EDWARD B., Mem.,
City Engineer's Office, 39 Plymouth street, Lowell, Mass.
- CARPENTER, GEORGE A., Mem.,
City Engineer, 77 Meadow street, Pawtucket, R. I.
- CARR, JOSEPH R., Mem.,
Civil Engineer, 466 Broadway, Chelsea, Mass.
- CARSON, HOWARD A., Mem.,
Chief Engineer, Boston Transit Commission,
20 Beacon street, Boston, Mass.
- CARTER, FRANK H., Mem.,
Engineer in charge of Street Work, City Engineer's Office,
Cambridge, Mass.

- CARTER, HENRY H., Mem.,
Consulting Engineer and President, Metropolitan Contracting Co.,
95 Milk street, Boston, Mass.
- CARVEN, CHRISTOPHER J., Mem.,
Assistant Engineer, Engineering Dept., 51 City Hall, Boston.
Residence, 34 Centre street, Dorchester, Mass.
- CHACE, GEORGE F., Mem.,
Superintendent, Water Works, Taunton, Mass.
- CHAMBERLAIN, EDWARD G., Mem.,
Topographical Surveyor, Auburndale, Mass.
- CHAMBERLAIN, WILLIAM G. S., Mem.,
Bridge Engineer, B. and A. R. R., Boston.
Residence, Auburndale, Mass.
- CHAMBERS, RALPH H., Mem.,
Chambers & Hone, Consulting Engineers,
60 New street, New York, N. Y.
- CHAPMAN, WILLIAM H., Mem.,
Waring, Chapman & Farquhar, Civil Engineers,
874 Broadway, New York, N. Y.
- CHASE, JOHN C., Mem.,
Chief Engineer, The Clarendon Water Works Co.,
Wilmington, N. C.
- CHEEVER, ALBERT S., Mem.,
Assistant Engineer, Fitchburg Division, Boston and Maine Rail-
road, Boston, Mass.
- CHIENEY, JOHN E., Mem.,
Assistant City Engineer, City Hall, Boston, Mass.
- CHILDS, STEPHEN, Mem.,
Deputy Street Com'r, Superintendent of Sewer Division,
City Hall, West Newton, Mass.
- CLAPP, OTIS F., Mem.,
City Engineer, City Hall, Providence, R. I.
- CLAPP, SIDNEY K., Mem.,
Assistant in office of the Metropolitan Water Board,
1 Ashburton Place, Boston, Mass.
- CLAPP, WILFRED A., Mem.,
Assistant Engineer, Metropolitan Water Board, Clinton, Mass.
- CLARK, W. LEWIS, Mem.,
Assistant, Middlesex Co., Engineer's Office.
50 Sacramento street, Cambridge, Mass.
- COFFIN, FREEMAN C., Mem.,
Civil and Hydraulic Engineer, 53 State street, Boston, Mass.
- COGGESHALL, ROBERT C. P., Mem.,
Superintendent, Water Works, City Hall, New Bedford, Mass.
- COOK, BYRON I., Mem.,
Superintendent, Water Works, Woonsocket, R. I.
- COOK, MAYO T., Mem.,
Assistant Engineer, Engineering Department,
65 City Hall, Boston, Mass.
- CORTHELL, ARTHUR B., Mem.,
Resident Engineer, The Boston Terminal Co.,
220 South Station, Boston, Mass.

- CORTHELL, ELMER L., Mem.,
Consulting Engineer,
Care Eddy, Hall & Cia, 399 Reconquista, Buenos Aires, Argentine Republic, S. A.
- CRAIB, CHARLES G., Assoc. Mem.,
General Contractor, 138 Pleasant street, Winthrop, Mass.
- CRAIGUE, JOSEPH S., Mem.,
With E. Worthington, Civil Engineer, Dedham, Mass.
- CRANE, ALBERT S., Mem.,
Chief Assistant Engineer, Michigan Lake Superior Power Co.,
Sault Ste. Marie, Mich.
- CROWELL, ALONZO K., Mem.,
Roadmaster's Clerk, N. Y., N. H. and H. R. R.,
97 Cohannet street, Taunton, Mass.
- CUMMINGS, W. WARREN, Mem.,
Engineer, N. E. Gas and Coke Co., Everett, Mass.
- CUNNINGHAM, FRED'K H., Mem.,
Mining, Thistle Creek Northwest Territory,
Address, Box 49, Bolton, Mass.
- CUNTZ, WILLIAM C., Mem.,
Engineer, London Office, The Pennsylvania Steel Company,
110 Cannon street, London, E. C., Eng.
- CURRIER, GEORGE C., Mem.,
Engineering Department, 60 City Hall, Boston, Mass.
- CURTIS, GREELY S., Mem.,
Hydraulic Engineer, Boston Fire Department,
Bristol street, Boston, Mass.
- CURTIS, JOSEPH H., Mem.,
Landscape Engineer and Gardener,
85 Devonshire street, Boston, Mass.
- CURTIS, LOUVILLE, Mem.,
Roadmaster, Western Division, Boston and Maine Railroad,
354 Andover street, Lawrence, Mass.
- CUTTER, CHARLES R., Mem.,
Boston Elevated Railway, Elevated Lines,
101 Milk street, Boston, Mass.
- CUTTER, LOUIS F., Mem.,
Assistant Engineer, Engineering Department, 60 City Hall, Boston,
Residence, 15 Rangeley, Winchester, Mass.
- CUTTER, ROLAND, N., Mem.,
Engineering Department, 51 City Hall, Boston, Mass.
- DAVIS, CHARLES HENRY, Mem.,
Consulting Engineer, 99 Cedar street, New York, N. Y.
- DAVIS, EDMUND S., Mem.,
Assistant Engineer, Boston Transit Commission,
59 Robinwood ave., Jamaica Plain, Mass.
- DAVIS, JOSEPH P., Mem.,
Chief Engineer, American Bell Telephone Company,
113 West Thirty-eighth street, New York, N. Y.
- DAVIS, LEONARD H., Mem.,
Assistant Engineer, Boston Elevated Railway Company,
Residence, 10 Allston Terrace, Brighton, Mass.
- DEAN, ARTHUR W., Mem.,
City Engineer, City Hall, Nashua, N. H.

- DEAN, FRANCIS W., Mem.,
Dean & Main, Mechanical and Mill Engineers,
53 State street, Boston, Mass.
- DEAN, LUTHER, Mem.,
Civil Engineer, 23 Crocker Bldg., 14 City Square, Taunton, Mass.
- DENNETTE, FRANCIS A., Mem.,
Constructing Engineer, 155 Huntington ave., Boston, Mass.
- DE WOLF, JOHN O., Mem.,
Mechanical Engineer, with W. B. Smith Whaley & Co.,
Tremont Bldg., Boston, Mass.
- DODGE, SAMUEL D., Mem.,
With Metropolitan Water Board, 1 Ashburton Place, Boston.
Residence, 29 Russell street, Arlington, Mass.
- DORR, EDGAR S., Mem.,
Chief Engineer, Sewer Division, Street Department,
30 Tremont street, Boston, Mass.
- DRAKE, ALBERT B., Mem.,
Civil Engineer and Surveyor,
164 Williams street, New Bedford, Mass.
- DREW, JOSEPH N., Mem.,
Civil Engineer, 45 Milk street, Room 61, Boston, Mass.
- DUNNE, GEORGE C., Assoc. Mem.,
Manager, Portland Stone Ware Co.,
42 Oliver street, Boston, Mass.
- DWELLEY, EDWIN F., Mem.,
Harris & Dwelley, Civil Engineers, 59 Exchange street,
Residence, 25 Baltimore street, Lynn, Mass.
- ELLIS, GEORGE A., Mem.,
Hydraulic Engineer, 158 Sherman street, Springfield Mass.
- ELLIS, JOHN W., Mem.,
Civil Eng., 178 Devonshire street, Boston, and Woonsocket, R. I.
- ELLIS, S. CLARENCE, Mem.,
1750 Beacon street, Brookline, Mass.
- ELLSWORTH, EMORY A., Mem.,
Consulting Engineer, 7 Main street, Holyoke, Mass.
- EMERSON, GUY C., Mem.,
Deputy Superintendent, Sewer Division, Street Department,
30 Tremont street, Boston, Mass.
- EMIGH, JOHN H., Mem.,
City Engineer, North Adams, Mass.
- ESTEY, HENRY W., Mem.,
Assistant Engineer, City Engineer's Office,
11 Page street, Malden, Mass.
- EVANS, GEORGE E., Mem.,
Civil and Hydraulic Engineer, 95 Milk street, Boston, Mass.
- EVANS, ROBERT R., Mem.,
City Engineer, City Hall, Haverhill, Mass.
- EWING, WILLIAM C., Mem.,
Chief Assistant and Clerk, The C. H. W. Wood Co.,
2380 Washington street, Boston, Mass.
- FALES, FRANK L., Mem.,
Assistant Engineer, Board of Trustees, Comm's of Water Works,
City Hall, Cincinnati, Ohio.

- FARNHAM, FREDERICK W., Mem.,
Engineer in charge of Sewer Department, City Engineer's Office,
City Hall, Lowell, Mass.
- FARNHAM, IRVING T., Mem.,
City Engineer, City Hall, West Newton, Mass.
- FARNUM, LORING N., Mem.,
Civil Engineer, 53 State street, Boston, Mass.
- FAVOR, WILLIAM A., Mem.,
Assistant Engineer, City Engineer's Office,
Chester street, Lowell, Mass.
- FAY, FREDERIC H., Mem.,
Assistant Engineer, Engineering Department,
60 City Hall, Boston, Mass.
- FELTON, BURTON R., Mem.,
Civil and Hydraulic Engineer, 1120 Tremont Bldg., Boston, Mass.
- FELTON, CHARLES R., Mem.,
City Engineer, City Hall, Brockton, Mass.
- FERGUSON, JOHN N., Mem.,
Assistant Engineer, Metropolitan Water Board,
1 Ashburton Place, Boston, Mass.
- FERNALD, CLARENCE T., Mem.,
Assistant Engineer, Boston Elevated Railway Company,
32 Malvern street, Melrose, Mass.
- FERNALD, GEORGE N., Mem.,
City Engineer and Commissioner of Public Works,
City Hall, Portland, Me.
- FITZ, CHARLES F., JR., Mem.,
With Metropolitan Park Commission, Watertown, Mass.
- FITZGERALD, DESMOND, Mem.,
Department Engineer, Metropolitan Water Board,
1 Ashburton Place, Boston, Mass.
- FLETCHER, AUSTIN B., Mem.,
Secretary, Massachusetts Highway Commission,
20 Pemberton Square, Boston, Mass.
- FLINN, ALFRED D., Mem.,
Prin. Office Assistant, Metropolitan Water Board,
1 Ashburton Place, Boston, Mass.
- FORBES, ARTHUR A., Mem.,
Engineer, Board of Public Works, City Hall, Pittsfield, Mass.
- FOLSOM, CHARLES W., Mem.,
District Engineer of Sewers, 30 Tremont street, Boston, Mass.
- FORBES, FAYETTE F., Mem.,
Superintendent, Water Works, Brookline, Mass.
- FOSS, CLIFFORD, Mem.,
With Metropolitan Water Board,
1 Ashburton Place, Boston, Mass.
- FOSS, WILLIAM E., Mem.,
Assistant Engineer, Metropolitan Water Board,
1 Ashburton Place, Boston, Mass.
- FOSTER, EDWARD S., Mem.,
Civil Engineer, 624 Tremont Bldg., Boston, Mass.
- FOSTER, WILLARD M., Mem.,
Assistant, with Rice & Evans, 95 Milk street, Boston,
64 Grove street, Lowell, Mass.

- FRANCIS, GEORGE B., Mem.,
Chief Engineer, Rhode Island Suburban Electric Railway Co.,
113 Keene street, Providence, R. I.
- FREEMAN, JOHN R., Mem.,
President and Treasurer, Manfs., Rhode Island and Mechanics
Mut. Fire Ins. Cos., 812 Banigan Bldg., Providence, R. I.
- FRENCH, ALEXIS H., Mem.,
Town Engineer, Town Hall, Brookline. Also of firm of French
& Bryant, Civil Engineers,
344 Washington street, Brookline, and 4 State street, Boston, Mass.
- FRENCH, EDMUND M., Mem.,
Assistant, with Metropolitan Water Board,
15 Morgan House, Clinton, Mass.
- FRENCH, FRANK B., Mem.,
Engineer and Superintendent for Board of Public Works,
4 Municipal Bldg., Woburn, Mass.
- FRENCH, GEORGE L. R., Mem.,
Roadmaster, Eastern Division, Boston and Maine Railroad,
Beverly, Mass.
- FRENCH, HEYWOOD S., Mem.,
Boston Representative of the J. W. Bishop Co.,
53 State street, Room 408, Boston, Mass.
- FRINK, HARRY A., Mem.,
Civil Engineer, 23 Pinckney street, Boston, Mass.
- FRIZELL, JOSEPH P., Mem.,
Hydraulic Engineer, 60 Congress street, Boston, Mass.
- FTELEY, ALPHONSE, Mem.,
Consulting Engineer, 14 West 131st street, New York, N. Y.
- FULLER, ANDREW D., Mem.,
Engineer Expert, Massachusetts Managers, Paris Exposition,
15 Lawrence street, Wakefield, Mass.
- FULLER, FRANK E., Mem.,
With Metropolitan Water Board, 1 Ashburton Place, Boston.
Residence, West Newton, Mass.
- FULLER, FRANK L., Mem.,
Civil and Hydraulic Engineer, 12 Pearl street, Boston, Mass.
- FULLER, FRED VINCENT, Mem.,
Manager, Carson Trench Machine Co.,
16 Dorrance street, Charlestown, Boston, Mass.
- FULLER, GEORGE W., Mem.,
Consulting Expert, Water Purification and Sewage Disposal,
220 Broadway, New York, N. Y.
- FULLER, WILLIAM B., Mem.,
Civil Engineer, 301 West Fifty-seventh street, New York, N. Y.
- GAGE, HERBERT E., Mem.,
In Chief Engineer's Office, B. and A. R. R., Boston, Mass.
- GANNETT, CHARLES H., Mem.,
Civil Engineer, 1102 Exchange Bldg., Boston, Mass.
- GAY, CHARLES W., Mem.,
Civil Engineer, 25 Exchange street, Lynn, Mass.
- GERRISH, JOHN H., Assoc. Mem.,
Agent, Eastern Dredging Co., 25 Congress street, Boston.
Residence, Melrose Highlands, Mass.

- GERRY, LYMAN L., Mem.,
With Engineer Department, Massachusetts Highway Commission,
Stoneham, Mass.
- GLEASON, WALTER A., Mem.,
Civil Engineer, 58 Front street, Worcester, Mass.
- GLOVER, ALBERT S., Mem.,
Secretary, Hersey Mfg. Co., 714 Tremont Temple, Boston, Mass.
- GOODNOUGH, BENJ. F., Mem.,
Assistant Engineer, Metropolitan Water Board,
1 Ashburton Place, Boston, Mass.
- GOODNOUGH, X. H., Mem.,
Chief Engineer, Massachusetts State Board of Health,
Room 140 State House, Boston, Mass.
- GOULD, JOHN A., Mem.,
Chief Engineer, Brookline and Dorchester Gas Co.,
24 West street, Boston, Mass.
- GOWING, E. H., Mem.,
Engineer, 20 Pemberton Square, Boston, Mass.
- GRAY, JOSEPH P., Mem.,
Vice-President, Boston Manfs. Mut. Fire Insurance Co., 31 Milk
street, Boston.
Residence, Hunter and Putnam street, West Newton, Mass.
- GREENE, LEVI R., Mem.,
Consulting Engineer, Walworth Manufacturing Company.
Residence, 35 Concord ave., Cambridge, Mass.
- GREW, HERBERT L., Assoc. Mem.,
With Waldo Bros., Contractors' and Builders' Supplies,
102 Milk street, Boston, Mass.
- GRISWOLD, LEON S., Mem.,
Mining Geologist, 238 Boston street, Dorchester, Mass.
- GROVER, ARTHUR C., Mem.,
City Engineer, Superintendent of Streets and Superintendent of
Water Works, 59 Evergreen ave., Rutland, Vt.
- GROVER, EDMUND, Mem.,
Civil Engineer, East Walpole, Mass.
- GROVER, NATHAN C., Mem.,
Professor of Civil Engineering, University of Maine, Orono, Me.
- GUPPY, BENJAMIN W., Mem.,
Bridge Engineer, Maine Central Railroad, Portland, Me.
- GUSHEE, EDWARD G., Mem.,
Civil Engineer, 1942 North Twenty-third street, Philadelphia, Pa.
- HABERSTROH, CHARLES E., Mem.,
Assistant Superintendent, Sudbury Department, Metropolitan
Water Works, South Framingham, Mass.
- HALE, RICHARD A., Mem.,
Principal Assistant Engineer, Essex Water Power Co.,
Lawrence, Mass.
- HALE, ROBERT S., Mem.,
Steam and Electrical Engineer, 31 Milk street, Boston, Mass.
- HALL, FRANK E., Mem.,
Civil Engineer, with Sumner & Goodwin Co.,
287 Congress street, Boston, Mass.

- HALL, GEORGE H., JR., Mem.,
Assistant Engineer, N. E. Telegraph and Telephone Co., 104 Milk
street, Boston. Res., 5 New Millet street, Dorchester, Mass.
- HAMILTON, GEORGE W., Mem.,
District Engineer of Sewers, 30 Tremont street, Boston, Mass.
- HAMLIN, GEORGE H., Mem.,
Civil Engineer, Orono and Bangor, Me.
- HAMMATT, EDWARD A. W., Mem.,
Civil and Hydraulic Engineer,
53 State street, Boston, and Hyde Park, Mass.
- HARDY, GEORGE F., Mem.,
Assistant Manager, Construction and Maintenance Department,
International Paper Co., 30 Broad street, New York, N. Y.
- HARDY, GEORGE R., Mem.,
Assistant Engineer of Construction, N. Y., N. H. and H. R. R.,
Forest Hills, Mass.
- HARRINGTON, DAVID A., Mem.,
Engineer, Boston Electric Light Co.,
77 Ames Bldg., Boston, Mass.
- HARRINGTON, EPHRAIM, Mem.,
Ephraim Harrington & Co., Civil and Consulting Engineers,
60 State street, Boston, Mass.
- HARRIS, CHARLES, Mem.,
Agent of Barber Asphalt Paving Co.,
70 Kilby street, Room 68, Boston, Mass.
- HARRIS, ISAAC K., Mem.,
Civil Engineer and Surveyor, 59 Exchange street, Lynn, Mass.
- HARRISON, CHRISTOPHER, Mem.,
City Engineer, City Hall, Everett, Mass.
- HART, FRANK S., Mem.,
Civil and Hydraulic Engineer, Assistant Engineer, Metropolitan
Water Works, South Framingham, Mass.
- HARWOOD, T. T. HUNTER, Mem.,
United States Assistant Engineer, Rockport, Mass.
- HASTINGS, ISAAC W., Mem.,
Assistant in City Engineer's Office, West Newton, Mass.
- HASTINGS, LEWIS M., Mem.,
City Engineer, City Hall, Cambridgeport, Mass.
- HASWELL, CHARLES H., Hon. Mem.,
Civil and Mechanical Engineer, Consulting Engineer, Department
of Public Improvements,
Room 1803 Park Row Bldg., New York, N. Y.
- HATCH, ARTHUR E., Mem.,
Manager, Bay State Dredging Co., 19 High street, Boston.
Residence, 43 Tennyson street, Somerville, Mass.
- HAWES, LOUIS E., Mem.,
Civil and Hydraulic Engineer, 751 Tremont Bldg., Boston, Mass.
- HAWKES, LEVI G., Mem.,
Civil Engineer, Saugus, Mass.
- HAWLEY, WILLIAM C., Mem.,
Assistant Engineer, Massachusetts Topographical Survey Com-
mission, 60 Broadway, Taunton, Mass.

- HAYES, HENRY W., Mem.,
Assistant Engineer, Fitchburg Division, Boston and Maine Rail-
road, Boston, Mass.
- HAZELTON, CHARLES W., Mem.,
Engineer and Treasurer, Turners Falls Co., Turners Falls, Mass.
- HAZEN, ALLEN, Mem.,
Consulting Engineer, St. Paul Bldg.,
220 Broadway, New York, N. Y.
- HEALD, SIMPSON C., Mem.,
Civil Engineer, 48 Congress street, Boston, Mass.
- HERING, RUDOLPH, Mem.,
Hydraulic and Sanitary Engineer,
100 William street, New York, N. Y.
- HERSCHEL, CLEMENS, Mem.,
Consulting Engineer, East Jersey Water Co.,
2 Wall street, Room 54, New York, N. Y.
- HERSEY, FREDERIC M., Mem.,
Assistant Engineer, with E. W. Bowditch,
60 Devonshire street, Boston, Mass.
- HEWS, JOSEPH R., Mem.,
Engineer Inspector, Charlestown Bridge,
18 Michigan ave., Dorchester, Mass.
- HICKS, C. ATHERTON, Mem.,
Civil Engineer and Landscape Architect, Consulting Room, 501
Tremont Bldg., Boston. Drafting Room at Needham, Mass.
- HIGGINS, HERMAN K., Mem.,
Assistant Engineer, N. Y., N. H. and H. R. R., 472 South Station,
Boston. Residence, 1799 Dorchester ave., Dorchester, Mass.
- HINCKLEY, DAVID, Mem.,
Assistant Engineer, Props., The Locks and Canals,
66 Broadway, Lowell, Mass.
- HODGDON, FRANK W., Mem.,
Engineer, Harbor and Land Commission,
131 State House, Boston, Mass.
- HODGES, GILBERT, Mem.,
Civil and Consulting Engineer, 60 State street, Boston, Mass.
- HOLDEN, HORACE G., Mem.,
Superintendent, Pennichuck Water Works Co., Nashua, N. H.
- HOLLIS, IRA N., Mem.,
Professor of Engineering, Lawrence Scientific School, Harvard
University, Cambridge, Mass.
- HOLMES, J. ALBERT, Mem.,
Engineer, Park Department, City Hall, Cambridgeport, Mass.
- HOLT, ARTHUR C., Mem.,
Treasurer, New England Structural Co.,
18 Post Office Square, Boston, Mass.
- HOPSON, ERNEST G., Mem.,
Assistant Engineer, Metropolitan Water Board, Clinton, Mass.
- HORTON, ARTHUR E., Mem.,
Assistant Engineer, Metropolitan Park Commission,
14 Beacon street, Boston, Mass.
- HORTON, THEODORE, Mem.,
With Metropolitan Sewerage Commission,
17 Everett street, Melrose, Mass.

- HOSMER, FRANCIS E., Meml.,
Inspector, Engineering Department, Boston,
569 Broadway, South Boston, Mass.
- HOSMER, SIDNEY, Meml.,
Electrical Engineer, Boston Electric Light Co.,
79A Ames Bldg., Boston, Mass.
- HOUGHTON, CHARLES E., Meml.,
Transitman, Sewer Department,
114 Erie street, New Dorchester, Mass.
- HOWARD, CHANNING, Meml.,
Whitman & Howard, Civil Engineers,
85 Devonshire street, Boston, Mass.
- HOWARD, JOHN L., Meml.,
Assistant Engineer, Metropolitan Water Board,
1 Ashburton Place, Boston, Mass.
- HOWE, EDWARD W., Meml.,
Assistant Engineer, Engineering Department,
65 City Hall, Boston, Mass.
- HOWE, GEORGE E., Meml.,
With Metropolitan Water Board, 1 Ashburton Place, Boston.
Residence, 20 Wesley Park, Somerville, Mass.
- HOWE, HORACE J., Meml.,
Assistant Engineer, Rapid Transit Railroad Commission,
231 W. 125th street, New York, N. Y.
- HOWE, WILL B., Meml.,
City Engineer,
5 Warren street, Concord, N. H.
- HOWLAND, ALBERT H., Meml.,
Civil Engineer,
60 Congress street, Boston, Mass.
- HOWLAND, CHARLES W., Meml.,
Civil Engineer and Surveyor, 44 Union street, Rockland, Mass.
- HUBBARD, DWIGHT L., Meml.,
Engineering Department,
51 City Hall, Boston, Mass.
- HULTMAN, EUGENE C., Meml.,
Inspecting and Auditing Engineer, West End Street Railway Sys-
tem,
101 Milk street, Boston, Mass.
- HUNKING, ARTHUR W., Meml.,
Civil and Hydraulic Engineer,
374 Stevens street, Lowell, Mass.
- HUNTER, FREDERIC S., Meml.,
Civil Engineer,
5 City Hall, Boston, Mass.
- HUNTER, HARRY G., Meml.,
Civil Engineer,
Hotel Denmark, Dorchester, Mass.
- HUNTER, WILLIAM B., Meml.,
Inspector, Boston Elevated Railway Co.,
23 Weston street, Waltham, Mass.
- HYDE, CHARLES G., Meml.,
Assistant Engineer Improvement, Extension and Filtration of the
Water Supply,
Testing Station Spring Garden Pumping Station, Philadelphia, Pa.
- JACKSON, WILLIAM, Meml.,
City Engineer,
City Hall, Boston, Mass.
- JANES, CHARLES F., Meml.,
Assistant Engineer, Park Department,
City Engineer's Office, Providence, R. I.

- JENNEY, WALTER, Mem.,
Superintendent, Jenney Mfg. Co.,
55 G street, South Boston, Mass.
- JOHNSON, ALPHEUS M., Mem.,
Assistant Engineer, Boston and Maine Railroad,
100 South State street, Concord, N. H.
- JOHNSON, FRANK P., Mem.,
Tide Water Trap Rock, East Haven, Conn.
- JOHNSON, JAMES W., Mem.,
City Engineer, Riverside, Cal.
- JOHNSON, LEWIS J., Mem.,
Assistant Professor of Civil Engineering, Lawrence Scientific
School, Harvard University.
100 Avon Hill street, North Cambridge, Mass.
- JOHNSON, WILLIAM S., Mem.,
Assistant Engineer, State Board of Health,
Room 140, State House, Boston, Mass.
- JONES, J. EDWIN, Mem.,
Civil Engineer, Jamaica Plain, Mass.
- KEENE, WILLIAM F., Mem.,
City Engineer, 84 Cross street, Central Falls, R. I.
- KEITH, HERBERT C., Mem.,
Assistant Bridge Engineer, N. Y., N. H. and H. R. R.,
New Haven, Conn.
- KENDALL, FRANCIS H., Mem.,
Civil Engineer for Middlesex County Commissioners,
Court House, East Cambridge, Mass.
- KETTELL, CHARLES W., Mem.,
Mechanical Engineer, 53 State street, Room 1112, Boston, Mass.
- KIDD, ALEXANDER L., Mem.,
District Engineer of Sewers, 30 Tremont street, Boston, Mass.
- KIMBALL, GEORGE A., Mem.,
Chief Engineer, Elevated Lines, Boston Elevated Railway Co., and
Member of Metropolitan Sewerage Commission,
101 Milk street, Boston, Mass.
- KIMBALL, HARRY L., Mem.,
In City Engineer's Office,
U. S. Engineer's Office, Custom House, Cincinnati, Ohio.
- KIMBALL, JOSEPH H., Mem.,
Office Assistant, City Engineer's Office, West Newton, Mass.
- KING, GEORGE A., Mem.,
City Engineer, City Hall, Taunton, Mass.
- KINNICUTT, LEONARD P., Mem.,
Professor of Chemistry, Worcester Polytechnic Institute,
Worcester, Mass.
- KNAPP, FREDERICK B., Mem.,
Principal of Powder Point School, Duxbury, Mass.
- KNOWLES, MORRIS, Mem.,
Assistant Engineer in charge, Testing Station, Improvement and
Filtration of Water Supply, Spring Garden Pumping Sta-
tion, Philadelphia, Pa.
- LANZA, GAETANO, Mem.,
Professor of Theoretical and Applied Mechanics, Massachusetts
Institute of Technology, Boston, Mass.

- LAVIS, FREDERICK, Mem.,
Engineer, Ur Expedition,
Care, United States Consul, Busch, Turkey in Asia.
- LAWTON, LOUIS C., Mem.,
With Engineering Department, Boston and Maine Railroad,
Waverley, Mass.
- LAWTON, PERRY, Mem.,
Civil Engineer, 7 Savings Bank Bldg., Quincy, Mass.
- LEARNED, WILBUR F., Mem.,
Superintendent of Streets and Sewers, Watertown, Mass.
- LEAVITT, ERASMUS D., Mem.,
Mechanical and Consulting Engineer,
2 Central Square, Cambridgeport, Mass.
- LELAND, GEORGE I., Mem.,
Assistant Engineer in charge of Sewers, City Hall, Lynn, Mass.
- LIBBEY, DANA, Mem.,
In City Engineer's Office, West Newton, Mass.
- LINCOLN, EDWIN H., Mem.,
Aspinwall & Lincoln, Civil Engineers,
120 Tremont street, Room 606, Boston, Mass.
- LINK, JOHN WILLIAM, Mem.,
With Metropolitan Water Board,
1 Ashburton Place, Boston, Mass.
- LOCKE, FRANK L., Mem.,
Assistant Superintendent, Boston Rubber Shoe Co., Malden, Mass.
- LOCKE, FRANKLIN B., Mem.,
Civil Engineer, North Adams, Mass.
- LOVIS, ANDREW M., Mem.,
Assistant Engineer, Massachusetts Highway Commission,
20 Pemberton Square, Boston, Mass.
- LUTHER, WILLIAM J., Mem.,
Civil Engineer, Assistant Superintendent, Attleboro Gas Light Co.,
Attleboro, Mass.
- LYMAN, EDWARD, Mem.,
Civil and Mechanical Engineer, Lowell Mfg. Co.,
431 Wilder street, Lowell, Mass.
- LYMAN, JOHN F., Mem.,
Consulting Engineer and Architect, P. O. Box 2295, Boston, Mass.
- LYON, JOSEPH P., Mem.,
Civil Engineer, Hanover, Conn.
- MACKSEY, HENRY V., Mem.,
Assistant Engineer, Boston Water Department,
64 City Hall, Boston, Mass.
- MACOMBER, HARRY F., Mem.,
With Luther Dean, C.E., 187 County street, Taunton, Mass.
- MAIN, CHARLES T., Mem.,
Dean & Main, Mechanical and Mill Engineers,
53 State street, Room 1112, Boston, Mass.
- MANAHAN, ELMER G., Mem.,
Assistant in office, Metropolitan Water Board,
1 Ashburton Place, Boston, Mass.
- MANLEY, HENRY, Mem.,
Assistant Engineer, Engineering Department,
51 City Hall, Boston, Mass.

- MANLEY, LAURENCE B., Mem.,
Engineer, Massachusetts Telephone and Telegraph Co.,
185 Franklin street, Boston, Mass.
- MARBLE, ARTHUR D., Mem.,
City Engineer, City Hall, Lawrence, Mass.
- MARTIN, JAMES W., Mem.,
Engineer to B. F. Smith & Bro., Water Supply by Artesian Well
Method, 38 Oliver street, Boston, Mass.
- MARVELL, EDWARD I., Mem.,
Civil and Mechanical Engineer,
81 Bedford street, Fall River, Mass.
- MASON, CHARLES A., Mem.,
W. A. Mason & Son, Civil Engineers and Surveyors,
631 Massachusetts ave., Cambridgeport, Mass.
- MATTICE, ASA M., Mem.,
Consulting Engineer, 110 Locust street, Dover, N. H.
- McALPINE, WILLIAM H., Mem.,
Hydrographic Surveyor, United States Steamship "Ranger,"
18 Abbott street, Lawrence, Mass.
- McCLINTOCK, WILLIAM E., Mem.,
Civil and Hydraulic Engineer, 15 Court Square, Boston, Mass.
- McINNES, FRANK A., Mem.,
Assistant Engineer, Engineering Department, Boston,
23 Salcombe street, Dorchester, Mass.
- McKAY, WILLIAM E., Mem.,
Assistant Engineer, Bay State Gas Co. and Boston Gas Light Co.,
10 Pearl street, Dorchester, Mass.
- McKENNA, JAMES A., Mem.,
Assistant Engineer, City Engineer's Office, Providence, R. I.
- McKIBBEN, FRANK P., Mem.,
Instructor in Civil Engineering, Massachusetts Institute of Tech-
nology, Boston, Mass.
- METCALF, LEONARD, Mem.,
Civil Engineer, 14 Beacon street, Boston, Mass.
- MILDRAM, HENRY C., Mem.,
Assistant Engineer, Street Laying-Out Department,
23 Old Court House, Boston, Mass.
- MILLER, EDWARD F., Mem.,
Professor, Steam Engineering, Massachusetts Institute of Technol-
ogy, Boston, Mass.
- MILLER, HIRAM A., Mem.,
Engineer, Reservoir Department, Metropolitan Water Board,
Clinton, Mass.
- MILLER, WILLIAM L., Assoc. Mem.,
Contractor for Public Works, 17 Milk street, Boston, Mass.
- MILLS, CHARLES, Mem.,
Chief Engineer, Massachusetts Highway Commission,
20 Pemberton Square, Boston, Mass.
- MILLS, FRANK H., Mem.,
City Engineer, Woonsocket, R. I.
- MINER, FRANKLIN M., Mem.,
Engineering Department, Surveying Division,
27 Old Court House, Boston, Mass.

- MIRICK, GEORGE L., Mem.,
Contracting Engineer, 17 Pleasant street, Malden, Mass.
- MITCHELL, HENRY, Mem.,
Nantucket, Mass.
- MOORE, ARTHUR C., Mem.,
Civil Engineer, 100 Main street, Southbridge, Mass.
- MORRILL, GEORGE S., Mem.,
Division Engineer, N. Y., N. H. and H. R. R., Boston, Mass.
- MORRIS, FRANK H., Mem.,
Civil Engineer, 86 Hudson street, Somerville, Mass.
- MORRISON, HARRY J., Mem.,
Assistant Engineer, Metropolitan Water Board,
Box 13, West Boylston, Mass.
- MORRISON, JOHN W., Mem.,
Manager, Branch Office Hornblower & Weeks,
53 State street, Room 203, Boston, Mass.
- MORSE, CHARLES F., Mem.,
Assistant Engineer, Metropolitan Park Commission,
12 Russell street, Malden, Mass.
- MORSE, WILLIAM P., Mem.,
Assistant City Engineer of Newton,
City Hall, West Newton, Mass.
- MOSES, JOHN C., Mem.,
Chief Draftsman, Boston Bridge Works,
70 Kilby street, Boston, Mass.
- MOTTE, M. IRVING, Mem.,
Manager and Engineer, Boston office, Elektron Mfg. Co.,
143 Federal street, Boston, Mass.
- MOULTROP, IRVING E., Mem.,
Constructing Engineer, The Edison Electric Illuminating Co.,
3 Head Place, Boston, Mass.
- NASH, HENRY A., JR., Mem.,
Civil Engineer, Weymouth Heights, Mass.
- NELSON, GEORGE A., Mem.,
Assistant Engineer, City Engineer's Office,
City Hall, Lowell, Mass.
- NELSON, WILLIAM, Mem.,
Engineer for A. B. Black, Concord and N. E. Agent, Climax Road
Machine Co., Laconia, N. H.
- NICHOLS, ALFRED E., Mem.,
With Swain Turbine and Mfg. Co.,
142 Wilder street, Lowell, Mass.
- NICKERSON, ADDISON C.,
Engineer to Sewer Commissioners, Hyde Park, Mass.
- NOBLE, WALTER E., Mem.,
Assistant Engineer, Reservoir Commission,
City Hall, Fall River, Mass.
- NORRIS, WALTER H., Mem.,
Chief Engineer's Office, Boston and Maine Railroad,
Boston, Mass.
- NYE, GEORGE H., Mem.,
Civil Engineer, 323 Cottage street, New Bedford, Mass.

OBER, ARTHUR J., Mem.,

United States Inspector on River and Harbor Work,

Newport, R. I.

OLMSTED, JOHN C., Mem.,

Landscape Architect,

Brookline, Mass.

PALMER, ALFRED T., Mem.,

Civil Engineer,

60 Fairbanks street, Brighton, Mass.

PARKER, HAROLD, Mem.,

Parker & Bateman, Civil Engineers, Clinton.

Residence, South Lancaster, Mass.

PARKER, WILLIAM, Mem.,

Division Engineer, B. and A. R. R.,

372 South Station, Boston, Mass.

PARSONS, CHARLES S., Mem.,

Chief Clerk, Engineer Department,

50 City Hall, Boston, Mass

PATCH, WALTER W., Mem.,

Assistant Engineer, Metropolitan Water Works,

Eastern ave., South Framingham, Mass.

PEARSON, CHARLES A., Mem.,

Civil Engineer and Surveyor,

21 City Square, Charlestown, Mass.

PEARSON, FRED. S., Mem.,

Chief Engineer, Metropolitan Street Railway Co.,

Cable Bldg., 621 Broadway, New York, N. Y.

PECK, CHARLES H., Mem.,

344 Blackstone street, Providence, R. I.

PEIRCE, EUGENE E., Mem.,

Assistant Engineer with Massachusetts Topographical Survey
Commission,

138 State House, Boston, Mass.

PEIRCE, FRANK A., Mem.,

Civil Engineer,

Greensboro, N. C.

PERKINS, CLARENCE A., Mem.,

Engineer, N. E. Telegraph and Telephone Co.

Residence, 57 High street, Malden, Mass.

PERKINS, THEODORE P., Mem.,

Assistant Engineer, Chief Engineer's Office, Boston and Maine
Railroad,

Boston, Mass.

PETTEE, EUGENE E., Mem.,

Draftsman, with J. R. Worcester, C.E., Boston.

Residence, 269 Lowell ave., Newtonville, Mass.

PHILLIPS, HENRY A., Mem.,

Architect,

120 Tremont street, Room 503, Boston, Mass.

PIERCE, ARTHUR G., Mem.,

Superintendent of Stations, The Edison Electric Illuminating Co.,

3 Head Place, Boston, Mass.

PIERCE, HERBERT F., Mem.,

Pierce & Barnes, Civil Engineers,

7 Water street, Boston, Mass.

PIERCE, WILLIAM T., Mem.,

Engineer, Metropolitan Park Commission,

14 Beacon street, Boston, Mass.

PLIMPTON, ARTHUR L., Mem.,

Civil Engineer in charge of the Department of Civil Engineering of
the Bureau of Surface Lines, Boston Elevated Railway Co.,

101 Milk street, Boston, Mass.

- POLLEYS, WILLIAM V., Mem.,
Engineer's Office, N. Y., N. H. and H. R. R.,
467 South Station, Boston, Mass.
- POPE, LEMUEL, Mem.,
Insurance Inspector, 118 State street, Portsmouth, N. H.
- POPE, MACY S., Mem.,
Civil Engineer, 31 Milk street, Boston, Mass.
- PORTER, DWIGHT, Mem.,
Professor of Hydraulic Engineering, Massachusetts Institute of
Technology, Boston, Mass.
- PRATT, DANA M., Mem.,
Assistant with French & Bryant,
334 Washington street, Brookline, Mass.
- PRATT, DANIEL W., Mem.,
Assistant Engineer with E. W. Bowditch,
60 Devonshire street, Boston, Mass.
- PRATT, N. RAYMOND, Mem.,
Civil Engineer, Sudbury, Mass.
- PRATT, ROBERT W., JR., Mem.,
Assistant in Engineer's Office, Massachusetts, State Board of
Health, Residence, Waban, Mass.
- PUTNAM, CHARLES E., Mem.,
Assistant Engineer, Park Department,
Jamaica Park, Jamaica Plain, Mass.
- REYNOLDS, HENRY J., Mem.,
City Engineer's Office, Providence, R. I.
- RICE, GEORGE S., Mem.,
Deputy Chief Engineer, Rapid Transit Railroad Commission,
320 Broadway, New York, N. Y.
- RICE, JAMES, Mem.,
Inspector, Hartford Steam Boiler Inspection and Insurance Co.,
125 Milk street, Room 40, Boston, Mass.
- RICE, L. FREDERICK, Mem.,
Assistant Engineer, American Bell Telephone Co.,
125 Milk street, Boston, Mass.
- RICE, OTIS D., Mem.,
Civil Engineer, Hancock House, Quincy, Mass.
- RICH, ISAAC, Mem.,
Assistant Engineer, N. Y., N. H. and H. R. R., Boston.
Residence, 36 Walnut street, Somerville, Mass.
- RICHARDS, ROBERT H., Mem.,
Professor Mining Engineering and Metallurgy, Massachusetts
Institute of Technology, Boston, Mass.
- RICHARDS, WALTER H., Mem.,
Engineer of Water and Sewer Departments, New London, Conn.
- RICHARDSON, THOMAS F., Mem.,
Engineer, Dam and Aqueduct Department, Metropolitan Water
Board, Clinton, Mass.
- ROLLINS, JAMES W., JR., Mem.,
Of Holbrook, Cabot & Daly, Contractors, 1007 Tremont Bldg.,
Boston. Residence, West Roxbury, Mass.

- ROBBINS, ARTHUR G., Mem.,
Assistant Professor of Highway Engineering, Massachusetts Institute of Technology, Boston, Mass.
- ROBBINS, FRANKLIN H., Mem.,
With Metropolitan Water Board, 1 Ashburton Place, Boston.
Residence, 13 Waterhouse street, Cambridge, Mass.
- ROSS, EDWARD L., Mem.,
Mechanical Engineer, Indian Orchard, Mass.
- ROSS, ELMER W., Mem.,
Assistant Engineer, Bridge Department, City Engineer's Office, Providence, R. I.
- ROWELL, FRANK B., Mem.,
Assistant Engineer, Boston and Maine Railroad,
14 Linwood Road, Lynn, Mass.
- SABINE, EDWARD D., Mem.,
Engineer, Boston Pneumatic Transit Co.,
89 State street, Boston, Mass.
- SAFFORD, ARTHUR T., Mem.,
Assistant Engineer, Props., The Locks and Canals on Merrimack River, 66 Broadway, Lowell, Mass.
- SAMPSON, GEORGE T., Mem.,
Division Engineer, N. Y., N. H. and H. R. R.,
South Union Station, Boston, Mass.
- SANBORN, FRANK B., Mem.,
Assistant Professor of Civil Engineering, Tufts College.
Residence, 17 Sacramento street, Cambridge, Mass.
- SANDO, WILL J., Mem.,
Manager, International Steam Pump Co., Brooklyn, N. Y.
- SARGENT, ALFRED F., Mem.,
Civil Engineer and Notary Public, 425 Main street, Malden, Mass.
- SAVILLE, CALEB MILLS, Mem.,
Assistant Engineer, Metropolitan Water Board,
1 Ashburton Place, Boston, Mass.
- SAVILLE, GEORGE G., Mem.,
178 Devonshire street, Boston, Mass.
- SAWYER, EDWARD, Mem.,
Civil Engineer, 60 Congress street, Boston, Mass.
- SAWYER, WALTER H., Mem.,
Civil Engineer, 60 Congress street, Boston, Mass.
- SCHWAMB, PETER, Mem.,
Professor of Mechanism, Massachusetts Institute of Technology, Boston, Mass.
- SEDGWICK, WILLIAM T., Mem.,
Professor of Biology, Massachusetts Institute of Technology, Boston, Mass.
- SELLEW, EDGAR P., Mem.,
Assistant Surveyor in Street Laying-Out Department,
23 Old Court House, Boston, Mass.
- SEMPLE, WILLIAM J. C., Mem.,
Street Laying-Out Department, Surveying Division,
23 Old Court House, Boston, Mass.
- SERVIS, GEORGE O. W., Mem.,
Assistant in City Engineer's Office, City Hall, Somerville, Mass.

- SHAW, EDWARD S., Mem.,
Bridge and Consulting Engineer, 12 Pearl street, Boston, Mass.
- SHEDD, EDWARD W., Mem.,
Civil Engineer, 146 Westminster street, Providence, R. I.
- SHEDD, GEORGE G., Mem.,
With Metropolitan Water Board, 75 Walnut street, Clinton, Mass.
- SHEDD, J. HERBERT, Mem.,
Consulting Engineer, Providence, R. I.
- SHEPARD, WALTER, Mem.,
Chief Engineer, B. and A. R. R., Boston.
Residence, 79 Bloomfield street, Dorchester, Mass.
- SHERMAN, CHARLES W., Mem.,
Assistant Engineer, Sudbury Department, Metropolitan Water
Works, 1 Ashburton Place, Boston, Mass.
- SHERRY, FRANK E., Mem.,
Hyde & Sherry, Civil Engineers and Surveyors,
15 Court Square, Boston, Mass.
- SHIRREFFS, REUBEN, Mem.,
Chief Engineer, Va. Electric Railway and Development Co.,
Richmond, Va.
- SKINNER, FENWICK F., Mem.,
Draftsman, Pencoyd Iron Works,
113 Rochelle ave., Philadelphia, Pa.
- SLEEPER, GEORGE E., Mem.,
Civil Engineer, P. O. Box 3108, Boston, Mass.
- SMILIE, EDWARD S., Mem.,
Civil Engineer and Surveyor, Newton, Mass.
- SMITH, CHESTER W., Mem.,
Assistant Engineer with Metropolitan Water Board,
373 Chestnut street, Clinton, Mass.
- SMITH, MELVIN B., Mem.,
Civil Engineer and Surveyor, 26 Hildreth Bldg., Lowell, Mass.
- SMITH, SIDNEY, Mem.,
Civil Engineer, 91 Maple street, West Roxbury, Mass.
- SNOW, F. HERBERT, Mem.,
Snow & Barbour, Civil and Sanitary Engineers,
1120 Tremont Bldg., Boston, Mass.
- SNOW, FRANKLIN A., Mem.,
Civil Engineer and Contractor, Brookline, Mass.
- SNOW, J. PARKER, Mem.,
Bridge Engineer, Boston and Maine Railroad,
Boston, Mass.
- SONDERICKER, JEROME, Mem.,
Associate Professor of Applied Mechanics, Massachusetts Institute
of Technology, Boston, Mass.
- SONNE, OTTO, Mem.,
Civil Engineer,
68 Devonshire street (P. O. Box 3051), Boston, Mass.
- SOPER, GEORGE A., Mem.,
Engineer and Chemist, 20 Broadway, New York, N. Y.
- SPALDING, FREDERIC P., Mem.,
Assistant Engineer, Engineering Department,
60 City Hall, Boston, Mass.

- SPEAR, WALTER E., Mem.,
Civil Engineer, 814 Banigan Bldg., Providence, R. I.
- SPOFFORD, NELSON, Mem.,
Civil Engineer and Surveyor for Massachusetts on her Northern
Boundary, 14 Water street, Haverhill, Mass.
- STANFORD, HOMER R., Mem.,
Civil Engineer, United States Navy,
Naval Training Station, San Francisco, Cal.
- STARK, WILLIAM E., Mem.,
Instructor of Physics, Rindge Manual Training School,
26 Whittier street, Cambridge, Mass.
- STEARNS, EDWARD B., Mem.,
Contracting Engineer, American Bridge Co.,
Chamber of Commerce Bldg., Cleveland, Ohio.
- STEARNS, FREDERIC P., Mem.,
Chief Engineer, Metropolitan Water Board,
1 Ashburton Place, Boston, Mass.
- STEPHENSON, FRANK H., Mem.,
With Metropolitan Water Board, 1 Ashburton Place, Boston.
Residence, 51 Aldrich street, Jamaica Plain, Mass.
- STEVENS, HAROLD C., Mem.,
Office Assistant, Engineering Department, Metropolitan Water
Board, 1 Ashburton Place, Boston.
Residence, Braintree, Mass.
- STEVENS, WALTER C., Mem.,
Civil Engineer, 541 Main street, Melrose, Mass.
- STODDARD, GEORGE C., Mem.,
Civil and Sanitary Engineer,
215 West 125th street, New York, N. Y.
- STOZY, ISAAC M., Mem.,
Engineer, N. Y., N. H. and H. R. R.,
21 Linden ave., Somerville, Mass.
- STRATTON, GEORGE E., Mem.,
Draftsman, United States Engineers' Office.
Residence, 145 West Newton street, Boston, Mass.
- STREET, LEONARD L., Mem.,
With Boston Transit Commission,
121 Stoughton street, Dorchester, Mass.
- SWAIN, GEORGE F., Mem.,
Professor of Civil Engineering, Massachusetts Institute of Tech-
nology, and Engineer, Massachusetts Railroad Commissioners,
Boston, Mass.
- SWEET, KILBURN S., Mem.,
Instructor in Civil Engineering, Massachusetts Institute of Tech-
nology, Boston, Mass.
- SYMONDS, HENRY A., Mem.,
Assistant Engineer with Taylor & Tyler, Box 98, Belmont Mass.
- TABER, JAMES C. S., Mem.,
Civil Engineer, 31 Milk street, Room 315, Boston, Mass.
- TAYLOR, EDWIN A., Mem.,
Civil Engineer with L. A. Taylor, C.E.,
10 Dean street, Worcester, Mass.
- TAYLOR, GORDON H., Mem.,
Civil Engineer, 1110 Tremont Bldg., Boston, Mass.

- TAYLOR, LUCIAN A., Mem.,
Civil Engineer and Contractor, 719 Tremont Bldg., Boston, Mass.
- TEMPERLEY, CHARLES, Mem.,
Assistant in City Engineer's Office,
7 High street, Medford, Mass.
- THOMPSON, SANFORD E., Mem.,
Civil Engineer,
Newton Highlands, Mass.
- THORNDIKE, STURGIS H., Mem.,
Assistant Engineer, Engineering Department,
60 City Hall, Boston, Mass.
- TIGHE, JAMES L., Mem.,
City Engineer,
Holyoke, Mass.
- TILDEN, JAMES A., Mem.,
General Manager, Hersey Mfg. Co.,
South Boston, Mass.
- TINGLEY, RICHARD H., Mem.,
Civil Engineer,
75 Westminster street, Providence, R. I.
- TINKHAM, S. EVERETT, Mem.,
Assistant Engineer, Engineering Department,
60 City Hall, Boston, Mass.
- TOMLINSON, ALFRED T., Mem.,
Consulting and Division Engineer, Boston Elevated Railway Co.,
4 Westminster ave., Roxbury, Mass.
- TITUS, JOHN E.,
Coolidge & Titus, Landscape Architects,
53 State street, Room 720, Boston, Mass.
- TREADWELL, EDWARD D., Mem.,
Surveyor, Engineering Department, Malden,
124 Linden ave., Malden, Mass.
- TRIPP, OSCAR H., Mem.,
Civil Engineer,
Rockland, Me.
- TUCKER, FRANCIS C., Mem.,
City Engineer,
Deadwood, S. D.
- TUCKER, LESTER W., Mem.,
Assistant Engineer, Boston and Maine Railroad,
Boston, Mass.
- TURNER, DANIEL L., Mem.,
Instructor in Topographical Engineering, Lawrence Scientific
School,
Cambridge, Mass.
- TURNER, EDMUND K., Mem.,
Civil Engineer,
442 Exchange Bldg., Boston, Mass.
- VARNEY, HENRY A., Mem.,
Assistant Engineer,
Room 2, Town Hall, Brookline, Mass.
- VAUGHAN, LOUIS B., Mem.,
Assistant Engineer, Boston Elevated Railway Co.
Residence, 100 Pembroke street, Boston, Mass.
- VICKERY, GILBERT S., Mem.,
With Pennsylvania Steel Co., 1222 Market street, Harrisburg, Pa.
- VOSE, GEORGE L., Hon. Mem.,
Civil Engineer,
Paris, Me.
- WAITT, CHARLES G., Mem.,
Civil Engineer,
Waitt's Block, Malden, Mass.
- WALES, FREDERICK N., Mem.,
Clerk of Board of Harbor and Land Commissioners,
131 State House, Boston, Mass.

- WALKER, ELTON D., Mem.,
Assistant Professor of Civil Engineering, Pennsylvania State Col-
lege, State College, Pa.
- WALLACE, CHESTER J., Mem.,
Assistant Engineer, Metropolitan Water Board,
1 Ashburton Place, Boston, Mass.
- WALLACE, JOSEPH H., Mem.,
Tower & Wallace, Mill Architects and Hydraulic Engineers,
309 Broadway, New York, N. Y.
- WALWORTH, ARTHUR C., Mem.,
President, Walworth Construction and Supply Co.,
100 Pearl street, Boston, Mass.
- WARREN, GEORGE M., Mem.,
With L. E. Hawes, C.E., 751 Tremont Bldg., Boston, Mass.
- WASON, LEONARD C., Mem.,
President, Aberthaw Construction Co., 7 Exchange Place, Boston.
Residence, 199 Harvard street, Brookline, Mass.
- WATERMAN, FRANK E., Mem.,
Civil Engineer, 86 Weybosset street, Providence, R. I.
- WATSON, WILLIAM, Mem.,
Secretary, American Academy of Arts and Sciences,
107 Marlborough street, Boston, Mass.
- WEBB, DEWITT C. Mem.,
Civil Engineer, 53 State street, Room 542, Boston, Mass.
- WEBBER, WILLIAM O., Mem.,
Consulting Engineer, Room 432, 53 State street, Boston, Mass.
- WEBBER, WINSLOW L., Mem.,
City Engineer, City Hall, Gloucester Mass.
- WELLINGTON, ARTHUR J., Assoc. Mem.,
Manager, Gates Iron Works, and Atlantic Dynamite Co.,
237 Franklin street, Boston, Mass.
- WELLS, CHARLES E., Mem.,
Division Engineer, Metropolitan Water Board,
55 Prescott street, Clinton, Mass.
- WESCOTT, FRANK T., Mem.,
Superintendent of Streets, North Attleborough, Mass.
- WESTON, EDMUND B., Mem.,
Consulting Engineer, 86 Weybosset street, Providence, R. I.
- WETHERBEE, GEORGE A., Mem.,
City Engineer, City Hall, Malden, Mass.
- WHEELER, BERTRAND T., Mem.,
Superintendent of Streets, 47 City Hall, Boston, Mass.
- WHEELER, WILLIAM, Mem.,
Civil and Hydraulic Engineer, 14 Beacon street, Boston, Mass.
- WHITE, HARTLEY L., Mem.,
White & Wetherbee, Civil Engineers, offices in Braintree, Brock-
ton and at 170 Summer street, Boston.
- WHITING, RUSSELL H., Mem.,
Assistant with French & Bryant,
334 Washington street, Brookline, Mass.
- WHITNEY, FRANK O., Mem.,
Chief of Surveying Division, Street Laying-Out and Engineering
Departments, 25 Old Court House, Boston, Mass.

- WHITNEY, GEORGE E., Mem.,
With Boston Gas Light Co., 24 West street, Boston, Mass.
- WHITNEY, ORVILLE J., Mem.,
With Boston Electric Ry. Co., 32 Franklin street, Medford, Mass.
- WHITTEN, ERNEST P., Mem.,
Civil Engineer with Aspenwall & Lincoln,
49 Irving street, West Roxbury, Mass.
- WHITTIER, CHARLES C., Mem.,
Civil Engineer, 20 Berkeley street, Malden, Mass.
- WIGGIN, ERNEST W., Mem.,
With Bridge Department, N. Y., N. H. and H. R. R.,
New Haven, Conn.
- WIGGIN, THOMAS H., Mem.,
With Metropolitan Water Board, 1 Ashburton Place, Boston,
154 Mountain ave., Malden, Mass.
- WILKES, CHARLES M., Mem.,
Sanitary Engineer, 1142 The Rookery, Chicago, Ill.
- WILLIAMS, WILLIAM F., Mem.,
City Engineer, 2 Court street, New Bedford, Mass.
- WILSON, HERBERT A., Mem.,
Engineering Department, 60 City Hall, Boston, Mass.
- WINSLOW, FREDERIC L., Mem.,
Assistant Engineer, Engineering Department,
49 City Hall, Boston, Mass.
- WINSOR, FRANK E., Mem.,
With Metropolitan Water Board,
82 Union ave., South Framingham, Mass.
- WOOD, GEORGE W., Mem.,
Agent, Best Manufacturing Co., 31 Milk street, Boston, Mass.
- WOOD, HENRY B., Mem.,
Chief Engineer, Topographical Survey Commission,
138 State House, Boston, Mass.
- WOOD, IRVING S., Mem.,
Assistant Engineer in charge of Water Department,
City Engineer's Office, Providence, R. I.
- WOODFALL, J. L., Mem.,
Civil and Sanitary Engineer, 15 Court Square, Boston, Mass.
- WOODS, HENRY D., Mem.,
Civil Engineer, 99 Highland street, West Newton, Mass.
- WOODWARD, M. GRANT, Mem.,
Assistant Engineer, Cambridge Bridge,
374 Cambridge street, Boston, Mass.
- WORCESTER, JOSEPH R., Mem.,
Civil Engineer, 53 State street, Boston, Mass.
- WYMAN, ALFRED M., Mem.,
Civil Engineer, 836 Main street, Waltham, Mass.
- YOUNG, E. ELBERT, Mem.,
Civil Engineer, Auburndale, Mass.

Civil Engineers' Club of Cleveland.

- ALLEN, GEORGE I., B.S., Act. Mem.,
 Mechanical Engineer, Cleveland City Forge and Iron Co.,
 84 Kennard street, Cleveland.
- ALLEN, LUTHER, Assoc. Mem.,
 President Adams Bag Co., 1695 Euclid ave., Cleveland.
- ALLEN, WALTER MORRISON, Act. Mem.,
 Superintendent for Warner & Swasey, 40 Spangler ave., Cleveland.
- ANDREWS, HORACE E., Ph.B., Act. Mem.,
 Director, The Cleveland Electric Railway Co.,
 The Cuyahoga, Cleveland.
- BAACKES, MICHAEL, Act. Mem.,
 Vice-President Baackes Wire Nail Co.,
 712 Willson ave., Cleveland.
- BALKWILL, STEPHEN, JR., Assoc. Mem.,
 Foreman, The Cleveland Frog and Crossing Co.,
 8 Van Ness ave., Cleveland.
- BARBER, CLARENCE M., C.E., Act. Mem.,
 Constructing Engineer, Semet-Solvay Co., Detroit, Mich.
- BARDONS, GEORGE C., Act. Mem.,
 Of Bardons & Oliver, Tool Manufacturers,
 Case ave. and Hamilton street, Cleveland.
- BARNETT, JAMES, Act. Mem.,
 President First National Bank, President The Geo. Worthing-
 ton Co., 697 Euclid ave., Cleveland.
- BARNUM, FRANK S., Act. Mem.,
 Architect, New England Bldg., Cleveland.
- BARREN, HENRY A., M.E., Act. Mem.,
 Master Mechanic, American Steel and Wire Co.,
 201 Miles ave., Cleveland.
- BARTOL, GEORGE, S.B., Act. Mem.,
 General Manager The Otis Steel Co., Ltd., Cleveland.
- BEARDSLEY, JOSEPH C., Act. Mem.,
 Second Assistant Engineer, Water Works Division, Department
 of Public Works, 354 Superior street, Cleveland.
- BENJAMIN, CHARLES H., M.E., Act. Mem.,
 Professor of Mechanical Engineering, Case School of Applied
 Science, 89 Adelbert street, Cleveland.
- BEVER, JOHN J., Act. Mem.,
 Superintendent Foundry, The Otis Steel Co., Ltd.,
 97 Scott street, Cleveland.
- BIDLE, WILLIAM S., B.S., M.E., Act. Mem.,
 Mechanical Engineer, Manager Turnbuckle Depa. tment, Cleveland
 City Forge and Iron Co., 955 Detroit street, Cleveland.
- BIDWELL, JASON A., Act. Mem.,
 Superintendent Union Steel Screw Co.,
 139 Kensington street, Cleveland.
- BISHOP, ALBERT C., Assoc. Mem.,
 Chief Engineer, The Independent Ice Co.,
 193 Sawtell ave., Cleveland.

- BISSELL, FRANK E., Act. Mem.,
Assistant Engineer, Lake Shore and Michigan Southern Railroad,
Ashtabula, Ohio.
- BLACKWELL, CHARLES, Act. Mem.,
Assistant Engineer, Wheeling and Lake Erie Railroad,
40 Oak Park street, Cleveland.
- BLUNT, WILLIAM T., Cor. Mem.,
U. S. Assistant Engineer, U. S. Eng. Office, Toledo, Ohio.
- BOALT, EUGENE E., C.E., Act. Mem.,
Civil Engineer, 45 Outhwaite ave., Cleveland.
- BOGARDUS, WILLIAM B., Act. Mem.,
Engineer, with The Osborn Co., 509 Osborn Bldg., Cleveland.
- BONE, W. H., Cor. Mem.,
General Manager The Ironsides Co., Columbus, Ohio.
- BOWLER, GEORGE H., Assoc. Mem.,
Machinery Dealer, partner Reade & Bowler,
513 Williamson Bldg., Cleveland.
- BOWLER, NOADIAH P., Act. Mem.,
Foundryman, firm of Bowler & Co., 14 Winter street, Cleveland.
- BRIGHT, FRED. E., Assoc. Mem.,
Superintendent of The Rogers Typograph Co.,
145 Cannon street, E. C., London, Eng.
- BROWN, ALEXANDER E., C.E., M.E., Act. Mem.,
Vice-President and General Manager The Brown Hoisting and
Conveying Machine Co., 1151 Prospect street, Cleveland.
- BROWN, FAYETTE, Act. Mem.,
President The Brown Hoisting and Conveying Machine Co.,
Chairman Stewart Iron Mfg. Co., Ltd., President The Na-
tional Chemical Co., Perry-Payne Bldg., Cleveland.
- BROWN, T. MORRIS, A.B., Act. Mem.,
Electrical Engineer, with The Brown Hoisting and Conveying Ma-
chine Co., 583 Sibley street, Cleveland.
- BROWN, WENDELL P., Act. Mem.,
Engineer, The King Bridge Co., 314 Hough ave., Cleveland.
- BURNS, WILLIAM H., Act. Mem.,
Firm of M. F. Bramley & Co., 97 Carroll street, Cleveland.
- CADWELL, CHARLES A., B.S., Act. Mem.,
Draftsman, Cleveland Electric Railway Co.,
1250 Curtiss ave., Cleveland.
- CARPENTER, ALLAN W., B.S., C. E., Cor. Mem.,
Assistant Engineer, New York Central and Hudson River Railroad,
502 Grand Central Station, New York city.
- CARTER, WILLIAM J., Act. Mem.,
Superintendent of Construction, Quartermaster's Department,
Ft. Preble, Portland, Me.
- CHAMBERLIN, FRANK H., Act. Mem.,
Proprietor and Manager Cleveland Facing Mill Co.,
49 Knox street, Cleveland.
- CHAPIN, LOOMIS E., C.E., Act. Mem.,
City Civil Engineer, Canton, Ohio.
- CHISHOLM, WILLIAM, Act. Mem.,
Former President Cleveland Rolling Mill Co.,
779 Euclid ave., Cleveland.

- CHISHOLM, WILLIAM, SR., Act. Mem.,
General Manager Chisholm Steel Shovel Works,
364 Case ave., Cleveland.
- CLARK, WILLIAM C., Act. Mem.,
Mechanical Engineer, 112 Twenty-third ave., Cleveland.
- COBB, PHILIP L., C.E., Act. Mem.,
Civil Engineer, 2509 Euclid ave., Cleveland.
- COFFIN, JOHN N., Act. Mem.,
Mechanical Engineer, 312 Perry-Payne Bldg., Cleveland.
- COMSTOCK, CHARLES W., Act. Mem.,
Purchasing Agent, Wellman-Seaver Eng. Co.,
1405 New England Bldg., Cleveland.
- COOKE, EDWARD C., C.E., Act. Mem.,
Civil Engineer, 44 Hough Place, Cleveland.
- CORLETT, JOHN F., Assoc. Mem.,
Iron and Steel Commission, 409 Perry-Payne Bldg., Cleveland.
- COVERT, JOHN STERLING, Act. Mem.,
Draftsman, The King Bridge Co., 3 Isham Court, Cleveland.
- COWLES, WALTER L., C.E., Ph.B., Act. Mem.,
Bridge and Structural Engineer, The Brown Hoisting and Con-
veying Machine Co., Cleveland.
- COWLES, WILLIAM B., Act. Mem.,
W. B. Cowles & Co., Lake and Wason streets, Cleveland.
- COX, JACOB DOLSON, JR., Act. Mem.,
Proprietor of Cleveland Twist Drill Co.,
Lake and Kirtland streets, Cleveland.
- CROMWELL, JOHN C., Act. Mem.,
Mechanical Engineer, Garrett-Cromwell Engineering Co.,
589 Case ave., Cleveland.
- CULLEY, GEORGE, Act. Mem.,
Civil Engineer, 4 Redell street, Cleveland.
- CULLEY, JOHN L., C.E., Act. Mem.,
Civil and Landscape Engineer, 33 Blackstone Bldg., Cleveland.
- DAILEY, CHARLES I., Act. Mem.,
Master Mechanic, American Steel and Wire Co., Lake Shore Dis-
trict, 281 Hough ave., Cleveland.
- DAVIS, CHARLES H., C.E., Act. Mem.,
Consulting Engineer, 99 Cedar street, New York city.
- DE FOREST, ALBERT T., Act. Mem.,
Manager American Steel and Wire Co.,
2677 Euclid ave., Cleveland.
- DE LA MATER, STEPHEN T., Act. Mem.,
With The Osborn Co., Civil Engineers,
509 Osborn Bldg., Cleveland.
- DERCUM, OTTO, Act. Mem.,
Civil Engineer, 38 City Hall, Cleveland.
- DODD, SAMUEL T., E.E., Cor. Mem.,
Electrical Engineer, Link Belt Machinery Co.,
Thirty-ninth street and Stewart ave., Chicago, Ill.
- DUNHAM, H. F., Act. Mem.,
Civil Engineer, 2 Wall street, New York city.

- DUTTON, CHAS. F., Act. Mem.,
Science Instructor, West High School,
349 Franklin ave., Cleveland.
- DYER, HAROLD P., Act. Mem.,
Constructing Engineer for E. H. Dyer & Co., builders of Sugar
Machinery, 705 New England Bldg., Cleveland.
- ESTEP, JOSIAH M., Act. Mem.,
Assistant Engineer, Department Public Works,
51 Bell ave., Cleveland.
- EVERS, WILLIAM H., Act. Mem.,
County Surveyor, Cuyahoga county, 70 Jersey street, Cleveland.
- FAIRFIELD, HOWARD P., Act. Mem.,
Head Instructor in Machine Practice, Worcester Polytechnic In-
stitute, Worcester, Mass.
- FALDING, FREDERICK J., Cor. Mem.,
Consulting Chemical Engineer, 45 Broadway, New York city.
- FARAGHER, BURTON P., Act. Mem.,
Engineer, Water Works Department,
63 Hampden street, Cleveland.
- FOOTE, ANDREW W.,
Machine Tool Manufacturer, 555 Sibley street, Cleveland.
- FORCE, CYRUS G., JR., Cor. Mem.,
Consulting Engineer, Succassunna, Morris Co., N. J.
- FULLER, HARRY, Act. Mem.,
Engineer, The King Bridge Co., 21 Gale ave., Cleveland.
- GALVIN, ARCHIE J., Act. Mem.,
Engineer, Intercepting Sewer Department,
849 Lorain street, Cleveland.
- GARRETT, WILLIAM, Act. Mem.,
Manager Garrett-Cromwell Engineering Co.,
46 Dorchester ave., Cleveland.
- GIBBS, HARLEY B., Act. Mem.,
Treasurer The King Bridge Co., Cleveland.
- GOBEILLE, JOSEPH LEON, Act. Mem.,
President The Gobeille Pattern Co.,
Leonard and Winter streets, Cleveland.
- GOFFING, CHARLES, Act. Mem.,
Mechanical Engineer, Water Works Department,
City Hall, Cleveland.
- GREEN, BERNARD L., Act. Mem.,
Civil Engineer, Member of The Osborn Co.,
509 Osborn Bldg., Cleveland.
- GREENE, STANLEY R., Act. Mem.,
Civil Engineer, Mechanic with The Brown Hoisting and Conveying
Machine Co., 743 Willson ave., Cleveland.
- HANDY, EDWARD A., B.S., Act. Mem.,
Chief Engineer, Lake Shore and Michigan Southern Railway,
L. S. and M. S. Railway Bldg., Cleveland.
- HANLON, WILLIAM B., Act. Mem.,
Chief Engineer, Cleveland, Lorain and Wheeling Railroad Co.,
Mining Engineer for Coal Companies,
825 Hickox Bldg., Cleveland.

- HARMAN, RALPH A., Ph.B., Act. Mem.,
 Manufacturer of Forgings, with Cleveland City Forge and Iron
 Co., Cleveland.
- HARRINGTON, FERDINAND F., Act. Mem.,
 Civil Engineer, 509 Osborn Bldg., Cleveland.
- HART, EMMETT E., Act. Mem.,
 Chief Engineer, New York, Chicago and St. Louis Railroad,
 98 Burt street, Cleveland.
- HATCH, JAMES N., Act. Mem.,
 Superintendent Construction, United States Public Buildings,
 Streator, Ill.
- HAUPT, CHAS. H., Act. Mem.,
 Civil Engineer, 73 Edgewood Place, Cleveland.
- HENDERER, WILLIAM O., Act. Mem.,
 Member of The Osborn Co., Civil Engineers,
 509 Osborn Bldg., Cleveland.
- HERMAN, LUDWIG, M.E., Act. Mem.,
 Master Mechanic, The Mechanical Rubber Co.,
 120 Second ave., Cleveland.
- HILL, HAROLD H., Act., Mem.,
 Agent, Erie City Iron Works, 786 Genesee ave., Cleveland.
- HOBBS, PERRY L., B.S., Ph.D., Act. Mem.,
 Professor of Chemistry, Western Reserve Medical College,
 Cleveland.
- HOFFMAN, ROBERT, Act. Mem.,
 Assistant Engineer, City Civil Engineer's Office, City Hall,
 55 Osborn street, Cleveland.
- HOIT, LEHMAN B., Act. Mem.,
 Hydraulic Engineer, Ohio Sales Manager, Henry R. Worthington,
 582 E. Prospect street, Cleveland.
- HONSBERG, AUGUST A., Act. Mem.,
 Draftsman, Department Public Works,
 309 City Hall, Cleveland.
- HOPKINSON, CHARLES W., B.S., Act. Mem.,
 Architect, 50 Euclid ave., Cleveland.
- HORNER, EDWARD, Act. Mem.,
 Draftsman, City Civil Engineer, 43 Lena ave., Cleveland.
- HOWE, CHARLES S., Ph.D., Act. Mem.,
 Professor of Mathematics and Astronomy, Case School of Ap-
 plied Science, Cleveland.
- HYDE, A. LINCOLN, Ph.B., C.E., Act. Mem.,
 Engineer, American Bridge Co. 100 Broadway, New York city.
- HYND, ALEXANDER, Act. Mem.,
 Mechanical Engineer, Great Lakes Register,
 94 Courtland street, Cleveland.
- JACKSON, ERNEST S., Act. Mem.,
 County Engineer, Lorain Co., Elyria, Ohio.
- JOHNSTON, ALBERT W., Act. Mem.,
 General Superintendent New York, Chicago and St. Louis Rail-
 road, 424 Hickox Bldg., Cleveland.
- JOHNSTON, ARTHUR C., B.A.Sc., Act. Mem.,
 Mechanical Engineer, Lorain Steel Co., Lorain, Ohio.

- JONES, HARRY ROSS, Assoc. Mem.,
With The Osborn Co., Civil Engineers,
517 Sibley street, Cleveland.
- JONES, WYNDHAM C., Act. Mem.,
Chief Engineer Cleveland and Eastern Railroad, President Stand-
ard Contracting Co., President W. A. McGillis Dredging Co.,
57 Wade Bldg., Cleveland.
- JUDSON, C. A., Cor. Mem.,
Erie County Safe Deposit and Abstract Co.,
232 Columbus ave., Sandusky, Ohio.
- KING, JAMES A., Act. Mem.,
President The King Bridge Co., 1325 Euclid ave., Cleveland.
- KINGSLEY, MARVIN W., C.E., Act. Mem.,
Superintendent Water Works, 354 Superior street, Cleveland.
- KOHLMETZ, GEO. W., Assoc. Mem.,
Internationál Range and Mfg. Co., Ashtabula, Ohio.
- LANDER, FRANK R., B.S., Act. Mem.,
County Draftsman, 321 Marcy ave., Cleveland.
- LANE, EDWIN G., Act. Mem.,
Engineer, Cleveland Terminal and Valley Railroad,
B. and O. Passenger Station, Cleveland.
- LANGLEY, JOHN W., B.S., Ph.D., Act. Mem.,
Professor Electrical Engineering, Case School of Applied Science,
Cleveland.
- LARNED, JOSHUA B., C.E., Act. Mem.,
Civil Engineer. The King Bridge Co., 13 Isham Court, Cleveland.
- LEEPER, JOHN B., C.E., Cor. Mem.,
Engineer, with Keystone Bridge Works, Pittsburg, Pa.
- LE PONTOIS, LEON J., B.S., Act. Mem.,
Electrical Engineer, Winton Automobile Co., Cleveland.
- LEWIS, CHARLES F., Act. Mem.,
Civil and Consulting Engineer, 307 Cuyahoga Bldg., Cleveland.
- LEWIS, RANSOME T., Cor. Mem.,
Civil Engineer, 119 Caldwell ave., Elmira, N. Y.
- LINDENTHAL, GUSTAV, C.E., Char. Mem.,
Chief Engineer, North River Bridge Co.,
45 Cedar street, New York city.
- LINE, FRANCIS, Assoc. Mem.,
Manager for The Keasbey & Mattison Co., Magnesía Coverings,
117 Water street, Cleveland.
- LUCAS, GEORGE C., Act. Mem.,
General Manager of The Cleveland Frog and Crossing Co.,
Bessemer ave. and Erie Railroad, Cleveland.
- LUCAS, HENRY MARTIN, Act. Mem.,
Lucas Machine Tool Co., 274 Perkins ave., Cleveland.
- MCGEORGE, JOHN, Act. Mem.,
Engineer, Wellman-Seaver Engineering Co.,
1404 New England Bldg., Cleveland.
- MCINTYRE, JAMES, Act. Mem.,
Master Carpenter, Mahoning Division, Erie Railroad,
136 Sawtell ave., Cleveland.

- McLOUTH, LEWIS C., B.S., Act. Mem.,
Principal, Central Manual Training School,
Cedar ave., near Willson, Cleveland.
- McMURRAY, MAX., Act. Mem.,
General Superintendent Newburg Steel Works, American Steel
and Wire Co., 1424 Euclid ave., Cleveland.
- MARANI, VIRGIL G. F., Act. Mem.,
Civil Engineer, Assistant Engineer, Cleveland Gas Light and Coke
Co., 145 Cornet street, Cleveland.
- MARBLE, HENRY D., Assoc. Mem.,
Secretary and Treasurer The Hutson Coal Co., Blackstone Bldg.,
405 Bolton ave., Cleveland.
- MARTENS, HENRY E., Act. Mem.,
Engineer, The Osborn Co., 19 Earle ave., Glenville, Ohio.
- METCALF, FREDERICK, Act. Mem.,
Treasurer, Chase Machine Co., 111 Elm street, Cleveland.
- MICHELSON, ALBERT A., Ph.D., Hon. Mem.,
Head Professor of Physics, University of Chicago, Chicago.
- MILLER, DAYTON C., Ph.B., A.M., D.Sc., Act. Mem.,
Professor of Physics, Case School of Applied Science, Cleveland.
- MILLER, WALTER, Act. Mem.,
Consulting Engineer, 407 Perry-Payne Bldg., Cleveland.
- MILLS, EDWIN S., Assoc. Mem.,
Sales Agent, The Carnegie Steel Co., Ltd.,
702 Perry-Payne Bldg., Cleveland.
- MITCHELL, ALBERT E., M.E., Char. Mem.,
Superintendent Motive Power Erie Railroad and lines operated,
21 Cortland street, New York city.
Residence, 90 High street, Passaic, N. J.
- MOORE, WALTER S., Act. Mem.,
Engineer, Maintenance of Way, Cleveland and Indianapolis divi-
sion, Big Four Railway, 859 Stark street, Cleveland.
- MORDECAI, AUGUSTUS, C.E., Act. Mem.,
Assistant Chief Engineer, Erie Railroad,
830 Garfield Bldg., Cleveland.
- MORLEY, EDWARD W., Ph.D., LL.D., Hon. Mem.,
Professor of Chemistry, Adelbert College, Cleveland.
- MORSE, BENJAMIN F., C.E., Act. Mem.,
Civil Engineer and Architect, 36 Cheshire street, Cleveland.
- NAYLOR, ERNEST W., Cor. Mem.,
Hydraulic and Consulting Engineer,
Fiftieth street and Lancaster ave., Philadelphia, Pa.
- NEFF, FRANK H., B.S., C.E., Act. Mem.,
Professor of Civil Engineering, Case School of Applied Science,
860 Doan street, Cleveland.
- NELSON, HARRY S., Act. Mem.,
Architect, with Barnum & Co., New England Bldg., Cleveland.
- NEWHALL, WALTER S., Act. Mem.,
Chief Engineer, Wheeling and Lake Erie Railroad,
277 Perkins ave., Cleveland.
- NEY, ROBERT W., Act. Mem.,
Assistant Manager American Steel and Wire Co.,
143 Crawford road, Cleveland.

- OLDHAM, JOSEPH R., Act. Mem.,
Naval Architect and Marine Engineer,
814 Perry-Payne Bldg., Cleveland.
- OLIVER, JOHN G., Act. Mem.,
Partner, Bardons & Oliver,
Corner Case ave. and Hamilton street, Cleveland
- OLMSTEAD, H. L., Act. Mem.,
With The Osborn Co., 50 Mayfield road, Cleveland
- ORR, CHARLES, Assoc. Mem.,
Librarian Case Library, Cleveland.
- OSBORN, FRANK C., C.E., Act. Mem.,
Of The Osborn Co., Civil Engineers,
503-509 O-John Bldg., Cleveland
- OTIS, CHARLES A., JR., Assoc. Mem.,
Otis, Hough & Co., Iron and Steel,
407 Perry-Payne Bldg., Cleveland.
- OTIS, WILLIAM L., Assoc. Mem.,
Artistic Home Decorations, 255 Erie street, Cleveland.
- PAINE, CHARLES, Hon. Mem.,
Consulting Civil Engineer, 32 Park Place, New York city,
Tenafly, N. J.
- PALMER, CHARLES O., Act. Mem.,
Mechanical Engineer, 32 Cedar ave., Cleveland.
- PARMLEY, WALTER C., M.S., Act. Mem.,
Assistant Engineer, Department of Public Works,
19 Burt street, Cleveland.
- PAUL, HOSEA, Act. Mem.,
Civil Engineer, Cuyahoga Falls, Ohio.
- PETTERSON, A. HUGO, Cor. Mem.,
Engineer, Anaconda Copper Mining Co., Anaconda, Mont.
- PIERSON, ISAAC K., Act., Mem.,
Civil and Consulting Engineer. 416 Cuyahoga Bldg., Cleveland.
- PORTER, ALBERT H., A.M., C.E., Act. Mem.,
Civil Engineer, 403 Osborn Bldg., Cleveland.
- PRENTISS, FRANCIS F., Act. Mem.,
Manfr. Cleveland Twist Drill Co., 102 The Lennox, Cleveland.
- RAWSON, MARIUS E., Act. Mem.,
Civil Engineer, 762 Genesee ave., Cleveland.
- RAY, W. MORRISON, C.E., Act. Mem.,
Assistant Engineer, Cleveland, Lorain and Wheeling Railroad,
625 Denison ave., Cleveland.
- RAYNAL, ALFRED H., Act. Mem.,
Mechanical Engineer, 1626 Riggs Place, Washington, D. C.
- REED, WILLIAM E., Act. Mem.,
With Warner & Swasey,
The Croxden, 977 Prospect street, Cleveland.
- RICE, JOSEPH H., Cor. Mem.,
Transitman, Lake Shore and Michigan Southern Railroad,
Ashtabula, Ohio.
- RICE, WALTER P., C.E., Act. Mem.,
Director of Public Works, City Hall, Cleveland.

- RICHARDS, FRANCIS H., Cor. Mem.,
Mechanical Engineer and Expert in Patent Cases,
9-13 Murray street, New York city.
- RICHARDSON, JOHN N., Act. Mem.,
Architect, Bangor Bldg., 262 Prospect street, Cleveland.
- RIDER, GEORGE S., Act. Mem.,
Consulting Engineer, 604 Century Bldg., Cleveland.
- RITCHIE, JAMES, B.S., C.E., Act. Mem.,
Chief Engineer, Department of Public Works, Cleveland.
- RUST, LUCIAN, Act. Mem.,
Assistant Engineer, Lake Shore and Michigan Southern Railway,
Cleveland.
- ST. JOHN, EDWARD M., Act. Mem.,
Structural Engineer, 213 Fisk street, Pittsburg, Pa.
- SAUNDERS, GEO. C., Act. Mem.,
With The Osborn Co., Civil Engineers,
509 Osborn Bldg., Cleveland.
- SAWTELLE, EDMUND M., Cor. Mem.,
Electrical Engineer, with the Westinghouse Electric and Mfg. Co.,
Norfolk street, Strand, London, Eng.
- SCHMITT, JOHN G., Act. Mem.,
Superintendent of Streets, Cleveland Gas Light and Coke Co.,
356 Superior street, Cleveland.
- SCHULZ, CHARLES F., Act. Mem.,
First Assistant Engineer, Water Works Division, Department of
Public Works, 354 Superior street, Cleveland.
- SEARLES, WILLIAM H., C.E., Act. Mem.,
Consulting Civil Engineer, Elyria, Ohio.
- SKEELS, ARTHUR A., B.S., Act. Mem.,
Instructor in Physics, W. High School,
890 Denison ave., Cleveland.
- SMITH, HOWARD WELLS, M.E., Act. Mem.,
Assistant Engineer, Shelby Steel Tube Co.,
American Trust Bldg., Cleveland.
- SMITH, JARED A., Act. Mem.,
Col. Corps of Engineers, U. S. Army, Civil and Military Engineer,
69 Flood Bldg., San Francisco, Cal.
- SMITH, JAMES A., Assoc. Mem.,
Contractor for Public Works,
1630 Williamson Bldg., Cleveland.
- SMITH, JAMES J., Assoc. Mem.,
Sanitary and Heating Engineer, 404 Erie street, Cleveland.
- SMYTHE, FRANK A., Act. Mem.,
President, Thew Automatic Shovel Co., Lorain, Ohio.
- STALEY, CADY, C.E., Ph.D., LL.D., Act. Mem.,
President Case School of Applied Science,
63 Adelbert street, Cleveland.
- STANFORD, J. VERNE, Act. Mem.,
Instructor, Case School of Applied Science,
14 Lees Court, Cleveland.
- STINCHCOMB, WILLIAM A., Act. Mem.,
Transitman, with City Civil Engineer,
1987 Denison ave., Cleveland.

- STOCKWELL, JOHN N., Ph.D., Hon. Mem.,
Astronomer, 1008 Case ave., Cleveland, Ohio.
- STOFFER, LESLIE B., Assoc. Mem.,
With Warner & Swasey, 148 Putnam street, Cleveland.
- STRONG, CHARLES H., C.E., Act. Mem.,
Civil Engineer and Contractor,
622 Cuyahoga Bldg., Cleveland.
- SWASEY, AMBROSE, Act. Mem.,
Firm of Warner & Swasey, Mfrs. of Machine Tools and Astro-
nomical Instruments, 1728 Euclid ave., Cleveland.
- TALBOT, JOSEPH T., Act. Mem.,
Assistant Engineer, Park Department,
73 Mayfield Road, Cleveland.
- THOMPSON, HENRY C., C.E., Act. Mem.,
Civil Engineer, 20 Brenton street, Cleveland.
- THURSTON, EDWIN L., Assoc. Mem.,
Patent Lawyer, 1028 Society for Savings, Cleveland.
- TITCOMB, GEORGE E., Act. Mem.,
Engineer, McMyler Mfg. Co., 23 LaGrange street, Cleveland.
- TREAT, FRANCIS HENRY, Act. Mem.,
Former General Superintendent Cleveland Rolling Mill Co.,
2644 Euclid ave., Cleveland.
- VAN DORN, THOMAS B., Act. Mem.,
Vice-President Van Dorn Iron Works, Cleveland.
- VARNEY, JOSHUA D., Act. Mem.,
Civil Engineer and Surveyor, 53 Public Square, Cleveland.
- WAITT, ARTHUR M., Cor. Mem.,
Superintendent of Motive Power and Rolling Stock, New York
Central and Hudson River Railroad,
Grand Central Station, New York city.
- WALKER, CHARLES F., Assoc. Mem.,
On staff of *Engineering News*, 1168 Euclid ave., Cleveland.
- WALKER, JOHN, M.E., Cor. Mem.,
Mechanical and Mining Engineer, Gurnee, Ill.
- WALKER, WILLIAM J., Assoc. Mem.,
Superintendent Plate Mills, Otis Steel Co., Ltd.,
444 Crawford Road, Cleveland.
- WALLACE, JAMES C., Act. Mem.,
General Manager American Ship Building Company,
120 Viaduct, Cleveland.
- WARNER, WORCESTER R., Act. Mem.,
Firm of Warner & Swasey, Mfrs. of Machine Tools and Astro-
nomical Instruments, 1722 Euclid ave., Cleveland.
- WATSON, WILBER JAY, Act. Mem.,
With The Osborn Co., Civil Engineers,
Osborn Bldg., Cleveland.
- WEBB, ROBERT L., Act. Mem.,
Engineer of The Forest City Steel and Iron Co.,
The Leighton, Cleveland.
- WEBSTER, C. E., Cor. Mem.,
Chief Engineer, Delaware Valley and Kingston Railway, Erie and
Wyoming Valley Railway, Clearfield, Pa.

- WELLMAN, SAMUEL THOMAS, Act. Mem.,
President Wellman-Seaver Engineering Co.,
New England Bldg., Cleveland.
- WEST, THOMAS D., Cor. Mem.,
General Manager Thos. D. West Foundry Co., Sharpsville, Pa.
- WHITE, ROLLIN H., M.E., Act. Mem.,
Assistant Superintendent White Sewing Machine Co.,
56 Hillburn ave., Cleveland.
- WHITE, WINDSOR T., B.S., Act. Mem.,
Vice-President White Sewing Machine Co.,
124 Euclid ave., Cleveland.
- WHITMAN, PAUL S., Act. Mem.,
With The Brown Hoisting and Conveying Machine Co.,
77 Sixth ave., Cleveland.
- WIGHT, ELMER B., Act. Mem.,
Engineer, with Cleveland Park Board, 23 Ware street, Cleveland.
- WILLARD, JOSEPH W., Assoc. Mem.,
Retired General Manager Hercules Powder Co.,
1339 Willson ave., Cleveland.
- WILLIAMS, JOHN S., Act. Mem.,
Treasurer and General Manager Forest City Steel and Iron Co.,
262 Franklin ave., Cleveland.
- WILLIAMSON, CHARLES S., Act. Mem.,
Chief Draftsman, No. 2 Works, Variety Iron Works,
39 Olive street, Cleveland.
- WILSON, FRANK W., C.E., Cor. Mem.,
Manager Boston Bridge Works, 70 Kilby street, Boston, Mass.
- WILSON, JOHN M., LL.D., Hon. Mem.,
Brigadier-General, Chief of Engineers, U. S. Army,
1773 Massachusetts ave., Washington, D. C.
- WINTON, ALEXANDER, Act. Mem.,
Superintendent Winton Bicycle Co., President Winton Automobile Co.,
Brookfield ave., Cleveland.
- WOLVERTON, IRVING M., B.S., C.E., Act. Mem.,
Chief Engineer, Mt. Vernon Bridge Works, Mt. Vernon, Ohio.
- WOOD, JAMES, Assoc. Mem.,
Contractor, 163 Bolton ave., Cleveland.
- WRIGHT, CHAS. H., Act. Mem.,
Chief Engineer, The Brown Hoisting and Conveying Machine Co.,
Cleveland.
- YATES, PRESTON K., Act. Mem.,
Engineer, L. P. & J. A. Smith Co.,
532 East Prospect street, Cleveland.
- ZESIGER, ALBERT W., Act. Mem.,
Draftsman, Department Public Works, 720 Logan ave., Cleveland.

Engineers' Club of St. Louis.

- ABBOT, FREDERICK WILLIAM,
President Abbot-Gamble Contracting Co., Engineers and Con-
tractors, 620 Chestnut street, St. Louis, Mo.
- ADKINS, JAMES, JR.,
Assistant Engineer, St. Louis Transit Co.,
1414 S. Ewing ave., St. Louis, Mo.
- ANGELL, J. E.,
Member of firm Walter L. Flower & Co.,
1611 Chemical Bldg., St. Louis, Mo.
- ASHBURNER, THOMAS,
Agent Babcock & Wilcox Co., Chicago, Ill.
- AXTEL, FRANK FOYE,
U. S. Inspector, Pilot Town, Ia.
- BAIER, JULIUS,
Conrey Placer Mining Co., Laurain, Madison Co., Mont.
- BAKER, VERNON,
Water Works Extension, 77 East May street, St. Louis, Mo.
- BARNES, WILLIAM EDDY,
Editor *The Age of Steel*, Fullerton Bldg., St. Louis, Mo.
- BARTH, CARL G. L.,
Mechanical Engineer, with Bethlehem Steel Co.,
121 S. High street, Bethlehem, Pa.
- BARWICK, OLIVER J.,
Building Contractor, 510 Pine street, St. Louis, Mo.
- BARY, MARK,
Electrical Engineer, with H. H. Humphrey,
1305 Chemical Bldg., St. Louis, Mo.
- BASCOME, WESTERN R.,
Assistant Engineer, with New East River Bridge,
84 Broadway, Brooklyn, N. Y.
- BAUSCH, FREDERICK EMIL,
Chief Engineer, Pittsburg Plate Glass Co., Crystal City, Mo.
- BEAHAN, WILLARD,
Division Engineer, C. and N. W. Ry., Winona, Minn.
- BEARDSLEE, FRANK DIXON,
Contracting Agent, Missouri Edison Electric Co.,
415 Locust street, St. Louis, Mo.
- BENDIT, LOUIS,
Member firm of Lanfetter & Bendit, Mechanical Engineers and
Contractors, 810 Olive street, St. Louis, Mo.
- BENNETT, WILLIAM A.,
First Assistant Engineer City Water Department,
3945 Castleman ave., St. Louis, Mo.
- BILHARZ, O. M. C.,
Mining Engineer of Doe Run and St. Joe Lead Co.,
Flat River, Mo.
- BLAISDELL, ANTHONY HOUGHTALING,
Civil Engineer, with Missouri River Commission,
1515 Lucas Place, St. Louis, Mo.

- BORDEN, ALBERT,
Structural and Mechanical Engineer,
808 Mermod & Jaccard Bldg., St. Louis, Mo.
- BOUTON, GEORGE INNES,
Principal Assistant Engineer, Bryan & Humphrey,
2909 Park ave., St. Louis, Mo.
- BOUTON, WILLIAM,
Vice-President Pitzman's Company of Surveyors and Engineers,
2909 Park ave., St. Louis, Mo.
- BOYD, ALFRED,
Beulah, Ark.
- BOYER, JOSEPH,
President Boyer Machine Co.,
Second and Amsterdam aves., Detroit, Mich.
- BRANCH, HENRY,
Tucson, Ariz.
- BRANNE, JOHN SEVERIN,
Chief Engineer Koken Iron Works,
Koken Iron Works, St. Louis, Mo.
- BRENNEKE, WILLIAM GEORGE,
Brenneke & Fay, Consulting Civil Engineers,
1000 Fullerton Bldg., St. Louis, Mo.
- BROWN, WALTER SEAVY,
Assistant Mechanical Engineer, Construction Department, St.
Louis Water Works, 3822 Hartford street, St. Louis, Mo.
- BRUNER, PRESTON MARTIN,
Contractor for Concrete Work,
304 N. Eighth street, St. Louis, Mo.
- BRYAN, CHARLES WALTER,
Agent American Bridge Co., Empire Bldg., Pittsburg, Pa.
- BRYAN, WILLIAM HENRY,
Consulting Engineer, 707 Lincoln Trust Bldg., St. Louis, Mo.
- BURGESS, ROBERT,
Division Engineer, St. Louis, Kansas City and Colorado Railroad,
Borbois, Gasconade county, Mo.
- BURNET, GEORGE,
Consulting Engineer, Rialto Bldg.,
4415 Washington ave., St. Louis, Mo.
- BUTLER, LAWRENCE PARKER,
First Lieutenant, 41st Infantry, U. S. V., Manila, P. I.
- CALDWELL, WILLIAM ANDERSON, JR.,
Mechanical Engineer, 4600 Maryland ave., St. Louis, Mo.
- CAMERON, DUNCAN F.,
General Manager of Mines, Donk Bros. Coal & Coke Co.,
Third and Pine streets, St. Louis, Mo.
- CARR, LOVELL H.,
Western Representative Atlas Cement Co.,
143 Liberty street, New York, N. Y.
- CHAPHE, JAMES MANNING,
Engineer, with Matthews Bros., 600 Carleton Bldg.,
3060 Sheridan ave., St. Louis, Mo.
- CHAPLIN, WINFIELD SCOTT,
Chancellor of Washington University,
Washington University, St. Louis, Mo.

- CHASSAING, CHAS. W.,
Draftsman Union Iron and Foundry Co.,
1702 Missouri ave., St. Louis, Mo.
- CHILDS, OLIVER W.,
Chief Engineer Stupp Bros. Bridge and Iron Co.,
2301 S. Seventh street, St. Louis, Mo.
- CHOLLAR, BYRON EDGAR,
Engineer Laclede Gas Light Company,
716 Locust street, St. Louis, Mo.
- CLARK, CHARLES WRIGHT,
Architect and United States Assistant Engineer,
Webster Groves, Mo.
- COLBY, BRANCH HARRIS,
Colby & Baker, Civil and Consulting Engineers,
708 Lincoln Trust Bldg., St. Louis, Mo.
- COLNOR, REDMOND STEPHEN,
Contractor, Room 127, Laclede Bldg., St. Louis, Mo.
- COMBER, WILLIAM GEORGE,
United States Assistant Engineer, Mississippi River Commission,
1115 Fullerton Bldg., St. Louis, Mo.
- CONNOR, EDWARD HANSON,
Engineer, Missouri Valley Bridge and Iron Works,
Leavenworth, Kan.
- COOK, ABRAHAM,
Secretary Laclede Car Company,
4500 N. Second street, St. Louis, Mo.
- CORDES, E. A.,
Superintendent Steam Plants, Missouri Edison Electric Co.,
4328 Duncan ave., St. Louis, Mo.
- CROSBY, BENJAMIN LINCOLN,
Assistant Auditor Burlington Lines,
1213 Charles street, St. Joseph, Mo.
- DAVIS, CHARLES HENRY,
Civil Engineer, 99 Cedar street, New York, N. Y.
- DEAN, JOHN,
Engineer Park Department, 1328 E. Aubert ave., St. Louis, Mo.
- DICKE, EDWARD CHRISTIAN,
Assistant Engineer, Brenneke & Fay, Box 31, Hartford City, Ind.
- DICKENS, ALBERT WHITE,
Assistant Engineer St. Louis Water Works Extension,
601 Baden ave., St. Louis, Mo.
- DUN, JAMES,
Chief Engineer Atchison, Topeka and Santa Fe Railroad,
Topeka, Kan.
- DUNAWAY, HORACE,
United States Assistant Engineer, United States Engineer's Office,
St. Paul, Minn.
- DZIATZKO, LEO CHARLES,
Resident Engineer M. and St. L. R. R.,
2912 Ellendale ave., St. Louis, Mo.
- FAUST, FRANK CORIDON,
Engineer and Superintendent of Construction, Flick & Johnson
Construction Co., of Davenport, Iowa. Newport, Tenn.

- FAY, EDWARD BAYRD,
Brenneke & Fay, Consulting Engineers.
1000 Fullerton Bldg., St. Louis, Mo.
- FERGUSON, OSCAR W.,
Assistant United States Coast and Geodetic Survey,
404 Ninth street, N. E., Washington, D. C.
- FISCHER, LOUIS E.,
Electrical and Mechanical Engineer, with Laufketter & Bendit,
810 Olive street, St. Louis, Mo.
- FISIL, EDWARD RUSSELL,
Secretary Heine Safety Boiler Company,
2328 Arkansas ave., St. Louis, Mo.
- FISHER, CHARLES OWEN,
Secretary Pitzman's Company of Surveyors and Engineers,
3140 Russell ave., St. Louis, Mo.
- FISHER, GEORGE W.,
Fulton Iron Works, Second and Carr streets, St. Louis, Mo.
- FISHER, SAMUEL B.,
Chief Engineer M., K. and T. Ry.,
406 Wainwright Bldg., St. Louis, Mo.
- FLAD, EDWARD,
Water Commissioner, City Hall, St. Louis, Mo.
- FOGARTY, W. J.,
Manager Magnetite Foundry,
3951 West Belle Place, St. Louis, Mo.
- FOSTER, CHARLES F.,
Mechanical Engineer, 1407 Manhattan Bldg., Chicago, Ill.
- FREEMAN, STUART ETHAN,
Consulting Mechanical Engineer, 4052 Olive street, St. Louis, Mo.
- FRENCH, GEO. H.,
United States Assistant Engineer Mississippi River Commission,
1115 Fullerton Bldg., St. Louis, Mo.
- GARRELS, WILLIAM LOUIS,
Consulting Engineer, 4531 West Pine street, St. Louis, Mo.
- GAYLER, CARL,
Bridge Engineer, Street Department, City of St. Louis,
City Hall, St. Louis, Mo.
- GOULD, WILLIAM TILLOTTSON,
Resident Engineer Texas Central Railway, Waco, Texas.
- GRAVES, WILLIAM NELSON,
General Superintendent and Mechanical Engineer Hydraulic Press
Brick Co., 2813 Lafayette ave., St. Louis, Mo.
- GRONEMANN, HENRY,
District Engineer, Street Department, City of St. Louis,
2719 Stoddard street, St. Louis, Mo.
- GUINN, JOHN BROOME,
Superintendent Durant, Compromise, Conomara, Smuggler, Late
Acquisition, etc., Mines, P. O. Box No. 603, Aspen, Col.
- HAMMOND, ALONZO JOHN,
Assistant Engineer Vandalia Line, Terre Haute, Ind.
- HARRINGTON, FERDINAND FINNEY,
Lake Superior Power Co., Sault Ste. Marie, Mich.

- HAWKES, CHAS. WM.,
Manager Springfield Boiler and Manufacturing Co.,
Springfield, Ill.
- HAZZARD, ALBERT B.,
Mechanical Engineer and Contractor,
615 N. Second street, St. Louis, Mo.
- HENDRICKS, VICTOR K.,
Engineer M. of W. Terre Haute and Logansport Rys.,
118 N. Eighth street, Terre Haute, Ind.
- HENBY, WILLIAM HASTINGS,
Pauly Jail Manufacturing and Building Co.,
2610 S. Jefferson ave., St. Louis, Mo.
- HERMANN, EDWARD ADOLPH,
Sewer Commissioner, City of St. Louis,
505 N. Spring ave., St. Louis, Mo.
- HILL, JOHN,
President Hill-O'Meara Construction Co.,
Wainwright Bldg., St. Louis, Mo.
- HOFMANN, ALWIN,
3641 Cleveland ave., St. Louis, Mo.
- HOLMAN, MINARD LAFEVER,
General Superintendent Missouri Edison Electric Company,
3744 Finney ave., St. Louis, Mo.
- HOWE, M. R.,
Professor of Civil Engineering, Rose Polytechnic Institute,
2108 N. Tenth street, Terre Haute, Ind.
- HUBBARD, ALBERT WINFRED,
St. Louis, Mo.
- HUMPHREY, HENRY H.,
Consulting Electrical Engineer,
1305 Chemical Bldg., St. Louis, Mo.
- HUNICKE, WM. A.,
2937 Henrietta street, St. Louis, Mo.
- HUTCHINSON, CARY T.,
Consulting Electrical Engineer, 71 Broadway, New York, N. Y.
- INGOLDSBY, FRANK S.,
Vice-President and General Manager Ingoldsby Automatic Car Co.,
608 Chemical Bldg., St. Louis, Mo.
- JENNINGS, JAMES GUSTAV,
District Engineer, Street Department, City of St. Louis,
City Hall, St. Louis, Mo.
- JEWITT, ELIOT C.,
Mining Engineer, with Cia Miniera, Fundidora y Afinadora,
Fundicion No. 2, Monterey, Mexico.
- JOHNSON, ALBERT LINCOLN,
Engineer St. Louis Expanded Metal and Fire Proofing Co.,
Room 606, Century Bldg., St. Louis, Mo.
- JOHNSON, GEORGE DYER,
Assistant Superintendent Mississippi Glass Co.,
3938A North Eleventh street, St. Louis, Mo.
- JOHNSON, JOHN BUTLER,
Dean of Engineering School, University of Wisconsin,
Madison, Wis.
- JOLLEY, EDWIN JAMES,
Engineer of Surveys, Street Department, City of St. Louis,
1119 Bayard ave., St. Louis, Mo.

- JONES, CHARLES E.,
Instructor in Forging and Engineer in Charge of Steam Plant,
Washington University,
Manual Training School, St. Louis, Mo.
- JUDSON, JOHN NICHOLAS,
American Metal Co., Ltd., and Wetherill Separating Co.,
52 Broadway, New York, N. Y.
- KIMBALL, CLINTON,
Consulting Engineer, Franklin Bank Bldg., St. Louis, Mo.,
Kirkwood, Mo.
- KINEALY, JOHN HENRY,
Professor of Mechanical Engineering,
Washington University, St. Louis, Mo.
- KRUTZSCH, HERMAN,
Vice-President and Manager St. Louis Iron and Machine Works,
3863 Cleveland ave., St. Louis, Mo.
- LAIRD, JOHN ALFRED,
Consulting Engineer, Fullerton Bldg., St. Louis, Mo.
- LAUFKETTER, FREDERICK CLEMENS,
Member firm of Lanfketter & Bendit, Mechanical Engineers and
Contractors, 810 Olive street, St. Louis, Mo.
- LAYMAN, WALDO ARNOLD,
Assistant Manager and Treasurer Wagner Electric Mfg. Co.,
2341 S. Compton ave., St. Louis, Mo.
- LEIGHTON, GEORGE BRIDGE,
President Los Angeles Terminal Railway,
Rialto Bldg., St. Louis, Mo.
- LEONARD, EDWARD FRANCKE,
President Toledo, Peoria and Western Railway; office, Peoria, Ill.
Springfield, Ill.
- LEVY, WILL,
Architect, Odd Fellows' Bldg., St. Louis, Mo.
- LIBBY, EDMUND DORMAN,
Assistant United States Engineer, Mississippi River Improvement,
Custom House, St. Louis, Mo.
- LICHTER, JOHN JAMES, JR.,
Electrical Engineer, St. Louis Transit Co.,
5305 Virginia ave., St. Louis, Mo.
- LLEWELLYN, FRANCIS JOHN,
President, Koken Iron Works, St. Louis, Mo.
- LUCKE, CHARLES EDWARD,
Manager St. Louis Branch, Keuffel & Esser Co.,
708 Locust street, St. Louis, Mo.
- MALTEY, FRANK BIERCE,
United States Assistant Engineer,
1515 Locust street, St. Louis, Mo.
- MCCULLOCH, RICHARD,
Manager, Compagnie Genevoise des Tramways Electriques,
La Jonction, Geneva, Switzerland.
- McFARLAND, C. M.,
American Arithmometer Co., 2102 Wash street, St. Louis, Mo.
- McMATH, ROBERT EMMET,
President of Board of Public Improvements,
City Hall, St. Louis, Mo.

- McMATH, THOMAS BRODIE,
Engineer, Greenfield and Indianapolis Rapid Transit Co., and En-
gineer Indianapolis Street Railway Co.,
1020 College ave., Indianapolis, Ind.
- McMILLIN, EMERSON,
President Laclede Gas Light Co., St. Louis,
40 Wall street, New York, N. Y.
- MEIER, EDWARD DANIEL,
President and Chief Engineer Heine Safety Boiler Co.,
11 Broadway, New York, N. Y.
- MEINHOLTZ, HERMAN CHARLES,
Superintendent Heine Safety Boiler Co.,
4812 Greer ave., St. Louis, Mo.
- MELCHER, CHARLES W.,
Western Manager Ingersoll-Sergeant Drill Co.,
84 Van Buren street, Chicago, Ill.
- MERSEREAU, CHARLES VERNON,
Assistant Engineer, Water Works Extension,
3838 Shenandoah ave., St. Louis, Mo.
- MILNER, ABRAM NEISWANGER,
422 Fullerton Bldg., St. Louis, Mo.
- MITCHELL, CHARLES DWIGHT,
Civil Engineer on Water Works Extension,
77 E. May street, St. Louis, Mo.
- MITCHELL, FRANK S.,
Civil Engineer,
15 Wall street, New York, N. Y.
- MITCHELL, MARCUS LAFAYETTE,
Chief Engineer, Wainwright Brewery,
1220 Armstrong ave., St. Louis, Mo.
- MITCHELL, WILLIAM SELBY,
Assistant Engineer, Improvement Mississippi River between Mis-
souri and Ohio Rivers, Custom House, St. Louis, Mo.
- MONELL, JOSEPH T.,
Superintendent Central Lead Co.,
Flat River St. Francois Co., Mo.
- MONTGOMERY, GEO. S.,
Superintendent Lincoln Gas and Electric Co.,
1200 O street, Lincoln, Neb.
- MOORE, PHILIP NORTH,
Consulting Mining Engineer, President Tecumseh Iron Co., Treas-
urer Rose Run Iron Co., of Kentucky,
Room 121, Laclede Bldg., St. Louis, Mo.
- MOORE, ROBERT,
Consulting Engineer, Room 110, Laclede Bldg., St. Louis, Mo.
- MOORE, WILLIAM HENRY,
District Engineer, Street Department, City of St. Louis,
4224 John ave., St. Louis, Mo.
- MOREY, RICHARD,
Engineer and Manager for Gilsonite Roofing and Paving Co.,
716 New York Life Bldg., Kansas City, Mo.
- MOULTON, JULIUS,
Civil Engineer, Harbor Department, City of St. Louis,
205 City Hall, St. Louis, Mo.

- MYSENBURG, THEODORE AUGUST,
Iron Manufacturer, American Central Bldg., St. Louis, Mo.
- NEFF, WILLIAM A., JR.,
Civil Engineer, 860 Doane street, Cleveland, Ohio.
- NICHOLSON, FRANK,
Mining Engineer, 504 Fifth ave., New York, N. Y.
- NIPHER, FRANCIS EUGENE,
Professor of Physics, Washington University, St. Louis, Mo.
- OCKERSON, JOHN AUGUSTUS,
Civil Engineer, Member Mississippi River Commission,
Fullerton Bldg., St. Louis, Mo.
- OLSHAUSEN, GEO. R.,
Post-Graduate Student, University of Berlin, Berlin, Germany,
2631 Louisiana ave., St. Louis, Mo.
- O'REILLY, ANDREW JOHN,
Supervisor of City Lighting, Room 326, City Hall, St. Louis, Mo.
- PARKER, EDGAR CHARLES,
Superintendent and Engineer Samuel Cupples Real Estate Co.,
2012 Oregon ave., St. Louis, Mo.
- PARKER, LEMON,
Superintendent Parker-Russell Mining and Manufacturing Co.,
3413 Oak Hill ave., St. Louis, Mo.
- PARKER, RUSSELL,
President Missouri Telephone Manufacturing Co.,
417 Pine street, St. Louis, Mo.
- PEGRAM, GEO. H.,
Chief Engineer, Manhattan Railway,
10 Dey street, New York, N. Y.
- PERKINS, NATHAN WAITE, JR.,
Mechanical Engineer, 4446 Page Boulevard, St. Louis Mo.
- PFEIFER, HERMAN JULIUS,
Assistant Engineer, Terminal Railroad Association,
Room 208, Union Station, St. Louis, Mo.
- PHILLIPS, HIRAM,
Consulting Hydraulic and Sanitary Engineer,
525 Lincoln Trust Bldg., St. Louis, Mo.
- PHILLIPS, RICHARD HARVEY,
Practicing Civil Engineer, 525 Lincoln Trust Bldg., St. Louis, Mo.
- PILLSBURY, F. S.,
Engineer of Motor Department, Wagner Electric Manufacturing
Co., 2017 Locust street, St. Louis, Mo.
- PITZMAN, JULIUS,
Street Improvement, Landscape Work and Surveying,
615 Chestnut street, St. Louis, Mo.
- PORTER, JOSEPH FRANKLIN,
President and Engineer Alton Railway, Gas and Electric Co.,
205 Market street, Alton, Ill.
- POSS, VICTOR H.,
Draftsman, United States Engineer's Office,
Custom House, St. Louis, Mo.
- POST, TRUEFMAN MARCELLUS,
Mechanical Draftsman, Mississippi River Commission,
5678 Cabanne ave., St. Louis, Mo.

- REBER, HENRY LINTON,
Secretary and Chief Engineer Kinloch Telephone Co.,
Century Bldg., St. Louis, Mo.
- REEL, CHARLES GORDON,
Consulting Engineer, 920 Rialto Bldg., St. Louis, Mo.
- REEVES, WILLIAM HENRY,
St. Louis Agent, Henry R. Worthington,
317 N. Ninth street, St. Louis, Mo.
- RINGER, FRANK,
Draftsman in charge of Records, M. K. T. Ry.,
406 Wainwright Bldg., St. Louis, Mo.
- ROHRICH, HAROLD A.,
Superintendent American Arithmometer Co.,
4063 Delmar ave., St. Louis, Mo.
- ROPER, DENNEY W.,
Superintendent Electric Equipment, Missouri Edison Co.,
Nineteenth and Gratiot streets, St. Louis, Mo.
- RUCKERT, LOUIS,
Dealer in Drawing Materials, etc.,
3023 Shenandoah ave., St. Louis, Mo.
- RUSSELL, S. BENT,
Assistant Engineer in Charge of Water Works Extension,
77 E. May street, St. Louis, Mo.
- SAXTON, EDMUND,
Street Railway Contractor,
1244 Eleventh street, N. W., Washington, D. C.
- SCHAUB, JULIUS WILLIAM,
Civil Engineer, Specialty: Bridges and Buildings,
1649-50 Monadnock Block, Chicago, Ill.
- SCHAUMLEFFEL, PETER W.,
Superintendent St. Louis Lead and Oil Co., Howard Station,
2329 Whittmore Place, St. Louis, Mo.
- SCHMITZ, OTTO,
Civil Engineer, with Julius Pitzman,
2114 S. Compton ave., St. Louis, Mo.
- SCHRAMM, OSCAR H.,
Manager The Brownell & Co., makers of Boilers and Engines,
1216 Union ave., Kansas City, Mo.
- SCHWEDTMANN, FERDINAND,
Superintendent Wagner Electric Manufacturing Co.,
2017 Locust street, St. Louis, Mo.
- SEDDON, JAMES ALEXANDER,
United States Assistant Engineer,
1637 Indiana ave., Chicago, Ill.
- SHAW, HOWARD BURTON,
Professor Electrical Engineering, State University, Columbia, Mo.
- SHERMAN, WALTER J.,
Riggs & Sherman, Civil and Consulting Engineers,
613 Nasby Bldg., Toledo, Ohio.
- SIEBERT, ALFRED,
Consulting Engineer and Refrigerating Expert,
4950 Columbia ave., St. Louis, Mo.
- SMITH, BATHURST,
United States Assistant Engineer, Sioux City, Iowa.

- SNEDDON, JAMES PRENTICE,
Stirling Boiler Co., Barberton, Ohio.
- SPALDING, FREDERICK PUTNAM,
Professor of Civil Engineering, University of the State of Missouri,
Columbia, Mo.
- SPENCER, EUGENE J.,
Engineer and Sole Western Agent for the Underground Electric
Cables of the Safety Insulated Wire and Cable Co. of New
York, Room 24, Laclede Bldg., St. Louis, Mo.
- STOLBERG, EMIL CHARLES,
Mechanical Engineering Department, Missouri Pacific Ry.,
2916 Eads ave., St. Louis, Mo.
- STUART, ALFRED A.,
Engineer and Manager for M. P. Davis, Constructing Substructure
of Quebec Bridge, Sillery P. O., Canada.
- SWOPE, GERARD,
Electrical Engineer and Representative in St. Louis of Western
Electric Company, Security Bldg., St. Louis, Mo.
- SYKES, HENRY HUTCHINS,
Chief Engineer, Bell Telephone Co. of Missouri,
Telephone Bldg., St. Louis, Mo.
- TAUSSIG, HUBERT PRIMUS,
Consulting Civil Engineer,
Room 320, Wainwright Bldg., St. Louis, Mo.
- TAYLOR, JOHN WALTER,
Chief Engineer, T. R. R. A. and St. L. M. B. T. Ry.,
Union Station, St. Louis, Mo.
- THACHER, ARTHUR,
President and Manager Central Lead Co.; President Renault
Lead Co., 4304 Washington ave., St. Louis, Mo.
- THOMPSON, WILBUR HAYES,
Electrical Engineer, Wagner Electric Manufacturing Co.,
1906 La Salle street, St. Louis, Mo.
- TIDEMANN, HENRY GERHARD,
Mechanical Engineer, with Heine Safety Boiler Co.,
1726 Mississippi ave., St. Louis, Mo.
- TREPP, SAMUEL,
Mechanical Engineer, Malinkrodt Chemical Works,
4150 Westminster Place, St. Louis, Mo.
- TRIPP, CHAS. A.,
Engineer, Bemis Bros. Bag Co. and allied firms,
Bemis Indianapolis Bag Co., Indianapolis, Ind.
- TUCKER, CHARLES H.,
Treasurer of A. Leschen & Sons' Rope Co.,
3853 Washington Boulevard, St. Louis, Mo.
- TURNER, ORVILLE H. B.,
United States Assistant Engineer, with Missouri River Commis-
sion, Maplewood, Mo.
- TYRRELL, WARREN A.,
Assistant Engineer, St. Louis Water Department,
3920 Folsom ave., St. Louis, Mo.
- URBAUER, HUGO FREDERICK,
President of Urbauer-Atwood Heating Co.,
3956 Morgan street, St. Louis, Mo.

- VAIL, JESSE AARON,
Agent, Hamilton Corliss Engine Works,
148 Laclede Bldg., St. Louis, Mo.
- VAN ORNUM, JOHN LANE,
Professor of Civil Engineering,
Washington University, St. Louis, Mo.
- VAN SANT, ROBERT LAWRENCE,
Engineer and Contractor, 609 Commercial Bldg., St. Louis, Mo.
- VARRELMANN, CHARLES,
Street Commissioner, City Hall, St. Louis, Mo.
- WAGNER, HERBERT APPLETON,
Mechanical and Electrical Engineer,
Westmoreland Hotel, St. Louis, Mo.
- WALL, EDWARD EVERETT,
First Assistant Civil Engineer, Sewer Department,
City Hall, St. Louis, Mo.
- WANGLER, JOSEPH FRANK,
Boiler Manufacturer, 1535 N. Ninth street, St. Louis, Mo.
- WARREN, BERTAH,
Master Mechanic, Toledo, Peoria and Western Railroad,
Peoria, Ill.
- WAY, SYLVESTER B.,
Superintendent Imperial Electric Light, Heat and Power Co.,
Tenth and St. Charles streets, St. Louis, Mo.
- WHEELER, HERBERT ALLEN,
Secretary and Treasurer Standard Tile Co.,
3124 Locust street, St. Louis, Mo.
- WILLIAMS, WALTER SCOTT,
Surveyor, Mississippi River Commission,
1115 Fullerton Bldg., St. Louis, Mo.
- WINSLOW, ARTHUR,
Geologist and Mining Expert,
104 West Ninth street, Kansas City, Mo.
- WISE, WILLIAM,
Assistant Sewer Commissioner, City Hall, St. Louis, Mo.
- WOERMANN, JOHN WILLIAM,
Resident Engineer, Illinois and Mississippi Canal, Sheffield, Ill.
- WOODWARD, EDWARD K.,
Engineer Maintenance of Way, Detroit Division, Wabash Railroad,
Fort Street Union Station, Detroit, Mich.
- YEATMAN, POPE,
Mining Engineer,
P. O. Box 67, Johannesburg, South African Republic.
- ZELLE, WILLIAM CHARLES,
General Manager, Mound City Construction Co.,
230 Lincoln Trust Bldg., St. Louis, Mo.
- ZELLER, ALBERT HENRY,
Civil Engineer, 1000 Fullerton Bldg., St. Louis, Mo.

Civil Engineers' Society of St. Paul.

- ALDERMAN, C. A.,
Chief Engineer, Dayton, Springfield and Urbana
Electric Railway Co., Columbus, Ohio.
- ANNAN, C. L.,
Chief Engineer's Offices, Choctaw, Oklahoma
and Gulf Railroad Co., Little Rock, Ark.
- ARMSTRONG, J. H.,
Civil Engineer and Surveyor, 504 Globe Bldg., St. Paul, Minn.
- BARBER, P. E.,
Land Department, Northern Pacific Railway Co., St. Paul, Minn.
- BLOLGETT, JOHN,
East Side House, Seventy-sixth street and East River, New York.
- CLARK, H. E.,
Overseer, United States Engineer's Office,
Army Bldg., St. Paul, Minn.
- CLAUSSEN, OSCAR,
Commissioner of Public Works, St. Paul, Minn.
- CROCKER, H. S.,
Assistant Engineer, Board of Public Works,
City Hall, Denver, Col.
- CROSBY, OLIVER,
President, American Hoist and Derrick Co., St. Paul, Minn.
- CURTIN, DAVID,
Engineer and Roadmaster, Twin City Rapid Transit Co.,
Minneapolis, Minn.
- CURTIS, W. W.,
Civil Engineer and Contractor,
549 Marquette Bldg., Chicago, Ill.
- DANFORTH, WILLIAM,
Civil Engineer, Red Wing, Minn.
- DARLING, F. S.,
Assistant Engineer, Northern Pacific Railway Co.,
Tacoma, Wash.
- DARLING, W. L.,
Assistant Chief Engineer,
Northern Pacific Railway Co., St. Paul, Minn.
- DU SHANE, JAMES D.,
Assistant Engineer, United States Engineer's Office,
Army Building, St. Paul, Minn.
- EDMONDSTONE, G. S.,
City Bridge Engineer, St. Paul, Minn.
- ELDER, ROBERT,
Civil Engineer, Fairbanks, Morse & Co., St. Paul, Minn.
- ESTABROOK, J. D.,
Civil Engineer, 699 Lincoln ave., St. Paul, Minn.
- FERNSTROM, H.,
Chief Engineer, St. Joseph and Grand Island Railway Co.,
St. Joseph, Mo.
- FORBES, CHAS. A.,
Surveyor, Room 11, Court Block, St. Paul, Minn.

- FREYHOLD, FELIX,
 Draftsman, Bureau of Yards and Docks, Navy Department,
 Washington, D. C.
- HARRISON, H. H.,
 Civil Engineer, Stillwater, Minn.
- HEDGES, S. H.,
 Contracting Engineer, Chicago Bridge and Iron Co.,
 Washington Heights P. O., Chicago, Ill.
- HERZOG, ROBERT,
 Assistant Engineer, Great Northern Railway Co., St. Paul, Minn.
- HEUSTON, GEO. Z.,
 City Engineer, Winona, Minn.
- HILGARD, K. E.,
 Civil Engineer, 18 Steinweissstrasse, Zürich V. Kreis, Switzerland.
- HOGELAND, ALBERT H.,
 Resident Engineer, Great Northern Railway Co., St. Paul, Minn.
- HORTON, H. E.,
 President and Chief Engineer, Chicago Bridge and Iron Co.,
 Chicago, Ill.
- HUNT, C. A.,
 Assistant Engineer, Montana Division, Great Northern
 Railway Co., Havre, Mont.
- JOHNSON, C. W.,
 Chief Engineer, C., St. P., M. and O. Ry. Co., St. Paul, Minn.
- JOHNSON, NOAH,
 Chicago Great Western Railway Co., St. Paul, Minn.
- LOWETH, C. F.,
 Consulting Civil Engineer,
 First National Bank Bldg., St. Paul, Minn.
- LUSERKE, OTTO,
 Chief Draftsman, Great Northern Railway Co., St. Paul, Minn.
- LYON, TRACY,
 General Superintendent, Chicago Great Western Railway Co.,
 St. Paul, Minn.
- MCCOY, F. W.,
 Assistant Engineer, Great Northern Railway Co., St. Paul, Minn.
- MILLER, HEW,
 Civil Engineer, Room 10, Floor 11, 100 Broadway, New York.
- MILLER, N. D.,
 Civil Engineer, 551 Westminster street, St. Paul, Minn.
- MORRIS, C. J. A.,
 Engineer and Contractor, 613 Goodrich ave., St. Paul, Minn.
- MUNSTER, A. W.,
 Bridge Engineer, Chicago Great Western Railway Co.,
 St. Paul, Minn.
- POWELL, A. O.,
 Assistant Engineer, United States Engineer's Office,
 418 Globe Bldg., St. Paul, Minn.
- RAYNOR, C. W.,
 United States Engineer's Office,
 418 Globe Bldg., St. Paul, Minn.
- ROCKWELL, SAMUEL,
 Principal Assistant Engineer, L. S. and M. S. R. R. Co.,
 Cleveland, Ohio.

- RUNDETT, L. W.,
Civil Engineer, 605 Lincoln ave., St. Paul, Minn.
- SMITH, W. C.,
Engineer, Guthrie & Co., St. Paul, Minn.
- SOMERS, W. A.,
Civil Engineer, Room 33, Metropolitan Opera House,
St. Paul, Minn.
- STARKEY, A. R.,
Office Engineer, Office Commissioner of Public Works,
St. Paul, Minn.
- STEVENS, H. E.,
Engineer and Contractor, 530 Grand ave., St. Paul, Minn.
- SWENSON, H. A.,
Assistant Engineer, Northern Pacific Railway Co., St. Paul, Minn.
- TOLTZ, MAX,
Mechanical Engineer, Great Northern Railway Co., St. Paul, Minn.
- TRUESDELL, W. A.,
Assistant Engineer, Great Northern Railway Co., St. Paul, Minn.
- WILGUS, W. J.,
Chief Engineer, N. Y. C. and H. R. R. and leased lines,
Grand Central Station, New York.
- WILLIAMSON, SYDNEY B.,
Assistant Engineer, United States Muscle Shoals Canal,
Kingman, Ala.
- WILSON, GEO. L.,
Assistant Commissioner of Public Works, St. Paul, Minn.
- WINSLOW, C. A.,
Assistant in City Engineer's Department, St. Paul, Minn.
- WOODMAN, E. E.,
Secretary, Tax Commissioner, C., St. P., M. and O. Railway Co.,
St. Paul, Minn.

Engineers' Club of Minneapolis.

-
- AVERY, HENRY B.,
 Mechanical Engineer, 2548 Nicollet ave., Minneapolis, Minn.
 BURCH, EDWARD P.,
 Consulting Electrical Engineer,
 1210 Guaranty Bldg., Minneapolis, Minn.
 CARROLL, J. E.,
 Assistant Street Engineer, City Engineer's Department,
 3452 Nicollet ave., Minneapolis, Minn.
 COMSTOCK, ROBERT,
 Levelman, City Engineer's Department,
 750 Madison street, N. E., Minneapolis, Minn.
 DEALING, W. F.,
 Sidewalk Engineer, City Engineer's Department,
 City Hall, Minneapolis, Minn.
 DURHAM, B. H.,
 Transitman, City Engineer's Department,
 618 E. Twenty-fourth street, Minneapolis, Minn.
 DUTTON, E. R.,
 Assistant City Engineer, 3340 Pleasant ave., Minneapolis, Minn.
 FANNING, RENNIE B.,
 Consulting Engineer, 602 Kasota Bldg., Minneapolis, Minn.
 GILLETTE, L. S.,
 Gillette-Herzog Mfg. Co.,
 627 Second street, S. E., Minneapolis, Minn.
 GRABER, ALFRED,
 Assistant Engineer, Bismark, Washburn and Great Falls Ry.,
 142 Fifth ave., N. E., Minneapolis, Minn.
 HOAG, PROF. W. R.,
 Professor of Civil Engineering, State University,
 Minneapolis, Minn.
 ILLSTRUP, CARL,
 City Sewer Engineer, City Hall, Minneapolis, Minn.
 PARDEE, WALTER S.,
 Architect, City Hall, Minneapolis, Minn.
 PILLSBURY, C. L.,
 Electrical Engineer, Minneapolis International Electric Co.,
 Minneapolis, Minn.
 REDFIELD WM. W.,
 Engineer of Construction, City Water Works,
 Room 8, City Hall, Minneapolis, Minn.
 SHEPARDSON, PROF. G. D.,
 Professor of Electrical Engineering,
 State University, Minneapolis, Minn.
 SMITH, PROF. H. E.,
 Assistant Professor of Mechanical Engineering,
 State University, Minneapolis, Minn.
 STACK, W. E.,
 Surveyor C. A. Smith Lumber Co.,
 Camden Place, Minneapolis, Minn.
 STOOPES, W. E.,
 Assistant County Surveyor, Court House, Minneapolis, Minn.
 SUBLETTE, G. W.,
 City Engineer, City Hall, Minneapolis, Minn.

Montana Society of Engineers.

- ADAMI, CHAS. J., Act. Mem.,
Mining Engineer for Butte and Boston Mining Co., Butte, Mont.
- BAKER, THOMAS T., Act. Mem.,
Baker & Potter, Civil and Mining Engineers, Butte, Mont.
- BARKER, SAMUEL, JR., Act. Mem.,
Pennington & Barker, Civil and Mining Engineers,
29 E. Granite street, Butte, Mont.
- BAYLISS, RAWLINSON T., Assoc. Mem.,
54 Old Broad street, London, E. C., England.
- BEACH, FRANK, Assoc. Mem.,
Civil Engineer, Las Animas, Col.
- BECKLER, ELBRIDGE H., Hon. Mem.,
Civil Engineer, 1838 Aldine ave., Chicago, Ill.
- BICKEL, PAUL S. A., Act. Mem.,
Civil and Mining Engineer, Thompson Block, Helena, Mont.
- BLACKFORD, FRANCIS W., Act. Mem.,
Civil and Mining Engineer, United States Deputy
Mineral Surveyor, 48 E. Broadway, Butte, Mont.
- BOND, BENJAMIN, Act. Mem.,
Civil Engineer, Dillon, Mont.
- BOOTH, CHARLES F., Act. Mem.,
Real Estate and Mining, Butte, Mont.
- BOWMAN, CHARLES H., Act. Mem.,
Montana State School of Mines, Butte, Mont.
- BREEN, JAMES, Act. Mem.,
General Manager Le Roi Mining and Smelting Co.,
Northport, Wash.
- CALDERWOOD, JAMES M., Assoc. Mem.,
General Manager Rota Anna Mines, Limited,
Kapnikbanya, Hungary.
- CANTINE, EDWARD I., Act. Mem.,
Roadmaster Northern Pacific Railway Co., Billings, Mont.
- CARROLL, EUGENE, Act. Mem.,
Chief Engineer and Superintendent Butte City Water Co.,
Box 356, Butte, Mont.
- CATLIN, ARTHUR W., Act. Mem.,
Finkelnburg & Catlin, Civil and Mining Engineers,
Missoula, Mont.
- CHANDLER, RICHARD E., Assoc. Mem.,
Civil Engineer, 3 Highland Place, Ithaca, N. Y.
- CHRISTIAN, AUGUST, Act. Mem.,
Chief Engineer Anaconda Copper Mining Co.,
Box 109, Butte, Mont.
- CLARK, CHARLES W., Act. Mem.,
General Manager W. A. Clark's Mines, Butte, Mont.
- CLARK, HARRY P., Act. Mem.,
General Manager Custer Mine, Winston, Mont.
- CLARK, JOSEPH K., Act. Mem.,
Mining and Metallurgical Engineer, Vice-President and Manager
of Mayflower Mining Co., Butte, Mont.

- CLARK, WILLIAM A., Act. Mem.,
President Moulton Mining Co., President United
Verde Copper Co., W. A. Clark Brothers, Bankers,
Butte, Mont.
- CROOKES, SPENCER H., Act. Mem.,
U. S. Deputy Mineral Surveyor, County Surveyor Park Co.,
Livingston, Mont.
- CUMMING, ADELBERT E., Act. Mem.,
Civil and Hydraulic Engineer, Harlem, Mont.
- DANFORTH, WM., JR., Assoc. Mem.,
Civil Engineer, Red Wing, Minn.
- DARLING, WILLIAM L., Assoc. Mem.,
Principal Assistant Engineer Northern Pacific Railway,
St. Paul, Minn.
- DAVIS, CHARLES H., Act. Mem.,
Consulting Engineer, 99 Cedar street, New York, N. Y.
- DAVIS, HENRY B., Act. Mem.,
Civil Engineer, Deer Lodge, Mont.
- DEAN, ANDREW L., Act. Mem.,
Superintendent Canadian Smelting Works, Trail, B. C.
- DECKER, RUDOLPH J., Act. Mem.,
Mechanical Engineer, Montana Ore Purchasing Co., Butte, Mont.
- DODGE, JOSEPH T., Hon. Mem.,
Civil Engineer, retired, 346 W. Washington ave., Madison, Wis.
- DOLE, ASHER, Assoc. Mem.,
Assistant Engineer Duluth, Superior and Belt Railway,
Superior, Wis.
- DONOVAN, JOHN J., Assoc. Mem.,
Civil Engineer, 1201 Garden street, New Whatcom, Wash.
- DUNSHEE, BERTRAM H., Act. Mem.,
Assistant Superintendent Boston and Montana Cons.
C. and S. Mining Co., Box 1011, Butte, Mont.
- ELLISON, JAMES H., Assoc. Mem.,
Civil Engineer, 3237 Stevens ave., Minneapolis, Minn.
- FINKELNBURG, OSCAR C., Act. Mem.,
Finkelburg & Catlin, Civil and Mining Engineers,
Missoula, Mont.
- FITCH, HOWARD A., Assoc. Mem.,
Western Agent and Engineer Gillette-Herzog Manufacturing Co.,
Salt Lake, Utah.
- FLOOD, WINFIELD J., Act. Mem.,
Mining Engineer, Anaconda Copper Mining Co.,
832 Quartz street, Butte, Mont.
- FORTINER, WALTER S., Act. Mem.,
Civil Engineer, 4 Colonial Bldg., Seattle, Wash.
- FOSS, GEORGE O., Assoc. Mem.,
Civil Engineer, 410 E. Nineteenth street, Minneapolis, Minn.
- FRANK, ALFRED, Act. Mem.,
Mining Engineer, Montana Ore Purchasing Co., Butte, Mont.
- FRENCH, JOHN, Act. Mem.,
Civil Engineer and Surveyor, P. O. Box 56, Great Falls, Mont.

- FULLER, F. D., Act. Mem.,
Smelter Foreman, Boston and Montana C. C. and S. M. Co.,
Great Falls, Mont.
- GILLIE, JOHN, Act. Mem.,
Superintendent Butte and Boston Con. Mining Co., Butte, Mont.
- GILLIES, DONALD B., Act. Mem.,
Mining Engineer, with C. W. Clark, Butte, Mont.
- GOODALE, CHARLES W., Act. Mem.,
Superintendent of Boston and Montana Cons.
Silver and Copper Mining Co., Great Falls, Mont.
- GOODRIDGE, ELMER O., Assoc. Mem.,
Chief Engineer Power Station, Lowell, Lawrence
and Haverhill Street Railway, Bradford, Mass.
- GRANT, ROBERT D., Act. Mem.,
General Manager Sioux and Utah Con. Mining Co.,
Salt Lake, Utah.
- GUTELIUS, FRED P., Act. Mem.,
Resident Engineer, Canadian Pacific Ry., Nelson, B. C.
- HAND, CARLTON H., Act. Mem.,
Mining Engineer, Butte, Mont.
- HARDENBROOK, D. WALKER, Act. Mem.,
Mining Engineer, Los Angeles, Cal.
- HARPER, JOSEPH H., Act. Mem.,
Harper & Macdonald, Civil and Mining Engineers, Butte, Mont.
- HARRISON, EDMUND P. H., Assoc. Mem.,
Civil Engineer and Contractor, Martinsburg, W. Va.
- HARRISON, WILLIAM H., Assoc. Mem.,
Mining Engineer, Shannon Copper Co., Clifton, Ariz.
- HAVEN, WILLIAM A., Hon. Mem.,
Inspecting Engineer Erie Railway,
Room 10, Erie R. R. Depot, Buffalo, N. Y.
- HEBGEN, MAX, Act. Mem.,
Electrical Engineer, Superintendent Butte Lighting
and Power Co., and General Manager Montana
Power Transmission Co., Butte, Mont.
- HEINZE, F. AUGUST, Act. Mem.,
President and General Manager Montana Ore Purchasing Co.,
Butte, Mont.
- HELLER, DANIEL E., Act. Mem.,
Mining Engineer, 816 Twenty-fourth street, Denver, Col.
- HENLEY, JAMES H., Act. Mem.,
Superintendent Little Johnnie Mine,
301 East Fifth street, Leadville, Col.
- HERRON, JOHN, Assoc. Mem.,
Mine Superintendent Tom Boy Gold Mines, Telluride, Col.
- HOBART, AZELLE E., Act. Mem.,
United States Deputy Mineral Surveyor, Butte, Mont.
- HORN, HENRY J., JR., Act. Mem.,
Superintendent Montana Division N. P. Railway Co.,
Livingston, Mont.
- HOVEY, ALBERT S., Act. Mem.,
Civil and Mining Engineer,
Room 26, Merchants' National Bank Bldg., Helena, Mont.

- INGERSOLL, GEORGE T., Act. Mem.,
 Mechanical Engineer, Butte, Mont.
- JAQUETH, ABRAM L., Act. Mem.,
 City Engineer, Kalispell, Mont.
- KEERL, JAMES S., Act. Mem.,
 Civil and Mining Engineer,
 P. O. Box 374, Rooms 23 and 25, Atlas Block, Helena, Mont.
- KELLEY, WALTER S., Act. Mem.,
 Manager The New Elkhorn Mining Co., Ltd., Leadville, Col.
- KERR, GUY M., Assoc. Mem.,
 Chemist and Metallurgist, 37 Bay street, Glens Falls, N. Y.
- KERR, JAMES H., Assoc. Mem.,
 Geologist and Metallurgist, Hotel Ruliff, Glens Falls, N. Y.
- KETCHUM, MILO S., Assoc. Mem.,
 Assistant Professor of Civil Engineering Illinois State University,
 Champaign, Ill.
- KING, ERNEST W., Act. Mem.,
 Superintendent Great Northern Mining and Development Co.,
 Gilt Edge, Mont.
- KINNEY, EDWARD C., Act. Mem.,
 General Manager West Gallatin Irrigation Co., Manhattan, Mont.
- KLEPETKO, FRANK, Act. Mem.,
 General Manager of The Boston and Montana Cons. Copper and
 Silver Mining Co. and Anaconda Reduction Works,
 Butte, Mont.
- KOBERLE, ALBERT, Act. Mem.,
 Assistant Engineer Anaconda Copper Mining Co.,
 909 Maryland ave., Butte, Mont.
- KORNBERG, GUSTAVE A., Assoc. Mem.,
 Civil Engineer, 112 Taylor street, San Francisco, Cal.
- LEGGAT, J. BENTON, Act. Mem.,
 Mining Engineer, Butte, Mont.
- LEONARD, FRANK M., Act. Mem.,
 Civil and Mining Engineer, Member United States Mineral Land
 Commission, Libby, Mont.
- LEONARD, R. L., Act. Mem.,
 President Montana State School of Mines,
 406 W. Broadway, Butte, Mont.
- MACDONALD, MALCOLM L., Act. Mem.,
 Harper & Macdonald, Civil and Mining Engineers, Butte, Mont.
- MACFARLANE, JAMES, Assoc. Mem.,
 Manager Horseshoe Gold Mining Co., Deer Lodge, Nev.
- MACGINNISS, JOHN, Act. Mem.,
 Vice-President and Manager Montana Ore Purchasing Co.,
 Box 427, Butte, Mont.
- MCARTHUR, ROBERT A., Act. Mem.,
 Mining Engineer Parrot Silver and Copper Co.,
 P. O. Box 757, Butte, Mont.
- MCCORMICK, EDMUND B., Act. Mem.,
 Instructor Mechanical Engineering Montana College of Agricul-
 ture and Mechanic Arts, Bozeman, Mont.
- MCHENRY, EDWIN H., Hon. Mem.,
 Chief Engineer Northern Pacific Railway, St. Paul, Minn.

- McNEILL, EDWARD R., Act. Mem.,
Engineer in Charge of Construction Montana Central Railway,
Boulder, Mont.
- METLEN, GEORGE R., Act. Mem.,
Mining Engineer and United States Deputy Mineral Surveyor,
Dillon, Mont.
- MOORE, CLINTON H., Act. Mem.,
Mine Owner,
Butte, Mont.
- MORRIS, ALBERT A., Act. Mem.,
Civil Engineer,
Billings, Mont.
- McRAE, FINLAY, Act. Mem.,
Clerk First Judicial District Court,
Helena, Mont.
- MAHON, ARCHIBALD W., Act. Mem.,
Civil Engineer, County Surveyor Valley Co.,
Glasgow, Mont.
- MASON, CARLISLE, Act. Mem.,
Mechanical Engineer,
Butte, Mont.
- McCLEAN, WILLIAM M., Act. Mem.,
Mechanical Engineer,
Gilt Edge, Mont.
- MOLSON, CHARLES A., Assoc. Mem.,
Mining Engineer Tom Boy Gold Mines,
Telluride, Col.
- MOULTHROP, GEORGE E., Act. Mem.,
Mining Engineer, Boston and Montana Cons. C. and S. Mining Co.,
P. O. Box 674, Butte, Mont.
- MUNROE, WILLIAM, Act. Mem.,
Civil and Mining Engineer,
Great Falls, Mont.
- PALMER, CHARLES H., Act. Mem.,
Mining Engineer,
No. 532 Exchange, Boston, Mass.
- PAGE, CLARENCE V., Act. Mem.,
Assistant Engineer Anaconda Copper Mining Co.,
Box 922, Butte, Mont.
- PAGE, JAMES M., Act. Mem.,
U. S. Deputy Mineral Surveyor for Montana and Idaho,
Pageville, Mont.
- PAINE, C. W., Act. Mem.,
Engineer in charge of new works, Butte City Water Co.,
Butte, Mont.
- PARKER, LEWIS C., Act. Mem.,
Mining Engineer,
Garnet, Mont.
- PARKER, MAURICE S., Act. Mem.,
Civil and Consulting Engineer,
Ogden, Utah.
- PATTERSON, HENRY M., Act. Mem.,
Architect,
Butte, Mont.
- PATTERSON, JOHN C., Act. Mem.,
Resident Engineer Great Northern Railway,
Great Falls, Mont.
- PUTNAM, BENJAMIN R., Act. Mem.,
Chemist, Montana Ore Purchasing Co.,
Butte, Mont.
- REED, MELVILLE E., Assoc. Mem.,
Assistant Engineer Great Northern Railway, Wellington, Wash.
- REPATH, CHAS. H., Act. Mem.,
Chief Engineer, Anaconda Copper Mining Co.
New Reduction Works,
Anaconda, Mont.
- RIPLEY, THERON M., Act. Mem.,
Prov. Mar. Gen.,
Manila, Philippine Islands.

- ROBINSON, GEO. H., Act. Mem.,
Supt. Mont. Ore Purchasing Co., Butte, Mont.
- ROSS, FRANK A., Assoc. Mem.,
General Manager Stromberg-Carlson Tel. Mfg. Co.,
76 Jackson Boulevard, Chicago, Ill.
- ROURKE, JERRY, Act. Mem.,
Mining Engineer, with W. A. Clark, Butte, Mont.
- RYON, AUGUSTUS M., Assoc. Mem.,
97 Main street, Flushing, N. Y.
- SALES, R. H., Act. Mem.,
Assistant Engineer, Boston and Montana Mining Co.,
Butte, Mont.
- SCHUMACHER, ADAM J., Act. Mem.,
Metallurgist, Dillon, Mont.
- SCOTTEN, FRANK, Act. Mem.,
Assistant Engineer Boston and Montana Cons.
C. and S. Mining Co., P. O. Box 582, Great Falls, Mont.
- SELIGMAN, ALBERT J., Assoc. Mem.,
Civil Eng., Nos. 108-109 Exchange Court, New York City, N. Y.
- SICKLES, EUGENE C., Act. Mem.,
Electrical and Mechanical Engineer, Anaconda Copper Manufacturing Co.,
Butte, Mont.
- SIZER, FRANK L., Act. Mem.,
Mining Engineer, with W. A. Clark, Box 1333, Butte, Mont.
- SHERMAN, FREDERIC W., Assoc. Mem.,
Park City, Utah.
- SMITH, CHARLES P., Act. Mem.,
Civil Engineer, Address unknown.
- SMITH, FORREST J., Act. Mem.,
Chief Mineral Clerk U. S. Surveyor-General's Office,
Helena, Mont.
- SMITH, FRANK M., Act. Mem.,
Manager of Great Falls plant of the United Smelting
and Refining Co., Smelter P. O., Great Falls, Mont.
- STRASBURGER, E. J., Act. Mem.,
Civil Engineer, Butte, Mont.
- SWEARINGEN, CLARENCE W., Act. Mem.,
City Engineer, Great Falls, Mont.
- TAPPAN, CHARLES, Assoc. Mem.,
De LaMar's Nev. Gold Mining Co., Delamar, Nev.
- TAYLOR, FREDERIC J., Act. Mem.,
Assistant Engineer N. P. Ry. Co., Tacoma, Wash.
- THORPE, CLAYTON M., Act. Mem.,
Civil Engineer, County Surveyor Gallatin Co.,
City Hall, Bozeman, Mont.
- TOWER, BURT. A., Act. Mem.,
Mining Engineer, Montana Ore Purchasing Co., Butte, Mont.
- TOWER, GEORGE W., JR., Act. Mem.,
Mining Engineer, Montana Ore Purchasing Co., Butte, Mont.
- TURNER, HARRY W., Act. Mem.,
General Mgr. Butte Lighting and Power Co., Butte, Mont.
- VAIL, CHAS. D., Act. Mem.,
Principal Assistant Engineer, Butte City Water Co.,
Box 561, Butte, Mont.

- VAIL, RICHARD R., Act. Mem.,
Assistant Engineer Anaconda Copper Mining Co.,
Box 561, Butte, Mont.
- VANCE, CHARLES C., Act. Mem.,
Civil Engineer, with Butte City Water Co., Butte, Mont.
- WARWICK, ARTHUR W., Act. Mem.,
Chemist and Mining Engineer,
Care Hersey & Bean, Stillwater, Minn.
- WEED, WALTER H., Act. Mem.,
Geologist U. S. Geological Survey, Washington, D. C.
- WEIR, THOMAS, Act. Mem.,
Consulting and Mining Engineer, Dooly Bldg.,
P. O. Box 57, Salt Lake City, Utah.
- WHEELER, HARRY V., Assoc. Mem.,
Goldsworthy & Wheeler, Civil and Mining Engineers,
128 N. Main street, Los Angeles, Cal.
- WHITCOMB, ADELBERT F., Act. Mem.,
Assistant Engineer G. N. Railway, St. Paul, Minn.
- WHITE, R. T., Assoc. Mem.,
Superintendent Highland Boy Smelter, Murray, Utah.
- WHITE, WILLIAM, Act. Mem.,
Architect, Butte, Mont.
- WHITTEN, BENJAMIN D., Act. Mem.,
Mechanical Engineer, P. O. Box 56, Great Falls, Mont.
- WHYTE, FRED'K W. C., Act. Mem.,
General Manager Coal Department Anaconda Copper Min. Co.,
Belt, Mont.
- WICKES, GEORGE T., Act. Mem.,
Mining Engineer, 602 N. Ewing street, Helena, Mont.
- WILLIAMS, WILLIAM H., Act. Mem.,
Professor of Mechanical and Electrical Engineering,
Montana State College of Agriculture and Mechanic Arts,
Bozeman, Mont.
- WILSON, GEORGE W., Act. Mem.,
Civil Engineer, Philipsburg, Mont.
- WILSON, ELLIOTT H., Act. Mem.,
Civil and Mining Engineer, Butte, Mont.
- WINCHELL, HORACE V., Act. Mem.,
Geologist, Anaconda Copper Mining Co., Butte, Mont.
- WISHON, WALTER W., Act. Mem.,
Superintendent Speculator Mine, Butte, Mont.
- WORD, WILLIAM F., Act. Mem.,
Superintendent Gagnon Mine, Butte, Mont.
- YOUNG, JOHN W., Assoc. Mem.,
Vice-President, Fraser & Chalmers, Chicago, Ill.
- ZASCHKE, WILLIAM, Act. Mem.,
Assistant Engineer Anaconda Copper Mining Co., Butte, Mont.

Technical Society of the Pacific Coast.

- ALLARDT, GEO. F., Mem.,
Civil Engineer, 420 California street, San Francisco, Cal.
- BALLANTYNE, A., Mem.,
Superintendent Light House Construction,
Room 89, Flood Bldg., San Francisco, Cal.
- BARTH, HERMANN, Mem.,
Architect, 601 California street, San Francisco, Cal.
- BASSELL, BURR, Mem.,
Civil Engineer, Standard Electric Company,
Mokelumne Hill, Cal.
- BEHR, H. C., Mem.,
Mechanical Engineer, Capetown, South Africa.
- BEHR, DR. H. H., Assoc. Mem.,
Scientist, Academy of Sciences, San Francisco, Cal.
- BELL, NEWTON M., Assoc. Mem.,
Manufacturer, 116 Battery street, San Francisco, Cal.
- BLOOD, GEO. D., Mem.,
Mining Engineer, Box F, Park City, Utah.
- BOWERS, A. B., Mem.,
Civil Engineer, 101 Sansome street, San Francisco, Cal.
- BOYD, JOS. C., Mem.,
Surveyor, Sacramento, Cal.
- BRANDEGEE, T. S., Mem.,
Scientist, Box 684, San Diego, Cal.
- BRIGHAM, H. A., Mem.,
Mining Engineer, Care Lick House, San Francisco, Cal.
- BRODIE, ALEX. O., Mem.,
Civil Engineer, Crown Point Mine, Crown Point, Ariz.
- BROOKS, T. W., Mem.,
Technologist, Dunham, Carrigan & Hayden Co.,
19 Beale street, San Francisco, Cal.
- BROWN, PERRY F., Mem.,
Civil Engineer,
Room 4, Tenth floor, Mills Bldg., San Francisco, Cal.
- BROWNE, ROSS E., Mem.,
Mining Engineer, Nevada Block, San Francisco, Cal.
- BUCKMAN, O. H., Mem.,
Surveyor, Napa City, Cal.
- BUTCHER, THOMAS W., Assoc. Mem.,
Builder, 4150 Twentieth street, San Francisco, Cal.
- BUXTON, WALTER DE, Mem.,
Civil Engineer, Box 137, Williams, Ariz.
- CHODZKO, A. E., Mem.,
Mechanical Engineer, 220 Market street, San Francisco, Cal.
- CONGDON, CHAS. H., Mem.,
Civil Engineer, Bakers-field, Kern county, Cal.
- CONNICK, HARRIS D., Mem.,
Civil Engineer, Board of Public Works,
City Hall, San Francisco, Cal.

- CROCKETT, J. B., Mem.,
Technologist, President San Francisco Gas and Electric Light Co.,
415 Post street. San Francisco, Cal.
- DAVIS, MAJOR C. E. L. B., Mem.,
Corps of Engineers, United States Army,
90 Flood Bldg., San Francisco, Cal.
- DAVIS, CHAS. HENRY, Mem.,
Consulting Engineer. 99 Cedar street, New York, N. Y.
- DAY, CHAS. A., Assoc. Mem.,
Builder, Builders' Exchange, San Francisco, Cal.
- DENIO, O. H. M., Assoc. Mem.,
Foreman Mason. United States Navy,
Vallejo, Solano county, Cal.
- DICKIE, GEO. W., Life Mem.,
Mechanical Engineer, Manager Union Iron Works,
San Francisco, Cal.
- DOW, GEO. E., Mem.,
Mechanical Engineer, Dow Steam Pump Works,
114 Beale street, San Francisco, Cal.
- DUTTON, HARRY S., Mem.,
Architect, 321 Market street, San Francisco, Cal.
- EATON, FREDERICK, Mem.,
Civil Engineer, Burdick Block, Los Angeles, Cal.
- EDINGER, F. S., Mem.,
Civil Engineer, Bowditch street, Berkeley, Cal.
- ELSEMORE, W. C., Mem.,
City Engineer, Eureka, Cal.
- ERLACH, ARNOLD D', Mem.,
Mechanical Engineer, 3821 Twentieth street, San Francisco, Cal.
- EVANS, GEO. H., Life Mem.,
Mining Engineer, Breckenridge, Col.
- FALKENAU, LOUIS, Mem.,
Chemist, 358 Sacramento street, San Francisco, Cal.
- FERRIS, J. W., Mem.,
Mining Engineer, 320 Sansome street, San Francisco, Cal.
- FORDERER, JOSEPH F., Assoc. Mem.,
Metal Worker, Forderer Cornice Works,
8 Natoma street, San Francisco, Cal.
- FORSYTH, ROBERT, Mem.,
Mechanical Engineer, Union Iron Works, San Francisco, Cal.
- GATES, H. D., Mem.,
Civil Engineer, 311 Lyon street, San Francisco, Cal.
- GJESSING, ERLAND, Assoc. Mem.,
732 Powell street, San Francisco, Cal.
- GRAY, JOHN W., Mem.,
Civil Engineer, 923 Linden street, Oakland, Cal.
- GREUB, ADOLF, Assoc. Mem.,
Instrument Maker,
Care A. Lietz Company, 422 Sacramento street, San Francisco, Cal.
- GRUNSKY, C. E., Mem.,
Civil Engineer, City Engineer, City Hall, San Francisco, Cal.
- GUTZKOW, FRED'K, Mem.,
Mining Engineer, 28 Columbia Square, San Francisco, Cal.

- HAAS, EDWARD F., Mem.,
Civil Engineer, 320 Sansome street, San Francisco, Cal.
- HALL, C. I., Mem.,
Mechanical Engineer, 21 Bernal ave., San Francisco, Cal.
- HALL, WM. HAM., Mem.,
Civil Engineer, Johannesburg, South African Republic.
- HARE, LOU G., Mem.,
Surveyor, Salinas, Monterey county, Cal.
- HARMON, DANA, Mem.,
Mining Engineer, Gaston, Nevada county, Cal.
- HELLMANN, FRED'K., Mem.,
Mining Engineer, Care East Rand Proprietary Mines,
P. O. Box 204, Boksburg, South Africa.
- HENDERSON, E. F., Mem.,
Civil Engineer, Care San Francisco and San Joaquin Valley Ry.,
Fresno, Cal.
- HENNY, D. C., Mem.,
Civil Engineer, Manager Excelsior Wooden Pipe Co.,
204 Front street, San Francisco, Cal.
- HERRMANN, CHARLES, Mem.,
Surveyor, San Jose, Cal.
- HERRMANN, F. C., Mem.,
Civil Engineer, 320 Sansome street, San Francisco, Cal.
- HESSE, FRED'K G., Mem.,
Professor, P. O. Box 452, Oakland, Cal.
- HEUER, COL. WM. H., Mem.,
Corps of Engineers, San Francisco, Cal.
- HEWITT, EDWARD T., Mem.,
Instructor, 619 Capp street, San Francisco, Cal.
- HINDES, STETSON G., Mem.,
Civil Engineer, 330 Market street, San Francisco, Cal.
- HOBSON, J. B., Mem.,
Mining Engineer, Quesnelle Forks, British Columbia.
- HOFFMANN, CHAS. F., Mem.,
Mining Engineer,
Care Ross E. Browne, Nevada Block, San Francisco, Cal.
- HOLLISTER, JOHN J., Mem.,
Civil Engineer, Santa Barbara, Cal.
- HOPPS, JOHN H., Mem.,
Mechanical Engineer, 330 Market street, San Francisco, Cal.
- HUGHES, D. E., Mem.,
Civil Engineer,
(United States Engineers), Box 416, San Diego, Cal.
- HUNT, LOREN E., Jun. Mem.,
Instructor in Civil Engineering,
University of California, Berkeley, Cal.
- IRVING, SAMUEL C., Assoc. Mem.,
Manufacturer, 116 Battery street, San Francisco, Cal.
- JACKSON, BYRON, Mem.,
Mechanical Engineer, 625 Sixth street, San Francisco, Cal.
- JOHNSTON, GEORGE, Mem.,
Mechanical Engineer, 326 Oak street, San Francisco, Cal.

- JONES, EDW. C., Mem.,
Mechanical Engineer, San Francisco Gas and Electric Company,
415 Post street, San Francisco, Cal.
- KEATINGE, RICHARD, Assoc. Mem.,
Builder, Builders' Exchange,
40 New Montgomery street, San Francisco, Cal.
- KELLOGG, H. CLAY, Mem.,
Civil Engineer, Santa Ana, Cal.
- KIEFFER, STEPHEN E., Mem.,
Civil Engineer, Sutter Club, Sacramento, Cal.
- KLUEGEL, C. H., Mem.,
Civil Engineer, P. O. Box 796, Honolulu, H. I.
- KNOWLES, F. E., Assoc. Mem.,
Builder, Builders' Exchange,
40 New Montgomery street, San Francisco, Cal.
- KOWER, HERMANN, Mem.,
Professor, University of California, Berkeley, Cal.
- KURTZ, CHARLES M., Mem.,
Civil Engineer,
Room 4, Tenth Floor, Mills Bldg., San Francisco, Cal.
- LACY, B. T., Mem.,
Mechanical Engineer, 615 Chestnut street, San Francisco, Cal.
- LAMAR, PETER E., Mem.,
Civil Engineer, Honolulu, H. I.
- LARKIN, HARRY, Assoc. Mem.,
Manufacturer, 116 Battery street, San Francisco, Cal.
- LE CONTE, L. J., Mem.,
Civil Engineer, P. O. Box 492, Oakland, Cal.
- LEONARD, JOHN B., Mem.,
Civil Engineer, Care Healy, Tibbetts & Co.,
42 Stewart street, San Francisco, Cal.
- LIETZ, ADOLF, Mem.,
Instrument Maker, 422 Sacramento street, San Francisco, Cal.
- LIVERMORE, NORMAN B., Mem.,
Civil Engineer, Board of Public Works,
City Hall, San Francisco, Cal.
- MAHONEY, JOHN J., Assoc. Mem.,
Builder, 200 Crocker Bldg., San Francisco, Cal.
- MANSON, MARSDEN, Mem.,
Civil Engineer, Board of Public Works,
City Hall, San Francisco, Cal.
- MARX, CHAS. D., Mem.,
Professor, Leland Stanford, Jr., University, Palo Alto, Cal.
- MASOW, FRANK H., Assoc. Mem.,
Builder, Box 133, Builders' Exchange, San Francisco, Cal.
- MCBEAN, P. MCG., Assoc. Mem.,
Manufacturer, 1358 Market street, San Francisco, Cal.
- MCCANN, RICHARD, Assoc. Mem.,
Building Contractor, 217 Waller street, San Francisco, Cal.
- MCCONE, ALEX. J., Assoc. Mem.,
Manufacturer, Fulton Foundry, Virginia City, Nev.
- MCGILVERAY, JOHN D., Assoc. Mem.,
Builder, Builders' Exchange,
40 New Montgomery street, San Francisco, Cal.

- McNICOLL, A. J., Mem.,
Mechanical Engineer, 122 Main street, San Francisco, Cal.
- McPHEE, DANIEL, Assoc. Mem.,
Builder, Nineteenth and Harrison streets, San Francisco, Cal.
- MEESE, CONSTANT, Mem.,
Mechanical Engineer, 129 Fremont street, San Francisco, Cal.
- MENDELL, COL. GEO. H., Mem.,
Military Engineer, Board of Public Works,
City Hall, San Francisco, Cal.
- MERRILL, E. H., Mem.,
Technologist, Standard Oil Co.,
421 Market street, San Francisco, Cal.
- MEYER, HERMANN, Mem.,
Mining Engineer, 1130 Eddy street, San Francisco, Cal.
- MILLER, J. W., Assoc. Mem.,
Builder, 3384 Eighteenth street, San Francisco, Cal.
- MOLERA, E. J., Life Mem.,
Civil Engineer, 2025 Sacramento street, San Francisco, Cal.
- MOORE, R. S., Mem.,
Mechanical Engineer, Risdon Iron Works,
Howard and Beale streets, San Francisco, Cal.
- MORRIN, THOMAS, Mem.,
Mechanical Engineer, Mills Bldg., San Francisco, Cal.
- MORSE, F. B., Mem.,
Mining Engineer, El Parian, Estado de Oaxara, Mexico.
- NOBLE, PATRICK, Mem.,
Mechanical Engineer, Pacific Rolling Mills, San Francisco, Cal.
- OATES, W. W., Mem.,
Architect, Stockton, Cal.
- O'SHAUGHNESSY, M. M., Mem.,
Civil Engineer, Crocker Bldg., San Francisco, Cal.
- POWER, GEO. C., Mem.,
Civil Engineer, San Buenaventura, Ventura county, Cal.
- POWER, HAROLD T., Mem.,
Mining Engineer, Michigan Bluff, Cal.
- PRINDLE, FRANKLIN C., Mem.,
Civil Engineer, United States Navy, Navy Yard, Mare Island, Cal.
- PRUTZMAN, PAUL W., Mem.,
Chemist, Sixteenth and Mississippi streets, San Francisco, Cal.
- QUINAN, WM. R., Mem.,
Chemist, care De Beers Consolidated Mines, Limited,
Guardian Bldg., Cape Town, South Africa.
- RANDALL, H. I., Mem.,
Professor, University of California, Berkeley, Cal.
- RANDLE, GEO. N., Mem.,
Civil Engineer, State Board Public Works, Sacramento, Cal.
- RANSOM, TOM. W., Mem.,
Mechanical Engineer,
330 Market street, Room 611, San Francisco, Cal.
- REID, JAS. W., Mem.,
Architect, Reid Bros., Call Bldg., San Francisco, Cal.
- RICHARDS, JOHN, Mem.,
Mechanical Engineer, 22 California street, San Francisco, Cal.

- RIDLEY, A. E. BROOKS, Mem.,
 Electrical Engineer,
 Parrot Bldg., Fifth Floor, San Francisco, Cal.
- ROSSOW, ERNEST F., Mem.,
 Draftsman,
 Vallejo, Cal.
- SALA, JOS. C., Mem.,
 Instrument Maker, 429 Montgomery street, San Francisco, Cal.
- SANBORN, A. H., Mem.,
 Surveyor, 632 Post street, San Francisco, Cal.
- SCHIERHOLZ, A., Mem.,
 Mechanical Engineer, care Risdon Iron Works, San Francisco, Cal.
- SCHILD, EDWARD T., Assoc. Mem.,
 Manufacturer, Gundlach-Bundschu Wire Co.,
 Second and Market streets, San Francisco, Cal.
- SCHILD, GEO. F., Mem.,
 Naval Architect,
 Vallejo, Cal.
- SCHINDLER, A. D., Mem.,
 Civil Engineer, Yosemite Hotel, Stockton, Cal.
- SCHULZE, HENRY A., Mem.,
 Architect, 94 Flood Bldg., San Francisco, Cal.
- SCHUYLER, J. D., Mem.,
 Civil Engineer,
 524 Stimson Block, Third and Spring streets, Los Angeles, Cal.
- SMITH, WM. P., Mem.,
 Civil Engineer, 1017 Monadnock Bldg., Chicago, Ills.
- SOULÉ, FRANK, Mem.,
 Professor, University of California,
 Berkeley, Cal.
- SPIERS, JAMES, Mem.,
 Mechanical Engineer, Fulton Iron Works, San Francisco, Cal.
- STEWART, COL. C. SEAFORTH, Hon. Mem.,
 Washington, D. C.
- TAYLOR, JAMES T., Mem.,
 Civil Engineer, Honolulu, H. I.
- THOMPSON, LAWRENCE, Mem.,
 Civil Engineer, 915 Geary street, San Francisco, Cal.
- TOWER, MORTON L., Mem.,
 Civil Engineer, United States Engineer Office,
 Empire City, Ore.
- UHLIG, CARL, Mem.,
 Civil Engineer, State Harbor Commission,
 Ferry Bldg., San Francisco, Cal.
- VAIL, R. M., Mem.,
 Civil Engineer, Bowers, Cal.
- VISCHER, HUBERT, Mem.,
 Civil Engineer, United States Debris Commission,
 Flood Bldg., San Francisco, Cal.
- VON GELDERN, OTTO, Mem.,
 Civil Engineer, 1513 Vallejo street, San Francisco, Cal.
- WAGGONER, W. W., Mem.,
 County Surveyor, Nevada City, Cal.
- WAGONER, LUTHER, Mem.,
 Civil Engineer, 705 Chestnut street, San Francisco, Cal.

- WALLACE, JOHN H., Mem.,
Civil Engineer, Southern Pacific Company,
4 Montgomery street, San Francisco, Cal.
- WEPPER, G. W., Mem.,
Mechanical Engineer, Box 2088, Johannesburg, South Africa.
- WETMORE, GEO. P., Assoc. Mem.,
Concrete Builder, 117 Sutter street, San Francisco, Cal.
- WILSON, COMMODORE THEODORE D., Hon. Mem.,
Washington, D. C.
- WING, CHAS. B., Mem.,
Professor, Leland Stanford, Jr., University. Palo Alto, Cal.
- WOLF, J. H. G., Mem.,
Civil Engineer, Fort Baker, San Francisco Harbor, Cal.
- WRIGHT, GEO. A., Mem.,
Architect, Merchants' Exchange Bldg., San Francisco, Cal.

Detroit Engineering Society.

- ALLOR, ELMER L.,
 Attorney-at-Law, with Clark, Durfee, Allor & Marston, 710 Union
 Trust Bldg. Residence, Detroit, Mich.
- ASHWELL, WILLIAM H.,
 Civil Engineer, with Wm. H. Ashwell & Co., 25 Whitney Opera
 House. Residence, Grand ave., Highland Park, Mich.
- ALLEN, JOHN R.,
 Professor Mechanical Engineering, University of Michigan, Ann
 Arbor, Mich.
 Residence, 226 S. Ingalls street, Ann Arbor, Mich.
- AMES, JOSEPH H.,
 Master Mechanic, Michigan Peninsular Car Co., Detroit, Mich.
 Residence, 445 Ferry ave., Detroit, Mich.
- BRIDGE, HENRY,
 Mechanical Engineer, Michigan Portland Cement Co.
 Residence, 24 N. Jefferson ave., Coldwater, Mich.
- BROWN, MASON L.,
 Civil Engineer, with Mason L. Brown, 820-823 Chamber Com-
 merce. Residence, Detroit, Mich.
- BARCROFT, F. T.,
 Civil Engineer, with Joy & Barcroft, 407-8 Ferguson Bldg.
 Residence, 122 Westminster ave., Detroit, Mich.
- BRINKERHOFF, W. E.,
 Draftsman, Detroit Bridge and Iron Works. Detroit, Mich.
- BOTHFELD, CHARLES C.,
 Civil Engineer, Iron and Steel Contractor, 34 Home Bank.
 Residence, 183 W. Fort street, Detroit, Mich.
- BIBBINS, J. R.,
 B.Sc., Edison Illuminating Co., Detroit, Mich.
 Residence, 56 Hastings street, Detroit, Mich.
- BIGLER, F. S.,
 Secretary, Michigan Bolt and Nut Works.
 Residence, Detroit, Mich.
- BISSELL, H. S.,
 With Shaw-Kendall Co., Toledo, Ohio.
 Residence, Toledo, Ohio.
- BURTON, CHARLES F.,
 Attorney, 12 Hodges Block, Detroit.
 Residence, 50 Brainard street, Detroit, Mich.
- CALDER, CHARLES B.,
 General Superintendent Detroit Shipbuilding Co.
 Residence, 67 Avery ave., Detroit, Mich.
- CONANT, WILLIAM S.,
 Consulting Engineer, 36 Moffat Block.
 Residence, 25 Eliot street, Detroit, Mich.
- COLLAMORE, RALPH,
 Assistant Engineer, with Field & Hinchman, 1206 Majestic Bldg.
 Residence, The Clayton, Detroit, Mich.
- COLBY, ARCHIE L.,
 Engineer, Detroit Bridge and Iron Works.
 Residence, 371 Vinewood ave., Detroit, Mich.

- COURTIS, WILLIAM MUNROE,
A.M., U. S. Potash Co., 412 Hammond Bldg.
Residence, 449 Fourth ave., Detroit, Mich.
- CORSE, WILLIAM M.,
S. B. M. I. T. '99, Detroit White Lead Works, 500 E. Milwaukee
ave. Residence, 26 Hendrie ave., Detroit, Mich.
- COLBURN, BURNHAM STANDISH,
Secretary and Treasurer Canadian Bridge Co., Ltd., Walkerville,
Ont. Residence, 25 Richard street, Detroit, Mich.
- CEDERSTROM, B. E.,
Mechanical Engineer, with Sammel F. Hodges & Co., 320 Atwater
street. Residence, 180 N. Grand Boulevard, Detroit, Mich.
- COOLEY, MORTIMER E.,
Professor Mechanical Engineering, University of Michigan, Ann
Arbor, Mich. Res., 727 S. State street, Ann Arbor, Mich.
- COFFIN, CHARLES L.,
Residence, 35 Medbury ave., Detroit, Mich.
- CAMPAU, M. WOOLSEY,
Draftsman, Dry Dock Engine Works, Detroit, Mich.
Residence, 564 Congress street, E. Detroit, Mich.
- DEMICK, A. H.,
Superintendent Engineer, Gilbert, Wilkes & Co., Union Trust Bldg.
Residence, Detroit, Mich.
- DOW, ALEXANDER,
General Manager, Edison Illuminating Co., 18 Washington ave.
Residence, 844 Cass ave., Detroit, Mich.
- DUNLAP, FRANK M.,
Mechanical Engineer, 57 Selden ave.
Residence, 57 Selden ave., Detroit, Mich.
- DOUGLAS, BENJAMIN,
Bridge Engineer, Michigan Central Ry., Detroit, Mich.
Residence, Grosse Isle, Mich.
- DAVIS, JOSEPH BAKER,
Professor Geodesy and Surveying, University of Michigan, Ann
Arbor. Residence, Ann Arbor, Mich.
- DENISON, CHARLES S.,
Professor, University of Michigan, Ann Arbor.
Residence, 502 E. Huron street, Ann Arbor, Mich.
- DIERKES, ANTHONY F.,
Draftsman, Detroit Water Works.
Residence, 962 Bellevue ave., Detroit, Mich.
- DIXON, CHARLES Y.,
Assistant Engineer, United States Improvement, Detroit River.
Residence, Amherstburg, Ontario, Canada.
- DUNCAN, W. J.,
Assistant Bridge Engineer, Michigan Central Ry., M. C. R. R.
Depot, Detroit. Residence, 660 John R street, Detroit, Mich.
- DU PONT, ANTOINE B.,
With St. Louis Transit Co., St. Louis, Mo.
- FIELD, HENRY GEORGE,
Consulting Engineer, with Field & Hinchman, 1206 Majestic Bldg.
Residence, 1477 Grand River ave., Detroit, Mich.
- FENKELL, GEORGE H.,
Chief Draftsman, Detroit Water Office, 232 Jefferson ave.
Residence, 275 Balwin ave., Detroit, Mich.

- FARMER, THOMAS, JR.,
Mechanical Engineer, Detroit Citizens' Street Railway, 12 Woodward ave. Residence, 68 Piquette ave., Detroit, Mich.
- GREEN, RUTGER B.,
Solvay Process Co. Residence, Detroit, Mich.
- GALWEY, J. H.,
Inspector, United States Inspection Service, 210 Old Federal Bldg. Residence, 79 Leverette street, Detroit, Mich.
- GOLDMARK, HENRY,
Resident Engineer, with Geo. S. Morrison, 35 Wall street. Residence, 270 W. Ninety-fourth street, New York.
- GREEN, A. H., JR.,
Manager Solvay Process Co. Residence, 64 Lafayette ave., Detroit, Mich.
- GERHAUSER, WILLIAM,
Mechanical Engineer, 1107 Chamber Commerce. Residence, 562 Congress street, E. Detroit, Mich.
- GREENE, CHARLES E.,
Professor Civil Engineering, University of Michigan, Ann Arbor. Residence, 415 E. William street, Ann Arbor, Mich.
- HASKELL, EUGENE E.,
United States Assistant Engineer, Engineer's Corps, United States Army, Jones' Bldg. Residence, Alhambra Flats, Detroit, Mich.
- HODGE, HARRY S.,
President Samuel Hodge & Co., Inc., 320 Atwater street. Residence, 66 Winder street, Detroit, Mich.
- HUBBELL, CLARENCE W.,
Civil Engineer Board Water Com., 232 Jefferson ave. Residence, 327 Field ave., Detroit, Mich.
- HANFORD, HERBERT O.,
Draftsman Detroit Water Office. Residence, 837 Fifteenth street, Detroit, Mich.
- HAWKS, JAMES D.,
President Detroit and Mackinac Ry. Co. Residence, 999 Jefferson ave., Detroit, Mich.
- HINCHMAN, THEODORE H., JR.,
Consulting Engineer, with Field & Hinchman, 1206 Majestic Bldg. Residence, 267 E. Larned street, Detroit, Mich.
- HEWITT, EDGAR,
Draftsman, Detroit Water Office, Detroit, Mich.
- KIMBALL, GEO. H.,
Chief Engineer, Pere Marquette Railway, Union Station. Residence, 117 Henry street, Detroit, Mich.
- KEEP, WILLIAM J.,
Superintendent, Michigan Store Co. Residence, 753 Jefferson ave., Detroit, Mich.
- KIEFER, ARTHUR E.,
Secretary and Treasurer Detroit Edge Tool Works, Detroit, Mich. Residence, 884 Congress street, E. Detroit, Mich.
- KIRBY, FRANK E.,
Chief Engineer, Detroit Dry Dock Co. Residence, 555 Woodward ave., Detroit, Mich.

- KING, W. C.,
City Engineer's Office, 16 City Hall.
Residence, 150 Calumet ave., Detroit, Mich.
- LITTLE, F. A.,
Civil Engineer, Standard Engine Co., 1101-2-3 Chamber Commerce.
Residence, 565 Bagg street, Detroit, Mich.
- LUNN, ERNEST,
Edison Illuminating Co., Miami ave., Detroit.
- LELAND, HENRY M.,
General Superintendent, Leland & Faulconer Mfg. Co.
Residence, 69 Watson street, Detroit, Mich.
- LEWIS, JACOB F.,
With John T. McRoy, 302 Broadway, New York, N. Y.
- LIVINGSTONE, WILLIAM A.,
Manufacturer, 40 Eliot street, Detroit, Mich.
- MAXWELL, DAVID,
Bridge Engineer, with Riter-Conley Co., Pittsburg, Pa.
Residence, 204 North ave., Allegheny, Pa.
- McMATH, FRANCIS C.,
President and Engineer Canadian Bridge Co., Walkerville, Ont.
Residence, 29 Rowena street, Detroit, Mich.
- McCRICKETT, THOS.,
With Russel Wheel and Foundry Co.
Residence, 12 Howard street, Detroit, Mich.
- MAURICE, WALTER B.,
B.S., Michigan Tax Com.
Residence, 1285 Jefferson ave., Detroit, Mich.
- MOLITOR, DAVID,
Consulting and Civil Engineer, Fred. Rueping Leather Co.
Residence, 125 Harney street, Fond du Lac, Mich.
- MOLITOR, EDWARD,
Assistant Chart Construction, United States Lake Survey, Room
14, Jones Bldg. Residence, 93 Winder street, Detroit, Mich.
- MASON, F. H.,
Michigan and N. W. Ohio Rep., Harrison Safety Boiler Works,
79 Moffat Block. Residence, 630 Cass ave., Detroit, Mich.
- MATTSSON, A. GEORGE,
Mechanical Engineer, Detroit Dry Dock Engineering Works,
Detroit, Mich.
- MASSON, GEORGE,
Civil Engineer, 39 Columbia street, E. Detroit, Mich.
- MORLEY, H. T.,
11 Kanter Bldg. Residence, 57 Canfield ave., W. Detroit, Mich.
- MARSHALL, A. C.,
Electrical Engineer, Rapid Railway Co.
Residence, 621 Second ave., Detroit, Mich.
- NEWKIRK, WALTER M.,
Buhl Malleable Co. Residence, 91 Winder street, Detroit, Mich.
- PIERSON, GEO. S.,
Consulting Engineer, Hydraulic and Sanitary Work,
Kalamazoo, Mich.
- PETTEE, WILLIAM H.,
Professor, University of Michigan, Ann Arbor, Mich.
Residence, 554 Thompson street, Ann Arbor, Mich.

- POPE, WILLARD,
President Detroit Bridge and Iron Works.
Residence, 37 Putman ave., Detroit, Mich.
- PARKS, GEORGE E.,
Mechanical Engineer, M. C. R. R., M. C. Car Shops.
Residence, 593 W. Boulevard, Detroit, Mich.
- PENTON, JOHN A.,
Publisher, *The Foundry*, 37 Buhl Block.
Residence, 26 Tuxedo ave., Detroit, Mich.
- PORTER, GEORGE F.,
Draftsman, Detroit Bridge and Iron Works,
Residence, 170 Twenty-third street, Detroit, Mich.
- ROBINSON, GEORGE A.,
Civil Engineer, City Engineer's Office, City Hall.
Residence, 425 Cass ave., Detroit, Mich.
- RUSSELL, WALTER E.,
Vice-President and Manager, Russel Wheel and Foundry Co.
Residence, 863 Jefferson ave., Detroit, Mich.
- RAYMOND, ALEXANDER B.,
Sanitary Engineer, Detroit Board of Health, Health Office.
Residence, 91 Prentiss ave., Detroit, Mich.
- REID, E. S.,
Mechanical Engineer, Northern Engine Works.
Residence, 505 Fourth ave., Detroit, Mich.
- RATHBONE, JNO. A.,
Superintendent United States Heater Co., Detroit, Mich.
- RUSSELL, C. W.,
Superintendent Russel Wheel and Foundry Co.
Residence, 75 Farnsworth street, Detroit, Mich.
- STEWART, C. B.,
Civil Engineer, Chicago Union Traction Co., 2521 Kenmore ave.,
Chicago. Residence, Anchor, Ill.
- STEPHENS, CLARENCE M.,
Civil Engineer, Alpena.
Residence, Sherman House, Mt. Clemens, Mich.
- SABIN, L. C.,
United States Assistant Engineer, Corps United States Engineers,
Port Huron. Residence, Detroit, Mich.
- SACK, RICHARD E.,
Draftsman, Edison Illuminating Co., 18 Washington ave.
Residence, 88 Preston street, Detroit, Mich.
- SMITH, JESSE M.,
Mechanical and Electrical Engineer, Room M 14, 220 Broadway,
New York. Residence, 7 W. Ninety-second street, New York.
- SCOTT, WILLIAM,
Superintendent Roe, Stephens Mfg. Co.
Residence, 697 Fourteenth ave., Detroit, Mich.
- SANDERSON, EDMUND L.,
Residence, 43 Alexandrine ave., W. Detroit, Mich.
- TORREY, AUGUSTUS,
Chief Engineer, Michigan Central Railway, Room 31 Michigan
Central Depot. Residence, 174 Henry street, Detroit, Mich.

- TUTHILL, G. C.,
Assistant Bridge Engineer, Michigan Central Railway, Michigan
Central Depot, Room 74.
Residence, 107 Horton ave., Detroit, Mich.
- TIPPEY, B. O.,
Mechanical Engineer, Detroit City Gas Co.
Residence, 131 Lafayette ave., Detroit, Mich.
- VAN TUYL, FRANK,
Electrical Engineer, Washtenaw Electric Co., Ypsilanti, Mich.
Residence, 324 Forest ave., Ypsilanti, Mich.
- WRIGHT, SIDNEY B.,
Assistant Purchasing Agent, Michigan Central Railroad.
Residence, 786 Congress street, Detroit, Mich.
- WILLIAMS, E. E.,
Mechanical Engineer, with W. R. Callahan & Co., E. Third street,
Dayton, Ohio. Residence, 229 Grafton ave., Dayton, Ohio.
- WRENTMORE, C. G.,
M. S., University of Michigan, Ann Arbor.
Residence, Ann Arbor, Mich.
- WHEELER, E. S.,
Assistant Engineer, United States Engineer's Office, Jones Bldg.
Residence, 76 Delaware ave., Detroit, Mich.
- WISNER, G. Y.,
Civil Engineer, 34 W. Congress street.
Residence, 39 W. Canfield ave., Detroit, Mich.
- WEIL, CHAS. L.,
Professor Mechanical Engineering, Mechanical Agricultural Col-
lege, Agricultural College P. O., Mich.
- WOLFENDEN, HEN. L.,
Civil Engineer, with Gilbert Wilkes & Co.,
1112 Union Trust Bldg., Detroit, Mich.
- WHITAKER, H. E.,
Mechanical Engineer, Cor. Fourth and Abbott Sts.
Residence, 301 Forest ave., Detroit, Mich.
- WILKES, GILBERT,
Consulting Engineer, with Gilbert Wilkes & Co.,
1112 Union Trust Bldg., Detroit, Mich.
- WILLIAMS, G. S.,
Professor, Experimental Hydraulics, Cornell University,
4 Valentine Place, Ithaca, N. Y.
- ZIWET, ALEX.,
Professor, University of Michigan, Ann Arbor.
Residence, 644 S. Ingalls street, Ann Arbor, Mich.

Engineers' Society of Western New York.

-
- ALVERSON, HARRY B., Mem.,
Superintendent Cataract Power and Construction Co.,
Buffalo, N. Y.
- BABCOCK, C. E. P., Mem.,
Assistant Engineer, Department Public Works,
13 City Hall, Buffalo, N. Y.
- BAPST, FRANK L., Mem.,
Contractor,
1348 Main street, Buffalo, N. Y.
- BARDOL, F. V. E., Mem.,
Chief Engineer, Department Public Works,
13 City Hall, Buffalo, N. Y.
- BASSETT, GEO. B., Mem.,
Manager Buffalo Meter Co.,
363 Washington street, Buffalo, N. Y.
- BOOZ, HORACE COREY, Mem.,
Assistant Engineer, Pennsylvania Railroad (S. W. Div.),
433 Prospect ave., Buffalo, N. Y.
- BOARDMAN, CHAS. S., Mem.,
Assistant Engineer,
702 Ellicott Square, Buffalo, N. Y.
- BRACKENRIDGE, W. A., Mem.,
Engineer, Cataract Construction Co.,
Niagara Falls, N. Y.
- BUSCH, CHAS. V., Mem.,
Private Practice,
Mooney Bldg., Buffalo, N. Y.
- BUSCH, GEO. M., Mem.,
Private Practice,
Mooney Bldg., Buffalo, N. Y.
- BUTTOLPH, H. T., Mem.,
Deputy Chief Engineer, Department Public Works,
13 City Hall, Buffalo, N. Y.
- CAINES, ALBERT W., Assoc.,
15 Waverly street, Buffalo, N. Y.
- CARLTON, NEWCOMB, Mem.,
Director of Works, Pan-American Exposition,
Service Bldg., Buffalo, N. Y.
- CLAHAN, JOHN J., Mem.,
Superintendent Buffalo Gas Co.,
133 Whitney Place, Buffalo, N. Y.
- CLARK, HENRY, Mem.,
Contractor,
794 Auburn avenue, Buffalo, N. Y.
- CORNELL, DOUGLAS, Mem.,
Structural Engineer, Bureau of Buildings,
Municipal Bldg., Buffalo, N. Y.
- DARK, SAMUEL J., Assoc.,
93 Windsor ave., Buffalo, N. Y.
- DAVIS, CHAS. HENRY, Mem.,
Private Practice,
99 Cedar street, Buffalo, N. Y.
- DECROW, DAVID AUGUSTUS, Mem.,
Designing Engineer for Holly Manufacturing Co., Lockport, N. Y.
- DIEHL, GEORGE C., Mem.,
Private Practice,
836 Ellicott Square, Buffalo, N. Y.

- EIGHMY, LEE W., Mem.,
Assistant and Engineer, Department Public Works,
13 City Hall, Buffalo, N. Y.
- ELLSWORTH, JOHN F., Mem.,
Private Practice, Franklin and Eagle streets, Buffalo, N. Y.
- FELL, CHARLES F., Mem.,
Assistant Engineer, Department Public Works,
13 City Hall, Buffalo, N. Y.
- FIELDS, S. J., Mem.,
Chief Engineer, Pan-American Exposition,
Service Bldg., Buffalo, N. Y.
- FOSTER, HORATIO A., Mem.,
Consulting Engineer, 310 Chestnut street, Philadelphia, Pa.
- FRANKLIN, JAMES, Jun.,
699 Seventh street, Buffalo, N. Y.
- FRANKLIN, WILLIAM, JR., Assoc.,
699 Seventh street, Buffalo, N. Y.
- FRUAFF, GEO. PH., Mem.,
Leveler, Department Public Works,
13 City Hall, Buffalo, N. Y.
- GARDINER, MATHEW S., Jun.,
144 Seventh street, Buffalo, N. Y.
- GASKIN, E. F., Mem.,
Superintendent Union Dry Dock Co.,
Ganson street, Buffalo, N. Y.
- GORHAM, MARVINE, Mem.,
Buffalo Bolt and Nut Works,
250 Elmwood avenue, Buffalo, N. Y.
- GUTHRIE, E. B., Mem.,
Chief Engineer, Grade Crossings Commission,
436 Ellicott Square, Buffalo N. Y.
- HAMMOND, RICHARD, Mem.,
President Lake Erie Engineering Works,
Perry street, Buffalo, N. Y.
- HARROWER, H. C., Mem.,
Iron and Steel Contractor, 35 Court street, Buffalo, N. Y.
- HAVEN, W. A., Mem.,
Inspecting Engineer, Erie Railroad,
Erie R. R. Depot, Buffalo, N. Y.
- HERRON, JOHN T., Mem.,
Engineer, Buffalo Gas Co., 248 Prospect avenue, Buffalo, N. Y.
- HILL, H. M., Mem.,
City Chemist, University of Buffalo, Buffalo, N. Y.
- HOFFMAN, A. W., Mem.,
Assistant Engineer, Department Public Works,
13 City Hall, Buffalo, N. Y.
- HOUCK, WM. C., Mem.,
Member of firm, Buffalo Structural Steel Works,
97 High street, Buffalo, N. Y.
- HUBBELL, GEO. S., Mem.,
Corps of Engineers, U. S. A., Adjuntas, Porto Rico, U. S. A.
- HUNTINGTON, EMMET W., Assoc.,
Contractor, 666 Main street, East Rochester, N. Y.

- HUMBERT, W. S., Mem.,
Sears-Humbert Cement Co.,
432 Prudential Bldg., Buffalo, N. Y.
- JOHNSON, WALLACE C., Mem.,
Niagara Falls Power Co.,
Niagara Falls, N. Y.
- KIELLAND, S. M., Mem.,
Civil Engineer, Buffalo Creek Railroad,
351 Humboldt Parkway, Buffalo, N. Y.
- KNAPP, L. H., Mem.,
Assistant Superintendent and Engineer, Bureau of Water,
Municipal Bldg., Buffalo, N. Y.
- KNIGHTON, JOHN A., Mem.,
Assistant Engineer, Grade Crossing Commission,
436 Ellicott Square, Buffalo, N. Y.
- LEWIS, CLARENCE CHAS., Mem.,
Engineer of Way, Buffalo Railway Co.,
Buffalo, N. Y.
- LUFKIN, E. C., Mem.,
Manager Snow Steam Pump Works,
150 W. North street, Buffalo, N. Y.
- MARCH, H. J., Mem.,
Assistant Engineer, Department Public Works,
13 City Hall, Buffalo, N. Y.
- MARSH, GEORGE E., Jun.,
108 Plymouth ave., Buffalo, N. Y.
- MARTIN, DR. T. J., Assoc.,
Rep. Buffalo Branch N. Y. Electric Vehicle and Trans. Co.,
279 North street, Buffalo, N. Y.
- MCCULLOH, WALTER, Mem.,
Private Practice,
Crick Block, Niagara Falls, N. Y.
- MEYER, CARL, Mem.,
Member of firm, Buffalo Bridge Works,
P. O. Box 170, Buffalo, N. Y.
- MORSE, CHAS. M., Mem.,
Mechanical Engineer,
Erie Bank Bldg., Buffalo, N. Y.
- MORSE, GEO. FRED'K, Mem.,
21 Columbus Place, Buffalo, N. Y.
- MARBURG, LOUIS, Assoc.,
Contractor,
264 Hoyt street, Buffalo, N. Y.
- MONIER, CHAS., Assoc.,
Contractor,
1266 Seneca street, Buffalo, N. Y.
- NORTON, GEO. H., Mem.,
Assistant Engineer, Department Public Works,
13 City Hall, Buffalo, N. Y.
- PATCH, MAURICE B., Mem.,
Buffalo Smelting Works,
1 Austin street, Buffalo, N. Y.
- POWELL, S. W., Mem.,
679 Auburn avenue, Buffalo, N. Y.
- ROGERS, THOS. J., Mem.,
Engineer, Park Department, 1322 Prudential Bldg., Buffalo, N. Y.
- RICKER, GEO. A., Mem.,
Private Practice,
702 Ellicott Square, Buffalo, N. Y.
- ROBERTS, GEO. T., Mem.,
Assistant Engineer, Department Public Works,
13 City Hall, Buffalo, N. Y.

- ROCKWOOD, A. J., Mem.,
 Division Engineer, N. Y. State Canal, Rochester, N. Y.
- SIKES, G. R., Mem.,
 Private Practice, 957 Ellicott Square, Buffalo, N. Y.
- SMITH, T. GUILFORD, Mem.,
 Vice-President N. Y. Car Wheel Works,
 9 German Insurance Bldg., Buffalo, N. Y.
- SORNBERGER, E. C., Mem.,
 Snow Steam Pump Works, 208 Lancaster avenue, Buffalo, N. Y.
- SPEYER, F. N., Mem.,
 Assistant Engineer, Grade Crossings Commission,
 436 Ellicott Square, Buffalo, N. Y.
- SYMONS, THOS. W., Hon. Mem.,
 Major of Engineers, U. S. A., Morgan Bldg., Buffalo, N. Y.
- TEIPER, CASPER, Mem.,
 Member of firm, Buffalo Structural Steel Works,
 24 Briggs avenue, Buffalo, N. Y.
- TRESISE, F. J., Mem.,
 Draftsman, Department Public Works,
 13 City Hall, Buffalo, N. Y.
- TUTTON, C. H., Mem.,
 Engineer. Grattan & Jennings, Ft. Main street, Buffalo, N. Y.
- VANDERHOEK, J., Mem.,
 Division Engineer, Lehigh Valley Railroad,
 L. V. R. R. Depot, Buffalo, N. Y.
- WITFORD, O. F., Mem.,
 Private Practice, 79 Woodlawn avenue, Buffalo, N. Y.
- WILSON, THOS. WM., Mem.,
 Assistant Engineer, Buffalo Railway Co.,
 448 Elmwood avenue, Buffalo, N. Y.
- WESTON, ALONZO H., Mem.,
 Service Bldg., Pan-American Exposition,
 Care S. J. Fields, Buffalo, N. Y.
- WITMER, J. F., Mem.,
 Civil Engineer, 705 Ellicott Square, Buffalo, N. Y.
- YOUNGS, JASPER S., Mem.,
 831 Seventh street, Buffalo, N. Y.

Louisiana Engineering Society.

- ARMSTRONG, J. W., Mem.,
Draftsman, Sewerage and Water Board,
602 Carondelet street, New Orleans.
- BEER, S. T., Jun. Mem.,
Engineering Supplies, Baronne, near Canal, New Orleans.
- BELL, A. C., Mem.,
Civil Engineer, Room 20 Denegre Bldg., New Orleans.
- BENSON, ROBT. B., Mem.,
Assistant Engineer, Drainage Commission,
City Hall, New Orleans.
- BLACK, A. L., Mem.,
Engineer St. Charles Street Railroad Co.,
2300 Decatur street, New Orleans.
- BLAKEMORE, A. B., Mem.,
General Manager C. C. Stock Yard and Slaughter House Co.,
New Orleans.
- BLANCHIN, GEO., Mem.,
Contractor, 316 Baronne street, New Orleans.
- BROWN, L. W., Mem.,
Civil and Mechanical Engineer,
741 Carondelet street, New Orleans.
- BROWNLEE, JAS. L., Mem.,
United States Assistant Engineer,
Custom House Bldg., New Orleans.
- CALONGNE, SIDNEY A., Assoc. Mem.,
Paving Contractor, 806 Perdido street, New Orleans.
- CAMORS, FREDERIC, Assoc. Mem.,
Dredge Contractor, 505 Tchoupitoulas street, New Orleans.
- CHAMBERLIN, C. H., Mem.,
Resident Engineer, Texas and Pacific Railroad,
106 Thalia street, New Orleans.
- CLEGG, JUDGE JNO., Assoc. Mem.,
Attorney-at-Law, 814 Hennen Bldg., New Orleans.
- COLEMAN, J. F., Mem.,
Civil Engineer, Firm of Coleman & Malochée,
121 Carondelet street, New Orleans.
- CROTTS, WM. T., Mem.,
Assistant Engineer, Sewerage and Water Board, New Orleans.
- DAVIS, CHAS. HENRY, Mem.,
Consulting Engineer, 99 Cedar street, New York city.
- DE BUYS, R. E., Mem.,
Civil and Architectural Engineer,
421 Carondelet street, New Orleans.
- D'HEUR, ALLARD, Mem.,
Engineer, Southern Pacific Railroad, Wumemucca, Nev.
- DUVAL, A. C., Mem.,
Chief Draftsman, State Board of Engineers, New Orleans.
- EARL, GEO. G., Mem.,
General Superintendent, Sewerage and Water Board,
602 Carondelet street, New Orleans.

- EASTWOOD, JOHN T., Mem.,
Assistant Engineer, Sewerage and Water Board,
602 Carondelet street, New Orleans.
- FLANAGAN, P. J., Assoc. Mem.,
Building Inspector, City Engineer's Office, New Orleans.
- FRAWLEY, JNO. J., Assoc. Mem.,
Contractor, 315 Carondelet street, New Orleans.
- GIBBENS, WILL. J., Mem.,
Gibbens & Stream, Sugar Machinery,
213 Carol street, New Orleans.
- GODCHAUX, JULES, Assoc. Mem.,
Planter, Raceland, La.
- GRASSER, E. A., Assoc. Mem.,
Contractor, 1306 Seventh street, New Orleans.
- HARDEE, WM. J., Mem.,
City Engineer, City Hall, New Orleans.
- HARRISON, G. B., Mem.,
Division Superintendent, Bridges and Buildings, Texas and Pacific
Railroad Co., Boyce, La.
- HARROD, MAJ. B. M., Mem.,
Chief Engineer, Drainage Commission, City Hall, New Orleans.
- HAUGH, JAS. C., Mem.,
Resident Engineer, New Orleans and Northeastern Railroad Co.,
Press and Levee streets, New Orleans.
- HAYGOOD, GEO. L., Mem.,
Civil Engineer, 921 St. Louis street, New Orleans.
- HAZLEHURST, J. M., Mem.,
Civil Engineer, 606 Commercial Place, New Orleans.
- HOFFMAN, WALTER H., Mem.,
Secretary State Board of Engineers,
Cotton Exchange Bldg., New Orleans.
- HYATT, E. C., Mem.,
Inspector, Drainage Commission, City Hall, New Orleans.
- IYV, ERNEST D., Mem.,
Engineer and Agent, Heine Boiler Co.,
Godechaux Bldg., New Orleans.
- JANCKE, ERNEST LEE, Mem.,
Superintendent Jancke Navigation Co.,
816 Howard ave., New Orleans.
- KERR, FRANK M., Mem.,
Civil Engineer, Cotton Exchange Bldg., New Orleans.
- KIRKLAND, W. C., Mem.,
Assistant Engineer, Drainage Commission,
City Hall, New Orleans.
- KLORER, JNO., Mem.,
Assistant United States Engineer,
1810 Dumaine street, New Orleans.
- LAMBERT, E. L., Mem.,
Assistant Engineer, Drainage Commission,
City Hall, New Orleans.
- LAWES, G. W., Mem.,
Assistant Draftsman, State Board of Engineers,
Cotton Exchange, New Orleans.

- LEWIS, S. F., Mem.,
Assistant State Engineer, Cotton Exchange, New Orleans.
- LION, L. E., Mem.,
Civil Engineer, 1010 Burgun'y street, New Orleans.
- LLEWELLYN, F. P., Mem.,
Engineer of Gillette-Herzog Mfg. Co.,
Room 1012 Hennen Bldg., New Orleans.
- LOCKETT, A. M., Mem.,
A. M. Lockett & Co., Contracting Mechanical Engineers,
330 Carondelet street, New Orleans.
- LOMBARD, GERVAIS, Mem.,
Engineer, Orleans Levee Board,
337 St. Charles street, New Orleans.
- MALOCHEE, H. J., Mem.,
Mechanical Engineer and Electrical Engineer, Firm of Coleman &
Malochée, 121 Carondelet street, New Orleans.
- MANNING, JOS. E., Assoc. Mem.,
Contractor, Room 306 Hennen Bldg., New Orleans.
- MIDDLEMISS, GEO. A., Mem.,
Assistant Engineer, New Orleans Drainage Commission,
City Hall, New Orleans.
- MULLEN, F. P., Assoc. Mem.,
General Manager, Barber Asphalt Paving Co.,
Hennen Bldg., New Orleans.
- MCCARKENDALE, WM., Mem.,
Chief Engineer, Edison Electric Co.,
317 Baronne street, New Orleans.
- McKINNEY, E. B., Mem.,
Chief Engineer New Orleans City Railroad Co. Power House,
1515 Constance street, New Orleans.
- NELSON, A. J., Mem.,
Manager New Orleans Roofing and Metal Works,
701 L. and L. and G. Bldg., New Orleans.
- ORDWAY, JOHN M., Mem.,
Civil Engineer, 3125 Chestnut street, New Orleans.
- PERRILLIAT, ARSENE, Mem.,
Assistant State Engineer, Cotton Exchange Bldg., New Orleans.
- RAYMOND, ALFRED, Mem.,
General Manager, New Orleans Drainage Commission,
City Hall, New Orleans.
- RAYMOND, CHAS. L., Mem.,
First Assistant Engineer, Drainage Commission,
City Hall, New Orleans.
- RICHARDSON, MAJ. HENRY B., Mem.,
Chief State Engineer of Louisiana,
Cotton Exchange Bldg., New Orleans.
- RICHARDSON, JOHN F., Mem.,
Assistant Engineer, Sewerage and Water Board,
602 Carondelet street, New Orleans.
- ROBERTSON, MARSHALL P., Mem.,
Assistant State Engineer, Cotton Exchange Bldg., New Orleans.
- SAMSON, P. H. Mem.,
New Orleans Wood Preserving Works,
3907 Magazine street, New Orleans.

- SMITH, WRIGHT, Mem.,
Assistant City Engineer, City Hall, New Orleans.
- STEWART, HUNTER, Mem.,
Civil Engineer, 218 Bourbon street, New Orleans.
- THEFARD, A. F., Mem.,
Assistant Engineer, Drainage Commission,
City Hall, New Orleans.
- THOMPSON, H. B., Mem.,
Assistant State Engineer, Cotton Exchange Bldg., New Orleans.
- TUTWILER, T. H., Mem.,
Engineer, New Orleans and Carrollton Railroad Co.,
L. and L. and G. Bldg., New Orleans.
- VILLERE, ST. DENIS J., Mem.,
Electrical and Mechanical Engineer,
2139 Dauphine street, New Orleans.
- VON PHUL, WILLIAM, Mem.,
Superintendent Edison Electric Co.,
317 Baronne street, New Orleans.
- WADDILL, F. H., Mem.,
Civil Engineer of Daney & Waddill,
Masonic Temple, New Orleans.
- WHITE, E. P., Mem.,
Superintendent of Estate of S. L. James,
601 Hennen Bldg., New Orleans.
- WHITE, W. M., Mem.,
Assistant General Manager, New Orleans Drainage Commission,
City Hall, New Orleans.
- WHITE, W. S., Mem.,
Engineer, Hunter Canal Co., Le Roy, La.
- WILLARD, BEN., Mem.,
Electrical Engineer and Manager General Electric Co.,
917 Hennen Bldg., New Orleans.
- WILLOZ, VICTOR L., Mem.,
Superintendent Orleans Railroad Co.,
1118 Marais street, New Orleans.
- WRIGHT, W. B., Mem.,
Assistant Engineer, Drainage Commission,
City Hall, New Orleans.
- ZANDER, HENRY L., Mem.,
Draftsman, New Orleans Drainage Commission,
City Hall, New Orleans.

Engineers' Club of Cincinnati.

- ANDERSON, LATHAM, Hon. Mem.,
Civil Engineer, Kuttawa, Ky.
- BAIRD, SAMUEL P., Act. Mem.,
Superintendent Portsmouth Street R. R. and Light Co.,
Portsmouth, Ohio.
- BALDWIN, BERT L., Act. Mem.,
Mechanical Engineer, 72 Perin Bldg., Cincinnati, Ohio.
- BALDWIN, HADLEY, Act. Mem.,
Engineer Maintenance of Way, Cleveland, Cincinnati, Chicago and
St. Louis Railway, Indianapolis, Ind.
- BALDWIN, WARD, Act. Mem.,
Consulting Engineer, 64 Mitchell Bldg., Cincinnati, Ohio.
- BIRCH, THOS. H., Act. Mem.,
Engineer and Assistant Manager Stacey Mfg. Co.,
239 Mill street, Cincinnati, Ohio.
- BIRCH, WM. W., Act. Mem.,
Assistant Engineer Stacey Mfg. Co.,
239 Mill street, Cincinnati, Ohio.
- BOGEN, LOUIS E., Act. Mem.,
Instructor in Physics, University of Cincinnati,
547 Hale ave., Avondale, Cincinnati, Ohio.
- BOUSCAREN, G., Act. Mem.,
Chief Engineer, Board of Trustees, Commissioners of Water
Works, City Hall, Cincinnati, Ohio.
- BRECKINRIDGE, CABELL, Act. Mem.,
Civil Engineer, Danville, Ky.
- BRYAN, R. A., Act. Mem.,
Civil Engineer, Portsmouth, Ohio.
- CALDWELL, J. NELSON, Act. Mem.,
U. S. Assistant Engineer, Custom House, Cincinnati, Ohio.
- CARLISLE, JOHN, Act. Mem.,
Carlisle Bldg., Cincinnati, Ohio.
- CARPENTER, E. J., Act. Mem.,
U. S. Assistant Engineer, Custom House, Cincinnati, Ohio.
- CARROLL, EUGENE, Act. Mem.,
Constructing Engineer and Superintendent Butte City Water Co.,
Butte, Mont.
- CONEY, W. W., Assoc. Mem.,
Dealer in Cement, etc., 1434 Main street, Cincinnati, Ohio.
- COWPER, JOHN W., Act. Mem.,
Engineer Maintenance of Way, Cleveland, Cincinnati, Chicago
and St. Louis Railway, Mattoon, Ill.
- COX, ALLAN, Act. Mem.,
Civil Engineer, Covington, Ky.
- CREAGHEAD, THOS. J., Act. Mem.,
President and General Manager Creaghead Engineering Co.,
802 Plum street, Cincinnati, Ohio.
- DAVIS, CHAS. H., Act. Mem.,
Civil Engineer, 99 Cedar street, New York, N. Y.

- DEVEREUX, H., Act. Mem.,
Resident Engineer Baltimore and Ohio Southwestern Ry.,
North Vernon, Ind.
- DIEMER, HUGO, Act. Mem.,
Professor M. E., Michigan Agricultural College,
Agricultural College P. O., Mich.
- DOANE, WM. H., Act. Mem.,
President Central Trust and Safe Deposit Co.,
Albany Bldg., Cincinnati, Ohio.
- DRESES, HENRY, Act. Mem.,
Dreses, Mueller & Co., Mfrs. of Machine Tools,
2261 Buck street, Cincinnati, Ohio.
- ELZNER, A. O., Act. Mem.,
Architect,
18 E. Fourth street, Cincinnati, Ohio.
- ENGLE, ROBERT L., Act. Mem.,
Civil Engineer,
1530 Westminster ave., Cincinnati, Ohio.
- EWING, CHAS. A., Act. Mem.,
Missouri, Kansas and Texas Railroad, New Braunfield, Texas.
- FALES, FRANK L., Act. Mem.,
Assistant Engineer Board of Trustees, Commissioners of Water
Works, City Hall, Cincinnati, Ohio.
- FENTON, B. W., Act. Mem.,
Superintendent Findlay, Ft. Wayne and Western R. R.,
Findlay, Ohio.
- FLINN, ESTUS T., Act. Mem.,
Road Master Southern Pacific Ry. Co., Tucson, Ariz.
- FRANK, ALFRED, Act. Mem.,
Montana Ore Purchasing Co., Butte, Mont.
- FRITCH, L. C., Act. Mem.,
Superintendent O. and M. Division, Baltimore and Ohio South-
western Railway, Washington, Ind.
- FRICTSCH, JOS. L., Act. Mem.,
Draftsman, Chief Engineer's Office, Board of Trustees, Commis-
sioners of Water Works, City Hall, Cincinnati, Ohio.
- GARRARD, JEPHTHA, Assoc. Mem.,
Attorney-at-Law, 407 Johnston Bldg., Cincinnati, Ohio.
- GOLDFOGLE, DAVID, Act. Mem.,
Civil Engineer, Dennison Hotel, Cincinnati, Ohio.
- GORDON, C. M., Act. Mem.,
County Surveyor, Brown county, Georgetown, Ohio.
- GRAY, GEO. A., Act. Mem.,
Manufacturer of Machine Tools,
Gest and Depot streets, Cincinnati, Ohio.
- GREEN, WM. C., Assoc. Mem.,
Manager Warren, Webster & Co., and O. H. Jewell Filter Co.,
42 Perin Bldg., Cincinnati, Ohio.
- HAUCK, ALBERT L., Act. Mem.,
Secretary and Treasurer The Manass Shoe Mfg. Co.,
709 Sycamore street, Cincinnati, Ohio.
- HOBART, JAS. C., Act. Mem.,
Secretary and Manager Triumph Electric and Ice Machine Co.,
610 Baymiller street, Cincinnati, Ohio.
- HILLER, JOHN A., Act. Mem.,
Assistant Engineer, Board of Trustees, Commissioners of Water
Works, 2545 Eastern ave., Cincinnati, Ohio.

- HOSBROOK, J. A., Act. Mem.,
Civil Engineer, 420 Pike Bldg., Cincinnati, Ohio.
- INNES, H. C., Act. Mem.,
Superintendent Warren-Scharf Asphalt Paving Co., 64 Blymyer
Bldg., Cincinnati, Ohio. or Hartwell, Ohio.
- JEWETT, WM. C., Act. Mem.,
Resident Engineer, Board of Trustees, Commissioners of Water
Works, 541 Ridgeway ave., Cincinnati, Ohio.
- KITTREDGE, GEO. W., Act. Mem.,
Chief Engineer Cleveland, Cincinnati, Chicago and St. Louis Ry.,
Cincinnati, Ohio.
- KNOWLTON, CHAS. A., Act. Mem.,
United States Resident Engineer, Guantanamo, Cuba.
- KOCH, H. A., Act. Mem.,
S. and R. R. V. R. R., Shreveport, La.
- LAIDLAW, WALTER, Act. Mem.,
President Laidlaw-Dunn-Gordon Co., Steam Power and Hand
Pumps, Mill and Factory Supplies.
Pearl and Plum streets, Cincinnati, Ohio.
- LANE, H. M., Act. Mem.,
President Lane & Bodley Co., Iron Founders, Engine, Boiler and
Saw Mill Builders, Cincinnati, Ohio.
- LIETZE, ERNST, Act. Mem.,
Mechanical Engineer, 13 Longworth street, Cincinnati, Ohio.
- LILLY, JAMES A., Act. Mem.,
Engineer and Road Master Cincinnati, Lebanon and Northern Ry.,
Cincinnati, Ohio.
- McAVOY, IRVING, Act. Mem.,
Southern Pacific Company, Gila Bend, Ariz.
- MEEDS, C. H., Act. Mem.,
Assistant U. S. Engineer, 518 Walnut street, Cincinnati, Ohio.
- MILLER, CLIFFORD N., Act. Mem.,
Assistant Engineer, Board of Trustees, Commissioners of Water
Works, City Hall, Cincinnati, Ohio.
- MITCHELL, F. S., Act. Mem.,
Engineer for R. M. Quigley & Co., Contractors, California, Ohio.
- MORRIS, FRANK E., Act. Mem.,
Assistant Engineer, Board of Public Service, City Hall,
or 2846 Harrison ave., Cincinnati, Ohio.
- NICHOLSON, G. B., Act. Mem.,
Chief Engineer Cincinnati, New Orleans and Texas Pacific Ry. Co.,
530 Garrard street, Covington, Ky.
- OSBORN, S. J., JR., Assoc. Mem.,
Roofing, Paving and Sidewalk Contractor,
Pearl and Eggleston ave., Cincinnati, Ohio.
- PETRY, ALFRED, Act. Mem.,
Resident Engineer, Board of Trustees, Commissioners of Water
Works, California, Ohio.
- PFISTER, HERMAN, Assoc. Mem.,
Instrument Maker, 428 Plum street, Cincinnati, Ohio.
- PUNSHON, THOS. B., Act. Mem.,
Civil Engineer and Surveyor, Glenn Bldg., Cincinnati, Ohio.
- RABBE, J. A., Act. Mem.,
Civil Engineer, 404 Pike Bldg., Cincinnati, Ohio.

- RANDOLPH, EFES, Act. Mem.,
Division Superintendent Southern Pacific Co., Tucson, Ariz.
- READ, ROBT. L., Act. Mem.,
Civil Engineer, 32 East Third street, Cincinnati, Ohio.
- RUGGLES, W. B., Act. Mem.,
Assistant Engineer, Department Western Cuba, Matanzas, Cuba.
- SCARBOROUGH, F. W., Act. Mem.,
Signal Engineer Chesapeake and Ohio Ry., Richmond, Va.
- SCHREIBER, CHARLES C., Assoc. Mem.,
Vice-President and General Manager L. Schreiber & Sons Co.,
Mfrs. of Architectural Iron Works,
Eighth street and Eggleston ave., Cincinnati, Ohio.
- SIEFERT, FRANK J., Act. Mem.,
Engineer Department Board of Public Service,
City Hall, Cincinnati, Ohio.
- STANLEY, H. J., Act. Mem.,
Chief Engineer, Board of Public Service,
City Hall, Cincinnati, Ohio.
- STEWART, JAS. A., Act. Mem.,
Civil Engineer, 517 Johnston Bldg., Cincinnati, Ohio.
- STUART, A. A., Act. Mem.,
Engineer and Manager for M. T. Davis, construction of Substructure Quebec Bridge,
Sillery P. O., Canada.
- TOTTEN, A. I., Act. Mem.,
Civil Engineer, 30 Woodland ave., Lexington, Ky.
- TOTTEN, W. H. D., Assoc. Mem.,
Resident Agent for Carnegie Steel Co., Lim., Pittsburg, Pa.,
Neave Bldg., Cincinnati, Ohio.
- VENABLE, M. W., Act. Mem.,
Civil Engineer, 56 Capitol street, Charleston, W. Va.
- VENABLE, W. M., Act. Mem.,
With National Contracting Co., 11 Broadway, New York, N. Y.
- WALSIL, M., Assoc. Mem.,
Superintendent Bridges and Buildings, C., N. O. and T. P. Ry. Co.,
Somerset, Ky.
- WALTER, HARRISON B., Act. Mem.,
General Contractor, Box 32, Danville, Ill.
- WARDER, R. H., Assoc. Mem.,
410 W. Eighth street, Cincinnati, Ohio.
- WARRINGTON, H. E., Act. Mem.,
Assistant Engineer, Cincinnati, New Orleans and Texas Pacific
Ry. Co., Odd Fellows' Temple, Cincinnati, Ohio.
- WHITE, I. F., Act. Mem.,
Superintendent Track and Structures, Cincinnati, Hamilton and
Dayton Ry., Hamilton, Ohio.
- WILSON, C. A., Act. Mem.,
Chief Engineer, Cincinnati, Hamilton and Dayton Ry.,
Carew Bldg., Cincinnati, Ohio.
- WILSON, J. F., Act. Mem.,
Chief Clerk, Engineer Department, Board of Trustees, Commis-
sioners of Water Works, City Hall, Cincinnati, Ohio.
- WRAPPELMEIER, F. W., Act. Mem.,
Chicago and Alton Railroad, Bloomington, Ill.
- WULFF, ADOLPH G., Act. Mem.,
Engineer with Joslin, Schmidt & Co., Chemical Engineers,
Spring Grove ave., opposite Bates, Cincinnati, Ohio.

MEMBERS ARE ADVISED . .
THAT THEY CAN OBTAIN

Reprints or Extra Copies of their Papers

AT THE FOLLOWING RATES:

			4 pages or less	5 to 8 pages	9 to 16 pages	17 to 24 pages	Covers extra.
100	Copies	. .	\$2.25	\$4.00	\$5.50	\$9.25	\$2.25
250	"	. .	2.75	5.00	6.50	11.25	2.75
500	"	. .	3.50	6.50	8.75	15.00	3.50
1000	"	. .	4.50	8.75	12.50	21.00	4.50

An extra charge will be made for printing and inserting such illustrations as are not printed on the same pages as the text, and for enameled paper, when this is used, but it is of course impossible to name rates for this in advance.

When reprints are wanted, notice of the fact, stating how many are desired and whether they are to be furnished with covers, should accompany the paper when it is sent to the Secretary of the Association.

If the paper has been discussed, please state whether it is desired that the reprint shall contain the discussion.

JOHN C. TRAUTWINE, Jr., Secretary,

257 SOUTH FOURTH STREET,
PHILADELPHIA.

JOURNAL

OF THE

Association of Engineering Societies.

BOSTON. CLEVELAND. MINNEAPOLIS. LOUISIANA.
MONTANA. ST. PAUL. BUFFALO. CINCINNATI.
DETROIT. PACIFIC COAST. ST. LOUIS.

CONTENTS AND INDEX.

VOLUME XXVII.

July to December, 1901.

PUBLISHED BY

THE BOARD OF MANAGERS OF THE ASSOCIATION OF
ENGINEERING SOCIETIES.

JOHN C. TRAUTWINE, JR., *Secretary*, 257 S. FOURTH STREET, PHILADELPHIA.

CONTENTS.

VOL. XXVII, July-December, 1901.

For alphabetical index, see page v.

No. 1. JULY.

	PAGE
Stone Arch Bridges Recently Constructed on the Fitchburg Railroad. <i>Albert S. Cheever</i>	1
Arch Centers. <i>James W. Rollins, Jr.</i>	9
Notes on the Industries of the Upper Rhine. <i>John Richards</i>	16
Proceedings.	

No. 2. AUGUST.

The Pitot Tube; Its Formula. <i>William Monroe White</i>	35
Discussion. <i>Messrs. Fenkell, Hubbell, Williams, Ferris and White</i>	67
A Plan to Utilize Unemployed Labor. <i>James A. Stewart</i>	80
Obituary.—Benjamin Thomas Lacy	85
Proceedings.	

No. 3. SEPTEMBER.

Efficiency of Multiple Voltage Control in Electric Power Transmission. <i>Lehman B. Hoit</i>	87
Discussion. <i>C. H. Benjamin</i>	97
The Position of the Engineer in Municipal Service. <i>Alex Dow</i>	99
Proceedings.	

No. 4. OCTOBER.

The Ore-Handling Plant at the Carrie Furnaces, Nos. 3 and 4, of the Homestead Steel Works of the Carnegie Steel Company. <i>W. L. Coates</i>	113
The Baltimore Dry Dock of the Wm. Skinner and Sons' Shipbuilding and Dry Dock Company. <i>James Ritchie</i>	131
Proceedings.	

No. 5. NOVEMBER.

The Lower Mississippi River: Physical Characteristics, Methods of Improvement, Character and Volume of Traffic. <i>J. A. Ockerson</i> ..	139
--	-----

The Abolition of Grade Crossings on the Providence Division of the New York, New Haven and Hartford Railroad, between Boston and Dedham. <i>Arthur S. Tuttle</i>	163
The Sewerage of New Orleans. <i>W. T. Crofts</i>	190
Proceedings.	

No. 6. DECEMBER.

Smoke Abatement in St. Louis. <i>Wm. H. Bryan</i>	215
Efficiency of Compound Centrifugal Pumps. <i>Prof. F. G. Hesse</i>	232
Summer Street Viaduct, South Boston. <i>Herman K. Higgins</i>	236
Proceedings.	

INDEX.

VOL. XXVII, July-December, 1901.

The six numbers were dated as follows:

No. 1, July.	No. 3, September.	No. 5, November.
No. 2, August.	No. 4, October.	No. 6, December.

ABBREVIATIONS.—P = Paper; D = Discussion; I = Illustrated.
Names of authors of papers, etc., are printed in *italics*.

	PAGE
Abolition of Grade Crossings on the Providence Division of the New York, New Haven and Hartford Railroad, between Boston and Dedham. <i>Arthur S. Tuttle</i>P., I., Nov.,	163
Arch Bridges. Stone—Recently Constructed on the Fitchburg Railroad. <i>Albert S. Cheever</i>P., I., July	1
Arch Centers. <i>James W. Rollins, Jr.</i>P., I., July,	9
Baltimore Dry Dock of the Wm. Skinner and Sons' Shipbuilding and Dry Dock Company. <i>James Ritchie</i>P., I., Oct.,	131
Bridges. Stone Arch—Recently Constructed on the Fitchburg Railroad. <i>Albert S. Cheever</i>P., I., July,	1
<i>Bryan, Wm. H.</i> —Smoke Abatement in St. Louis.....P., I., Dec.,	215
Carnegie Steel Company. Ore-Handling at the Carrie Furnaces, Nos. 3 and 4, of the Homestead Steel Works of— <i>W. L. Cowles</i> .	
P., I., Oct.,	113
Carrie Furnaces. The Ore-Handling Plant at the—, Nos. 3 and 4, of the Homestead Steel Works of the Carnegie Steel Company.	
<i>W. L. Cowles</i>P., I., Oct.,	113
Centers. Arch—. <i>James W. Rollins, Jr.</i>P., I., July,	9
Centrifugal Pumps. Efficiency of Compound—. <i>Prof. F. G. Hesse</i> .	
P., I., Dec.,	232
<i>Cheever, Albert S.</i> Stone Arch Bridges Recently Constructed on the Fitchburg RailroadP., I., July,	1
Compound Centrifugal Pumps, Efficiency of—. <i>Prof. F. G. Hesse</i> .	
P., I., Dec.,	232

	PAGE
<i>Cowles, W. L.</i> Ore-Handling at the Carrie Furnaces, Nos. 3 and 4, of the Homestead Steel Works of the Carnegie Steel Company.	
	P., I., Oct., 113
<i>Crotts, W. T.</i> Sewerage of New Orleans.....	P., I., Nov., 190
Dry Dock, Baltimore—of the Wm. Skinner and Sons' Shipbuilding and Dry Dock Company. <i>James Ritchie</i>	P., I., Oct. 131
Efficiency of Compound Centrifugal Pumps. <i>Prof. F. G. Hesse</i> .	
	P., I., Dec., 232
Efficiency of Multiple Voltage Control in Electric Power Transmission. <i>Lehman B. Hoit</i>	P., D., I., Sept., 87
Electric Power Transmission. Efficiency of Multiple Voltage Control in—. <i>Lehman B. Hoit</i>	P., D., I., Sept., 87
Engineer. Position of the—in Municipal Service. <i>Alex Dow</i> .	
	P., Sept., 99
Fitchburg Railroad. Stone Arch Bridges Recently Constructed on the—. <i>Albert S. Cheever</i>	P., I., July, 1
Grade Crossings. Abolition of—on the Providence Division of the New York, New Haven and Hartford Railroad, between Boston and Dedham. <i>Arthur S. Tuttle</i>	P., I., Nov., 163
Hesse, <i>Prof. F. G.</i> Efficiency of Compound Centrifugal Pumps.	
	P., I., Dec., 232
<i>Hoit, Lehman B.</i> Efficiency of Multiple Voltage Control in Electric Power Transmission	P., D., I., Sept., 87
Homestead Steel Works. Ore-Handling Plant at the Carrie Furnaces, Nos. 3 and 4, of—. <i>W. L. Cowles</i>	P., I., Oct., 113
Industries. Notes on the—of the Upper Rhine. <i>John H. Richards</i> .	
	P., July, 16
Labor, Unemployed—A Plan to Utilize—. <i>James A. Stewart</i> .	
	P., Aug., 80
Lacy, Benjamin Thomas—. Obituary	I., Aug., 85
Lower Mississippi River: Physical Characteristics, Methods of Improvement, Character and Volume of Traffic. <i>J. A. Ockerson</i> .	
	P., I., Nov., 139
Mississippi River. Lower—Physical Characteristics, Methods of Improvement, Character and Volume of Traffic. <i>J. A. Ockerson</i> .	
	P., I., Nov., 139
Multiple Voltage Control in Electric Power Transmission. Efficiency of—. <i>Lehman B. Hoit</i>	P., D., I., Sept., 87
Municipal Service. Position of the Engineer in—. <i>Alex Dow</i> .	
	P., Sept., 99
New Orleans. Sewerage of—. <i>W. T. Crotts</i>	P., I., Nov., 190
New York, New Haven and Hartford Railroad. Abolition of Grade Crossings on the—. <i>Arthur S. Tuttle</i>	P., I., Nov., 163
Notes on the Industries of the Upper Rhine. <i>John Richards</i> ..	P., July, 16

Obituary. Benjamin Thomas Lacy. Technical Society of the Pacific Coast	P., L., Aug.,	85
Ockerson, J. J. The Lower Mississippi River: Physical Characteristics, Methods of Improvement, Character and Volume of Traffic.	P., L., Nov.,	139
Ore-Handling Plant at the Carrie Furnaces, Nos. 3 and 4, of the Homestead Steel Works of the Carnegie Steel Company. <i>W. L. Cowles</i>	P., L., Oct.,	113
Pitot Tube; Its Formula. <i>Wm. Munroe White</i> ,	P., D., L., Aug.,	35
Plan to Utilize Unemployed Labor. <i>James A. Stewart</i> ,	P., Aug.,	80
Position of the Engineer in Municipal Service. <i>Alex Dore</i> , ...	P., Sept.,	99
Providence Division of the New York, New Haven and Hartford Railroad. Abolition of Grade Crossings on the—between Boston and Dedham. <i>Arthur S. Tuttle</i> ,	P., L., Nov.,	163
Pumps. Efficiency of Compound Centrifugal—, <i>Prof. F. G. Hesse</i> ,	P., L., Dec.,	232
Power Transmission. Efficiency of Multiple Voltage Control in Electricity—, <i>Lehman B. Hoit</i>	P., D., L., Sept.,	87
Rhine. Notes on the Industries of the Upper—, <i>John Richards</i> ,	P., July,	16
<i>Richards, John</i> . Notes on the Industries of the Upper Rhine..	P., July,	16
<i>Ritchie, James</i> . Baltimore Dry Dock of the Wm. Skinner and Sons' Shipbuilding and Dry Dock Company,	P., L., Oct.,	131
River—the Lower Mississippi—Physical Characteristics, Methods of Improvement, Character and Volume of Traffic. <i>J. A. Ockerson</i> ,	P., L., Nov.,	139
<i>Rollins, James W., Jr.</i> Arch Centers	P., L., July,	9
Sewerage of New Orleans. <i>W. T. Crotts</i> ,	P., L., Nov.,	190
Smoke Abatement in St. Louis. <i>Wm. H. Bryan</i> ,	P., L., Dec.,	215
Steel Works, Homestead—, The Ore-Handling Plant at the Carrie Furnaces, Nos. 3 and 4, of the—of the Carnegie Steel Company. <i>W. L. Cowles</i>	P., L., Oct.,	113
<i>Stewart, James A.</i> Plan to Utilize Unemployed Labor, ...	P., Aug.,	80
St. Louis. Smoke Abatement in—, <i>Wm. H. Bryan</i> , ...	P., L., Dec.,	215
Stone Arch Bridges Recently Constructed on the Fitchburg Railroad. <i>Albert S. Cheever</i>	P., L., July,	1
Tube. Pitot—Its Formula. <i>Wm. Munroe White</i> ,	P., D., L., Aug.,	35
<i>Tuttle, Arthur S.</i> Abolition of Grade Crossings on the New York, New Haven and Hartford Railroad, between Boston and Dedham.	P., L., Nov.,	163
Unemployed Labor. Plan to Utilize—, <i>James A. Stewart</i> ,	P., Aug.,	80
Upper Rhine. Notes on the Industries of the—, <i>John Richards</i> ,	P., July,	16
<i>White, Wm. Munroe</i> . Pitot Tube; Its Formula,	P., D., L., Aug.,	35
Wm. Skinner and Sons' Shipbuilding and Dry Dock Company. Baltimore Dry Dock of—, <i>James Ritchie</i> ,	P., L., Oct.,	131

Editors reprinting articles from this journal are requested to credit not only the JOURNAL, but also the Society before which such articles were read.

ASSOCIATION OF ENGINEERING SOCIETIES.

Organized 1881.

VOL. XXVII.

JULY, 1901.

No. 1.

This Association is not responsible for the subject-matter contributed by any Society or for the statements or opinions of members of the Societies.

STONE ARCH BRIDGES RECENTLY CONSTRUCTED ON THE FITCHBURG RAILROAD.

BY ALBERT S. CHEEVER, MEMBER BOSTON SOCIETY OF CIVIL ENGINEERS.

[Read before the Society, December 19, 1900.*]

DURING the fifteen months just past, five stone arch bridges have been constructed on the Fitchburg Railroad. The construction of these arches, instead of steel bridges, was primarily due to the high prices of structural steel which prevailed during the year 1899, and to the difficulty of getting quick delivery after orders were placed. The bridges were located as follows:

(a) One double track railroad bridge, having two spans of 140 feet each, carrying the Cheshire Branch over the Connecticut River at Bellows Falls, Vt.

(b) One highway bridge, having two spans of 38 feet each and two spans of 14 feet each, carrying New Street, in Fitchburg, Mass., over the Nashua River.

(c) One highway bridge, having two spans of 40 feet each, carrying Putnam Street, in Fitchburg, Mass., over the Nashua River.

(d) One double-track railroad bridge, having two spans of 100 feet each, carrying the tracks of the Fitchburg Railroad over the Hoosick River at Hoosick Junction, N. Y.

(e) One double-track railroad bridge, having one span of 58 feet, carrying the tracks of the Fitchburg Railroad over the Tomhannock River near Schaghticoke, N. Y.

The largest and most interesting of these structures is the bridge at Bellows Falls. In the latter part of August, 1899, it be-

*Manuscript received May 27, 1901.—Secretary, Ass'n of Eng. Socs.

came evident that the old wooden bridge which had carried trains ever since the construction of the Cheshire Railroad, was in such condition that immediate renewal was necessary. The old bridge (Fig. 1) was a double-track bridge of the trussed-arch type, the arches consisting of four members of white pine, each 10 x 16 inches in section, the lower chord being hung by rods from the arch when the latter was above the chord, and supported on the arch when the arch was below the lower chord. The old bridge was 38 feet wide over all. For twenty years only one track has been used, it having been thought unsafe to load the middle truss, which was apparently the same as the outside trusses, with trains on both



FIG. 1. OLD BRIDGE AT BELLOWS FALLS.

tracks at the same time. At the time named, the price of steel was very high and it was impossible to get delivery of bridges until the middle of winter.

Owing to the impossibility of erecting and maintaining false work in the river at that point during the winter and spring, it was probable that if a steel bridge had been ordered at once, it would not have been safe to begin erection earlier than about the middle of May. It was also found that stone arches for a double-track bridge could be built for a little more than a single-track steel bridge, and for considerably less than a double-track steel bridge would cost, and that there would be time to build the arches before cold weather set in. The water in the river was then very low, and there was not much probability of a material rise unless heavy rains

should occur during the fall. For these reasons it was deemed best to build arches, and contractors were found who were willing and ready to take the risk of starting at once. Work was begun on September 12th, on November 19th trains were running over a trestle built on the arches, and on December 7th the masonry was completed. The site of the bridge, which is almost directly over the falls, is particularly well adapted for arches, as the bed and banks of the river are of solid ledge, and there is a natural pier of rock in the middle of the river, dividing the stream into two channels. The



FIG. 2. NEW BRIDGE AT BELLOWS FALLS.

westerly channel is much deeper than the other, and in dry weather carries all the water. At low water the larger part of the water in the river is held up by the dam about a quarter of a mile above the site of the bridge, and is carried around through the canal and the mills, and is discharged into the river channel a short distance below the bridge. During all the time of construction only a small amount of water was passing under the bridge, so that it was possible to place all the posts carrying the false work directly on the ledge, the width of the channel to be spanned being only 40 feet. Nature having already supplied the abutments, it was only necessary to bed the skewback stones in Portland concrete enough to fill

up the holes in the rock, and give a smooth and even bearing. The span of the arches was fixed by the natural conditions, and the rise was limited by the old bridge which had to be kept in place for the operation of trains. The arch ring was carried as close as it was possible to lay stone under the bottom chord of the bridge, and, in order to work with all possible rapidity, the outside trusses and one track of the bridge, which was a three-truss double-track bridge, were removed. This left only 12 feet of the width of the arches under the bridge, and made it possible to lay the ring stones without difficulty, except a few at the crown of the arches, which had to be handled by tackle attached to the floor of the bridge. The ring stones are 4 feet thick, 2 feet wide and from 6 to 8 feet long. There are 72 courses in each arch. The stones are cut to a $\frac{1}{2}$ -inch joint on the intrados, opening to 2 inches on the extrados. As the stones were laid, V-shaped strips of wood were fitted between the joints on the intrados, to prevent the mortar from dropping out. The joints were then filled with Portland cement mortar, mixed one part of cement to two of sand, and they were thoroughly tamped with strips of $3 \times \frac{1}{2}$ -inch iron about 4 feet long, so that every crevice was completely filled. After this was done, as many pinner stones as could be put in were forced into the joints. The arch first built was turned in six days, the second in four days. Considerable discussion arose as to the probable amount of settlement which would occur, and, to provide for it, the centers were made 3 inches high. Before the rings were closed the weight of the stone settled the centers 1 inch, but after the centers were removed no settlement whatever could be measured in either of the arches. After the arches were turned, it was an easy matter to build the rubble masonry of the side walls, and this was rapidly done. Trains were transferred to a single-track trestle built on the arches and the remaining part of the old bridge was thrown into the river bed and burned. The centers were removed in the latter part of December, so that they were in place only about a month after the second arch was turned. The completed bridge is shown in Fig. 2 and in Plate I. The dimensions and quantities of the work are as follows:

Span of arches	140 feet.
Rise of arches	20 "
Thickness of rings	4 "
Width of arch sheeting	27 "
Width of bridge at track level	29 "
Length of coping over all	414 "
First-class masonry	1,443 cu. yards.
Third-class masonry	2,467 " "
Timber in centers	232 M feet.

At the same time that the Bellows Falls arch was started, the work of abolishing the grade crossings at Water and Putnam Streets at Fitchburg was going on. The plan provided for two steel bridges with plank floors for carrying highways over the Nashua River. As there was a strong desire among the citizens of Fitchburg to have solid floors with granite paving, it was finally arranged to substitute arches for the steel highway bridges. The high price of steel brought the cost of a bridge, heavy enough to carry a floor of I-beams and concrete arches, to about that of a stone arch bridge. The angle of the crossing of New Street (Plate II) and the river is 45° , and if the skew arches had been built, the cost would have been




FIG. 3. BRIDGE AT HOOSICK JUNCTION.

prohibitive. It seemed at first rather startling, and opposed to the usual practice, to build skew arches with the joints parallel to their axes, and to cut off the ends on so great an angle, especially as there was only 30 feet of the total length of 70 feet of the abutments squarely opposite. Arches had been built in a similar manner, but no case came to notice where the ends had been cut at so great an angle. Faith in the efficacy of Massachusetts granite and Portland cement finally prevailed, and the arches were built with joints made in the same manner as at Bellows Falls. As this work caused considerable comment among observers, the contractors, as soon as the first river arch was turned, before any of the backing and side walls had

been built and after centers had been drawn, placed a hoisting engine on the keystone at one end of the arch and a derrick on the other end, using them to handle the larger part of the stone laid in the second arch and in the side walls. This was a good object lesson, and thoroughly proved the stability of the arch. When the centers were removed there was no settlement, and no cracks have appeared. The span of these arches is 38 feet, the rise 19 feet. The ring stones are $2\frac{1}{2}$ feet thick.

The bridge carrying Putnam Street over the river was similar to that at New Street, except that the angle of skew was much smaller, only 25° . The span of these is 40 feet, the rise $12\frac{1}{2}$ feet.




FIG. 4. CENTERING AT HOOSICK JUNCTION.

The arch bridge built at Hoosick Junction (Fig. 3 and Plate III) was constructed to replace a two-span iron bridge which was too light for the increased weight of the engines now in use. In order to bring the cost of a masonry bridge down to the cost of a new steel bridge, it was necessary to build the cheapest kind of work that would be sufficient. Cut ring stones could not be used, on account of the expense, and such good success had resulted from the use of open joints tamped full of Portland cement mortar that it seemed perfectly safe and proper to build a rubble arch in the same way, using large sheet stones just as they were taken from the quarry. The railroad company is fortunate in having, on its line, a

quarry in which the seams are regular and parallel, and so even that the natural beds of the stones are almost good enough for ashlar work without any cutting. All the stone used in the bridge was from this quarry. The end ring stones alone were cut, all the rest of the arch sheeting being made of rough stone. The centers were covered tightly with plank (Fig. 4) and the sheeting was set on the centers as closely as possible, all openings being thoroughly filled and tamped with Portland cement mortar, in the same way as was done at Bellows Falls. The result, after removing the centers, was even better than was expected, no settlement occurring and not a single crack appearing in any of the masonry. The foundations for






FIG. 5. BRIDGE OVER TOMHANNOCK RIVER AT SCHAGHTICOKE.


this structure deserve some mention. Samples of material from borings, to a depth of 30 feet below the bed of the river, indicated that piles should be driven, but this question of pile foundations was most thoroughly settled when the temporary pile bents were driven, to carry the iron bridge, which was moved to one side to carry trains around the work. The driving of these piles showed the difficulty of penetrating the bed of the river, and that the borings did not give a proper idea of the material. This was still further proved by the time one of the foundation pits was excavated to the point where the masonry was to start. The bottom was of hard compacted gravel, and it became evident that piles were unnecessary and they were omitted. The iron bridge was moved to

one side to allow room to construct the arches. The bridge was on a 45° skew, and consisted of three quadruple lattice trusses continuous over the pier, placed 9 feet apart center to center. The bridge was 250 feet long, about 16 feet deep, and, with the track ties, which were not removed, weighed about 225 tons. Previous to moving the bridge and without any disturbance of traffic, it was jacked up enough to remove the bed plates on rollers, so as to pass rails under the ends on the centers. Three lines of heavy pile trestle were built, extending from the masonry to the new position of the bridge, each of them being capped with 14 x 14-inch hard pine timbers carrying three lines of rails. Hitches were made to timbers buried in the ground, and to the ledge on the other side of the river opposite the ends and the center, and lines were carried from the bridge through two sets of double blocks back to three hoisting engines. The first pull moved the bridge about 5 feet, and, as the lines were so arranged that no overhauling of the falls was necessary, the bridge could have been moved over in ten minutes had it not been for the trouble caused by rivet heads in the bottom chord binding against the nuts in the joints of the rails. It was not possible for the hoisting engines to pull equally, and the bridge could be moved only a few feet at a time. It was then stopped by one end getting a little ahead of the other, and this caused the rivet heads to bind against the bolts of the rail joints. Considerable time was used up in finding and cutting out the rivets which were holding the bridge. This was, of course, greatly increased by the large angle of skew; but, notwithstanding the trouble caused by the rivet heads, the bridge was in its new position in one hour and twenty minutes after the first pull was made.

The arch over the Tomhannock River at Schaghticoke (Fig. 5 and Plate IV) was built under the middle span of a three-span plate girder bridge and the other two spans were filled up, after removing the old iron bridge. This arch was built in the same way as that at Hoosick Junction, and was comparatively a small affair, the interesting point about it being that it enabled a bridge 200 feet long to be removed and a solid roadbed to be carried over the river, and that it cost no more than it would have cost to renew the superstructure of the bridge with new plate girders for double track.







ARCH CENTERS.

BY JAMES W. ROLLINS, JR., MEMBER BOSTON SOCIETY OF CIVIL ENGINEERS.

[Read before the Society, December 19, 1900.*]

A PROPERLY designed arch center must have three vital qualities: strength to carry the weight of the arch before the key is placed; stiffness in its members to prevent distortion under a partial load, and a foundation to start on. With these conditions satisfied, any arch should be laid and should be closed without trouble.

In columns and beams the question of mere strength is easily solved. That of stiffness is much more difficult. Necessarily,




FIG. 1. CENTERING FOR A FLAT ARCH.

centers are often trussed in some way, and absolute rigidity in a truss cannot be secured in practice.

As for foundations, there is always difficulty in getting such as are able to carry a heavy load without any settlement whatever.

The trouble of settlement from weakness of foundations, or from lack of rigidity in frames, begins when the sheeting extends about 20° from the skewback; for, except in very flat arches, most of the weight of the first few courses is carried by the skewback, and very little by the centers, so that after some weight comes onto the centers, their joints are compressed, and this opens some of the joints in the masonry already laid. If the foundations are firm, this

*Manuscript received May 27, 1901.—Secretary, Ass'n of Eng. Soes.

cracking may be avoided, in part, by using counter-bracing at the first and second "panel points" of ribs.

For small arches the simplest center is a circular rib made of three pieces of 2-inch plank, laid with broken joints, all being spiked solidly together, with a tie of plank at the springing. On this, 1-inch lagging is laid close. For a larger arch, the circular rib, as above described, with generally three braces, one at center and one on the quarter at each side, is used, the center of the whole rib having a post under it. We have used such a center up to 30-foot span for both brick and granite arches, carrying a 30-inch arch sheeting.

The design of a center for larger arches depends upon local conditions, also upon the relation of rise to span. In flat arches,




FIG. 2. CENTERING AT BELLOWS FALLS.

Fig. 1, with low side walls, it is well to use posts with intermediate bracing, on numerous supports. In a high arch we may use long braces extending directly from a center support to the rib, at intervals of 6 feet to 8 feet.

In the construction of the large arches for the Fitchburg Railroad over the Connecticut River at Bellows Falls, over the Hoosick River at Hoosick Junction, and over the Tomhannock Creek at Schaghticoke, as described in Mr. Cheever's paper, a departure from the usual method of building the rib itself was made with excellent results.

In the Bellows Falls arch the weight on each post was about 20 tons, and to carry this weight on two pieces of timber bolted to

the end of the post tenoned down to receive them, like a "girder cap" in a railroad trestle, seemed to be poor construction, unless excessively heavy timber was used, and unless most careful jointing was done to distribute the weight evenly over the whole of the bearing surfaces. The method of building ribs for this center, 140 feet span, 20 feet rise, was as follows: A platform was built in an open space, 25 x 80 feet, the half-span of the arch; on this platform the rib was laid out to full size, and templates were made of each post and brace. Then all the timbers, for the twelve ribs making the centers for both arches, were framed from these templates. (Figs. 2 and 3.)




FIG. 3. CENTERING AT BELLOWS FALLS.

The foundations for posts of bents supporting the ribs were cut out of the solid rock, and doweled to it, no sills being used except in the bents on each side of the river. All timber in bents was 14 x 16 inches yellow pine, second-hand material.

These bents, of six posts each, with cap, had short corbels at top of cap under each rib, and on these corbels was placed the lower chord of ribs, 10 x 12 inches spruce, simply butted together. The posts and braces were then put in and stay-braced.

The top chord of the rib was made of four thicknesses of 3-inch plank, laid with broken joints and spiked to posts and braces. The latter were sawed off square or beveled, according to their position, and thus required no mortises, tenons or bolting

in the centers. The posts and braces were then thoroughly X-braced.

The lagging was 8 x 8 inches spruce, 2 feet on centers and under the lagging, at each intersection with rib, a pair of oak wedges 4 inches wide were placed. The arch sheeting was thus placed on 420 pairs of wedges, there being six ribs under the arch, 5 feet on centers. The arch sheeting was 27 feet wide over all. (Fig. 4.)

To hold lagging in position and give the workmen a fair place to work on, 2-inch planks were spiked to the lagging about 2 feet




FIG. 4. LAYING ARCH STONES AT BELLOW'S FALLS.

center to center, and on this the "sheeting" was laid. As the intrados of the arch was rock-faced, an allowance was made for 3-inch projection, the sheeting being kept to line by wedges on top of the plank. This center proved to be most satisfactory, with the exception of the wedges, and settled only 1 inch under a load of 1500 tons. When the centers were ready to be struck, the wedges "stuck" and refused to budge, except under the most severe mauling, it being necessary in many cases to actually cut them out.

The centers for arches at Hoosick Junction, (Fig. 5) two 100-foot spans, were of similar construction to those at Bellows Falls, the former, however, having a pile foundation. The bottom of the river was a hardpan and into this the piles were driven to a

"refusal." A perfectly solid foundation was thus obtained. Here the rib was of 2-inch plank, six thicknesses, on account of smaller radius of arch, and short corbels were put between the ends of the posts and the top chord of the rib, to stiffen the latter. The method of wedging for this arch proved the best we have ever used, so that, when centers were struck, they came out without any trouble. In this case the wedges were of seasoned oak 8 inches wide, 4 inches thick at thick end, 2 inches at thin end, and 18 inches long. They were *planed* on sliding faces, and were then thoroughly greased. When put in place they were "tacked" together to prevent their




FIG. 5. CENTERING AT HOOSICK JUNCTION.

slipping, and were put in between the caps on the bents and the corbels under the lower chord of rib.

At Schaghticoke an arch of 58 feet span was built (Fig. 6), over the Tomhannock River, between two piers which carried an iron bridge. This arch was almost semicircular, and was over a very shallow river with a solid rock bottom. The center for this was built with a 2-inch plank rib, stiffened by 8-inch timbers between five braces of 6 x 8-inch spruce timbers. All the braces came together on a central support, and, while the structure looked exceedingly light, it stood the test of wear without any sign of failure. The braces were, however, most thoroughly X-braced. The wedges were under the central support and were easily driven out, they having been planed and greased as at Hoosick Junction.

The last arch built—that at Medford, across the Mystic River, of about 60 feet span—presented a problem as to the method of centering. The springing line of arch being 6 or 8 feet under high tide, it was necessary to construct a cofferdam for that part of the arch below the highest watermark, it being deemed impracticable to try to lay the sheeting by "tide work." Piles were driven for the cofferdam at each side, about ten feet inside the springing lines of arch, and on this and a center line of piling, the ribs of centers were built—with extensions down to the skewbacks. To avoid driving too many piles in the river, a trussed center was designed, and stood




FIG. 6. BRIDGE AND CENTER, SCHLAGTICKE.

up well, under a 30-inch sheeting on a very flat arch. No wedges were used in this center, they being struck by knocking out a line of blocking at the central support.

The question is often raised, How soon can centers be drawn after the arch has been closed? In the opinion of the writer, they should not be drawn until the cement has set enough to stand the pressure, and in pursuance of this practice centers have been struck in three days on a 30-foot arch, in five days on a 60-foot arch and in four weeks on the Bellows Falls arch, with no signs of cracks in any case. If there is no necessity for drawing centers, time will surely add to the certainty of stability of the structure, and no

trouble will ensue if the foundations are equal to the load placed upon them.

For centering for a large arch, or one where the distance from the foundation to top of arch is more than 40 feet—in our opinion the best practice is to use the longest posts available; X-brace them thoroughly; avoid all trussing, as far as possible, and make as few vertical joints as possible.

NOTES ON THE INDUSTRIES OF THE UPPER RHINE.

BY JOHN RICHARDS, MEMBER TECHNICAL SOCIETY OF THE PACIFIC COAST.

[Read before the Society, June 7, 1901.*]

I HAD recently to visit briefly on business the upper Rhine country, especially the Swiss portion, and found time to make some notes relating to technical and industrial matters there that I venture to present before the Society this evening. I am influenced to do so because of various things that were novel and of much interest to myself; no doubt in some cases well known to some of the members present, but not to all. I therefore beg indulgence in respect to what is not novel; also in respect to the broken and discursive nature of these notes, which were jotted down en route and had been worked out by the stenographer here before I arrived at home.

A portion of my journey was made on the River Rhine, and my notes will begin with that, remarking first that the changes of more than twenty years since I had last visited this country have made all things new. Old "Cologne," with 120,000 people then, is now "Köln," with 350,000. Nearly all the Rhine cities have doubled, and many other things have changed accordingly.

The scenic portion of the Rhine, from Bingen to Bonn, has been the subject of more descriptive writing perhaps than any other part of Europe, due more, however, to historic association than to its natural features. The traveler's portion of the Rhine, or that usually traversed by passenger steamers in the summer season, is from Cologne, or Köln, to Mannheim, a distance of about 150 miles, requiring usually twenty hours of time. Throughout that portion of the river that lies between Bingen and Bonn, the Rhine flows between hills 500 to 1000 feet high, rising abruptly from the water's edge, and on all southern exposure the whole attainable surface is terraced and cultivated in vines in a manner that has no parallel in the east and completeness of the work.

I will venture to say something of this vine or wine culture, and to express some views that I fear will be at variance with commonly accepted opinions.

In the first place, I do not believe that there is much more in this Rhine wine country, in so far as physical features are concerned, than the warmth of the soil from underlying stone cliffs and in a wonderful cultivation, and that, while the climate is harsh

*Manu-script received June 13, 1901.—Secretary, Ass'n of Eng. Socs.

and cold for at least half of the year, this warmth and deep cultivation preserves a genial temperature up to a short distance below the surface.

This feature of warmth, so far as I have noticed it, seems to be peculiar to limestone regions. In Ohio, Kentucky and other Middle States having both lime and freestone bedrock, land resting on the former is several weeks earlier in its vegetation, and the snow melts much sooner in the limestone regions. I do not know whether the Rhine cliffs are limestone, but suspect they are.

Other features are exposure to the sun's hot rays in summer, not attainable on flat lands; also perfect drainage and a freedom from saturation not possible on level lands in any country; but most of all is the intense cultivation and care, of which we know nothing here in California and will not for at least half a century to come.

The depth to which the soil is prepared and the careful manner of it, not to mention the expensive means of retaining the earth, would, to use a slang phrase, "paralyze" a California grower of vines. For a depth of two to three feet, and in some cases much more, the earth is stirred, pulverized, mixed with loam, vegetable mold and manure. It is carefully and endlessly cultivated, indeed, so long as the earth is accessible beneath the spreading vines. The result is an intense growing power, so to speak, carefully modified to the conditions required by the vines.

As to local influences and environment, and in all except the skillful treatment of the vines, there is, in my opinion, nothing in the Rhine Valley that has not a parallel here a thousand times repeated on the mountain sides in California. I also believe that in the Middle States, Ohio, Kentucky, Tennessee and Georgia, for example, the cultivation seen on the Rhine might have a like result.

The great reputation of the wines of the Rhine is at this day to a great extent based on commercial incentives. The trade is immense, and the quality of the wine is unquestionable; but that its merits are due to local conditions of a geographical or climatic nature I much doubt.

It amazes one to think of the possibilities of wine culture here in California. The northern counties could alone sustain a population of many millions of people devoted to this pursuit if a market for the product could be found. Lake County, lying within one hundred miles of this city, has more area for vines than the Rhine Valley from Bingen to Köln, situated at levels up to 3000 feet high, where the best grapes are now grown, down to the lake level or below that, a range of 2000 feet. Nearly the whole of Lake County

could be cultivated in vines under conditions much more favorable than in the Rhine Valley, except as to means of transportation.

The Main, Lahn, Mosel, Nohe, Nette, Wied and other streams enter and swell the Rhine in this hill district; otherwise the volume of water would be insufficient for navigation through the many rapids and obstructions that exist in this portion of the river,—the classic part, it may be called.

In this country we are apt to suppose that the Rhine, after reaching the broken district above Cologne, continues between hills and mountains that grow higher and more abrupt until it enters Switzerland. This is not the case. Above Bingen, and after passing the main wine district, the country again spreads out on each side of the river into wide plains. Basel, Baden, Müllhauser and even Zürich are not in mountains, but in plains, nearly the same as those that begin below Cologne and extend one hundred and fifty or more miles to the delta at Rotterdam.

Throughout its navigable length, the river is not a natural, but an artificial stream; a canal indeed, because dredged out, embanked, straightened and otherwise trimmed up in a manner unknown to any stream on this continent. How such a thing can be made profitable will appear when I come to speak of the traffic.

The number of steam dredges at work on the Rhine in the district from Mannheim to Cologne, or for one-third of the navigable length of the river, is not less than fifty, all of them of an efficient kind and uniform except as to size, which varies a good deal. They are constructed of iron or steel, of the chain-bucket type, and are employed for various purposes besides deepening the channels. They build the embankments and the "rip walls" or wing dams, as we would say, that jut out from the shores to confine the water in the channel.

Of these intercepting dykes or dams there are thousands. In fact, they may be said to be nearly continuous for hundreds of miles, 200 to 500 yards apart, and at low water they just show above the surface and are fully disclosed by the swash of passing steamboats. The banks of the Rhine are walled. It is not an exaggeration to say this, because natural banks between Mannheim and Cologne, if existing at all, are only short reaches where willows are planted. This protection by walls is necessary, because in so narrow a stream, where boats are driven at high speed, a hundred or more passing daily, the banks would soon be destroyed. In front of all cities these shore walls are of ashler work laid in cement. They are, however, of various character in other places, commonly of the "rip" kind, inclined at an angle of 1 : 2 or 1 : 3;

but in many cases where there are landings the walls are vertical or nearly so, and in the latter case are built with the stones "on edge," so to call it. This latter is a remarkable feature and worthy of remark, also of imitation. Such stones are usually laid flat or in loose walls, depending on gravity alone for stability; but by setting the same stones in a vertical position, or on their edge, they are wedged into position and firmly held against the waves or any other disturbing action.

The commerce of the Rhine is its most important fact. In our sparsely populated country it is impossible to conceive of a traffic produced by a highly industrial population of 400 or more to each square mile, and this I assume to be a fair estimate for the Rhine Valley. Belgium has 450 people to each square mile, and the Rhine Valley from Schaffhausen to Rotterdam must equal if not exceed this number.

Evidences of this enormous traffic are seen in various ways, especially between Cologne and Mannheim. Above the latter city the traffic is not great, because the larger steamers stop at that point. It is doubtful whether in any other part of the world goods are conveyed by water in so complete and economical a manner.

At low stages in the winter the water is but 9 feet deep in the channels, and the draft of boats is limited to about 7 feet. All the heavy traffic is conveyed in barges 200 to 250 feet long, built of iron or steel, and modeled in a highly scientific manner, with narrow beam not exceeding one-twelfth of the length. They are finely molded, so as to avoid resistance and disturbance of the water and to prevent injury to the banks. They are built with many water-tight compartments that have no communicating doors, and consequently are safe in case of accident. These barges are loaded low in the water, not exposing more than a foot of free-board, or just enough for buoyancy in case one compartment is filled with water.

From end to end, the top is covered with narrow movable hatches, so that any compartment or each alternate compartment can be wholly uncovered for lifting out or loading freight. Then the hatches are shifted over the loaded or emptied compartment, so the whole is practically an open vessel. The hatches interlock at the center, slope each way and form a close weather-proof deck or roof. There are neat cabins, hinged masts, with sail tackle and powerful steering gearing, anchors, winches and various other rigging, including sails, so that these barges are, in fact, complete navigating vessels.

The towing boats each draw two or three of these barges, mak-

ing up an immense cargo for the steam power expended and for the depth of the water. These boats are fine examples of constructive art, with lines but little less fine than those of the passenger steamers to be hereafter described. In most cases they are driven by inclined triple-expansive engines, connecting directly to center cranks, and are of the highest class. The boilers are in most cases of the type known as the Scotch marine, and fuel consumption is brought down to the lowest point attainable in powers of this extent. The paddle wheels are of the feathering type, and the whole system indicates evolution under long experience at the hands of highly trained engineers,—German, Belgian and Dutch, all these countries participating in the traffic.

Some idea of the amount of material conveyed may be formed from the fact that in this Rhine Valley is concentrated the great share of the industries of Germany, and that the fuel, as well as crude material and product must be carried out and in. The earthen-work industries are of an extent hard to imagine,—in brick, tile pipes, hollow ware, copings and a dozen more classes I cannot name. Between Mannheim and Köln are not less than twenty of these works, and one can see acres covered with finished material and from two to eight acres covered by the works or buildings.

Glass also forms a heavy and an enormous product of the Rhine country. Indeed, nearly all the main industries are directed to heavy products of one kind or another, and all have the air of being put down to endure.

I am sorry to be unable to furnish you with accurate statistics of these matters, but, as explained at the beginning, these notes are confined mainly to hurried observation.

The use of wire ropes on the Rhine boats is amazing. They seem to have supplanted the fibrous kind for nearly all uses. The towing-ropes employed for barges are of wire, about $\frac{1}{2}$ inch in diameter and invisible at a little distance. They are from 200 to 400 yards long, and so light as to be always clear of the water, so that the barges seem to be following a course of their own independent of the towing steamers, and indeed do so to a great extent. Some screw towing boats are employed, and, to my astonishment, they seemed to perform very well, notwithstanding the shallow depth of water. I judged of this by the relative size of the barges and the number towed by the screw boats.

There are three companies that operate passenger steamers. My journey was made in one of the Rotterdam Company's boats that ply from Rotterdam to Mannheim. The other two companies

are in Cologne and Mannheim. The three companies have collectively about forty steamers. The towing boats can be numbered by hundreds, belonging in great part to private companies who own their own boats and barges.

Reverting again to some of the industries of the upper Rhine country, Mannheim has become a very great center of industry, because of its being at the head of navigation on the Rhine and because various industries have been founded there by citizens of other countries in order to escape the German tariff, on a method that we know something of in this country. Take the case of Messrs. Sulzer Bros., of Winterthur, Switzerland, as an example. They are extensive makers of steam engines of a very high class, and now employ about 4500 men. The German tariff, like all others, does not tax workmen or skill, and as soon as this customs law went into effect Sulzer Bros. sent men, tools, drawings and other equipment to Germany to make engines there, the "tariff" remaining in Winterthur, the same as much of our and the French customs taxes find their way to London. I visited these works of Sulzer Bros. at Mannheim, and I can bear testimony to the very high quality of the work done there, where about 1200 men are employed by this firm.

Mannheim and Ludwigshafen form practically one city, being on opposite sides of the Rhine, connected by a wonderful bridge, as are all Rhine bridges, especially those at Coblenz, Mayence and Cologne. In Mannheim and Ludwigshafen there is, to use a common phrase, a forest of chimneys, and the chimneys are not a disfigurement, but the contrary. To a visitor from this country, there is indeed nothing that is more striking than the industrial chimneys in Germany, Belgium and Switzerland. They are not square, with various degrees of taper and form, but always round, symmetrical, from 200 to 300 feet high, all of harmonious design, with elegant coping, entablatures and commonly are iron-bound at spaces of 15 to 20 feet.

I am of the opinion that the skill attained in Germany, especially in manipulative processes, now acknowledged to be among the most advanced, has been to a great extent an "overflow" from the adjoining cantons in Switzerland. There is, indeed, no question of this, and there is the problem; and it is one of some intricacy, how the Swiss have attained so much skill in a country without coal or iron and remote from the great lines of traffic. I gave to this subject such observation as was possible in the short time at command, and consulted engineers and owners at Zürich, Oerlikon, Baden and Winterthur, where are situated four leading machine

industries,—namely, Sulzer Bros., Brown, Bouveri & Co., Escher, Wyss & Co. and the Oerlikon Co., employing together about 12,000 men, all engaged on the finer classes of machine work.

Judged by the skill in evidence, the appearance of the workmen and of the works, with the harmonious relations that exist between the employers and the employed, and by a tolerably careful inspection of processes, I am inclined to believe that in no part of the world has skilled industry of this class been so well and thoroughly developed. Among the reasons for this, such as I could discover, are: (1) A complete system of education, secular and technical; (2) a strong predisposition of the people to mechanical pursuits, engendered no doubt by a struggle for comfortable existence where the areas capable of cultivation are limited and the climate unfavorable; (3) the existence all over the country of water power from numerous streams that descend toward the Rhine and lower-lying plains; (4) and especially, the fact that the enhanced price of fuel and iron forces the Swiss engineers to a higher class of work, in which skill is the principal component.

This last reason was given to me uniformly by a number of people who were consulted, and is no doubt the true cause of a very high development of skill in that country. No cheap work of any kind is made, and none in which skill is not a very considerable factor, if not the chief one.

Coupled with this high development of skilled industry in Switzerland, which I believe is not overestimated, are some facts of much interest to Americans. In Belgium, Holland and Germany one hears but little of America, but as soon as Switzerland is entered the whole changes. The English tongue comes into use again; one may with confidence assume that all the owners, engineers and managers not only speak English, but have been in America. I found myself in many cases corrected respecting firms and industries in the Eastern States. In the four great works I have named, nearly every one I met or conversed with had been in America, and in many cases to work here and learn our methods.

Mr. Henry Sulzer, who is head of the firm of that title, has three sons to inherit and conduct the business; one of them now in principal charge, and all of them well acquainted with American engineering practice. Carl Sulzer, the eldest son, could converse with me in excellent English concerning the various shops in this city, of the Yosemite Valley, Mount Shasta, Mount Tamalpais; indeed, had traveled from Puget Sound to San Diego and examined most things on this coast worthy of noting. I had the honor to be entertained at the house of Mr. Henry Sulzer, where there

was a company of nine, four of whom were ladies, and all were able to speak in English and knew more or less of America. While I was in Switzerland another son of Mr. Sulzer was in this city, on his way to Japan, where the firm has an agent and does a considerable business.

At the Oerlikon Works I was conducted through by the manager, who had been eleven years with the General Electric Company in this and other countries. At Escher, Wyss & Co.'s works my conductor was a son of the general manager, and, although quite a young man, had been all over this country. At Basel, Switzerland, I called on the veteran engineer Mr. Charles Brown, now retired from active service. He was for thirty years with the firm of Sulzer Bros., chief engineer there for most of that time. He will leave behind him a monument of successful work as great if not greater than any other man of whom I have knowledge. In speaking with Mr. Henry Sulzer, of the great works at Winterthur, he said: "Many men have had a part in building up these works. Mr. Brown has done a great part of it. We had less than one hundred men when he came in 1856." I also visited Brown, Bouveri & Co., who employ about 2000 men on electrical work pertaining to power transmission, and who are now putting down a large plant at Magdeburg, Germany, for the manufacture of the Parsons steam turbine. The capital of this company is to be about \$5,000,000.

I had been informed that there was wear upon the vanes of these engines, but Mr. Charles Brown, Sr., said this was a mistake, and that no appreciable wear had appeared in any case. I had also been informed that the De Laval steam turbines had not been successful above 100 or 200 horse power. This also was a mistake, because the Oerlikon Company is erecting a new plant for this manufacture and has contracts now made for engines of large size; I think of several thousand horse power, and none of less than 500 horse power are to be furnished. The large-unit idea is now a ruling feature there in electrical generating plants. There are now in course of construction in Sulzer Bros.' Works at Winterthur single engines of 5000 horse power for a central plant in St. Petersburg, Russia.

What most of all attracted my attention in the Swiss works was the iron castings. They were perfect; not the slightest fault on any face, and their outline at least as true as the patterns. In the foundry processes, I could discover nothing peculiar except convenience, room, order, fine tackle for handling and a means of drying molds by hot air that I had not seen elsewhere. When a

mold is completed, a light furnace is set on top, and a current of air is forced through this furnace down into the mold, permeating it and removing the moisture from every part, also heating the mold before it is poured.

All duplicate work is done on molding machines, but, as Mr. Sulzer informed me, not to the extent that such machines are employed in the foundry of the Worthington Company at Elizabethport, N. J. The sand blast is in general use for cleaning castings, and is applied by very ingenious machines designed in that country.

The Swiss are a free-thinking and intelligent people. Their history shows how far personal rights are esteemed and preserved by all conditions of men. They are also given in the highest degree to association in all forms affecting their business and social interests, but the relation between the employers and their men seems to me to partake more of the co-operative sentiment than in other countries. The men are treated with much respect, which they demand and deserve. Mr. Henry Sulzer, chief of his firm, is in the works at 8 o'clock each morning, and leaves there between 6 and 7 in the evening, and this, I am told, is the custom of owners in other works of the country. He, his sons and all concerned in the works have the respect of the men in their employ, and they in turn are respectful in all dealings with their workmen, who are nearly all Swiss people.

Some years ago the firm built a "casino" or clubhouse for the workmen, containing hot, cold and vapor baths, a dining-room with heating and cooking appliances, a library and surgery. This was done not as a patronizing gift to the men, but as a necessary adjunct to the works. At Oerlikon the company is just completing a similar building, which I think would cost in this country from \$30,000 to \$40,000, perhaps twice as much. There are eighty plain bathrooms, several vapor baths, a surgery and other offices, as before mentioned, and, as I before pointed out, these are not heralded as patronizing "gifts" to the men, but are provided as a necessary part of the equipment, built out of profits that the men have earned. They have the management of these departments, and feel a proprietary interest in them.

It is nearly useless to indulge in homilies on the management of skilled labor or to attempt much improvement of the circumstances in a country so long as men are hired and paid by time, irrespective of what they perform or produce. Successful reform lies in the direction of education, responsibility, wages regulated by their product and a system that provides declared profits and an equitable incidence for taxation. Workmen in Switzerland, such

as work by time, receive only about one-half the rated wages paid here on this coast, but the real difference is much less than this and is indeed to a great extent made up by a difference in taxation and the cost of commodities and necessities of life. When one wants to ascertain the rate of wages paid for skilled labor in any country, a "payroll" is not the thing to examine. That is surrounded by intricate conditions not open to the average observer. The true way is to examine the men themselves. Look into their faces, note their clothing and tools; go into their houses, see them on Sundays and holidays, and, above all, attend their meetings when labor and other problems are discussed.

Thus far the upper Rhine country has escaped labor discontent and disturbance, such as has occurred in other parts of Europe and in this country. Mr. Sulzer could inform me of but one strike in Switzerland, and that of unimportant extent.

Swiss enterprise is overflowing the Confederacy on the Italian side. At Milan, in Italy, is a very successful engineering plant, managed by a relative of Mr. Charles Brown, of Basel, who reports a fair degree of skill among the Italian workmen and an extreme interest in and devotion to the work, which has of course the charm of novelty to the Italian workmen.

I will add some remarks on the railways and highways of the Rhine country, including Belgium, where roadmaking has reached its highest development. It is in this feature that our country suffers most in comparison with Europe, owing in part to a want of wealth or taxable property along the highways, but also to methods that seem to me in many respects at fault. In comparison with those of Europe, our roads are only trails over the natural surface, with ditches at the sides to collect the water that runs off and convert it into a stream that goes on to do mischief in some manner. In Europe the roads are raised above the natural surface, and the water runs off at all points, is diffused over the land and causes no trouble.

Material for grading is taken from cuts or other sources, but, come from where it may, all roads are raised above the level of saturation, and thus are drained, so that no water stands on the surface, consequently they are always hard, and are not cut into ruts by wheels. The roads are always narrow, 10 to 12 feet wide, and this seems to be all that is required. The expense of construction and maintenance is much reduced by this, and we might learn a lesson from it in this country, although there is little hope of attaining a good system of highways under our present complicated system of diverse laws and means of taxation, also dearth

of skilled and responsible officers clothed with proper authority to direct such work, and, above all, the absence of a uniform system of construction.

In Belgium the principal roads are all paved in the manner known here as the "Belgian block system," consisting of cubes of hard stone, and are no doubt the most perfect highways to be found in any country of Northern Europe.

The Swiss railways are peculiar as compared with others in Europe, and many features may be noted by a stranger. The engines and trains are adapted to the loads to be carried. There are heavy wagons and locomotives, but these are not seen in the normal traffic. A passenger train for a certain number of people will not, I think, weigh more than half as much as in this country. The passenger carriages are very convenient, consisting of coupés with a corridor extending along the side, at the ends of which, for all classes, will be found closets and conveniences for washing. The carriages are warmed by steam, and this, as well as ventilation, is controlled by the occupants in each coupé. There is also electrical connection to the guard or officer in charge, and the windows do not slide up from the bottom, as in this country, but are let down from the top and stay where one puts them. The glass is bound around with a narrow rim of brass, that forms a guide, so that the windows are full width between the frames. These brass frames are planed, and slide noiselessly in grooves of wood.

It may seem that a narrow frame of brass would not form a support for the glass, but, if we think of the matter, neither does a wooden sash as we make them. When the glass is not in the sash, the latter is but a weak thing. The glass needs protection against torsion only, and this is provided for independently of the sash, which acts as a slide or guide.

Speaking of the weight of European engines and trains brings to mind some observations in this country during a recent trip by the Southern route from here to Washington city and back; also a previous trip a few months earlier out and back over a Northern route; respecting the enormous weight of everything pertaining to trains.

Engines of 100 tons are as common as those of 50 tons were twenty years ago, and the carriage weight per passenger must be at least 1500 pounds. The railways seem to be following the pace set by ocean steamers, perhaps with a like aim, but with infinitely more danger to those who travel. From Washington to this city, in the month of April, we passed five wrecks, one for each day.

Two were on the lines east of New Orleans, and three this side of New Orleans, and, as far as could be learned, these accidents all had their cause in the immense weights carried. In Georgia an engine of 200,000 pounds and a train to correspond had been run on a siding. The earth was soft from rain, and the permanent way was crushed, sleepers broken, rails bent and the train ready to topple over on its side. The tendency to greater weights seems to be due to an effort to increase earnings, but it must operate the other way. Lighter and more frequent trains, at higher speed, give a better and safer service, and correspond to the European system, where severe penalties follow careless administration of traveling facilities. The number of people injured and killed each year on American railways is reported to be from 25,000 to 30,000, or about fifty times as many as in Europe, including Great Britain.

I note that in Belgium, Holland, Germany and Switzerland the time schedules for railways always give the time of trains leaving stations, and not the time of their arrival, except at terminals. The advantage of this is that one does not have to ask how long a train will wait. The time shows that, and it is a comfort, especially as they always leave precisely at the time indicated. There is one new feature creeping into railway service there, the same as here, "*trains du luxe*" that charge extra because of speed. After purchasing a ticket from Zürich to Mannheim, I was called upon, when about half-way, for 2.5 marks for the "platz" or seat. I employed my highest powers in German to dispute this. "Schnellzug," said the guard. "Schnell!" said I "why, your train has not run at 40 miles an hour at any time through the day. It did no good, and I paid the "schnell" rate. It is a collusion of the continental railways, who have adopted this expedient of increasing rates, adding sleeping and dining carriages. Perhaps it is right, and letting one off with 2.5 marks is moderate, at any rate. The German Government has spent about 23,000,000 marks getting up these *trains de luxe*, and naturally wants to get some of it back again.

The German people especially will not submit to extortion. On the steamer out the passengers were mostly German, and prices had to conform to the standard. Cigars from 10 to 20 centimes, or 2 to 4 cents; wines, beer and other commodities were supplied at shore prices. The stores are procured in Belgium.

On the whole, traveling in Northern Europe is convenient and safe, not only from dangers, but from the arrogant treatment that seems necessary for the regulation of passengers on our own railways. The curtained Pullman sleeping carriages of our lines

seem to me far inferior to the "*schlafwagen*" of Germany and the Continent. We have, indeed, some evidence of this in the recent adoption of the same coupé system on some of the lines in this country.

The principal distinction of all is, however, in the cost of things. In our dining cars the common charge for a meal, or for the use of a table rather, is one dollar. In Europe it is for what you buy, down to five cents or less, and personal right is continually present in the fact that no one will permit himself to be cheated.

In conclusion, I will venture the opinion that our trade to Europe in skilled products is not likely to be permanent, and that it has been in the past a result of sudden and remarkable evolution in the arts, much more rapid than the conservative customs of our European friends would permit. There can be no profitable and permanent trade between nations of like civilization and skill unless based upon a difference of natural products, and, however greatly circumstances may for a time point to a different conclusion, the end must conform to inexorable economic laws. Cane sugar cannot long be produced in Louisiana by planting each year against tropical countries that plant once in four years.

The exportation of the smaller class of machine tools to Europe, which last year amounted to half a million dollars a month, has fallen to half this amount, owing in some degree to a very dull state of business in Germany and other North European countries, but more to the fact that the same machines are now produced there by the same methods we employ here, which have rendered export trade possible,—namely, an organized and extensive manufacture of duplicated products. They "make" machine tools in Europe. We "manufacture" them; but this same method is fast making its way in Northern Europe, and the principal center of activity is now and will probably remain in what may be called the upper Rhine Valley.

To one who was familiar with the circumstances of trans-Atlantic traffic between New York and European ports twenty years ago, it is a curious matter to note the changes that have been made since then. The character of the ships, their size and equipment and even the personnel of the crew are altered in such a degree that an old traveler feels at a loss respecting many things.

It has been my misfortune to have crossed the Atlantic about forty times in steamers instead of having been as often confined in jail for a like period, and the only comfort ever discovered in such a performance has been in observing the circumstances attending on this enormous traffic, that has no parallel in the world in its

volume, and perhaps none in the vicious weather that exists along the route that borders the Gut Stream.

The aggregate value of the steamers now in service between the Atlantic ports and Europe is \$250,000,000, and one-third of this amount is represented in express steamers sailing out of New York, carrying annually about 140,000 first-class and 500,000 steerage passengers; the latter coming mainly this way.

Of the companies owning and operating these steamers, eight have vessels valued as follows:

The Hamburg-American.....	\$15,000,000
North German Lloyd.....	15,000,000
White Star Company.....	12,000,000
Cunard Company.....	10,000,000
Red Star and American.....	10,000,000
Atlantic Transport.....	10,000,000
Trans-Atlantic (French).....	8,000,000
Holland-American	7,000,000

The principal line, the Hamburg-American, and the greatest in the world, has 109 steamers, with an aggregated tonnage of 600,000, all employed in trade to this Continent,—North and South America. The North German Lloyd is not much behind, with steamers amounting to 500,000 tons. These two lines employ about 12,000 people. Their capital shares are the same, \$20,000,000 each, but this contains no water. On the contrary, it covers property of twice this value. They own their own piers at New York, worth \$3,000,000. Other lines rent their piers, paying in some cases \$200,000 a year.

The sails have disappeared, and we may say the sailors also. It is a steamboat problem now. The wind resistance of spars and sail tackle, at moderate rates of speed, far outweighs any propelling force that can be derived from canvas, to say nothing of the weight of such tackle and the expense of handling it.

The captain of the "Westernland," a Belgian steamer, built at Laird's eighteen years ago, told me that when the sails and their tackle were taken down from his ship and piled up on the quay, it seemed half a cargo, and, as this weight is carried at an average of 40 feet above the spar deck, one can imagine the effect on a vessel.

The only reasons left for the use of sails are the risk of failure of the machinery and to prevent rolling in a beam wind, and these reasons are nearly neutralized by the fact that duplicate units of machinery give almost complete assurance against disablement.

while rolling is to a great extent counteracted by bilge keels and by the great size and the form of the hulls.

It is common in this country to hear people speak of ocean carrying as an industry that is not profitable. The same remark was made by Æsop's fox that could not reach the grapes. Ocean carriage does pay, and it never before paid as it does now. On a late voyage, the "Ivernia," of the Cunard Line, earned \$50,000, and her expenses, all told, were \$20,000. I think she is about 10,000 tons capacity. The "Celtic," now building at Belfast, is over 20,000 tons, and the Germans are busy building like vessels. The rates of carriage are now uniform or nearly so, and such ships are like a gold mine,—a good one, I mean.

Last year the Hamburg-American Company earned a dividend of 10 per cent., the North German Lloyd $8\frac{1}{2}$ per cent, and the White Star Company 15 per cent, on their capital shares.

The United States Commissioner of Navigation, in his last report, says about 30,000 tons of shipping owned by Americans is sailed under foreign flags. This does not look like an unprofitable business. The American Line—that is, the four ships, or three at this time, sailed under the American flag—makes up our part in this great trans-Atlantic fleet. The Red Star Line, which for advertising purposes is included in the title, is Belgian, in fact, with headquarters in Antwerp, but several of the steamers in this service are British. The "Kensington" and "Southwark," 600 feet long, that carry 8000 tons of freight, are British, and two new vessels building for this line will no doubt be sailed under the same flag. The British owner does not care where his vessel serves, so long as she sends the profits to London or Glasgow.

The "Southwark," on which I went out to the Continent in March last, was loaded at and sailed from the American Line dock, but I noted that the crew were British; and as soon as the lines were cast off the English ensign was run up, and from that on we were in a British ship.

Past President Mr. G. W. Dickie has explained before this Society in part, but not fully, some of the causes that lie at the bottom of our humiliating position in the ocean carrying trade, and the effects of our antiquated navigation laws, but he has not, that I am sure of, exposed the fallacy of the reasons commonly assigned for this state of things.

In the first place, every one here knows that, sailing out of this port, we have but one deep sea line under the American flag, and that a subsidized one. We see here German, British, Japanese and other foreign flags in many cases on our American-owned vessels.

This should be enough to indicate to every one some fundamental error in our laws relating to shipping. Capital is invited to this country for all other purposes, but no foreigner can own any part of an American ship, and not even an American can who resides usually abroad. Our people can buy and import anything by paying the duty, except ships and obscene books. These are absolutely excluded. An American ship that is disabled abroad and has repairs done must on her return home pay a duty of 40 per cent. on the amount expended; a vessel once sold to a foreign owner can never be bought back again, with much more of a like nature that I will not consume time to describe.

In 1861 American tonnage almost equaled that of Great Britain,—about 5,000,000 tons. Twenty years later it was one-fifteenth as much, and the decline was not much greater during the Civil War than before and after that.

Here and in many other States deep-water ships are taxed as personal property. A vessel must pay for sewers, lights, police, streets and other municipal expenditures, but does not use them, and when she comes home cannot land or unload except by paying high charges for lying at the docks which she has been taxed to build. This subject need not be pursued. Those interested will find the matter fully treated in "Our Merchant Marine," by David A. Wells, now, I believe, an officer of the Revenue Department. The preface of his book begins as follows:

"The expulsion of the Moors and Jews from Spain and the repeal of the Edict of Nantes, which deprived these countries of their artisans and industries, have been accepted by all historians and economists as the most striking examples in modern times of great national disaster and decay, directly contingent on unwise and stupid, but at the same time deliberately adopted, state policies.

"It has been reserved for the United States, claiming to be one of the most enlightened and liberal nations of the world, after an experience of nearly three hundred years since the occurrence of the above precedents, to furnish a third and equally striking and parallel example of results, contingent in like causes, in the decay and almost annihilation of her merchant marine and ocean carrying trade,—a branch of her domestic industry that formerly ranked in importance second only to her agriculture."

Returning now to German companies, about 1875, or something later than this (I have not the reference at hand), the great Chancellor Bismarck proposed to subsidize German shipping as the French had done, with a view to its expansion. This called out from the Hamburg merchants, through their Board of Trade, a

memorial to the government, which, tersely translated, means "Please let our shipping alone. We will take care of that." "History shows that attempts of this kind have an effect opposite to that intended," and so on. A careful translation of this memorial can be found in the book above mentioned.

The result is before us. The French subsidies have done no good and much harm. How often do we see a French ship in our port? German shipping, without subsidies, has undergone a phenomenal development. The Germans have the second place in number, and the greatest ships that come into our ports. The express ship "Deutschland" is believed to be the fastest. She burns 600 tons of coal a day, steams 500 or more miles and carries comparatively no cargo,—only 600 tons. She is an advertisement, but pays a profit besides.

The North German Lloyd Company is building, at Settin, two ships to run at a greater speed. In this country, the Great Northern Company is building, in New London, Conn., two ships 630 feet long, 73 feet beam, to carry over 20,000 tons each. These steamers will sail from Puget Sound ports, and no doubt under the British or some other foreign flag.

At the Union Iron Works here and at the East are being built very large steamers to run from this port. The "Korea," of 18,000 horse power, 572 feet long, was launched at Newport in March. Two of 12,000 tons each are building here.

All large ships are now provided with double screws. This is essential on account of insurance rates alone, even if there were not many other reasons. It divides the weight of reciprocating parts and permits a correspondingly higher rate of revolution, without excessive risk and wear. One ship I traveled on recently had a low-pressure cylinder 93 inches in diameter, with a piston and connections that weighed 20 tons. This mass moved at the rate of 700 feet per minute, and was reversed 140 times per minute. The strains can be imagined. The duplicate power units give more room, because placed at the sides of the ship, leaving a wide room between, into which light can enter from the engine hatches.

There is much wonder at this time that the British companies do not keep up the speed of their vessels to that of the German lines. This, I think, can be accounted for, in part at least, by an expectation that the turbine engine will soon be a means of propulsion. The *Viper* and *Cobra* gunboats are now driven by engines of this type at a speed of 37 miles an hour, and a small steamer now building at Dunbarton for Channel service is to be fitted with these engines.

Twelve or more years ago I ventured the prediction before this Society that rotative engines and pumps would supplant in time the reciprocating type, and I feel some confidence in this prophecy, owing to the fact that certain Swiss firms at this time are preparing to set at work over 2000 men on turbine engines. In pumping fluids there is the same promise. Rotative turbine pumps now raise water against a pressure of 300 pounds per square inch. The two problems of receiving and applying the dynamic energy of moving fluid and imparting motion and energy to the same fluids are in many respects analogous. This is especially true of liquids, and the two would fall equally under the same mathematical laws were it not for centrifugal force, which performs a considerable part in the action of the latter-named class of machines. A manufacture of these will be commenced in this city before long, and I hope in due time to present here some of the very interesting features that are being developed in Europe and in this country.

MR. DICKIE: I rise on your order, although I doubt my ability to say anything in regard to this very interesting paper, except to express the interest with which I have listened to it.

The field covered by the paper is so wide that discussion of it is hardly possible. I followed Mr. Richards closely while he was reading, and on many things I could agree with him, while on some things I could not.

Last year I spent a little while in Germany, and noted a great many things that Mr. Richards mentioned, especially the movement that was going on there for the manufacture of machines and engines that had hitherto been built as individual designs.

Very large establishments have been recently brought into operation, embracing the very newest methods of production, and using the best known tools and methods of work. What one might call the humanities of manufacturing seems to have reached a very high development there. I visited establishments where every one of the thousands employed might have his daily bath in the works and a table to eat his lunch at in a great dining hall.

Somehow, that sort of thing does not go very much here. Our men look upon it as a kind of paternal management that needs to be resented. Such provision made for our men here only prompts them to inquire where we got the money to provide it; and this inquiry is usually answered by the labor organizers who tell them that it is stolen from their labor, with the advice to demand more wages and buy bath tubs for their homes, and shorter hours, that they may have time to use them.

I agree with Mr. Richards in regard to the short life that is likely to be the result of what is now called "American competition" with Europe. When these people get fairly into the methods of manufacture they are now adopting, they will produce as much per man per day as we do; and we will then be in luck to hold our own markets.

I cannot agree with Mr. Richards in what he says in regard to the comfort of railroad travel in Europe, compared with the comfort of traveling on American railroads. My opinion is that you can travel from San Francisco to New York with less discomfort, and arrive fresher at your destination, than you will experience in traveling from Paris to Berlin.

I think most of what Mr. Richards says about American shipping is true. I have stated here before, and often, that we are not likely to become a great ship-owning country until wiser legislation prevails in regard to ship owning. Municipal and state taxation of ships should be abolished throughout the whole country. A new art cannot be built up on being taxed. This is true the world over, and as long as the tax gatherer has his fingers on the throat of our shipping it will not succeed.

Is it not absurd that the city of San Francisco, which is an inland town, with no harbor nor any water front, may tax a ship in mid-ocean to support the city government; build and mend streets, sewer and light them, simply because the name of that ship is registered in a building on one of her streets called the Custom House?

Last year there was a proposition to build a new Custom House for San Francisco, and to build it on the sea wall instead of on Battery street. Had that been done, our ships would have escaped municipal taxes, for then they would be registered in the State and not in the city.

Few people know that this is an "inland" city built near a harbor of the same name. This city terminates 150 feet from the water front. Beyond that line San Francisco officials lose their authority. Only one is allowed to cross with authority and that is the tax collector.

It is unfortunate that our people cannot be made to realize this. If they did there would be no rest until the harbor of San Francisco would be free to every ship built and owned in this State, and no municipal or State taxes imposed on ocean-going ships.

Editors reprinting articles from this journal are requested to credit not only the JOURNAL, but also the Society before which such articles were read.

ASSOCIATION OF ENGINEERING SOCIETIES.

Organized 1881.

VOL. XXVII.

AUGUST, 1901.

No. 2.

This Association is not responsible for the subject-matter contributed by any Society or for the statements or opinions of members of the Societies.

THE PITOT TUBE; ITS FORMULA.

BY WILLIAM MONROE WHITE, B.E., MEMBER LOUISIANA ENGINEERING SOCIETY.

[Read before the Society, May 13, 1901.*]

THE writer had the pleasure of delivering before the Louisiana Engineering Society on October 8, 1900, a paper entitled "Water Measurements in Connection with a Test of a Centrifugal Pump at Jourdan Avenue Drainage Station." Professor Gregory, of Tulane University, wrote an article on the same series of tests, which was read before the American Society of Mechanical Engineers at the December meeting in New York city. The water measurements of these tests were largely made with the assistance of the Pitot tube. In our use of the Pitot tube, its formula was taken as $V = \sqrt{2gh}$.

At the reading of Professor Gregory's paper Mr. William Kent, author of "Kent's Mechanical Engineer's Pocket-Book," severely criticized this formula, and said that the true formula is $V = \sqrt{gh}$. In his criticism he said:† "I am especially interested in this paper, for the reason that some of the experiments and deductions in it constitute the best experimental proof that I have yet seen of the inaccuracy of the formula quoted in the last line of the first page of the paper; that is, the time-honored formula $V = \sqrt{2gh}$. It is a perfectly correct theoretical formula when the velocity is produced by the head, but it is incorrect when the head is

*Manuscript received June 15, 1901.—Secretary, Assn. of Eng. Soes.

†Transactions of the American Society of Mechanical Engineers, vol. xxii, p. 284.

produced by the velocity, and the proof of the last statement is shown in the paper in the most satisfactory way I have ever seen.

"Take the Pitot tube. Several writers on the Pitot tube have said that the proper formula for it is $V = \sqrt{2gh}$, but the experiments in this paper proves that it is not correct. The correct theoretical formula is $V = \sqrt{gh}$ or $H = \frac{V^2}{g}$, and the correct practical formula is $H = C \frac{V^2}{g}$, in which C is an experimental coefficient, always less than unity, whenever the head is the effect produced by the velocity. I have never seen a better statement of how to test the Pitot tube than the one given in the paper. I do not know a better method than to put one in a canal where there is no current and tow it in a boat at a uniform velocity. The author obtained in his experiment $V = .849 \sqrt{2gh}$, which, transposed, is $H = 1.39 \frac{V^2}{2g}$, or 39 per cent. greater than the head, which many writers on the Pitot tube say is the theoretical head that can be produced by the velocity. If we take the correct formula we obtain $H = .695 \frac{V^2}{g}$ in which .695 is the coefficient of efficiency of the tube. The difference between .695 and unity is the loss of head in the Pitot tube, due to eddies or to the currents not striking it squarely, and being deflected at right angles to its orifice. It is well known that the pressure produced by a jet striking a blade at right angles to the jet is theoretically equal to twice the head which would produce the velocity, or $2 \times \frac{V^2}{2g}$. We would get the same result on the Pitot tube, provided the jet would strike it fairly and leave at right angles, which it does not do. As one of the speakers said, we can have no confidence in the Pitot tube unless it is standardized every time it is used. The Pitot tube thus standardized would be an excellent instrument for testing the velocity of water flowing at a uniform speed. But in no current, stream or pipe is there such a thing as uniform velocity of water, so that even if you have the Pitot tube properly standardized, the next question is how to use that and get the average velocity of water through the pipe. This is a matter of great difficulty, and has to be done by taking the velocity at different points of the area and making a computation by the aid of the calculus to find the average velocity.

"This theoretical formula, $H = C \frac{V^2}{g}$ applies to centrifugal pumps, Pitot tubes, centrifugal fans and windmills, and generally to all cases in which the velocity of a current is the cause and the head is the effect; while $V = \sqrt{2gh}$ is the correct formula where the head is the cause and the velocity is the effect."

Let us examine Mr. Kent's transposition of the formula $V = .849 \sqrt{2gh}$. The transposition is $H = 1.39 \frac{V^2}{2g}$. Mr. Kent's reasoning, by which this formula is made to appear as giving the Pitot tube an efficiency greater than 100 per cent., would be perfectly rigid if H were the value of the *velocity head alone*. The Pitot tube under discussion is made according to the Darcy principle, with two glass tubes connected to a common vacuum. One tube is connected to the nozzle, and gives the velocity head; the other is connected to the rear part of the tube, and is supposed to give the hydraulic head. H is not only the velocity head, then, but is made up of two readings, being the difference of two water levels. One reading is the velocity head, the other may or may not be the hydraulic head; its value may be above or below the hydraulic head. If a suction action takes place about that part of the tube which is supposed to measure the hydraulic head, the hydraulic head is decreased and the value of H is increased. The value of H for the tube which was used on the test is $H = \frac{V^2}{2g} + .39 \frac{V^2}{2g}$. The last term in the equation is the value, in terms of velocity head, of the suction action at the hydraulic part of the tube. The writer gave the reason for the introduction of the constant ϕ in his paper read before the Society last October.

In looking up the authorities on the subject of the Pitot tube, the writer finds quite a diversity of opinion as to its formula. Weisbach writes the equation " $V = \mu \sqrt{2gh}$, or, more simply, $V = \phi \sqrt{h}$," and states that "with fine instruments, when the velocities were between .32 and 1.24 meters, we found $V = 3.545 \sqrt{h}$ meters." J. T. Fanning writes the equation $V = \sqrt{C2gh}$. Mr. Church, author of "Mechanics of Engineering," gives the theoretical formula as " $H = 2 \frac{V^2}{2g}$, or $V = \sqrt{gh}$."

The following theoretical consideration is taken from Church's "Mechanics," page 801 (the writer uses Church's "Mechanics" because it is the one which he studied while at college, and is the one with which he is most familiar) :

"IMPULSE OF A JET OF WATER ON A FIXED CURVED VANE
(WITH BORDERS).

"The jet passes tangentially upon the vane (Fig. 1) ; B is the stationary nozzle from which a jet of water of cross-section F (area) and velocity V impinges tangentially upon the vane, which has plane borders, parallel to paper, to prevent the lateral escape of the jet. The curve of the vane is not circular necessarily. The

vane being smooth, the velocity of the water in its curved path remains $= V$ at all points along the curve. Conceive the curve divided into a great number of small lengths, each $= ds$, and subtending some angle $= d\phi$ from its own center of curvature, its radius of curvature being $= r$ (different for different ds 's), which makes some angle $= \phi$ with the axis Y (at right angles to original straight jet BA). At any instant of time there is an arc of water, AD , in contact with the vane exerting pressure upon it. The pressure dP of any ds of the vane against the small mass of water $F ds \gamma \div g$ then in contact with it is the 'deviating' or 'centripetal'




FIG. 1.

force accountable for its motion in a curve of radius $= r$, and hence must have a value

$$dP = \frac{Fr ds}{g} \frac{V^2}{r}. \quad (1)$$

"The opposite and equal of this force is the dP shown in Fig. 1, and is the impulse or pressure of this small mass against the vane. Its X -component is $dX = dP \sin \phi$. By making ϕ vary from 0 to a , and adding up the corresponding values of dX , we obtain the sum of X -components of the small pressures exerted simultaneously against the vane by the arc of water then in contact with it,—i.e., noting that $ds = r d\phi$,

$$\begin{aligned} \therefore \int_{\phi=0}^{\phi=a} dX &= \int_0^a dP \sin \phi = \frac{Fr V^2}{g} \int_0^a \frac{ds}{r} \sin \phi \\ \frac{Fr V^2}{g} \int_0^a [\sin \phi] d\phi &= \frac{Fr V^2}{g} \left[-\cos \phi \right] \end{aligned} \quad (2)$$

hence the X -impulse against fixed vane $= \frac{Fr V^2}{g} [1 - \cos a]$ (3)

"For a fixed plate, then, Fig. 2, at right angles to the jet, we have for the force or impulse (on the plate) (with $\alpha = 90^\circ$; then $\cos \alpha = 0$) and

$$P = \frac{F V^2}{g} \quad (4)$$

"The experiments of Bidone, made in 1838, confirmed the truth of equation (4) quite closely, as do also those of two students of the University of Pennsylvania in 1887.




FIG. 2.

"Equation (4) is applicable to the theory of the Pitot tube, if we consider the edge of the tube plane and quite wide. (Fig. 3.) The water in the tube is at rest, and its section at 'A' (of area $= F$) may be treated as a flat vertical plate receiving not only the




FIG. 3.

hydrostatic pressure Fx/r , due to the depth x below the surface, but a continuous impulse

$$P = F r V^2 \div g \quad (5)$$

For the equilibrium of the end A of the stationary column AD we must have, therefore,

$$F x r + \frac{F V^2 r}{g} = F x r + F h r; \text{ i.e., } h = (2.0) \frac{V^2}{2g}$$

Mr. Church's reasoning holds good about the pressure on a flat plate being $2F \frac{V^2}{2g}$, but he is wrong when he applies that reasoning to the Pitot tube. He assumes that a jet of area A (Fig. 3) exerts its whole force upon the equal area of the tube. If this be true, why should the walls of the tube be "plane and quite wide"? Is it that they take a portion of the pressure P ? They cannot, or the pressure would be divided between A and the walls of the tube.

If the tube (Fig. 3) should receive the whole impulse of a jet of the same area A , the whole force exerted upon the tube at A would be $P = 2 \frac{V^2}{2g} F$. The 2 in the equation would not belong to F , because the areas are the same; therefore, it must belong (if the above reasoning is true) to the $\frac{V^2}{2g}$. If we place the 2 before $\frac{V^2}{2g}$, we say that a head h will cause a velocity head $\frac{V^2}{2g}$, but that a velocity head $\frac{V^2}{2g}$ will cause a head $2h$, which, of course, cannot be, for the same reason that a pendulum loosened on one side of its swing will not rise to a greater height on the other. But the area of the jet and the area over which it acts cannot be the same, because the formula deduced depends for its solution upon the existence of a radius of curvature of the jet at striking the plate. If this radius be reduced to 0, the solution of the equation would be impossible. Therefore, the radius r must exist, and the area over which the jet acts is greater than the area of the jet. I submit, therefore, that the equation as deduced by Mr. Church should be less than $h = 2 \frac{V^2}{2g}$, and that it depends for its value upon the maximum pressure per unit of area on the plate. We would expect the greatest pressure per unit of area to be $h = \frac{V^2}{2g}$.

From the solution of the equation we see that the pressure on the plate extends over an area greater than the area of the jet. The first thing to do, then, in arriving at the formula is to find the relation between the area of the jet and the area of the plate over which it acts, and next to find the distribution of the pressure on the plate and the greatest pressure per unit of area.

EXPERIMENT I.

A Round Jet of Water Impinging on a Flat Plate.

The object of this experiment is (1) to determine the pressure on a plate of a round jet of water of known area and velocity impinging on the plate; (2) to determine in what manner the pressure

of the jet is distributed on the plate; (3) to determine the greatest pressure per unit of area.

Apparatus. The apparatus used in this experiment is as follows: (Fig. 4.) One end of a rectangular wooden box, 18 x 32 x 60 inches, is fitted with baffling plates, over which and under which the water must pass in reaching the center. A hose discharging into the end of the box creates eddies, but the water in flowing past the baffling plates becomes quiescent by the time it reaches the center of the box. A hole 6 inches in diameter is in the center of the floor of the box. Over this hole are fitted the different orifices used. The orifices are plates of brass and iron of 1-16-inch thickness, each with a round hole in the center. The upper edges of the hole are filed to a knife-edge, making a clean, sharp orifice. The




FIG. 4.

plate (Fig. 5) upon which the jet impinges is $\frac{1}{2}$ inch thick by 8 inches in diameter, and is of aluminum. Thirty-three 1-16-inch holes are drilled in its upper surface. They lie on fifteen concentric circles, whose radii differ from each other by increments of $\frac{1}{4}$ inch and vary from $\frac{1}{4}$ to $3\frac{3}{4}$ inches. One hole is in the center, and two holes are on each circle, except the one of 2-inch radius, which has four holes about equally spaced from each other. The holes all lie as nearly along one diameter as it was convenient to place them. Each hole, 1-16 inch in diameter, leads into a nipple, $\frac{1}{2}$ x 3 inches, screwed into the bottom of the plate. The nipples are connected by

rubber tubes to vertical glass tubes (see Fig. 4). Behind the glass tubes is a scale reading in tenths of an inch. When the water fell through the orifice, it was noticed that a whirling action was set up in the jet, tending to distort it. In order to overcome this, 1-32-inch plates were placed vertically above the orifice. These plates broke up any small eddies, and the water fell in a very quiet stream onto the plate below. The plate was placed exactly level and so that the jet struck it in the center. The pressure on the plate forced water through the 1-16-inch holes and through the nipples into the glass tubes. The height of the water in each of these tubes, above




FIG. 5.

the surface of the plate, was the pressure in inches of water on the plate at the hole to which the tube was connected. The holes in the plates are lettered for convenience of reference (Fig. 5). The center hole is A. The holes along one-half of the diameter are lettered from B to P, inclusive, and those on the other half of the diameter from B' to P'. The two additional holes on the circle of radius 2 inches were lettered I_1 and I'_1 , respectively. The pressure, given by the reading of the tube connected to the center hole A, is supposed to extend over the area of a circle of $\frac{1}{4}$ inch in diameter. The pressure given by the hole B is supposed to extend over the area of a $\frac{1}{4}$ -inch circular strip of $\frac{3}{4}$ inch outside diameter and $\frac{1}{4}$ inch inside diameter, and so on. The area corresponding to each letter is given in Column 6, Table I.

TABLE I. OBSERVATION 1

Orifice = 3". Height of water in box above orifice = 2.85".
 Diameter of Jet at Plate = 1.78". Area = 2.49 sq. in.
 Height of Orifice above Plate = 10.5". Total Fall of Water = 13.35".
 Velocity of Water at Plate from $V = \sqrt{2gh}$ = 8.45 ft. per sec.

1	2	3	4	5	6	7	8	9
Tubes on Scale	Scale Readings in Inches.			Average (3 and 4).	Areas of Annular Strips A to P in Square Inches.	Areas (6) - Average Pressure A to P (Sq. in. - in.)	Total Pressure on Plate required to change the direction of jet.	2 h - Area of Jet the water falls.
	Height of Water in Water Box.	Pressure on Plate in Inches of Water.						
		A to P	A to P'					
A	13.35	13.25	13.25	13.25	.049	.649		
B	13.35	13.25	12.35	12.80	.3928	5.027		
C	13.35	12.20	12.55	12.37	.7854	9.720		
D	13.35	11.25	9.10	10.15	1.1781	11.950		
E	13.35	9.10	7.70	8.40	1.5707	13.190		
F	13.35	6.80	3.05	4.92	1.9635	9.650		
G	13.35	3.40	1.70	2.50	2.3561	5.880		
H	13.35	1.65	.60	2.12	2.7494	5.820		
I	13.35	.65	.50	.57	3.1420	1.791		
J	13.35	.35	.40	.37	3.5330	1.207	64.874	66.5
K	13.35	.30	.25	.27	3.9280	1.058		
L	13.35	.30	.20	.25	4.3240	1.080		
M	13.35	.30	.15	.22	4.7080	1.035		
N	13.35	.20	.20	.20	5.1050	1.020		
O	13.35	.20	.15	.17	5.4980	.935		
P	13.35	.20	.10	.15	5.8890	.895		
I ₁	13.35	.65	.55	.60	3.1420			

In determining the pressure on an area, an average of the readings BB', CC', etc., was taken. By multiplying the average pressure by the area of the corresponding strip, the total pressure on the annular strip was determined. This pressure is given in Column 7, Table I, and is given in inches of water pressure per square inch of surface, or in cubic inches. The total pressure on the plate is obtained by summing up the pressures on the several annular strips. In Table I it will be noticed that the pressure is integrated only so far from the center as it is seen that the jet really exerts any pressure. The remaining pressure from this point to the edge of the plate is due to the dead weight of the water. An inspection of the curve of pressure of Observation 1, Fig. 6, shows this clearly. The pressure on the plate from the center to the circle J is the pressure necessary to turn the jet, but the pressure from J to P is only the weight of the water as it flows off the plate. The manner in which the pressure of the jet is distributed on the plate is shown by the curves 1 to 11 (Figs. 6 to 17). The irregularities in the curves, Figs. 1, 2, 3, 4 and 8, are caused by the jet not being quite in the center of the plate. The remaining curves are smooth and are of exactly the same form, showing that the curve of pressure on the plate obeys the same law, whatever the diameter of the jet or its velocity upon striking the plate.




FIG. 7. OBSERVATION II. CURVE OF PRESSURE ON
PLATE IN INCHES OF WATER.




FIG. 6. OBSERVATION I. CURVE OF PRESSURE ON
PLATE IN INCHES OF WATER.




FIG. 9. OBSERVATION IV. CURVE OF PRESSURE ON PLATE IN INCHES OF WATER.




FIG. 8. OBSERVATION III. CURVE OF PRESSURE ON PLATE IN INCHES OF WATER.




FIG. 11. OBSERVATION VI. CURVE OF PRESSURE ON
PLATE IN INCHES OF WATER.




FIG. 10. OBSERVATION V. CURVE OF PRESSURE ON
PLATE IN INCHES OF WATER.




FIG. 12 OBSERVATION VII. CURVE OF PRESSURE ON
PLATE 1N INCHES OF WATER.




FIG. 13. OBSERVATION VIII. CURVE OF PRESSURE ON
PLATE 1N INCHES OF WATER.




FIG. 15. OBSERVATION N. CURVE OF PRESSURE ON
PLATE IN INCHES OF WATER.




FIG. 14. OBSERVATION IX. CURVE OF PRESSURE ON
PLATE IN INCHES OF WATER.




FIG. 16. OBSERVATION XI. CURVE OF PRESSURE ON PLATE IN INCHES OF WATER




FIG. 17

TABLE II.

1. Total pressure of jet impinging on a plate, in inches of water.
2. Greatest pressure per unit of area.
3. Area of plate over which jet acts.

1	2	3	4	5	6	7	8	9	10	11	12	13
Observation.	Orifice (Inches).	Height of Water over Orifice (Inches).	$h =$ the Distance from the Water Surface to Jet (Inches).	Velocity of the Jet at the Plate from $V = 1.28 \sqrt{h}$ (Inches).	Diameter of the Jet at the Plate (Inches).	Area of Jet (Sq. In.).	Area $\times h$ (Sq. In. \times In.).	Observed Pressure on the Plate (Sq. In. \times In.).	(Obs. Press. \bullet Area $\div h$ \bullet)	(Greatest Pressure per Unit of Area in Inches of Water (Compare with 4.))	Total Area over which Jet Acts (Sq. In.).	Total Area \div Area of Jet \bullet
1	3.0	2.85	13.35	8.45	1.78	2.7900	33.25	64.874	1.95	13.25	21.6	7.7
2	3.0	5.76	16.20	9.34	2.00	3.1450	51.10	91.640	1.80	16.22	17.7	5.6
3	3.0	13.10	21.60	10.75	2.25	3.9760	84.50	149.270	1.77	21.50	25.9	6.5
4	3.0	7.60	18.10	9.85	2.12	3.6300	65.70	113.580	1.78	18.00	25.9	7.1
5	2.5	6.51	17.01	9.56	1.61	2.0220	34.80	68.140	1.96	17.00	14.2	7.0
6	2.5	8.60	19.10	10.12	1.76	2.4440	46.70	82.430	1.77	19.05	17.7	7.2
7	2.5	10.05	20.55	10.50	1.79	2.5200	51.70	94.040	1.82	20.52	17.7	7.0
8	2.5	3.70	14.20	8.55	1.50	1.7670	25.10	47.520	1.90	14.10	14.2	8.0
9	1.5	4.61	15.11	9.04	.91	.6450	9.75	20.280	2.08	15.10	8.3	12.9
10	1.5	7.91	18.41	9.94	.97	.7382	13.60	29.170	2.14	18.40	5.9	8.0
11	1.5	10.41	20.91	10.60	1.05	.8500	17.97	36.020	2.00	20.00	5.9	6.9

The tabulation of the results of these different observations is given in Table II. The diameter of the jet was taken at its smallest part just before it struck the plate. This diameter was obtained by calipers, but is not very accurate.

Column 8 gives the area of the jet multiplied by its height. The factor of the heaviness of the water is left out because it is constant.

Column 9 gives the total pressure on the plate, ascertained from the individual readings, as explained in Table I. The method used in determining this total pressure is, of course, not very accurate, because the area of an annular strip at the outer edge of the jet is rather large comparatively; and, as the integration is by means of these strips, if we take one strip too many or one too little the value of the total pressure is considerably varied.

Column No. 10 is a constant obtained by dividing column No. 9 by column No. 8, and it confirms fairly closely the experiments of Bidone and of the two students at the University of Pennsylvania. The greatest pressure per unit of area is in the center of the jet, and by comparing column 11 with column 4 it is seen that the greatest pressure per unit of area is equivalent to the velocity head contained in the water.

Column 12 gives the total area over which the jet acts. Dividing this by the area of the jet, we obtain the quotients given in column 13, or the relation between the area of the jet and the area over which it acts on the plate.

In conclusion, we see that Mr. Church cannot apply equation (4) to the Pitot tube, (1) because the area over which the jet acts is not the same as the area of the jet; (2) because the greatest pressure on the plate never rises higher than the velocity head contained in the water. The readings of the column of water connected to the hole A, if we consider it as a Pitot tube, agree exactly with the formula $V = \sqrt{2gh}$.

EXPERIMENT 2.

Impingement of a Falling Jet of Water upon Nozzles of Different Forms.

There is such a variety of opinion as to the best form of nozzle or impact tube for use in a Pitot tube that it seemed to the writer advisable to experiment on tubes of different forms, with a view of obtaining some law regarding their variation.

Fig. 17 shows nozzles of four different shapes. Nozzle A is made canonically converging, according to descriptions given by Mr. Darcy. Nozzle B is Pitot's original form. It is made canonic-

ally diverging, or funnel-shaped. Nozzle C is the one Weisbach used in his experiments. Nozzle D is made according to the descriptions of Mr. Church, with the edges "plane and quite wide."

Object of the Experiment. The object of the experiment is (1) to determine the static head which nozzles of different forms will support when struck by a jet of known velocity; (2) to prove that velocity head is converted into static head according to the law $V = \sqrt{2gh}$.

The apparatus (Fig. 18) for obtaining the jet was the same as that used in Experiment 1. Two vertical glass tubes, 1½ inches




FIG. 18. EXPERIMENT WITH NOZZLE A.

inside diameter and 8 inches long, are placed side by side on the box. The left-hand tube is connected directly, by ¼-inch gas piping and rubber tubing, with the interior of the box, while the other is connected with the nozzle by similar means. The large glass tubes are used in order to eliminate the effect of capillarity. The glass tube on the left (Fig. 18) gives the height of the water in the water box over the orifice, and the difference between this level and the point of the nozzle gives the total distance through which the water falls. The velocity of the water, then, at striking the nozzle is given by substituting this distance, in feet, in the formula

TABLE III.—EXPERIMENT 2.
Impingement of a Falling Jet of Water on Nozzles of Different Forms.

1	2	3	4	5	6	7	8	9	10	11
Observation.	Nozzle.	Orifice, Inches.	Height of Orifice Above Nozzle, Inches.	Height of Water Level over Orifice, Inches.	Total Distance Water Fall to Nozzle, Inches.	Height Water Rose in Tube Above Nozzle, Inches.	Per Cent. (7) of (6).	Velocity of Water at Striking the Nozzle, from $V = \sqrt{2gh}$ Ft. per Sec.	For Pitot Tube $V = \sqrt{2gh}$ 1 2 g h (6) 1 2 g h (7)	Date of observation, 1901.
1	B	1.5	32.750	5.5000	38.2500	38.1680	.9978	14.52	1.0022	MARCH 2.
2	A	1.5	29.370	8.5000	34.8700	34.7810	.9974	13.03	1.0026	"
3	A	1.5	29.370	8.5000	37.8700	37.7760	.9974	14.19	1.0025	"
4	A	1.5	29.370	3.2500	32.6200	32.5810	.9988	12.79	1.0012	"
5	A	1.5	29.370	3.2500	32.6200	32.5890	.9990	12.79	1.0010	"
6	C	1.5	32.250	3.5000	35.7500	35.6990	.9980	13.79	1.0020	"
7	C	1.5	32.250	9.7500	41.9410	41.9110	.9980	14.99	1.0020	"
8	D	1.5	32.370	4.5000	36.8700	36.8080	.9982	14.03	1.0018	"
9	D	1.5	32.370	8.5000	40.8700	40.7700	.9979	14.35	1.0021	"
10	D	1.5	15.500	8.5000	21.0000	20.9990	.9995	10.85	1.0015	"
11	D	1.5	15.500	9.0000	24.5000	24.4530	.9981	11.40	1.0019	"
12	C	1.5	15.500	3.8700	19.3700	19.3150	.9974	10.18	1.0018	"
13	C	1.5	15.500	3.8700	19.6200	19.5910	.9971	10.20	1.0029	"
14	B	1.5	15.750	8.0000	23.7500	23.7110	.9985	11.23	1.0015	"
15	B	1.5	15.750	8.0000	20.7500	20.7200	.9978	10.42	1.0025	"
16	A	1.5	12.250	8.0000	20.2500	20.2000	.9978	10.42	1.0022	"
17	A	1.5	12.250	8.0000	20.2500	20.1620	.9986	9.22	1.0044	"
18	A	1.5	12.250	3.7500	16.0000	15.9730	.9973	9.22	1.0017	"
19	A	1.5	12.250	3.7500	16.0000	15.9570	.9974	9.22	1.0026	"
20	A	1.5	18.750	8.3516	27.1016	27.0813	.9991	12.04	1.0009	MARCH 13.
21	C	1.5	18.750	10.5036	29.2536	29.2073	.9989	12.20	1.0011	"
22	C	1.5	18.750	10.5036	30.3818	30.3318	.9984	12.89	1.0016	"
23	C	1.5	18.750	11.9228	31.9728	31.9043	.9983	12.75	1.0017	"
24	C	1.5	18.750	7.3878	26.1378	26.0799	.9981	13.08	1.0019	"
25	C	1.5	18.750	6.1198	24.8698	24.8345	.9977	11.80	1.0023	"
26	C	1.5	18.750	5.312	23.9735	23.9508	.9985	11.59	1.0015	"
27	C	1.5	18.750	6.2528	25.0028	24.9508	.9990	11.30	1.0010	"
28	B	1.5	5.312	6.2528	11.5648	11.5575	.9993	7.86	1.0007	MARCH 21.
29	B	1.5	5.312	8.3828	13.6943	13.6890	.9996	8.50	1.0004	"
30	B	1.5	5.312	7.4855	14.0575	14.0490	.9993	8.67	1.0007	"
31	B	1.5	10.3230	15.6358	15.6248	15.6248	.9993	9.15	1.0007	"
32	B	1.5	12.3132	17.6252	17.6127	17.6127	.9993	9.72	1.0007	"
33	B	1.5	5.312	3.6447	8.9567	8.9560	.9990	6.92	1.0001	"
34	B	1.5	5.312	5.4233	8.1733	8.1677	.9993	6.66	1.0007	"
35	B	1.5	2.750	5.3700	18.8700	18.8170	.9988	10.08	1.0012	"
36	B	1.5	19.500	8.4172	24.9172	24.9203	.9988	11.50	1.0012	"
37	B	1.5	25.500	5.3972	30.8972	30.7638	.9986	12.78	1.0014	"
38	B	1.5	31.500	5.4405	36.9405	36.8705	.9986	14.08	1.0020	"
39	A	1.5	28.750	5.4007	34.1507	34.0943	.9984	13.50	1.0017	"
40	A	1.5	5.125	5.4302	10.5552	10.5488	.9994	7.52	1.0006	"

SCALE GRADUATED IN FT. S.

MICROMETER.

Observations 1 to 19, Table III, give the results as determined by this method. The results by this method of measurement varied too widely, and on another day of the experiment two micrometer screws were constructed (see Fig. 18). A hook was attached to each screw and dipped into one of the two glass tubes. In making an observation, (1) three readings were taken with the glass tubes connected as shown in Fig. 18, and (2) three readings were taken with the rubber tubes, which are connected to the bottom of the glasses, reversed. An average of these readings eliminated any error there might be in the zeros of the micrometers.

Observations 20 to 40 were made with the micrometers. These observations are the best that could be made. Nozzles of different




FIG. 20. EXPERIMENT WITH NOZZLE B.

forms were used, and the jet was caused to strike each nozzle at different velocities. The difference between the two water levels was so slight that it was very hard to obtain any law of variation.

Column 10, Table III, gives the constant ϕ as determined for the Pitot tube effect on these nozzles. The constant ϕ contains all the losses. If we could eliminate the air friction and the friction at the orifice, its value would be unity.

Fig. 18 shows nozzle A in the jet. The jet binds closely around the nozzle and adheres to the pipe down to the elbow.

Fig. 19 shows the jet impinging on nozzle C, and observations in Table III were taken under this condition.

Fig. 20 shows a jet striking nozzle B. This jet is smaller than

the one used in the tabulated experiments, and was used in order to get a better photograph of the water as it leaves the nozzle. The two water levels can be seen in the glass tubes.

In Fig. 19 it is seen that the jet is deflected from its course by an angle $\alpha = 45^\circ$. If we substitute the value of the cosine of this angle in equation (3) (page 38) we have for the pressure on the nozzle (per unit of area according to Mr. Church)

$$P = F\gamma \frac{V^2}{g} \left(1 - \frac{1}{2}\right) = F\gamma \frac{1}{2} \frac{V^2}{g}$$

In Fig. 20 it is seen that the jet is turned from its course by an angle $\alpha = 135^\circ$. If we substitute the value of the cosine of this angle in equation (3) we have for the pressure on the nozzle,

$$P = F\gamma \frac{V^2}{g} \left(1 - \left(-\frac{1}{2}\right)\right) = F\gamma \frac{3}{2} \frac{V^2}{g}$$

But by experiment the pressure per unit of area at the point of the nozzle is constant and equal to the velocity head contained in the water, no matter at what angle the jet may be deflected. Therefore, equation (3) does not apply to the pressure per unit of area, but to the total pressure necessary to turn the jet.

In Fig. 18 the jet binds closely to the nozzle, but the stream lines may leave the point of the nozzle at some angle which has not been determined.

Conclusions. From the results of Table III we see (1) that velocity head is converted into static head according to the law $V = \sqrt{2gh}$; (2) that no matter at what angle the water leaves the nozzle, the greatest pressure per unit of area never rises above the velocity head contained in the water.

Stream Lines and Velocities of a Jet Impinging on a Flat Plate.

It is claimed by Mr. Kent that the formula is $V = \sqrt{gh}$, and the reason that the calibration of tubes never shows quite so high a result is that a cone of still water may exist at the center of the nozzle of the tube and that the water sliding down the sides of this cone fails to exert its full force upon it. An experiment was made to determine whether this cone existed.

A small jet was caused to impinge on nozzle D (Fig. 17), of such a diameter that the jet was turned at right angles as it left the plate. The hole in the center of the nozzle was connected by piping and rubber tubes to a funnel placed above the level of the water in the water box. A blue solution of metalyne was poured gently into the funnel. The solution came out quietly through the hole in the nozzle in the center of the jet. If a cone of quiet water should exist at that point, the blue solution would force its way in and gradually displace the clear water, leaving a blue cone, which could

be seen. But the moment the bluing came to the surface of the nozzle it disappeared along the surface as fast as it was supplied. This, I submit, proves that no such cone exists.

Another experiment (Fig. 21) was made to determine the stream lines throughout the jet. In this experiment a 2-inch jet was allowed to impinge upon a large flat glass plate. An $\frac{1}{8}$ inch tube was connected by rubber tubing to the funnel, and the same solution of metalyne used. By holding the small tube in the jet as it came through the orifice, and pouring the solution of metalyne in the funnel, a small blue line could be plainly seen running down through the jet onto the plate and running off at right angles.




FIG. 21. STREAM LINES AND VELOCITIES OF A JET IMPINGING ON A PLATE.

When the small tube was held in the center of the jet, the blue line seemed to run to the surface of the plate and then turn suddenly at right angles along the surface. By moving the small tube along a diameter of the jet, the stream lines could be traced, as shown in Fig. 21. The numbers in the small circles (Fig. 21) give the velocities in feet per second at that point of the jet. These velocities were obtained by the means of a very small Pitot tube. The point readings of the Pitot tube always remain near the water level in the box, the static part of the tube varying as the velocities. In other words, the sum of the static and velocity heads is always equal to the distance through which the water falls.

It will be noticed that the velocity of the jet during its change of direction is less than it is either before reaching the changing point or after leaving it. The changing point of the jet seems to act like a reservoir under pressure, being supplied from the jet above and discharging along the surface of the plate. The stream lines show very clearly that no cone exists at the center of the jet.

The stream line in the center of Fig. 21, together with the velocities inclosed in the little circles along that line, show very prettily the conversion of velocity head into static head. For instance, at the top of the line, where the velocity is 6.7, the static head is zero. From that point to the plate the velocity head gradually decreases, being replaced exactly by the static head, as the reading of the Pitot tube shows.




FIG. 22.

EXPERIMENT 3.
Calibration of Nozzles.

This experiment (see Fig. 22) was made to test the nozzles under actual working condition. The tubes were moved through still water at a known velocity, and the constant of the tubes determined in this way. This calibration was made in the Jourdan Avenue Canal, which is blanked off at one end: it consequently has very little current, and offers exceptional conditions for a calibration of this kind. For a course, a No. 8 galvanized iron wire was stretched 600 feet just above the surface of the water. A point was marked on the wire 150 feet from each end. Stakes driven at these marks were used as starting and stopping points, and left

between them a clear measured course of 300 feet; 150 feet on each end was used to get a start before crossing the line and to check the headway after crossing the last line. Two small boats were placed side by side, with their center lines 6 feet apart. A decking was built over them, forming a catamaran. One side of the catamaran was fastened to the wire with staples. A tow line running to the shore was used to haul the boat along the canal at any desired velocity. On the first day of the experiment nozzles A, B, C and D, Fig. 17, were connected by gas pipes and glass tubings to the same vertical scale, graduated to .01 foot. The tubes and scale were fastened to a long 2 x 4-inch wooden piece, and could be




FIG. 23.

changed from one end of the boat to the other at will (see Fig. 23). The nozzles were placed about 24 inches in front of the bow of the boat, 12 inches from each other, and submerged 18 inches. When in position for reading, part of the scale and of the glass tubes was under the water. To get the static head of water, as referred to the scale, a butcher knife, *a*, with the scale etched to .01 foot, was placed between the scale and the end of the nozzle at *h* (Fig. 23). In making a reading, a spirit level was placed on the boat, and the observers so arranged themselves that the boat was perfectly level. Three observers were necessary: one to lay on the catamaran and put his head over within a few inches of the water and read the two scales; another recorded these readings as rapidly as read; the third took the time with a stop-watch, reading in fifths of a second in going the 300 feet. The greatest care was taken to get the nozzles exactly in the line of motion. When the boat was hauled forward, the water rose in the glass tubes on the scale, and the four heights

Column 9, Table IV, gives the direction of the observations determining the values of ϕ in column 10, showing that there was a slight current in the canal. But by taking a reading up the canal, immediately followed by a reading down the canal, the error due to this current was eliminated. Observation No. 4 does not give the correct reading, because the boat was not exactly level and, as shown by the reading on the static scale, the knife was too deep in the water. But this observation has not been discarded. In fact, no observation has been discarded throughout this series of tests. The value of ϕ for the eight observations is 1.0053 for $V = \phi \sqrt{2gh}$. The calibration of nozzle D applies to nozzles A, B and C, because on the first day of the test they were hauled at different velocities and they always gave exactly the same reading of h . The highest velocity obtainable by hauling the boat through the water was about 6 feet per second. Nozzles A, B, C and D, Fig. 17, were afterward all connected to the same scale by pipes and inserted in the discharge pipe of a centrifugal pump. The velocities of the water through the pipe were varied from 8 to 15 feet per second, but the reading of h on the four different tubes was always exactly the same.

In conclusion, we see from this experiment that velocity head is converted into static head in accordance with the law $V = \sqrt{2gh}$, and that the correct formula for the theoretical Pitot tube is $V = \sqrt{2gh}$ without the introduction of any constant.

EXPERIMENT 4.

Calibration of Pitot Tubes.

In this experiment four different tubes (Fig. 24) were calibrated under exactly the same conditions. Tubes M and N are designed by the writer. Tube M is made of gas pipe, having nozzle B fastened on the end of one of the pipes for the impact tube. Nozzle b is made round, long and sharp, with a hole at right angles to the length running through the nozzle, the middle of the hole being connected to the gas pipe, as shown by the dotted lines.

Tube N is made in the same manner, except that it is entirely of gas pipe. Nozzle c is an ordinary $\frac{1}{4}$ -inch gas pipe with its end filed square. Nozzle f is a $\frac{1}{4}$ -inch gas pipe drawn to a point, and a hole is drilled through it at right angles to its length.

The hatchet-shaped tube is one designed by Professor Gregory. It is made of brass, nicely polished.

The Tulane tube is the one that was used in the test, and is the one under criticism by Mr. Kent. It is made of two $\frac{1}{4}$ -inch tees fastened together by an iron plug. On the end of one of them is

fastened a nozzle, g , and through the other are drilled holes which are intended to give the static pressure. Unfortunately, the tee k was broken after the calibration of last year, and had to be replaced by a slightly larger one. This causes a slight difference in the value of its constant ψ . The four tubes were fastened in front of the boat at the same depth below the water, and 14 inches apart. The tubes were all connected to glass tubes placed on the same vertical scale. All the glass tubes were connected together at the top to a common vacuum chamber. The air was exhausted from this chamber, and the water levels thus drawn up on the scale. When the boat was hauled forward at any velocity, the readings of the impact tubes of the four different Pitot tubes were always




FIG. 24.

exactly the same, but the static readings of the different tubes were always different, showing that there was a suction action of greater or less degree on some of the tubes.

The same method of observation was used in this experiment as was used in Experiment 3. An observer read the different water levels on the scale, which were recorded as rapidly as read. The timekeeper took the time by the stop-watch in going the 300 feet. Ten readings were usually made in one observation, and the average of these readings gave the different values of h for the different tubes in an observation. Table V gives the result of this experiment.

TABLE V.—CALIBRATION OF PIVOT TUBES.

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22
Observation	All Readings on Same Scale.						Point Reading Minus Static Reading, or, h_s .						Velocity by Tubes from $V = 1.23h$.						ϕ For Pivot Tube \sqrt{h} True Velocity Pivot Tube Velocity			
	Point Read- ings of all Tubes.	Static Read- ing of Tube M.	Static Read- ing of Tube G.	Static Read- ing of Tube N.	Static Read- ing of Tube Gregory's	Static Read- ing of Tube Gregory's	Tube M.	Tube N.	Tube Gregory's	Tube Gregory's	Tube Gregory's	Tube Gregory's	Tube Gregory's	Tube Gregory's	Tube Gregory's	Tube Gregory's	Tube Gregory's	Tube Gregory's	Tube Gregory's	Tube Gregory's	Tube Gregory's	Tube Gregory's
	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.
1	0.286	.6086	.5828	.5857	.5771	.5771	.3200	.3468	.3129	.4515	4.54	4.72	4.69	5.39	64.0	300	4.59	Down	1.0116	.0740	.980	.858
2	.0866	.5933	.5416	.5783	.4933	.4933	.4233	.4450	.4983	.5233	5.22	5.35	5.13	5.86	57.4	300	5.23	Down	1.0226	.0780	1.026	.902
3	.0086	.6428	.6100	.6171	.5114	.5114	.2688	.2986	.2915	.3972	4.13	4.38	4.33	5.05	73.0	300	4.12	Up	.9986	.9100	.986	.876
4	.0112	.6437	.6187	.6212	.5325	.5325	.2675	.2925	.2900	.3787	4.14	4.34	4.32	4.93	74.0	300	4.06	Up	.9816	.9360	.946	.824
5	.9816	.5933	.5616	.5683	.4416	.4416	.4183	.4116	.4133	.5400	5.19	5.32	5.15	5.86	58.4	300	5.14	Up	.9910	.9070	.998	.874
6	.9483	.5916	.5614	.5650	.4880	.4880	.3567	.3869	.3633	.4633	4.79	4.99	4.83	5.16	63.4	300	4.71	Up	.9966	.9050	.982	.870
7	.0471	.5843	.5628	.5857	.4971	.4971	.3628	.3813	.3614	.4800	4.83	4.97	4.82	5.55	62.4	300	4.82	Up	.9980	.9090	1.000	.874
8	.8416	.6111	.5733	.5900	.5166	.5166	.3300	.3683	.3516	.3250	3.84	4.16	4.01	4.57	73.8	300	4.07	Down	1.0000	.9070	1.000	.874
9	.8000	.6471	.6286	.6471	.6128	.6128	.4529	.4714	.4529	.4872	3.13	3.32	3.13	3.47	92.8	300	3.23	Down	1.0300	.9710	1.000	.874
10	1.0325	.5700	.5300	.5775	.5725	.5725	.4695	.5025	.4550	.6600	5.45	5.69	5.41	6.82	54.4	300	5.52	Down	1.1000	.9000	1.000	.874
																	Average		1.0071	.9060	1.000	.874
11	.8457	.6687	.6313	.6600	.6411	.6411	.4800	.4911	.4857	.4343	3.49	3.66	3.45	3.88	84.0	300	3.87	Down	1.0500	.9070	1.000	.874
12	.8616	.6700	.6450	.6816	.6416	.6416	.4916	.4966	.4800	.4200	3.51	3.86	3.49	3.76	85.0	300	3.83	Down	1.0500	.9120	1.000	.874

Observations {11} made with tubes turned ten degrees to the {right} of the direction of motion {left}

The values of ϕ for the tubes M and N are within .7 per cent. of unity. For Professor Gregory's tube, $\phi = .9636$, showing a slight suction action at the static part of the tube. The value of ϕ for the Tulane tube is .867, showing a suction action of $.33 \frac{V^2}{2g}$.

Observations 11 and 12 were made with all the tubes turned 10° to the right and left of the direction of motion. These observations are to determine what effect there is when the tubes are not exactly in line.

In conclusion, we see that the theoretical formula for all Pitot tubes is $H = \frac{V^2}{2g}$, but in most practical tubes the value of H is increased by a suction action at the static attachment; and so, when we take this action into account, we have for the value of H,

$$H = \frac{V^2}{2g} + C \frac{V^2}{2g}, \text{ or simply}$$

$$V = \phi \sqrt{2gh}$$

$$\text{where } \phi = \sqrt{1 - \frac{1}{C}}$$

EXPERIMENT 5.

Comparison of Velocities made with the Pitot Tube having the Oil Gage Attached, and with the Price Current Meter.

The Pitot tube, as ordinarily used, will not give accurate readings for low velocities, because the difference of the water levels is very slight, and it therefore cannot be read accurately.

The writer has devised a method for exaggerating the difference between the water levels for the same pressure at the point of the nozzle. The invention consists in substituting oil for air in the Pitot tube gage. When the pressure at the point of the tube is .1 of a foot of water, corresponding to a velocity of 2.53 feet per second, the reading of the difference of the two water levels on the scale, with air above them, is .1 of a foot. When the pressure at the point remains the same and oil is substituted for air in the gage, the difference between the two water levels increases until the difference between the weights of the column of oil and the column of water, due to their different specific gravities, is equal to the pressure at the point.

Let P = the pressure at the point of the nozzle in feet of water.

Let L = the difference between the two water levels in feet.

Let y = the specific gravity of the oil. Then $P = L (1-y)$.

Let us suppose, for example, that oil of specific gravity .9 be substituted for the air in the gage, then $P = .1 L$, or the scale reading is multiplied ten times.

TABLE VI.
COMPARISON OF READINGS OF THE PITOT TUBE WITH OIL GAUGE ATTACHED AND THE PITCH CURRENT METER.

Observation.	Point.	Scale Reading of Pitot Tube	Oil Gauge Readings.		Difference (2)-(3)	h in feet of Water Multiplied by (4) 0.078	Revolutions of Pitch Current Meter.	Revolutions per Second.	Distance.	Time.	True Velocity in Feet Per Sec.	Velocity by Pitot Tube.	Velocity by Pitch Current Meter.	True Vel.	True Vel.	Direction.
			Feet.	Feet.		Feet.	Total.	—	Feet.	Secs.						
1	2	2.7081	1.0137	1.1044	.0907	.09317	95	.7505	300	125.6	2.388	2.440	2.435	.977	.982	Up
2	2	2.7203	1.5921	1.1372	.0880	.08860	94	.7550	300	124.5	2.410	2.385	2.430	1.010	.992	Down
3	2	2.5215	1.8215	.7000	.05400	.05400	93	.5080	300	155.8	1.928	1.873	1.945	1.028	.991	Up
4	2	2.5124	1.8333	.6791	.05200	.05200	95	.5820	300	163.4	1.837	1.844	1.895	.996	.969	Down
5	2	2.4185	1.0445	.4740	.03090	.03090	93	.4800	300	193.8	1.550	1.542	1.578	1.005	.982	Up
6	2	2.4228	1.9390	.4838	.03768	.03768	91	.4700	300	193.8	1.550	1.550	1.550	.997	1.000	Down
7	2	2.3098	2.0740	.2352	.01832	.01832	93	.3330	300	279.4	1.075	1.085	1.125	.992	.950	Up
8	2	2.3085	2.0705	.2380	.01808	.01808	91	.3301	300	275.8	1.088	1.075	1.115	1.012	.970	Down
9	2	2.2550	2.1437	.1113	.00868	.00868	89	.2137	300	417.0	.719	.747	.755	.963	.953	Up
10	2	2.2588	2.1344	.1244	.00994	.00994	89	.2348	300	371.2	.808	.800	.810	1.010	.998	Down
11	2	2.2267	2.1797	.0470	.00360	.00360	88	.1295	300	680.2	.442	.485	.495	.910	.893	Up
12	2	2.2215	2.1888	.0327	.00255	.00255	78	.1013	300	770.0	.390	.495	.497	.903	.958	Down
13	2	2.3053	2.0800	.2253	.01758	.01758	91	.3150	300	288.2	1.042	1.003	1.070	.980	.974	Up
14	2	2.3091	2.0000	.2485	.01930	.01930	91	.3110	300	297.6	1.122	1.118	1.148	1.003	.978	Down
15	2	2.4033	1.9551	.4479	.03492	.03492	91	.4500	300	199.4	1.504	1.498	1.505	1.004	.998	Up
16	2	2.4971	1.9487	.5484	.03578	.03578	91	.4470	300	203.6	1.475	1.514	1.475	.979	1.000	Down
17	2	2.5011	1.8320	.6695	.05268	.05268	91	.5725	300	164.2	1.828	1.830	1.895	.999	.981	Up
18	2	2.5080	1.8155	.6925	.05400	.05400	92	.5840	300	157.6	1.904	1.863	1.900	1.022	1.002	Down
19	2	2.6080	1.7000	.9080	.07680	.07680	94	.6640	300	141.6	2.120	2.134	2.148	.991	.987	Up
20	2	2.6180	1.6895	.9285	.07320	.07320	93	.6810	300	130.0	2.198	2.198	2.200	1.012	1.000	Down
21	2	2.7105	1.5804	1.1211	.08750	.08750	90	.7490	300	129.0	2.347	2.372	2.383	.976	.970	Up
22	2	2.7005	1.5915	1.1150	.08700	.08700	92	.7290	300	129.2	2.378	2.395	2.340	1.005	1.015	Down
23	2	2.8241	1.4895	1.3346	.10450	.10450	90	.8070	300	110.0	2.502	2.503	2.502	.973	.973	Up
24	2	2.8178	1.4023	1.3555	.10580	.10580	93	.8240	300	112.8	2.600	2.608	2.605	1.020	1.005	Down
25	2	2.9033	1.3713	1.5320	.11910	.11910	97	.8390	300	110.8	2.710	2.770	2.605	.979	1.018	Up
26	2	2.9150	1.3734	1.5416	.12010	.12010	94	.8870	300	109.0	2.830	2.783	2.840	1.018	.997	Down

In the experiment linseed oil of .922 specific gravity was used. Consequently the scale readings were multiplied by .078 for reduction to difference of water levels in feet of water. The specific gravity of the oil was determined at the same temperature at which it was used in the experiment.

The Pitot tube, with oil gage attached, and Price current meter were placed on the catamaran. The catamaran was hauled through still water at different known velocities, and the readings of the velocities, as given by the Pitot tube and by the Price current meter, were compared with the true velocity. The same method of observation was used in this experiment as in Experiment 3. The Pitot tube used was tube M (Fig. 24), and its constant was taken as unity.

The Price current meter was rated in October, 1900. Its rating is $y = ax + b$. Where y is the velocity in feet per second, x is the number of revolutions of the meter wheel per second, and a and b are the constants of the instrument. The value of a was determined to be $a = 3.0968$. The value of b , $b = .0936$.

The rating was very carefully made over a 500-foot course, and there is every reason to believe that it is accurate. The current meter and the Pitot tube were placed 2 feet in front of the bow of the catamaran and submerged equal depths below the surface of the water. After each observation, the direction of the boat was reversed, and the next observation taken in going back over the course. This eliminated any error due to a current in the canal. Table VI gives the results of these observations.

Column 4 gives the average difference between the water levels on the oil gage. These differences are averages of about fifteen readings.

Column 5 gives the equivalent of column 4 in feet of water. The numbers in column 5 substituted in the formula $V = \sqrt{2gh}$ give the velocities recorded in column 11.

Columns 13 and 14 give the percentages of error of the Pitot tube and of the current meter. By an inspection of these two columns it is seen that the Pitot tube, with the oil gage attached, is as accurate on low velocities as the current meter, and offers the advantage of having no time element.

The writer wishes to express his indebtedness to Mr. B. Shall for the splendid photographs taken by him and for his assistance with the Price current meter. The writer is also indebted to Mr. H. Rummel, engineer of Jordan Avenue station, and to his efficient force, for many courtesies extended.

DISCUSSION.

MR. GEORGE H. FENKELL.*—The experiments conducted and described by the author are extremely interesting and instructive, for it is by means of such as these that the laws governing the flow of water will be better understood.

Table VI shows that the "Pitot tube, with the oil gage attached, is as accurate on low velocities as the current meter," etc. This depends upon circumstances. In a wide and deep-flowing river the current meter offers advantages which the Pitot tube does not possess, although this does not imply that the latter cannot be used; for in April, 1898, a Pitot tube connected to the oil differential gage, described in the Proceedings of the American Society of Civil Engineers for May, 1901 (Experiments at Detroit, Mich., on the Effect of Curvature Upon the Flow of Water in Pipes, page 382) was used for taking velocity measurements at various depths in the Detroit River near the Detroit Water Works pumping station. The oil gages had been constructed in 1897, and were used to a limited extent in determining velocities in pipes under pressure.

In many places the Pitot tube offers advantages. To cite one investigation that the writer conducted: It was necessary to determine the quantity of water used by a water wheel working under a very low head. Floats could not be used, and weir would cause back-water on the wheel; but excellent results were obtained with a Pitot tube. A temporary shute was constructed in the tail race, 16 feet long and 15 feet wide, through which the water passed at a high velocity and from 10 to 15 inches deep. A sled, sliding on a carefully leveled track formed of 6 x 12-inch timbers, carried the tube, and readings were taken at various depths and positions.

Although almost any form of tube, if properly rated, can be used in open streams, some work better than others; for, if improperly constructed, when readings are taken with the point near the surface, the eddy caused by the tube will allow air to follow down the downstream side of the tube and reach the side or static opening, thereby destroying the partial vacuum maintained in the gage by admitting air in the tube. It would seem to the writer that this would be true with the Tulane tube, Fig. 24.

No matter what tube is used, the water must be free from floating moss and weeds, and if the tube openings are small, trouble will be experienced in any water carrying large quantities of mud or silt.

*Member Detroit Engineering Society.

MR. CLARENCE W. HUBBELL.*—The experiments described are of more than usual interest to the writer, who has, during the last four years, used and rated a number of Pitot tubes of various forms and designs in his connection with the work of the engineering department of the Detroit Water Works; first as chief draftsman, and since October, 1898, as civil engineer in charge. A paper published in the May Proceedings of the American Society of Civil Engineers, and still open for discussion, describes original investigations in which Pitot tubes and oil gages were used. The writer does not feel it necessary to enter into a description or details of work there fully given, but will merely call attention to a few points which the present paper brings out.

First, from a personal experience with the difficulties to be overcome in conducting such investigations, the writer especially appreciates the amount of painstaking labor involved and careful observations and reductions necessary to reach the published results and conclusions presented by the author. All experimental data must be closely scrutinized, and the results accepted only after a careful analysis, and even then with both caution and judgment. The well-worn axiom still stands, however, that "an ounce of experimental truth is worth more than a pound of theoretical deduction." Along this line the experimental determination of the action of a jet impinging on a plane surface apparently shows, in a very interesting manner, both the truth and fallacy of existing theories.

In describing the third experiment, the author states that "the form of nozzle for Pitot tube makes no difference, so long as it is a surface of revolution and its axis exactly in the line of motion." It appears to the writer, however, that the results of the first experiment, taken in the light of those which follow, would authorize a somewhat broader statement, and that the form of nozzle need not necessarily be a surface of revolution,—a result apparently substantiated by experiments with tubes of the knife-edge type, with which the writer is familiar. The point is well taken that each individual tube must be standardized, and that the opening giving the static pressure causes the principal variation in the rating of different tubes.

In the fall of 1897, the writer used an oil gage with a Pitot tube in determining the flow through a 42-inch cast iron main under pressure, and experimented with various oils of different specific gravity, common kerosene giving the best results.

Numerous data with reference to oil gages, their calibration and use will be found in the paper above referred to. The time

*Member Detroit Engineering Society.

required for an oil gage to reach equilibrium is, however, much greater than for the same gage filled with air and water. This is especially true when a heavy oil is used and the tube openings are small. Where there are a large number of points to be observed in a cross-section, requiring the frequent moving of the point of the tube, the extra time required at each position becomes a serious objection.

MR. GARDNER S. WILLIAMS.*—This paper is one of particular interest to the writer, as it throws much additional light upon phenomena observed by him in connection with an investigation† to which he has devoted considerable attention for several years. The experiments of the writer and his co-laborers confirm the explanation of the author of the reason why a Pitot tube frequently indicates a higher velocity than actually exists when the theory that $V^2 = 2gh$ or $h = \frac{V^2}{2g}$ is applied to the observations. If more evidence upon the effect of water flowing past the pressure openings of such instruments is desired, attention is called to the head observed by means of a 1-inch pipe laid transversely across an open channel and 8 inches above the bottom, with $\frac{1}{2}$ -inch diameter perforations on its under side, as compared with that observed upon a pipe having a similar series of perforations laid transversely in the bottom of the channel, the openings being flush with and at right angles thereto, as represented in columns 5 and 6 of Table No. 8, pages 326 and 327, Transactions of the American Society of Civil Engineers, Vol. XLIV. That orifices, situated similarly to those in the upper transverse pipe, do not give a head in open channels corresponding to the height of the water surface above them when placed in a current has been observed by the writer many times, the fact having been first brought to his attention by Mr. Hiram F. Mills, C. E., of Lowell, Mass. It has always seemed to the writer that a more careful reading of Weisbach by those authorities who have adopted the impact theory for the Pitot tube would have shown that the case of the limited stream impinging upon an unlimited surface was quite a different matter from the unlimited stream impinging upon a limited surface, and it requires no very great stretch of imagination to conceive that the Pitot tube velocity opening conforms to the latter and not the former condition. In view of this, the writer early decided to cast his lot with Darcy, Bazin, Mills and Freeman, and adopted the formula $h = \frac{V^2}{2g}$ for

*Member Detroit Engineering Society.

†See Proc. Am. Soc. C. E., May, 1901 "Experiments at Detroit, Mich., on the Effect of Curvature, etc."

the reduction of Pitot tube observations. But although the experiments with which the writer has been connected have convinced him of the correctness of his conclusions, he is none the less pleased to see the question worked out in the very conclusive and accurate manner in which it is presented by the author, and he ventures the prediction that when it is shown, as it can be, that the observed results will be the same, whether one foot or one mile of connecting hose intervenes between the orifice and the tube gage, it will be rather difficult to controvert the author's deductions with a claim of frictional losses in the apparatus.

The conclusion drawn from these experiments as to the effect of the form of the velocity or point ajutage upon its coefficient,—*i.e.*, that for an orifice bounded by a surface of revolution,—in a plane at right angles to the direction of motion, the coefficient is sensibly the same, whatever the form or extent of the exterior walls, is also of especial interest. This view is that generally accepted by those most familiar with the instrument, and follows from the theoretical discussion based upon straight line flow in the water, but the experiments of the author do show a very slight variation of coefficient for the tubes as experimented upon in the jets, which may, however, be easily accounted for by small errors in observation or position of the instrument. From the writer's experience, he has been inclined to the view that in flowing water the coefficient of the velocity opening might be modified slightly by the form of the surrounding walls, and the experiments discussed upon pages 380 and 381 of the paper already referred to* seem to bear out this conclusion, although it is to be admitted that the differences there exhibited, except in one case, are not so great but that they might be accounted for by slight changes of condition within the pipe or in the position of the point of the instrument; nevertheless the coincidence of similar points, as those of tubes Nos. 3 and 6 and of tubes C and E as exhibited in the equations on page 343 and on Plate XII of that paper, would seem to favor the other contention. The points Nos. 3 and 6 were the only ones strictly conforming to the author's specification, as the others were circular orifices in knife edges and not in surfaces of revolution. It appears quite clear, however, that a point of the type of tube D of the writer, in which the knife edge projects beyond the center of the orifice, will have a higher coefficient than will one in which all sides of the orifice are in a plane. The experiments of the writer indicate, as is also shown by the author's work, that the

*Proc. Am. Soc. C. E., May, 1901.

coefficient of any given instrument is practically a constant for both point and pressure openings for all velocities so long as the conditions of flow do not change; but the same coefficient that holds for the conditions of normal flow does not hold for either point or pressure opening when the instrument is brought within the influence of a contraction in a pipe.

So far as the experiments go with which the writer is familiar, as well as those in the paper under discussion, they seem to indicate that the coefficient of a Pitot tube obtained by dragging the instrument through still water is not applicable to the apparatus when used in running water. For how much of this difference of coefficient the two parts of the apparatus are severally responsible the writer is unable to state, but his opinion is that the major part is to be accounted for at the pressure openings.

The oil differential gage described by the author was also invented, in 1897, by the writer and his associates at Detroit, Mich., and used by them to measure Pitot tube heads and losses of head in pipes in 1898; and instruments of that type, together with the results obtained by them, were exhibited to various members of the American Society of Civil Engineers at its annual convention at Detroit in July of that year, and, among others, were shown to a gentleman from New Orleans, connected with the drainage work, who received permission to communicate the device to the subordinates on that work. So far as the writer is aware, this was the first application of the device to the measurement of differences of head in water, although he has since learned of the use of a similar instrument to measure losses of head in flowing gases. The author's reduction of the gage observations is slightly in error, for, as determined by a long series of experiments, the coefficient of such a gage, computed from the specific gravities of the liquids, in the case of oil and water does not agree with that obtained by a comparison directly with two water columns. For kerosene, the true coefficient of multiplication has been found to be about 4 to 5 per cent., and for sperm oil 10 to 12 per cent. in excess of those computed from the specific gravities. That is to say, the instrument actually magnifies the difference of head more than is indicated by the author's computation. It is also very essential when using this gage to take account of the temperature, which has a very marked influence upon the coefficient, though the change of specific gravities is small.

This increased multiplying effect seems to be due to the adhesion of the oil to the glass, which is equivalent to an added weight of material when motion of the fluids begins. The fact

that thus far no such phenomena have been observed with mercury differential gages where the liquid has no affinity for the glass supports this explanation. Experiments upon tubes of different diameters would probably demonstrate its error or correctness, but the fact remains, however it be explained.

In the author's experiments the error in velocity would not be very great, as it is reduced in taking the square root of the observed quantity. The effect would be, when it is corrected, to increase the velocity obtained by the tube, and therefore to bring its coefficient down more nearly to that of the current meter.

In closing, the writer would express his high appreciation of the ingenuity exhibited in devising the experiments and the care in their execution, of which the results give ample intrinsic evidence. He also fully appreciates the many difficulties connected with such work, and would extend to the author his thanks for this valuable contribution to the all too scant literature of the subject.

MR. WALTER FERRIS.—In October, 1899, the writer made some experiments on a form of Pitot meter, the results of which may be interesting in connection with the author's deduction that the head shown by a pair of tubes may be largely affected by suction at the static opening.


The apparatus, as shown in the accompanying figure, consists of a cast-iron throat piece, bored 2 inches inside diameter and 2 inches long, connected to a length of 30 feet of 2-inch iron pipe. The gap between the flange on the pipe and that on the throat is bridged by a funnel of very thin sheet brass, to prevent agitation of the stream. The water passed through the throat, part of which is here shown, and discharged through about 150 feet of 2-inch pipe into an iron tank 17 feet diameter and 6 feet deep. The depth of water in this tank was measured by a large float, reading on a graduated board, with a home-made vernier. All quantities of water were read, it is believed, within less than 0.5 per cent. of error.

The Pitot tube, as shown in the figure, was separated into two parts,—viz, a static opening, S, which consisted of a $\frac{1}{4}$ -inch hole drilled through the top of the throat, and the dynamic opening, or Pitot tube proper, P_1 , consisting of a piece of $\frac{1}{4}$ -inch (outside diameter) seamless brass tube, $\frac{5}{8}$ -inch bore, facing the flow and sharpened off to a knife edge, as shown. With this arrangement of tubes, connected to a differential mercury gage, were taken the readings of Series A in table below.

At the same time, another set of readings, called Series B, was taken from a second differential mercury gage, one leg of which

was connected to the same Pitot tube, P_1 , while the other leg, instead of receiving the static pressure through S , was attached to another Pitot tube, P_2 , exactly similar to P_1 , except that P_2 was reversed in position, as shown. All these three pressure openings terminated in approximately the same cross-section of the throat.

The duration of each experiment was from eight to twenty-six minutes, read by an ordinary watch, probably within two seconds in each case. The head upon the throat was about 200 feet, the



velocity of flow being controlled by a valve in the discharge pipe from the meter.

From the table of results, it appears:

(1) That the "suction" effect on the reversed Pitot tube, P_2 , is very little greater than upon the plain static opening, S . Compare lines 4 and 6, giving the two simultaneous heads, A and B . The ratio of these two heads, as given in line 8 of the table, averages, 1.031, giving only about 3 per cent. increase of head. This does not seem to bear out the theory that a form of static opening

may be employed which will materially increase the head in the tubes as a pair, for in this case the static opening was placed in apparently the best possible position to receive the suction effect, but the consequent decrease in the pressure recorded is very slight.

(2) Comparing lines 4 and 9, as is done in line 10, it is evident that these tubes do give a much greater head (about 60 per cent. greater) than the theoretical velocity head, $h = \frac{v^2}{2g}$, derived from the actual velocity V , as measured by means of the discharge into the tank.

Now, it has been proved, by experiments on the Venturi meter, that the static pressure, indicated by a gage attached to a $\frac{1}{4}$ -inch hole drilled through the wall of a closed conduit, is within from 2 to 4 per cent. of the total head less the theoretic velocity head. From this we may infer that the large excess head shown in the writer's experiments is due in some way to the impact of the water against the Pitot tube, P_1 , and not to any action on the static openings, S or P_2 . Moreover, as the Pitot tube P was situated at a distance from the top of throat equal to one-half of the throat radius, which the Detroit experiments of Messrs. Williams, Fenkell and Hubbell show to be the region of mean velocity, there seems to be no reason to attribute the excessive head to high velocity at the impact opening.

The writer does not feel justified in drawing any general conclusions from a comparison of these experiments with those of the author, partly because the writer has not yet had opportunity to study the author's paper with the care which such an elaborate series of experiments demands, and partly because there is already considerable evidence that the laws governing the action of Pitot tubes in closed conduits and in open bodies of water are not identical. The author's experiments seem to prove definitely that in certain cases the head in the Pitot tube, as distinguished from that in the static tube, is independent of form and is equal to the theoretic velocity head. On the other hand, the experiments herein reported seem to prove with equal certainty that, under the conditions of these experiments, the Pitot head is greatly in excess of the theoretic velocity head, and that this is not due to suction at the mouth of the static tube.

The foregoing facts, together with the experiments of Messrs. Williams, Fenkell and Hubbell, published in the Proceedings of the American Society of Civil Engineers, May, 1901, which showed different coefficients for the same pair of Pitot tubes when calibrated in an open canal and in a closed pipe, suggest the hypothesis that the

head in any Pitot tube will be greater or less, for a given velocity, according to the obstructions offered to the deflection of that part of the stream which strikes the point of the tube and which must change its course in order to pass around it. Near the surface of an open canal, the presence of the tube would cause merely a slight rise or wave in the surface, affecting very slightly the pressure against the tube; whereas, deeper down, the increase of pressure might be expected to be greater. In a closed conduit, the whole mass of flowing water must be more or less accelerated as the tube reduces the cross-section, and the resistance to the transverse motion of the particles of water impinging against the mouth of the tube and passing off at right angles to their former course may be expected to be much greater on account of the confining walls. Hence it seems reasonable to expect that the pressure in the tube, when placed in a closed conduit, should be greater than when in an open stream, as many experiments have shown that it is.

TABLE.

(1) Experiment No.	138	139	140	141	142	143	144	145
(2) Duration in Minutes.	10.230		16.350	16.320	26.560	16.430	8.170	8.170
(3) Actual mean velocity in 2'' throat, by tank, in feet per second.	13.950		5.700	3.240	4.320	6.700	11.720	16.680
(4) Heads, "Series A," in feet of water.	4.790	Omit. Observations not Reliable.	0.807	0.252	0.478	1.110	3.430	6.860
(5) $V_A = 8.02 \sqrt{\bar{A}}$	17.560		7.200	4.020	5.540	8.440	14.850	21.00
(6) Heads, series "B" in feet of water.	4.970		0.832	0.277	0.479	1.160	3.490	7.060
(7) $V_B = 8.02 \sqrt{\bar{B}}$	17.850		7.310	4.210	5.550	8.630	14.990	21.300
(8) Ratio $\frac{\text{Head B} = (6)}{\text{Head A} = (4)}$	1.037		1.031	1.100	1.003	1.045	1.017	1.028
(9) Velocity head $\frac{V^2}{2g}$, due to actual mean velocity, shown by tank measurement.	3.020		0.503	0.103	0.290	0.608	2.130	4.330
(10) $\frac{\text{Head A}}{\text{True Velocity Head } \frac{V^2}{2g} = (9)}$	1.586		1.593	1.550	1.050	1.590	1.610	1.584

*Computed with slide rule.

MR. W. M. WHITE.—The writer wishes to express his appreciation of the just criticisms of his paper. A point that the writer wishes to make clear is the fact that the correct formula for the Pitot tube is $V = \sqrt{2gh}$, whether it be considered from the point of view of impact or not. Experiments 1 and 2 show the effect of a "limited jet impinging upon an unlimited surface," as Mr. Williams puts it, but the maximum pressure per unit of area never rises higher than the velocity head contained in the water. Experiment 3 shows the effect of an "unlimited stream impinging upon a limited surface," and shows that the pressure at the point is equal to the velocity head contained in the water.

Mr. Williams, in discussing his tube D, in which the knife edge projects beyond the center of the orifice, says "it will have a higher coefficient than will one in which all sides of the orifice are in a plane." This bears out the writer's statement that the point of a Pitot tube should be a surface of revolution. That tube which converts all the velocity head into static head, exactly according to the law $V = \sqrt{2gh}$, should be the one selected for use, for, if a tube does not do this, it is not a Pitot tube in the true meaning of the term.

There is evidence that the rating of some Pitot tubes, obtained in open canals, does not apply when the tubes are used in closed conduits under pressure. There can be only two causes affecting this result, when the cross-section of the conduit is not materially affected by the introduction of the Pitot tube: First, some change in the law for the conversion of velocity head into static head at the point, due to the increased pressure, or, second, some change in the value of the suction action at the pressure opening, due to the increased pressure.

That the law for the conversion of velocity head into static head can be affected by pressure is hardly conceivable, since the pressure at the point is increased by an equal amount in all directions. That the increased pressure could affect the suction action at the pressure openings seems possible. This suction action is caused by the irregularities of the tube near the pressure openings, as, for instance, the Tulane tube, where the irregularities of the nipple and the tee cause a suction action equal to 39 per cent. of the velocity head. These irregularities distort the flow of the water, causing it to take a direction away from the openings. This flow, striking the surrounding water with constant impact, relieves the pressure at the openings.

When the pressure of the surrounding water is small, the effect of the impact is large, comparatively. As pointed out by Mr.

Fenkell, the distortion could be so great as to admit air into the openings when the tube was used near the surface of the water. When the pressure on the surrounding wall of water is increased, the effect of this distorting force is small, comparatively, and hence changes the coefficient of the tube.

In June, 1900, the writer made some tests* with a Pitot tube inclosed in a 52-inch pipe. The pressure within the pipe was a little less than atmospheric pressure. The tube was worked under an average pressure of 2 feet of water. The side of the pipe was tapped for the static opening, and a pipe led to the Pitot tube gage, connecting it with the point and pressure pipes. The point and static readings were treated as those of a Pitot tube having a constant of unity, and the constant of the point and pressure was calculated to be 0.856. The Pitot tube (Tulane) was afterward calibrated in an open canal under a head of 2 feet, and its constant determined to be 0.849. That is to say, the point of the Pitot tube converted velocity head into static head according to the law $V = 0.993 \sqrt{2gh}$. This is well within the limits accorded to the errors of observation.

An examination of the paper referred to by Mr. Williams will show the same thing when those tubes whose points are surfaces of revolution are considered with the "ring" openings for pressure readings. For four observations, the constant of the point does not vary from unity more than 3 per cent. In fact, a traverse in the 2-inch pipe agrees with the writer's deduction by $\frac{1}{2}$ per cent.

Mr. Ferris's experiments seem to prove exactly the opposite, but the writer does not believe that those experiments are subject to the deductions which Mr. Ferris draws. The areas of the small pipes that are inserted into the 2-inch pipe are so large as to seriously affect its cross-section. The writer takes exception to the position of the small pipe marked P_2 in the figure. In the paper referred to by Mr. Williams it has been shown that slight irregularities in the pipe produce abnormal distortions in the velocity curve. According to that fact, the pipe P_2 , owing to its position, may readily shift the point of maximum flow from the center of the 2-inch pipe to the center of the pipe P_1 . Whether the maximum velocity would be at P_1 or not, it is readily seen that the velocity there would be considerably increased. Let us suppose, for example, that the maximum velocity does occur at P_1 . Under the existing conditions, this supposition seems as tenable as that the average velocity should occur at P_1 . According to the paper re-

*JOURNAL OF THE ASSOCIATION OF ENGINEERING SOCIETIES, October, 1900.

ferred to by Mr. Ferris, the ratio of the mean to the maximum velocity is 0.81. Assuming that the effective cross-section of the 2-inch pipe is reduced by 5 per cent., owing to the position of pipe P_2 , then the mean velocities, as given by Mr. Ferris in line 3 of his table, should be increased 5 per cent. Dividing this increased mean by 0.81, we obtain the maximum velocity, which occurs, according to the writer's deduction, at P_1 . In the following table line B gives the velocities thus obtained. The velocities in line B are to be compared with the velocities given in line 5 of Mr. Ferris's table. If the writer's deductions are correct, it is seen that the center of the velocity curve has not been shifted quite as high at P_1 . If Mr. Ferris would make a traverse on a diameter with pipe P_1 , he could easily determine the correctness or fallacy of the writer's deductions. But a traverse made under the same conditions, in a pipe of

VELOCITIES TO BE COMPARED WITH THOSE IN MR. FERRIS'S TABLE.

No. of Mr. Ferris's Ob- servation	Line	138	140	141	142	143	144	145
Mean Velocity, Line 3, copied from Mr. Fer- ris's table	A	13.95	5.70	3.24	4.32	6.70	11.72	16.68
Line A $\times \frac{1.05}{.81}$	B	18.15	7.41	4.21	5.61	8.70	15.21	21.65
Line 5 from Mr. Ferris's table	C	17.50	7.20	4.02	5.54	8.44	14.85	21.00

the same size, under a pressure of 35 pounds per square inch, described in the paper referred to by Mr. Williams, bears out the writer's deductions within $\frac{1}{2}$ per cent.

The pipe P_2 is not placed in the best position for the greatest suction action. The writer has experimented with nozzles of different shapes moving through water and placed at different angles with reference to the line of motion. He finds that the maximum suction action of a pipe similar to P_2 occurs when the axis of the pipe is at right angles to the direction of motion. The suction action gradually decreases to a minimum as it approaches the position of P_2 , with respect to the flow.

The writer regrets that he did not know of the existence of the differential gage, as it would have saved him considerable time and worry in the solution of the problem.

In conclusion, the writer draws the following deductions:

(1) That an impact tube, whose impinging surface is one of revolution, converts velocity head into static head exactly according to the law $V = \sqrt{2gh}$, whatever the pressure of the surrounding fluid.

(2) That only pressure openings which give the true static head of water should be used in connection with the point of a Pitot tube. That is to say that only tubes which have unity as their coefficient should be used.

(3) That Pitot tubes whose constants are unity in open canal ratings will remain unity, whatever the pressure of the liquid. Tubes M and N, Fig. 24, are of this type.

A PLAN TO UTILIZE UNEMPLOYED LABOR.

BY JAMES A. STEWART, MEMBER, ENGINEERS' CLUB OF CINCINNATI.

[Read before the Club, May 23, 1901.*]

My subject is somewhat out of the usual line of our professional work, but one that I think the engineers should interest themselves in.

It has been well said that the engineer's duty is "to adapt the forces of nature to the use and convenience of man."

There is a great force which, properly organized and managed, will produce wealth sufficient to improve immeasurably the condition of the laborer and mechanic. To my knowledge, this force has never been organized under a simple system, so that it could be made productive and self-sustaining.

In this and in foreign countries, efforts have been and are still being made to better the condition of man through political efforts and the enactment of laws establishing labor bureaus, reducing the hours of labor and making appropriations for public work. This is all well enough so far as it goes, but I believe the true solution of the labor problem is to be reached through the efforts of man in a businesslike way, without the aid of any laws or financial assistance from political governments.

The human force, physical and mental, that is lost in idleness for lack of opportunity or means of being employed is, in my opinion, great enough to produce the wealth of a corporation or trust equal in magnitude to any of the trusts now in existence.

Politicians, labor agitators and economic writers are trying to solve this problem. I believe that it is a problem in engineering, and should be taken up, studied and solved by the profession. No body of men comes in closer contact with the laboring classes than the engineers. No one is in a better position to judge of the value and magnitude of their efforts than is the engineer.

He it is who prepares the plans and specifications for all improvements and starts the army of laborers and mechanics to work. Under his constant supervision they bring the improvement to a successful completion, and then very often, though not always, it becomes his duty to organize and superintend the operating forces.

So that, in the line of his duties, it falls to his lot to be closely identified with an enterprise from the time it originates in the promoter's brain through all the different stages of development, from unimproved land to wealth yielding an income to the capitalist.

*Manuscript received July 31, 1901.—Secretary, Ass'n of Eng. Socs.

There his duties generally end. He is not consulted in regard to the clipping of coupons, as he was never known to have any of his own to clip, and he therefore lacks the necessary experience, through no fault of his, however.

Now, there are reasons why we have no coupons to clip, and each individual can no doubt look back over his experiences and in one way or another account for his lack of wealth. We shall no doubt find many reasons, and each individual's reason may be different from the others; but I believe there is one reason common to us all, and if we can prepare plans and specifications by which this reason can be obviated we shall have solved the problem of the "unemployed."

This underlying reason, common to all, is time lost in idleness, or in not being engaged in profitable employment. If each individual will estimate the number of months lost at the average rate of his salary during seasons of his employment, or, if engaged in private business, the amount of work he might have done had it been offered him at a reasonable profit, I think the total will be a sum great enough to have paid for a comfortable home free of incumbrance.

The home is the foundation of civilization. It represents the wealth of nations and of municipalities, upon which their bonds and credit are based.

Each individual or family must have a home, whether it be one room in a crowded tenement house or a mansion in the suburbs, and the location and character of the home is a fair barometer of the social condition of the occupants.

Now, admitting that the home is a prime necessity to all, and that our weak financial condition is due, in part, to time lost in idleness, the problem to solve is, can we utilize our idle time in the securing of a home? If so, how, when and where?

The engineers and architects are respectfully requested to submit plans and specifications for the solution of this problem.

I am going to present for your consideration to-night a plan which I believe will help solve the problem, and which, if taken up, studied and improved upon by the profession, will lead to gratifying results. Upon the efforts of the laborer and mechanic depend the success of our work, and we should give our best efforts to the amelioration of their condition.

If I can present one single idea that will tend to make work for any one out of employment, my effort will not have been in vain.

Statistics show that 70 per cent. of the people do not own a home, and I propose to build homes for these people by the co-

operation of landowners, material men, merchants and unemployed laborers and mechanics.

I would organize a savings and a building company, the object of which would be to assure the accumulation of an estate to each of its shareholders by giving him employment at or in his own trade, profession or business when he is out of employment, or giving him an opportunity to increase his business in dull seasons. The result of this labor to be deposited with the company and invested by it in the manner best calculated to secure to each depositor fair dividends on the result of his labor.

The affairs of the company are to be managed by a Board of Directors, thoroughly conversant with land values, cost of material and labor, experienced in public works and having the confidence of the people.

I think there would be little trouble in securing all the land necessary, and about 50 per cent. of the material and labor can be secured. Money would have to be secured to make up the remaining cost of material and labor at the start, but after the confidence of the public was once established little actual money would be needed. A simple system of exchange of credits is all that is necessary. When an individual's credit amounts to the value of a house, he could be given a deed to the property and his account balanced. The rentals from ten to twenty houses would pay from 4 to 6 per cent. on the investment, and members not wishing a home would be satisfied with that and would leave their principal to be used in the business.

To give you an idea of the wealth that might be produced in a year, I will give you the difference in cost of buildings erected in Cincinnati in 1898 and 1899, as shown by figures from the Building Inspector's office:

In 1899 the total cost of structures was.....\$2,378,000

In 1898 the total cost of structures was..... 1,736,000

The difference was..... \$642,000

This difference approximately represents one year's loss of material wealth in the building trade alone for the lack of opportunity to invest labor and material in productive enterprises. The same labor that produced \$2,378,000 of wealth in 1899 was willing and anxious to have produced the same amount in 1898.

It is an indisputable fact that a majority of the people living in the tenement house are the people whose labor is necessary for the construction of homes, and this labor is idle about three months in a year. This enforced idleness keeps them in poverty when, by

co-operation with land owners, material men and merchants who wish to increase their business, they could utilize their labor during that time in the construction of a home. Three months of enforced idleness, for the labor engaged in home-building, represents a loss to that labor in material wealth of about \$1500.

Distributed among the different classes of labor as follows: Common labor, about \$90; bricklayers, about \$216, and others in similar proportions, one day's labor, invested at 6 per cent., will double in twelve years.

The laborer, at \$1.50 per day, for sixty days in the year, would accumulate about \$1700. A very comfortable home can be built for that amount of money, and the better paid labor could secure a better home in less time. Banks and building associations are paying larger dividends than this.

It is possible for all men engaged in the building trades to become the owners of their homes in less than ten years, and they will have been paid for in labor performed in time that would otherwise have been spent in enforced idleness.

How many have been able to build a home and have it free from incumbrance in that time by borrowing money from a building or loan association or savings bank? A very small percentage, I think.

The average time required to obtain a home on the instalment plan will exceed fifteen years, and the amount paid in interest and premium in that time will have doubled the cost of the home. And many an unfortunate one has lost his home and all payments made thereon because he could not keep up his interest, premium and dues. The old story, money scarce, dull times, no work for laboring men or mechanics.

Did you ever stop to think how simple and easy it has been made for the people to invest their idle capital in the form of money, and how hard for them to invest their idle capital in the form of labor, the source of all capital?

If you have \$1000 or more of idle capital in money, it will not take you more than one hour to get to a savings bank and trust company where you can deposit the money and draw about 4 per cent. interest on it from the day of deposit.

If you have \$1 per week idle capital in money you can deposit it weekly in a building and loan association which meets near your home, and will pay you semi-annually about 6 per cent. interest on your money.

In building a home, you start all the wheels of industry to moving. Stone must be quarried from the hill, brick made from

the original clay, trees felled in the forest, iron and lead taken from the mines; that which is not produced at home must be shipped by rail or water to its destination. The engineer surveys the lot and stakes out the house; the architect prepares plans and specifications; the laborers dig the cellar; teamsters haul the material to the site, and skilled mechanics in their respective branches erect the home. With this labor engaged in productive enterprise, it will necessarily increase the labor engaged in distributing enterprise and improve the business of merchants.

Until we have built homes for 70 per cent. of the people who now live in rented property, I see no good reason for men being out of employment or merchants not doing a profitable business. Put men to work in a productive enterprise and establish a system of credits with the home as the basis, which will have the confidence of the public, and I believe the profits in ten years would exceed that of the savings banks, and they are not small. The Union Saving Bank and Trust Co.'s profits are in part represented by the skyscraper, and that will be a dividend producer for many years to come.

Now, in conclusion, allow me to request you to think of this plan (if you think of it at all) as a business proposition, and a business proposition only. Do not look upon it as a socialistic measure or a political reform of any kind. The only difference between this proposition and a banking institution is that one accepts money deposits while the other accepts money, material and labor deposits, and they would both invest their capital in the same manner.

I trust that this Club will not deem my plan Utopian. All reforms have been regarded as futile until carried to a successful issue. There can be no nobler work for the engineer than to devise some kind of a scheme to capitalize the energies of the self-respecting fellow-laborer out of employment.

OBITUARY.

Benjamin Thomas Lacy.

MEMBER, TECHNICAL SOCIETY OF THE PACIFIC COAST



BENJAMIN THOMAS LACY, a member of the Technical Society of the Pacific Coast, died at his residence in San Francisco on the 21st of May last. He was long and widely known to the membership, and did much to promote the practical objects of this Association, both as a merchant and as an engineer. His unbounded energy and assiduous labor in conducting the business of the Park & Lacy Company, of which he was the president and chief owner, was no doubt one of the causes that led to his death at the early age of fifty-six years.

Mr. Lacy was born in 1846, at Wexford, on the east coast of Ireland, from which the family removed to Liverpool, England, where Mr. Lacy was educated and apprenticed to an engineering firm in that city, serving seven years and passing through the regular course, including the various departments, as is the custom there. This training laid the foundation of his business life, because, while known here mainly as a merchant, he was nevertheless thoroughly acquainted with the construction and operation of all kinds of machinery, and has always maintained an engineering department in his business.

He came to this country in 1867, and was engaged in the early development of pneumatic drilling machines and compressors at Fitchburg, Mass., and afterward at many places in this country in erecting and operating this class of machinery. He also went to Europe, and at the Mont Cenis Tunnel superintended the installation of the American rock-drilling machines. He then came to Nevada to introduce pneumatic machinery in the construction of the great Sutro Tunnel at Virginia City. When there he met Mr. Lyman C. Park, with whom a partnership was formed to deal in machinery and mining supplies in San Francisco. This firm prospered, and established branches at Salt Lake City, at Portland, Ore., and at Sydney, New South Wales. There have indeed been few if any firms on this coast that have ventured so far afield or taken so comprehensive a view of the trade in any line of business.

About ten years ago he purchased the interest of Mr. Park, and later on founded an incorporated company with a view of some relief from labor and care involved in the management of the extensive business; but the strain had been too great and had sapped his vital powers, producing organic disease that his vigor could not overcome.

Mr. Lacy's environment had always been of an engineering nature. Mrs. Lacy was of the Canning family that for several generations were noted engineers and millwrights in the North of Ireland, she having eight brothers all in this pursuit.

Your committee is glad to present this tribute to one who was a prominent and valued member of our Society, who has done much and his full share to promote the interests of engineering on this coast as well as that of the Technical Society.



Respectfully submitted,

J. RICHARDS,

G. W. DECKER,

GEO. E. DOW,

Committee.



INVERTED SIPHON AT EVERETT, MASS.

To accompany discussion by Mr. W. W. Cummings on "Subaqueous Tunnels for Gas Conduits," JOURNAL OF THE ASSOCIATION OF ENGINEERING SOCIETIES, Vol. XXVI, No. 6, June, 1901, pages 342-344.

Editors reprinting articles from this journal are requested to credit not only the JOURNAL, but also the Society before which such articles were read.

ASSOCIATION OF ENGINEERING SOCIETIES.

Organized 1881.

VOL. XXVII.

SEPTEMBER, 1901.

No. 1.

This Association is not responsible for the subject-matter contributed by any Society or for the statements or opinions of members of the Societies.

EFFICIENCY OF MULTIPLE VOLTAGE CONTROL IN ELECTRIC POWER TRANSMISSION.

BY LEHMAN B. HOIT, MEMBER CIVIL ENGINEERS' CLUB OF CLEVELAND.

[Read before the Club, May 14, 1901.*]

THE use of electricity for the transmission of power has become an attractive problem, especially since the general introduction of electric lighting has rendered the installation of some kind of generating plant a necessity. The progress which has been made within the last few years in the centralization of power-generating units, in the abandonment of long and heavy lines of shafting and in the elimination of complicated belt drives makes it self-evident that this form of power transmission has entered upon a new phase of development. As a result of this modern advance in the use of electricity for power transmission, the methods of applying and controlling have become matters of ever-increasing importance.

That this subject is far more than a technical problem of engineering is evinced by the exhaustive study and experiments made by our ablest mechanical and electrical engineers. While the results of their investigations and experiments have been very gratifying, and have borne fruit in many directions, there is still open a wide field for improvement. Unfortunately, the general trend of investigation has been upon the lines of the character of the current to be used in power transmission rather than in its application.

This controversy, however, has awakened the interest of those closely associated with the development of electrical ma-

*Instructions to publish received August 23, 1901.—Sec'y, Ass'n of Eng. Soc's.

chinery; but the arguments advanced by the advocates of one system or the other, which constitute the bulk of literature available on the subject, concern the improved methods of generating and transmitting this energy, and not its application and control. The arguments in favor of the direct current system over the alternating current system, and *vice versa*, have been of a technical rather than a commercial value, and, as a result, the purchaser has had little opportunity, owing to his limited knowledge of the subject, to exercise his judgment in the matter. When he is inclined to suggest improvements in his own plant in the use of either the alternating or direct current apparatus, along the lines he has found acceptable in those of other locations, he finds that the circumstances are so different that it is difficult for him to determine which system is more applicable to his requirements.

It would be well, therefore, to let the person interested in the use of electric power transmission place in one column the features in which the direct and alternating current machines are alike, and in another those in which they differ, and the results will surprise him. Speaking generally, it is safe to say that direct and alternating current machinery manifests like rather than unlike characteristics, so there is really no justification in the stand taken by one advocate or the other, simply because of a supposed difference in the efficiencies of the two systems.

The prevailing defect in the treatment of the direct or alternating current transmission is the failure to observe that neither system is capable of universal application. Hence, the question of the best system for general use is a problem of great complexity, because we must take into account at once the relative values of the different systems as regards different conditions. The difficulties encountered in one location are not always of the same kind as those met with in another, and it would be folly to pass judgment on the efficiency of one system over the other without considering them from the same standpoint, or under the same conditions. Every intelligent person will admit that conditions may differ in this particular field of engineering to the same extent as in others, and that neither the theory nor the practice can be sound which takes no cognizance of the differences.

It would seem, therefore, that the first requisite for intelligent action in formulating methods of electric power transmission is an accurate and comprehensive knowledge of the existing conditions. It becomes, then, a matter of great importance, first,

to recognize that under all conditions the power generated and transmitted costs something and has a value, and, secondly, that the power imparted to the motor mechanism has a value in proportion to the use made of it. With these data, a foundation will be laid for deciding whether, when the results are not what they ought to be, a remedy should be sought, first, by substituting one form of current for the other, or, secondly, by modifying the conditions so as to make the values of transmission what they ought to be.

It is not my purpose, however, to discuss which form of current should be employed to produce the highest efficiency, nor to recommend any special type of machinery, but, rather, to call your attention to the several ways in which losses occur in the use of the power electrically transmitted. While it may seem necessary, in order to elucidate all the conditions which involve loss of efficiency, to enter into the discussion of the power plant as a whole, the subject embraces topics of so diversified a character, and so extensive in their bearing, that it would be inconsistent with my proposed limit to do more than briefly illustrate the several methods of application and control, and the way in which losses occur.

The word "loss," used in connection with this subject, should not, however, mislead us, nor should we consider it as a principal factor in the operation of this form of power transmission; because, in many cases where the difference in cost between the power produced and the results obtained are not excessive, the difference is principally a price paid for services rendered, and there is no loss.

While the application and control of this energy were the last of the several requisites considered in the early installations, the order of things is at the present time reversed. This reversal is due to the fact that the question of economical use of the power transmitted has become a far more important factor than the cost of production in the early installations. The question of efficiency, in the application and control of the power transmitted, was of less importance than was its use; but as the introduction of this form of energy became more general, and its functions better understood, comparisons were made between the cost of generating power and the amount of work performed by it. It was found that these two factors formed a very wide parallel in many of the installations, due to the fact that the power was wasted simply because the means of saving it were not known.

With the gradual increase in the size of the generating plants, and the increase in the number of motors, the cost of operating was more carefully considered, and this stimulated a closer study of the efficiency of the various methods of application and control. In considering the use of electric power transmission at the present day, there are two ends to the question of economy, with a middle of some magnitude. The practical efficiency of electric power transmission over the old method suggested the centralization of the steam plant, and the rearrangement and location of machinery suggested the use of motors, while these two suggestions, joined together, determined, in a measure, the methods to be employed in order to secure the best results for the money invested.

With these facts before us, we are prepared to determine the efficiency of the several methods used in the application and control of the power transmitted, and to fix a certain value for the work performed. To bring this matter still closer, and to emphasize the importance of considering the several methods employed for the economical use of the current, it seems necessary to define the formula which concerns the question of efficiency. We cannot do this, however, without determining the *value* or *utility* of the current in relation to its employment under different conditions of service. Let us, therefore, decide that the *value* of electricity, as a medium of transmitting power, rests primarily in its application, as compared with some other form of *transmission*, and its *utility* in the degree to which it can be controlled compared with some other *power*. The *value* and *utility* of electric power transmission, when considered from one standpoint, are inseparable, while from another they are no more to be confounded than any other two distinct things.

We will readily understand the value and utility of electricity as a medium of transmission by considering the methods used at the present time for operating and controlling the power in connection with variable speed machines. For convenience we shall divide these under three general heads, namely:

First. Belt transmission with mechanical speed control.

Second. Direct connected transmission with rheostatic control.

Third. Direct connected transmission with multiple voltage control.

Mechanical Speed Control. This method of applying and controlling the power transmitted requires no special mention, for the reason that every one interested in mechanical and electrical

engineering is familiar with the systems now in vogue. The only distinctive feature which this form of transmission possesses over the old system of direct line shafting rests in the reduction of frictional losses incident to the construction. The same counter-shaft losses which, in many plants, amount to nearly double that of the main line are present, and must be taken into consideration as a troublesome factor. No particular economy is obtained in this method of applying and controlling the power transmitted, except in the way of cutting out one or more groups of machinery that are not in constant use, and in shutting down the motor during periods of delay. There are other features, of course, which make this form of transmission desirable, notwithstanding the fact that the excessive losses of countershafting and belting are realized. There can be no question as to the advantage of electricity in many instances, for the reason that it is the only agency of transmission available. But these facts are generally understood, and the value of electricity, as a means of transmitting power, is proportionate to the benefits derived. Therefore, it is *valuable*. Its *utility*, however, under these conditions is questionable, because electricity makes open confession of its inability to do intermittent work or to give variable speeds at constant voltage without loss. Then, again, when the factor of time, in changing the speed of machines mechanically, is taken into account, this form of transmission has no particular advantage over any other system, except perhaps in its being able to make a virtue of a necessity.

In the installation of a system of this character, much depends upon the arrangement of the motor in relation to the machines that are to be operated. The grouping of the machines, of course, will depend upon the length of time each is in commission during a given part of the day. But this method has its limits, and it is a question of a very short time when all forms of belting will be eliminated. To meet the growing demand for motor-driven tools, the machine builders are hard at work trying to design proper speed variation which can be attached mechanically from a constant speed motor. There is nothing at present to recommend in this line, but, undoubtedly something will be gotten up in the near future to suit these conditions.

Rheostatic Control. This system was suggested as a means of controlling the motors applied directly to individual machines, and as a method of eliminating the countershafts and their belt connections. It was, however, a step in the wrong direction, as experience proved.

The supposition that the speed of the motor could be reduced to meet the various conditions of service, by inserting an external ohmic resistance in the armature circuits, is not borne out by the facts. It is found that while the motors would operate at substantially the same speed under variable loads, when the speed of the motor was normal, the ohmic resistance inserted destroyed proper regulation and it could not be automatically controlled. In order to maintain a standard speed less than the normal speed of the motor, it is necessary to move the lever of the speed regulator by hand each and every time the load changes on the motor.

Another peculiarity in speed variation is the fact that the power required on some kinds of machinery when running slowly takes almost as much current as at full speed. Whenever the load driven by the motor varies greatly, the regulation of its speed by means of external resistance in the armature circuit is almost sure to be more or less unsatisfactory, except, of course, where an attendant is always present, as, for example, in operating cranes, elevators, etc.

Many attempts have been made by the manufacturers of speed-controlling rheostats to devise some form of mechanism in which these objectionable features would be overcome. It is difficult, however, to understand how this may be accomplished, because the underlying principles of controlling any current, where its voltage is constant, are exactly the same as the regulation of water pressure where the supply is constant and the demand variable. The relief valve used in hydraulics has its defects, notwithstanding the fact that many years of study and experiment have been consumed in endeavoring to perfect its functions.

But the control of the motor is not the most serious drawback in the use of regulating rheostats, for when the speed of the motor is cut down by resistance in the armature circuit, all current consumed in the resistance box is wasted. It is very much like putting a friction brake on the fly wheel of an engine in order to vary its speed, instead of adjusting the governor. Such practice as this means an enormous waste of current, which must be dissipated in the rheostat, consequently the efficiency of a motor operated under these conditions falls considerably below that of a very poorly constructed line shaft and belt transmission. To bring this matter out more clearly it might be well to give the efficiency of a motor operated with rheostatic control. The motor tested was designed to run at 480 revolutions at normal speed,

and its efficiency at this speed and under full load was about 90 per cent., which is as high as is found in motors of good construction. At one-sixth of its normal speed, or 80 revolutions, the efficiency of the motor was only 12 per cent., showing that 86 per cent. of its output power was lost in the rheostat.

We feel justified, therefore, in saying that the rheostat is unsatisfactory, as regards both its ability to regulate the speed of the motor and its inability to lower the voltage, which it must do in order to obtain variation in speed without excessive loss of current. It would not be inconsistent with the facts, therefore, to state that, by the use of this method of control, electric transmission possesses neither *value* nor *utility*.

Multiple Voltage Control. The gain in the economical use of power, attributable to the adoption of electricity as an agency of transmission, carries with it some uncertainty when its application to motors connected to variable speed machines depends upon some form of mechanical or electrical control. The first method of application and control of the current supply has some advantage over the second, or rheostatic control, but neither has any particular field of usefulness or adaptability. Realizing the importance of the full control of the power transmitted as an indispensable factor in the economical operation of the plant, other methods were sought. All circumstances seemed particularly to invite the application of some system in which the speed of the motor could be controlled by an economical method of changing the voltage.

The Bullock Electric Manufacturing Company was the first to give this subject consideration, and was successful in devising a system in which all the objectionable features of the mechanical or rheostatic control were eliminated. The principal feature of its system is the means of varying the speed of the motor by generating currents of different voltage. This system of multiple voltage, because of its general adaptability to old installations as well as new, marks it as the coming method of controlling the speed of the motor connected to variable speed machines. While this is not new, there are, perhaps, some features connected with it that are not fully understood. It, therefore, seems proper to explain briefly its functions in order to compare the various systems.

This system of multiple voltage control is one which is adapted to varying the speeds of the motor by supplying the armature circuit with different voltages while the fields are constantly excited from any one specific voltage. The advantage

of this system over the two systems just described are, first, it gives the motor a constant torque, regardless of the speed; second, when the motor is set to run at any one speed, it will run at this speed, regardless of the load, and, third, the different speeds are obtained without passing the current through any resistance. Considering this system as applied to existing installations, one of the most important features is that any motor can be run on the multiple voltage system, as it requires no change whatever in the motor. To illustrate one method of supplying the different voltages which, in a measure, is the form of all others, your attention is called to the arrangement of the generators shown in Fig. 1. This consists of two generators, one with single and one with double commutators. Generator No. 1, having two




FIG. 1.

commutators, is wound for 44 volts and 66 volts, and generator No. 2, for 140 volts. It will be seen that if we connect the armature terminals of the motor across A and B the armature will receive 44 volts; if across B and C, 66 volts; if across A and C, 110 volts; if across C and D, 140 volts; if across B and D, 206 volts, and if across A and D, 250 volts. This gives the motor six different speeds. As the speed of the motor is almost exactly in proportion to the voltage, the motor will vary in speed from 44 revolutions to 250 revolutions, or in this ratio. Constant speed motors would be connected between A and D, giving 250 volts for these motors, and the variable speed motors would take any current desired to give the different speeds. The voltage is selected for the various speeds by means of a controller, and this may be so arranged that the motor can be reversed and be made to run at six speeds in either direction without any resistance whatever from the circuit.

By the use of this system, the motor would run at a fixed speed, regardless of the load, after the controller was once set for the voltage required to give the desired speed. The torque of the motor would remain constant, regardless of the speed, whereas the horse power would vary as the speed. The diagram shown represents what is termed a four-wire system. This will give six variations of speed. A five-wire system will give ten variations, and a three-wire system, three variations of speed, if the voltages are unequal. Fig. 2, which shows a double commutator machine giving 44 and 66 volts, would give three voltages for the motor, either 44, 66 or 110 volts. In the majority of cases the four-wire system will answer all requirements. In some cases the three-wire system will suit the conditions of service. The system we have just described covers a complete installation




FIG. 2.




FIG. 3.

and includes the generators. Where a plant is equipped with a permanent generating unit, it is a simple matter to arrange this system in connection with it. Fig. 3 illustrates how this may be accomplished. Assuming that the generator is delivering the current at 125 volts, we would then install a double commutator belt-driven generator and arrange the wiring as shown. Across the terminals B and C we secure 44 volts; across C and D, 66 volts; across B and D, 110 volts; across A and B, 125 volts; across A and C, 169 volts, and across A and D, 235 volts, and the speeds would be proportional. The same plan can be followed whenever the present source of supply is insufficient and some additional energy is required. If the mains are for 250 volts instead of 125, the transformer would be wound for double

the voltages, and if for 500 volts, for four times the voltages, giving the same proportional speeds as for 125 volts. The efficiency of this system, as compared with the rheostatic control, is best illustrated by giving the value of the curve taken from a 25-horse-power motor controlled first by ordinary rheostatic control, and then by the system just described. The efficiency of the motor under rheostatic control was only 12 per cent., whereas with the multiple voltage system of control the efficiency was 70 per cent. There were 19,000 watts lost in the rheostat at this point, whereas there were only 1150 watts lost with the multiple voltage control, the rheostatic loss being nearly seventeen times as great. The reduction of the speed of the motor in both instances was one-sixth of its normal speed.

The particular advantages of this system are that there is no loss whatever in the current supplied, and that the machine is under the absolute control of its operator, and the speeds may be changed as rapidly as required. By the use of this system every loss due to friction of countershaft and belting, resistance in rheostat and delays incident to change in the speed of the machine are eliminated. It would seem, therefore, that this system possesses *value* and *utility* in its application and control.

In conclusion, I would say that the methods of application and control described seem to suggest the use of the direct current rather than the alternating current for operating variable speed machinery. I would say, however, in deference to the prevailing idea of the relation of the direct current to the alternating current, that as neither is a power transmitter pure and simple, as a belt or cable may be said to be, and as both are capable of performing many other functions, the power-transmitting capabilities of each have special fields of usefulness.

DISCUSSION.

MR. C. H. BENJAMIN.—I am obliged to approach this subject from the side of the mechanical engineer, and to look for results rather than for methods. Although it is generally understood that mechanical transmission is wasteful, not half of the power developed at the engine usually reaching the machine, this fact does not constitute much of an argument for electric transmission.

In the first place, the cost of power in a machine shop is usually only two or three per cent. of the total expense account; in the second place, electric transmission, either direct current or alternating, either individual or group system, does not show

a marked gain in economy. The average loss, in individual motors belted to large machines, is about 25 per cent., while motors driving groups of machines through line shafts show a loss of from 40 to 50 per cent., if we include friction of shafting and line losses.

I am glad that the author has emphasized the application rather than the generation, and especially the speed control.

When a shop contains a large number of small machines of approximately the same character and of constant speed, it is cheaper to group them and drive them by short-line shafts, with one motor to each shaft, no motor being of less than five horse power. For this class of work the induction constant speed motor is much in favor. It is durable, needs little attention, is not injured by dust or oil and never sparks or burns out.

For larger machines, consuming five horse power and upward, it is more convenient and more economical to use individual, variable speed motors, either belted or direct connected. This means, of course, direct current. The great advantage of electric control over mechanical is in its greater promptness. It takes time to shift gears and belts, which frequently means that it is not done, and loss of efficiency results. The wastefulness of rheostat control is well understood. If the method described by the author will secure prompt control of speed and constant torque, without too much expense, it will be of great advantage in all classes of heavy machinery.

Everything that saves the time of man and machine is of importance.

I had understood that similar results had been attained by varying the strength of the field, *i.e.*, by what has been called commutating the field.

MR. JOHN W. LANGLEY.—The writer of this paper has done good service in directing attention to the importance of considering the economy of the application of electric power, as well as the economy of its transmission, a phase of the subject which, as he says, is very often overlooked.

It is doubtless true that an undue amount of attention has been given to the question of loss rather than to the more important subject of the availability and control of the power electrically delivered. Loss, however, is inherent and inevitable in any system of regulation. In the method of rheostatic control the feeding voltage at the brushes of the motor is reduced, for a diminished speed, by wasting the excess by a resistance, while in the method of variable voltage, recommended by the author, a cer-

tain loss of plant efficiency at the generating end is implied, for when the voltage is dropped the generators do less work and the full value of the plant installation is not being used.

Theoretically, the ability to feed the motor with just the voltage adapted to its speed for the time being is better than to obtain this same voltage by wasting a fraction of a supply taken from a source at a fixed potential; but, since the variable voltage plan requires specially wound generators having multiple windings, the practical economy of this plan takes the purely commercial aspect of balancing the saving in rheostatic losses against the expense of installing special dynamos, good only for this particular purpose, and running them on the average below their normal plant capacity, and, therefore, at less than their normal efficiency.

THE POSITION OF THE ENGINEER IN MUNICIPAL SERVICE.

ADDRESS BY ALEX. DOW, PRESIDENT DETROIT ENGINEERING SOCIETY.

[Delivered at the annual meeting, April 12, 1901.]

THE Detroit Engineering Society has always avoided any semblance of political action. We have at times discussed matters of engineering interest so closely akin to what we recognize as politics that our discussion took a distinctly political tinge, but the tendency of each discussion was toward the education of our members as individuals and away from any action or even expression of opinion by us as a Society. In choosing the subject of this presidential address I have not forgotten our laudable custom. The intent of this discourse is educational. It is based on personal experience and observation as an engineer, and is offered to you as engineers in the belief that it will be of interest and perhaps of service.

You will find my text in the *Detroit Evening News* of April 5, where one of the Public Lighting Commissioners is quoted as saying, "I used to think that municipal ownership was a good thing, but my experience has taught me that it is impossible to divorce public business from politics. It is all politics, and just now the Public Lighting Commission is composed of two Republicans and four Democrats."

It is quite true that the Public Lighting Commission is suffering from politics,—Democratic politics, labor politics, reform politics, and just enough Republican politics to season the mess. I suppose the labor men and the reformers object to being called politicians. Perhaps they are not such. Perhaps they are merely playing at being politicians,—you know the tale about the man who thought he played poker, but really didn't,—but they are partisans; and it is not the politician, in the honorable sense of the word, but the "offensive partisan," to use the expression invented by Grover Cleveland, who is a discredit to politics. The man who in public service endeavors to represent or to serve a faction instead of to represent or to serve the whole body politic is an offensive partisan. What his faction is or calls itself is a matter of no consequence. He may represent the Good Government League, or the Women's Christian Temperance Union, or the Associated Charities, but when he announces that his service as a commissioner or his employment as a subordinate of a commission is in the interest of, or as the

special representative of, any part of the people, and not all of the people, he is a partisan.

In my experience the most offensive partisans have been those who claimed to represent moral agencies. When they were honest, they were doctrinaires; when they were dishonest, their dishonesty overpassed exceedingly the dishonesty of the politician who admits that he is a politician. My experience is not peculiar. A friend of mine who has paid for his knowledge of city councilors in an Ohio city, where there is an organized reform party, tells me that the only difference between Democrats and reformers is that the reformers don't stay bought.

The common form of speech by which we express the offensive partisan is to call him a practical politician. This expression differentiates him from the man who takes an occasional whirl at politics because he has a momentary feeling that it is his public duty to do so. The practical politician calls that kind of a man a mugwump, and I think he deserves the name. I shall use the euphemistic expression in the remainder of this address, and you will understand that when I speak of the practical politician I am calling the person by the name which he has himself chosen.

The interest of the practical politician in any public department is primarily the money paid by that department as wages. The politician believes that the jobs belong entirely to him. He is even more interested in these than he is in the contracts which are given for supplies or for construction. On these contracts he and his friends can only expect a percentage of the profits, but he and his friends are ready to place their names on the payroll of the city for all the money in the treasury. Whether they can earn their stipends is immaterial. Of course, the work must be done by somebody, but the politician believes that if he and his friends are employed in sufficient numbers the work will be well enough done to keep the public quiet without any one wasting too much of his time and energy on the performance of the small part which becomes his share.

You must not suppose that the politician in office is an idle man. He is exceedingly busy,—as busy as the devil in a gale of wind. The trouble is that he is not doing the work he is paid to do. He spends his time in promoting the interests of his party. He attends conventions, sometimes forgetting to get leave of absence, and always forgetting to have his name removed from the time-book. He is active at caucuses, and is a worker before elections,—a very hard worker. And when, after election, his worn-out system requires repose he takes the same cheerfully; still

omitting to notify the timekeeper of his absence from duty. The interference with the work he is paid to do is just about the same as if he went on occasional drunks. The only real difference is that his irregularities are exceedingly regular, being predetermined by the laws fixing the dates on which elections shall be held.

Public opinion has long ago officially and practically condemned the man who allows his pleasures to interfere with his duties, but public opinion has not yet reached the stage of practical condemnation of the man who lets his politics interfere with his doing the work for which he is paid by the public. When it is effectively recognized that politics and dissipations are on the same footing if they prevent a man from doing the work which he is hired to do, public service can be performed as cheaply and as efficiently as is private service.

When a practical politician holds an office which gives him the power of appointing other public servants, he attains his maximum power for mischief. He not merely fails himself to earn his salary, but he employs others of his kind with a distinct understanding that they are to justify their employment by work done in the interest of him and his faction. That they are supposed to make some kind of a bluff at filling the nominal duties of their office is true, but the politician so appointed looks to his sponsor for protection in his idleness and does not in the least hold himself amenable to the taxpayers whose money he eats. He is not the servant of the city, but he is the "*man*" of such and such a boss. Sometimes the "boss" is a recognized party leader, and the appointment is made in the interest of the party. "The party owed me the job after all these years of work for it; I intend to take things easy and have a rest." That is how a man in this city, receiving such an appointment, stated the case, and he is even now resting at the public expense.

To return to my text. My experience is different from that of the commissioner quoted. It has taught me that it is entirely possible to keep public business separate from politics, even the public business of that very commission. My experience has led me to believe it possible to divorce public business from politics after the two have formed such an unholy alliance. To keep them separate in the beginning was the work of an engineer, and I now propose to tell how it was done. Hereafter I may justify my belief that the old condition can be restored.

The first Lighting Commission was absolutely non-partisan. In its constitution there was the usual recognition of each of the great parties, but each of those six men stood for the whole city and never for a moment for his own political friends. That was

as it should be. A bi-partisan board is not a non-partisan board. You cannot neutralize three aggressive Republicans by appointing three equally aggressive Democrats. Two blacks don't make one white, and the result in practice is at best a deadlock. If by any chance a Republican partisan votes with the Democrats, he is called a traitor, and there is a howl for his political scalp.

This non-partisan commission decided that its duties were essentially legislative. Its members were business men who certainly could not give attention to details of commission work. You remember that these commissioners are unpaid,—well, perhaps I should not put it so, but the payment they get is of the kind best described by a tale concerning our fellow-member, Mr. Frank E. Kirby, who served a term as a Water Commissioner of this city. The Water Board of a large Eastern city visited Detroit in the course of a tour in search of information. Mr. Kirby dropped his other duties to entertain the visitors, one of whom in conversation spoke as follows: "In our city there are three water commissioners; we each get \$3600 a year. How many are there of you in Detroit, and what do you get?" The answer was grim, but precise, "There are five of us, and we get hell." The first Lighting Commissioners were well paid in the coin named by Mr. Kirby. Some of them are, I think, still receiving small instalments of their salary. Be that as it may, they decided that their duties were legislative, and therein they made a wise decision. They sought as their executive an experienced electrical engineer of good administrative ability. They failed to be satisfied by any of the numerous applicants who asked for the position; they made guarded inquiries concerning a number of men who were engaged in such work as they had to do, and they ended by offering the appointment to a man who was about as thoroughly surprised as any one could be by such an offer. That was me.

From the beginning, the separation of legislative and executive functions was complete. The commission decided on a policy. I reported on and advised as to possible plans whereby that policy could be carried out. The commission authorized the execution of a general plan presented by me, and then it became my duty to carry out that plan, myself selecting the immediate agents and settling the details. On me lay the responsibility for results. Logically to me was given the choice of means.

Given full charge of the work and the force; given power to employ and discharge help; ordered positively to see that each employe earned his pay; to require no qualifications other than citizenship and competence; to disregard all indorsements which

were not supported by my own observation of the work actually done for the commission, it would appear that I should have been able to keep practical politicians out of the service of the Public Lighting Commission. Did I do so? Well, I think I did. I was convinced of it by the fact that the Republican politicians of the city condemned me for a Democrat, and the Democratic politicians cursed me for a Republican. That was at first; after a year or two they sized me up better. Toward the end of my service I had the expert opinion of a recognized authority on such subjects as to whether I had succeeded in organizing a non-partisan force. The authority was the Hon. Hazen S. Pingree. I think no one here will question his competence. The opinion was given to me personally, in explicit language, and at some length. I do not know that it is advisable to quote it in full or verbatim; indeed, my memory fails me. But the salient point thereof was, "You people down there at the lighting plant are political eunuchs." Now, really, I don't like being called a eunuch, and I think that the Hon. Hazen S. Pingree's metaphor is somewhat startling, but it is so thoroughly expressive that I venture to pass it on to posterity by embalming it in this presidential address.

How did I carry out my plan? Well, I began, so far as the laborers and mechanics were concerned, at the top of the long list, which was arranged according to priority of application. I called for these men in bunches, sized them up personally after the fashion of all engineers who have to hire men; you know how it goes; you don't have to be told that some men are not worth a continental; you can see that by looking at them. I questioned them as to their citizenship and previous experience, rated them according to their claims and set them to work. I personally hired each man, and the hiring was a big part of my work. In a short time I could tell whether or not a man was competent. If he showed himself such, he remained in the service. Some of the men employed in this way seven or eight years ago are still on the Public Lighting Commission's payroll. If a man showed himself incompetent, he was summarily discharged. The orders of the commission were that no man should have a time appointment; that each man should be hired from day to day or from month to month.

There was an application blank which had spaces for name and address, trade or profession, previous experience and references. The references were often autographic. The rule that a man should be a citizen and a *bona fide* resident of Detroit led to many of the applicants establishing their status by presenting the signature of one of the aldermen of their ward or some other well-known

Detroit man. Our foreign-born residents almost always secured the alderman's signature before presenting their application. The rule as to local residence was not absolute, but (after my own name) there never was but one selection made outside of the city; that selection was Mr. Walter D. Steele, a former member of this Society, and who became my chief assistant and afterward my successor. Mr. Steele brought to my aid a knowledge of high-tension electric constructions, and particularly of underground cables, such as was not possessed by any Detroit man, and which was essential to the performance of the duties which fell to him.

In the original selection of employes many presented the indorsement of local politicians. During the first three years, which were years of very hard times, there was an unusually large selection of employes available. Capable tradesmen were glad to get work as helpers or laborers, and for every position, excepting those requiring special technical training, there were from twenty to fifty applicants. It would have been possible to fill each such place after turning down every man indorsed by a politician. That would, however, have been a mistake. A selection from men indorsed only by the "goo-goo" element of our citizenship would, I think, have furnished about as large a proportion of utterly useless and worthless employes as could possibly have resulted had none but pernicious politicians been chosen. Some of the poorest specimens of mankind that were tried in the service brought the most magnificent indorsements from preachers and from pillars of churches. I honestly believe the average preacher does not know the making of a decent workman. I must expressly exempt the Catholic priesthood from this reproach. I noticed that a man who referred us to his parish priest was almost always a good find. On the other hand, some of the best men whom I found, including men who are still employed by the commission, carried the indorsements of politicians whose reputations are far from saintly. I don't say that a tough alderman invariably recommended a good man for a job; what I mean to say is that, especially in these years of business depression, the tough alderman could and did furnish from among their constituents enough mechanics and tradesmen, of a thoroughly reliable character, to fill any number of positions such as I had to offer. Of course the tough aldermen sometimes sent worthless men to me, but I had an effective method of dealing with such cases. If the man proved worthless, I summarily discharged him, and then I did not wait for his political sponsor to come to me complaining that his man had been "thrown down." I made the announcement myself to the sponsor, and followed it up by a few well-chosen

remarks in the vernacular which let him understand that it was his business to know that a man was a good, capable worker before he sent him down to the Public Lighting Commission, and that if the said sponsor did not know any better than to send such a damnable specimen as the one just discharged I would decline hereafter to consider any of his recommendations.

I commend this prescription to any of you who may find yourselves in such a position as I then was in. The first dose, if liberal, effects a complete cure.

The places which required technical training were more difficult to fill. I have already mentioned that one place had to be filled by employment of a man from outside the city. The first draftsmen and inspectors were found by inquiry among the manufacturing and technical concerns in town. They were college men, and their coming to the service was followed by a succession of applications for employment from other college graduates, largely University of Michigan men. The names of most of those men have been on the roll of our Society.

The engineering staff of the construction period was formed of these young men, and when the operating force was organized a number of positions were filled from the construction staff. The pay of these places was not high,—\$75 per month being the standard. I could not expect to retain such men permanently at the salaries which were possible, but I could and did arrange for a continuous succession in office. There was no place which was not well filled, and behind each occupant of a place there was a possible successor; the final vacancy of the series being a draftsman's position, which could naturally be filled by any graduate of the engineering department of the University of Michigan. The plan worked during my term; the men have assured me that they found their Public Lighting experience of value, and I am proud to say that they are all to-day filling positions of responsibility with credit to themselves and to their earliest employment.

I see in the press that one of these positions, formerly filled by a graduate engineer, is vacant, and that a competent man cannot be had for the pay. Well, I think the trouble is that a competent man will not take the place under the present limitations. The pay is plenty, and if the place at the salary named were vacant in one of my plants instead of in the city plant it would be filled mightily promptly by an Ann Arbor man.

The steam engineers and similar expert mechanics were selected from the list of applicants. In these classes the plan of putting a man to work and seeing what would happen could not be

tried with the same freedom as was permissible with laborers. An incompetent engineer might wreck an engine in demonstrating his incompetence; or an unskillful electrician send himself to paradise by the electric route, and thereby cost the city \$5000 or so. It is really remarkable how valuable such a man becomes after he is dead. But the method was modified only in degree, not in kind. A man was first questioned and then tried. His indorsements counted for nothing, his politics for less than nothing.

The relations of the plant to what is called "union labor" were very early defined. The first commission announced that it recognized citizenship and competence as being the only essentials for employment. It classed union labor affiliations together with politics and religion, as being immaterial so long as they did not interfere with the performance of a man's duties. It resulted that we made no inquiry as to a man's being union or non-union, and that naturally a large proportion of the men employed were union men. I think the ground taken in the matter was solid, and that it is the only ground which promises permanent freedom from trouble.

It was not sufficient to obtain employes who were free from political obligations. It was necessary that they should remain clear of such entanglements. Our rule in the beginning was clearly stated, and it was reiterated from time to time as occasion required. It was that every employe should have opportunity to vote at primary and regular elections; that there should be no inquiry as to how or for whom he voted, but that no employe should on any pretense engage in what is called party work. A report that an employe was making himself notable in politics caused him at once to be called on the carpet and notified that a persistence in such activity would surely lead to his dismissal. In the early days of the commission it was necessary, in more than one case, to warn men individually of the consequence which would follow their persistence in political activity. These warnings took the form of a statement that the Public Lighting Commission was non-partisan; that the retention on the roll of an active partisan of either party would lead to demands from the other party that some equally active partisan of that stripe should be employed; that the commission did not propose to engage in any such balancing of evils, and that therefore the employe must limit his activities or quit the service. No man was ever discharged for political activity. One man resigned with the friendly statement to me that he thought he could better himself otherwise by his political work, and that he therefore preferred to sacrifice his present job. Anonymous charges were occasionally made that men were discharged because

of their politics, but the record was easily cleared. These charges were all made in the early days, when each party said I was a vile tool of the other party.

For five years—three years of my service and two years of my successor's term—the relations of the commission to its electrical engineer were unchanged. You will recognize that these relations were essentially those of a board of directors of a corporation to their general manager. In my own case they were exactly the relations which I now hold to the directors of the corporations whose property I manage. They were the relations which exist in every such department in every city whose work is well done and free from political taint. Instances can be multiplied not only of the successful operation of this distribution of duties, but also of the evil results following when any other distribution is essayed. The Chicago newspapers have just furnished an excellent illustration of success and of failure. The success is in the management of the South Parks. In the past and in the present the South Park Commissioners have performed precisely the duties of a directorate of an incorporated company. The name and title on their letter heads, "J. Frank Foster, general superintendent and engineer," means just what it says. Mr. Foster is general superintendent in fact as well as in name. The West Parks have been managed on the other plan. The commissioners have been partisans, and have appointed partisan employes. The general superintendent has too often been chosen for his efficiency as a party worker. The engineer has always been a subordinate, and too often a negligible quantity in the equation. I speak from knowledge, because I have done engineering work on behalf of each of these municipal bodies. The results of the two systems are summed up by the published cost of maintenance per acre of each system. The average cost of maintaining the West Side Parks is \$498 per acre per annum. The average cost of the Washington Park is \$220 per acre per annum. And those who know their Chicago and can mentally compare the two park systems will promptly agree with the newspapers that the conditions of the two systems are in the inverse ratio of the moneys spent upon them.

In Canadian cities the man in charge of public works is usually a civil engineer, and he is actually in charge. The Public Works Committee has legislative functions only, and a law duly enacted, not merely a ruling of a commission, prohibits the activity of any city employe in politics.

I have spoken of the successful operation of the public lighting plant while the functions of the commission and the engineer

remained clearly defined. It is now in order to tell what happened when this definition became hazy. After five years' operation of the plant, ill-advised economies, insisted upon by the board in direct opposition to the advice of the engineer, caused a strike of the arc lamp trimmers. The question of detail was whether the trimmers did or did not do enough work for their pay; whether, in fact, their duties were proportionate to their wages; whether they had what in the newspaper discussion at the time was called a "snap." I think the trimmers' duties were no snap, and I know whereof I speak. A man who trims sixty open lamps on a circuit of average length daily, Sundays included, summer and winter, in fair weather and in foul, in the early hours of the summer morning and in the bitter sleet storms of our winter and early spring, has no snap if he does his work properly. Electrical Engineer Steele told the commissioners this. They overruled him. Be this minor fact as it may, the major fact was that the commission, to secure a small economy of operation, overruled its executive officer and ruined the discipline of the plant. The damage to the commission, directly and indirectly, by loss of discipline from that day to this, by the loss of capable employes and the expense of educating others, has offset many times the saving which was expected to be made. The trimmers struck, as I have said, and thereby put themselves in the wrong. They had no right to conspire to put the metropolitan city of Michigan in darkness. They forgot they were public servants when they planned such a stroke. That also is a minor detail. The major fact was that the commission assumed control of details which, even had it been competent to judge, it could not personally oversee, and deliberately permitted employes to feel that they had a grievance.

The engineer did his best. He won the strike for the commission, feeling that his duty to the city overrode his sympathy for the men; but thereafter he avoided responsibility, knowing that he could not depend on the support of his directors, and the clamor raised by the aggrieved employes had its unavoidable result. The appointing power, the mayor of the city, tried to remedy the harm done by nominating a commissioner who undertook to specially represent these employes, and who entered on his duties with a prejudice against his associates. This appointment was followed by another; this second nominee frankly declaring himself the special representative of organized labor. Partisans both of them, these commissioners; well meaning, no doubt, but limited in their action by the circumstances of their appointment, carrying to their duties not a receptive mind, but a preconceived hostility to the past

management. At meetings of the board charges and counter-charges, criticisms and squabbles took the place of frank discussion and of willing submission to the decision of the majority. Tale-bearing by employes was encouraged, different members assuming the protection of different employes or cliques of employes. Matters of detail took up the time of the board, and business was impossible. The plant kept on going from sheer inertia, but the engineer very early concluded that he should end his connection with the institution. He had been wiser for himself, I think, had he come to this conclusion a year sooner than he did; but he, like almost all engineers, was faithful to his salt and tried to do the best for his masters, the public, under adverse circumstances. He economized to a fault; he left his machinery in perfect condition and a surplus of over \$50,000 in the treasury. The older commissioners finally gave an opportunity for the restoration of harmony by resigning almost in a body, and new nominees of the mayor, on whom, by these resignations, has devolved the appointment of every present member of the commission, accepted appointment to the vacancies.

Had the commission then reverted to the original system of operation, all might have gone well. Seeing that all personal difficulties had been eliminated, they could have resumed their proper legislative duties, placing the executive responsibility in the hands of one competent engineer. If a local man were not available, they could have sought for such an engineer beyond the city, as did the first commission. Unfortunately, the factional spirit still survived. Employes and ex-employes who had given aid and comfort to the commissioners now dominating during the time when they were a minority apparently had to be taken care of, and these commissioners found themselves the representatives of a faction of the most impracticable kind. A general superintendent was chosen, but he is superintendent in name only. When appointed he did not know the elementary principles of electrical generation and distribution, and he thereby became dependent on one of the re-appointed ex-employes, who was nominated as his assistant. In the public reports and specifications of the commission there is nothing to indicate that during the past year the general superintendent has learned any more about the electrical business than he knew when he started. I regret to say also that these reports and specifications indicate that not merely the general superintendent lacks essential knowledge, but that the assistant is far from having sufficient engineering ability to make good the deficiencies of his chief. It seems ridiculous that a plant which has sent a dozen smart electrical engineers to profitable employment elsewhere should

not be able to find one able man to take intelligent charge of its own affairs. A private plant, offering the same salary, would have found such a man very promptly.

Of course (as shown by my text) the belief has gone abroad that partisan politics have dominated the selection of employes by the new commission. There is too much evidence in favor of this belief to allow one to contradict it lightly. There is a good working majority vote in the commission, and under those conditions it behooves the majority to be careful of its appointments if it desires that its motives shall not be impugned. To appoint as a general superintendent a person who has been a practical politician since the memory of man runneth not to the contrary is a proceeding subject to criticism under the best of circumstances. When the person so appointed knows absolutely nothing about the business he is running, when he and his assistant jointly send around to their subordinates a subscription paper inviting the donation of campaign funds for the party having the majority vote on the Public Lighting Commission; when other appointees to office are also notably party workers, and either without electrical experience or with an experience which is a record of failures, it seems to be a prejudged case that politics control the department.

The financial results do not clear the record. The past president started in with a remarkable program of proposed economies. He announced that expenses could be reduced \$20,000 per annum. During the year of his control the expenses apparently have been increased to the tune of \$10,000 per annum, and for the first time in its history the commission comes before the Board of Estimators reporting that it will apparently have a deficit at the end of the current fiscal year. That result indicates that there was something wrong with the program, and increases rather than decreases the evidence against the present system.

My conclusion is that a public works department can be operated efficiently and economically on the same lines as is the service of a private corporation; the commissioners assuming the duties of the directorate of such a corporation and the general superintendent, who must be a thoroughly competent engineer, performing all the executive duties. I can admit no exception to this rule. I am aware that in some organizations the peculiar knowledge of individual directors makes their advice exceedingly valuable in the executive department. This was the case in the first Public Lighting Commission of the city of Detroit. Of that commission, there was not one man who had not a general knowledge of the apparatus and methods involved in the electric lighting business;

three of these had served as directors of electric lighting enterprises. The factory of one was a pioneer in the use of electric power distribution, and the commissioner who knew the least of electrical affairs was surprisingly familiar with the routine and costs of a model street railway plant in which he had an interest. Two of the members had technical knowledge and ability which brought them, in the course of their business, a large recompense, and which they gave freely to the service of the city of Detroit. One of these men had been a pioneer in telephone, electric light and electric railway developments, and he is now an officer and director of one of the largest telephone companies in the Middle West. The other, whom I may name, seeing that he is dead, Mr. George Howard Lothrop, was reputed the best authority on electrical patents west of the city of New York. The advice of these men was constantly sought by me as the executive officer of the Public Lighting Commission, and it was always freely given and always valuable. I have indicated sufficiently the peculiar fitness of the first Lighting Commissioners of this city to take charge of detail and to perform the executive duties of their department, and yet it was these commissioners, who knew exactly what they were doing and who were, without exception, better fitted for their public work than any of their successors have ever been, who positively declined to depart from their legislative functions and who insisted upon the assumption by their general superintendent and engineer of the full responsibility and the full authority which his executive duties required. It has remained to men of less knowledge to initiate the contrary policy and to fail in it.

What has been done can be done. Let the Public Lighting Commission of the city of Detroit re-enact the rules of the first commission. Let it place the execution of these rules in the hands of a general superintendent who shall be—who must be—a thoroughly competent electrical and mechanical engineer. Let the commission confine its members to their legislative functions, and loyally support its superintendent in his executive duties. Then there will be again a Public Lighting Department free from politics, free from partisans, economical in operation and a model to be followed not only by other municipalities, but by private corporations. Go outside of Detroit if necessary to find the right superintendent. If he is an honest, capable engineer,—and an engineer, to remain in his profession, must be honest and capable,—his freedom from local acquaintance and entanglements will tend to his success.



Editors reprinting articles from this journal are requested to credit not only the JOURNAL, but also the Society before which such articles were read.

ASSOCIATION OF ENGINEERING SOCIETIES.

Organized 1881.

VOL. XXVII.

OCTOBER, 1901.

No. 4.

This Association is not responsible for the subject-matter contributed by any Society or for the statements or opinions of members of the Societies.

THE ORE-HANDLING PLANT AT THE CARRIE FURNACES, NOS. 3 AND 4, OF THE HOMESTEAD STEEL WORKS OF THE CARNEGIE STEEL COMPANY.

BY W. L. COWLES, MEMBER, CIVIL ENGINEERS' CLUB OF CLEVELAND.

[Read before the Club, September 24, 1901.*]

THE reduction, in recent years, in the cost of producing steel has come about very largely through the elimination of manual labor and the substitution therefor of mechanical appliances. This substitution of machinery for men has taken place all along the line, from the first removal of the ore from its bed by steam shovels to the automatic loading of the finished rails on cars ready for shipment, and at every stage in the transformation of the ore into the rail, when a machine has replaced a man, if the machine has been wisely designed, properly installed, and efficiently operated, cost has been reduced and a cheaper final product made possible.

It is the intention of the author in this paper to describe briefly the method of accomplishing one stage in this transformation, as seen in the handling of ore and limestone from the incoming car to the furnace top at the Carrie Furnaces, Nos. 3 and 4, of the Homestead Plant of the Carnegie Steel Company at Rankin, Pa., through appliances largely designed and installed by the Brown Hoisting Machinery Company.

These furnaces are situated on the north bank of the Monongahela River, and extend from the river to the Pittsburgh and Lake Erie and Baltimore and Ohio Railroads, the general arrangement

*Manuscript received September 26, 1901.—Secretary, Ass'n of Eng. Soes.

of the plant being shown on general plan No. 1, only those tracks, however, having been included which constitute a portion of the ore-handling system.

By referring to the profile on this plan, it will be seen that the tracks used for handling the cars of ore and limestone to and from the car dumper, or tipple, are laid on grades especially designed to suit the plan of operations as described below.

The cars of ore and of limestone, upon being brought into the yard, are first made up into trains, having regard to the relative quantities and kinds of ore and limestone with which it is desired




FIG. 1. GROUNDHOG.

to fill the bins, and these trains are then switched onto the tracks marked "Inbound to Dumper," the locomotive pushing the train on one track in toward the dumper until all the cars are beyond the apex of the first grade, when all brakes are set and the locomotive runs back to push up the train on the other track. The brakes on the first car of train No. 1 are now released, and the car starts down the grade by gravity and its momentum carries it beyond the pit wherein is placed the disappearing car, or "Groundhog," as it is sometimes termed and its motion is checked by the ascending grade between this point and the dumper. The groundhog, shown in Fig. 1, consists of a small but strongly built car, of such a width that it can descend into the pit.

which is placed in the center of the track and upon the walls of which are laid the rails of the standard gage track. The groundhog travels on a narrow track laid between the rails of the standard gage track, and is operated by means of a wire rope




FIG. 2. Tipples.

leading to a drum in the engine house of the dumper, where it is controlled by the one operator who has charge of the entire mechanism of this portion of the plant.

When the loaded car has reached the point at which we left it, the groundhog is made by the operator to rise from the pit,

and, coming up behind the car, it pushes it up the grade and onto the section of level detached track which forms the floor of the dumper. The car dumper, or tippie, shown in Fig. 2, consists essentially of a massive frame, in the shape of an irregular U, hinged at one side, and having attached to the other side wire cables leading to drums in the engine house above, by means of which the frame, or cradle, may be made to revolve about the 10-inch shaft which forms part of the hinge. The engine house is supported by columns, with heavy bracing, designed to carry the constantly changing loads which come upon them during the revolution of the cradle. A counterweight is attached to the cradle by means of wire cables passing over sheaves in the upper part of the fixed framework, and is so adjusted that its weight assists the engine in lifting the cradle at the beginning of its revolution, and, again, in retarding its motion after the center of gravity of itself and loaded car has passed over and beyond the hinge. When the car has been properly located in the cradle, the groundhog runs back by gravity to its pit, ready to repeat the operation with the next car.

It may be stated here that, while this method of placing the cars in the dumper was the one designed for and at first used at this plant, and is the same as is successfully used at other points, it appeared, after it had been in operation for some time, that the groundhog could profitably be dispensed with, for the reason that in this case the yard room was limited, the extent of track which could be devoted to the incoming cars was insufficient and the permissible grade was not great enough to insure rapid handling. The number of cars which could be accommodated on the down grade was not great enough to permit any other use of the locomotive while these cars were being dumped, and it therefore stood idle during this time. It was therefore determined to remove the groundhog and use the locomotive continuously in pushing the string of cars one by one onto the dumper, and this method is in operation at the present time.

Meanwhile the car in the dumper has been secured to the cradle by means of horizontal and vertical clamps operated by hydraulic power, and is being lifted and overturned, as shown in Fig. 3, until the contents, guided by a steel apron extending the entire length of the car, are emptied into a bin having a capacity of about two large carloads. The cradle and empty cars are then returned to their normal position, when, after the clamps are released, the following car, coming onto the dumper, pushes off the empty car. By referring again to the profile on

general plan No. 1, it will be seen that beyond the dumper is a steep descending grade (9.8 per cent.), followed by a level portion, which is occupied by a spring switch set for the return track and beyond this again is a still steeper ascending grade (20 per cent.). These grades are so related that the energy acquired by the car




FIG. 3. TITILE.

in descending the first grade, making allowance for the loss by friction, carries the car across the level portion, through the spring switch and up the last grade just far enough to fairly pass the point of the switch. When returning, the energy again acquired will carry the car around the curve, by the dumper and down the track to the storage for empties.

A buffer is placed at the end of the track, but is rarely touched by the car, which usually comes within a foot or two of it, when its energy is entirely absorbed and it starts on its return trip. The car dumper is capable of handling thirty 60-ton cars per hour, or 18,000 tons per day of 10 hours. This capacity cannot at present be continuously realized, as the appliances for taking away the ore are not of equal capacity. They are sufficient, however, for the needs of the plant as it now exists, and the excessive capacity of the dumper will provide for a large extension of the plant in the future, if desired. The capacity mentioned has been reached in practice,




FIG. 4. GATE MECHANISM.

sixteen cars having been dumped in thirty-two minutes, when it became necessary to cease operations on account of the bins being full. The largest number of cars dumped in one day is 171.

The dumper bin, as seen in Fig. 3, is divided into eight compartments, each compartment being provided with a chute and gate. These are so spaced that when the car with buckets is properly placed on the track below the bin, each alternate chute will deliver into one of the buckets, which thus are quickly filled without further shifting of the car. The gates are operated by means of a special motor attached to a shaft which extends the full length of the bin, and which has a clutch opposite each gate, enabling the operator, by throwing in any clutch, to open or

shut the corresponding gate. This mechanism may be seen in Fig. 4, which also shows clearly the conduit which carries the wires for supplying current to the cars. These cars, shown in Fig. 5, and with loaded 10-ton buckets in Fig. 6, are made in pairs, coupled, for ease in passing around curves, each car having its own motor, but both controlled from the end of one car, which is fitted with a cab. The track upon which these cars operate, called the transfer track, consists of a straight track extending the whole length of the ore-storage yard, with a connection to the system of yard tracks, and a curved side track passing under the




FIG. 5. BUCKET CAR.

damper bin, the spring switches connecting the two being so placed that the cars will first run through, and then, returning, follow their proper track, thus making the circuit continually without the necessity of any hand switching. Space is provided on these cars for four buckets, but only three places are occupied when the car leaves the bin, one place being left for the last bucket taken full from the preceding car, which, having been carried away and dumped while the car of empty buckets moves away, is returned to the new car of loaded buckets which has taken its place. This car is stopped opposite the point where it is desired to deposit the contents of the buckets, and under one of the bridge tramways which has been placed at that point.

There are two of these bridge tramways, shown in Fig. 7 and in plan No. 2. Each bridge tramway consists of a central span of 250 feet 3 inches, with a cantilever 160 feet $\frac{3}{4}$ inch long extending over the transfer track, and another cantilever 147 feet $9\frac{1}{4}$ inches long extending to the other end of the stockyard, making a total length of 558 feet $\frac{1}{2}$ inch, end to end of stringers, or a total trolley travel of 540 feet 1 inch. At one end of the central span this superstructure is supported by a steel pier 62 feet high above the yard level, having a base 19 feet 6 inches x 15 feet, and at the other end by a shear leg of the same height, having a spread at the bottom of 20 feet. The general construction



FIG. 6. BUCKET CAR.

is shown on general plan No. 2, from which it will be seen that the pier rests upon a platform of girders, which in turn is carried by double trucks, while the shear leg is carried directly by two sets of equalized double trucks. The whole construction runs upon tracks laid on top of the parabolic ore and limestone bins which will be referred to later. The motive power is supplied by an electric engine consisting of two 135-horse-power Elwell-Parker motors in an engine house located on an extension of the platform which carries the pier, and supported by another set of double trucks. Power is transmitted to the four sets of trucks under the engine house by a system of shafts and gears, so proportioned as to develop a speed of 75 to 100 feet per minute. By means of similar

shafts and gearing, rising to the top of the pier, passing across the bridge and thence down to the trucks supporting the shear leg, corresponding motion is imparted to the latter. The bridge is not rigidly attached to its supporting pier and shear leg, but at the pier end it is free to revolve, within limits, about a pin passing through the center of the pier cap, the bearing plates of the bottom chord resting on nests of conical steel rollers at the pier top, while at the shear leg end the bridge is carried by a yoke which is suspended, by means of a 4 $\frac{3}{4}$ -inch steel saddle rod, from a socket casting, which in turn rests upon a ball casting on top of the shear leg. This construction permits of a skewing of the bridge to the extent of 1 foot in 9 of length. The tilting of the shear leg, due to this motion, is taken care of by providing ball-and-socket bearings between the feet of the shear legs and the trucks.

The compression chords of the bridge and cantilever are constructed of channels and plates. The tension chords of the cantilevers and their back stays consist of eye bars, while those of the bridge are of wide flat plates. The main posts over the pier and shear leg are of channels laced, but all other posts are of extra strong gas pipe of varying sizes. All tension diagonals are made of round rods of B B iron, and braces of gas pipe.

Between the trusses of the bridge are transverse floor beams supporting two lines of stringers, suspended below them, and upon these stringers runs a trolley from end to end of the bridge, the pier and shear leg being so designed that there is free room for the passage through them of trolley and bucket, all bracing being omitted at those points and the effect of wind pressure and other horizontal forces being taken up by bending stresses. This trolley is quite different from the ordinary type used in these machines, in which the hoisting rope leaves the main sheaves centrally and runs free to the ends of the structure. In this case the length from end to end is so great that the sag in the rope, when the trolley is at one end, would cause it to drag on the ore pile, and it became necessary to devise some means of preventing this condition. To this end, the rope, which, on account of the high stress, is made double, after leading off from the main sheaves, is carried by tilted deflecting sheaves to the sides of the trolley, one part to each side, whence it leads out in each direction over a series of sag carriers suspended from the trusses, and thus placed far enough apart to permit of the free passage between them of the block and suspended load. The trolley will pick up the rope as it passes over a sag carrier, and, as it proceeds, the rope settles again into its place. These sag carriers, consisting of small sheaves supported by the

depending frames, may be seen in Fig. 2, while the trolley is half hidden behind the counterweight framework shown in Fig. 3. Despite the precaution taken to guide the rope into the sag carrier, as it settled down from the trolley, it was found that it




FIG. 7. BRIDGE TRAMWAYS.

would occasionally flop over the side. To prevent this, the inner guard of the sag carrier was increased somewhat in length, and a steel wire rope was stretched from tip to tip throughout the entire length, with the result that, if the rope should so flop out of its guide, its own tension caused it to follow the guard rope back over the tip and into its carrier sheaves.

From the trolley is suspended, by means of a block and clevis, a detachable bail which may be attached quickly to any bucket or detached from the same at will.

The hoisting rope, from which hangs the block, and which in this case is double, of $\frac{3}{4}$ -inch plow steel, leads from a drum in the engine house, forming part of the engine already referred to, through a system of deflecting sheaves, to the top of the pier, thence along the bridge, supported at intervals by the sag carriers already described, to one end of the same and back to the trolley; thence, after passing down to the block and up again, to the other end of the bridge, to which it is fastened by a spring buffer. Winding upon two other drums in the engine house are the so-called





FIG. 8. SHOVEL BUCKET.

"racking ropes," of which, after also passing through the system of deflecting sheaves, one leads to one end of the bridge, around a sheave and back to the trolley, and the other to the other end of the bridge and back to the trolley. These ropes are also double. By this means the trolley, with its suspended load, may be rapidly moved to any point between the ends of the bridge. The speed of hoisting a 10-ton bucket of ore, or a total weight of about 13 tons, is from 250 to 300 feet per minute, and the speed of racking is from 800 to 900 feet per minute.

The bucket can be dumped either in one of the bins which support the bridge or on the stock piles on either side of and between the bins, by means of a simple dumping device, consisting of a piece of heavy gas pipe suspended from the truss by wire ropes.



PLAN No. 3. DUMPING DEVICE. FURNACES 1 AND 2.

like a trapeze. This gas pipe can be placed at any point and at such a height that, as the bucket reaches it, it trips a latch and the bucket dumps by gravity. To dump into a bin, the trolley is stopped directly over the desired point, and the bucket is lowered until a similar trapeze, properly placed, trips the latch. The construction of the bucket is such that, upon dumping, the entire contents fall vertically, without any side scattering whatever.

Another dumping device, applied to the bridge tramway at Furnaces Nos. 1 and 2, of the same plant, is shown in plan No. 3, and consists of a light framework between each truss and the adjacent stringer, extending along the central portion of the bridge. In this case the bucket is lifted at one end and brought to the




FIG. 9. SHOVEL BUCKET.

desired position under the framework. A slight raising of the bucket then brings a pair of spring latches in contact with the bottom of the framework, which thus releases them and the bucket dumps.

During the summer season the bins are ordinarily filled by buckets direct from the dumper, the excess of ore received over current requirements being deposited in the storage yard. When navigation is closed in the winter, ore still comes in from the lake docks, where great quantities are stored, but in the worst weather it becomes impracticable to draw from this source, and, no ore being received from outside, the bins are filled from the storage yard. This is accomplished by the use of a shovel bucket, shown in Figs. 8 and 9, which is attached to the block in place

of the detachable bail. This shovel bucket is lowered to the base of the pile of ore, and the trolley is moved forward until the hoisting rope leads back at an angle of about 45 degrees, when the trolley is held in position by a brake while the hoisting drum is started, with the result that the bucket fills with the ore as it drags up the pile, and is then carried to the bin and dumped.

The engine runs continuously and is not reversing, the several operations of digging, hoisting and racking, and the traveling of the structure, being accomplished by suitable clutches and brakes, manipulated by one operator, who is located in a small house above the engine house, whence he commands a view of all portions of the plant. The brake used for holding the trolley while digging is a powerful one, operated by hydraulic pressure, but it is not sensitive enough for the ordinary use of controlling the motion of the trolley while carrying a load. An auxiliary mechanism is therefore provided, whereby the same brake is operated by the foot, and the motion is easily controlled. An indicator in the operator's house, showing the position of the bucket at any moment, enables the operator to dump it at any desired point with accuracy.

The trolley, with its bucket, is capable of making twenty-five to thirty-five trips per hour, according to the distance which it has to travel, or an average of thirty trips per hour, giving a capacity of 3000 tons per day of 10 hours for each bridge tramway. Up to the present time, the highest record of buckets handled by one machine is 62 buckets in 105 minutes, equal to a rate of 254 buckets in 10 hours; but the greatest number handled in a full day of 10½ hours is 303, some time being lost in oiling, adjusting the dumping trapezes and changing the position of the bridge tramway for dumping in different parts of the yard.

Returning now to the car with loaded buckets, we have seen that it is stopped under the bridge tramway, which has already been placed over that portion of the bin or storage yard where it is desired to deposit the ore or limestone. The last bucket from the preceding car having been emptied while the car is moving away, it is returned and lowered to the vacant place in this car, and the detachable bail is transferred to the next full bucket, which is hoisted, racked, dumped and returned, and the process is repeated until the last bucket is taken, when the car moves away with three empty buckets, while another car with three full buckets takes its place.

One of the bins, upon which are laid the tracks which carry the bridge tramways, is seen in Fig. 10. These bins are parabolic in form, and are suspended from longitudinal plate girders,

which, in turn, are supported at frequent intervals by rigid frames consisting of heavy columns and transverse girders, the latter taking up the horizontal component of the pull from the suspension plates. The longitudinal girders which carry tracks are triangular in cross-section, having two webs meeting at the bottom, with a common bottom flange, and separated at the top by a distance equal to the gage of the track, but connected by a wide plate, which, with the connecting angles, constitutes the top flange. The outside web is so inclined as to make it tangent to the parabola, and extends below the bottom flange to provide a connection for the suspension plates. The inclination of the inside web from the




FIG. 10. BIN.

vertical is the same as that of the outside web. This construction forming a closed section, holes are provided in one web to permit of painting the interior. Vertical partitions are added at intervals, dividing the bins into a series of pockets, in order that the limestone and different kinds of ore may be kept separate. In each section, between any two columns, two chutes are provided at the bottom, one to deliver to the right and one to the left. These are closed by gates revolving about a horizontal axis, whose center is a short distance below the bottom of the bin. These gates are operated by steam power.

Below each bin, and at every pair of posts, is a cross-beam

supporting a suspended double track, on which travel electric locomotives, each with two larries. The tracks are so located that the chutes will deliver directly into the larries, and the latter are provided with scales, so that, by drawing successively from different pockets, mixtures of ore in exact proportions can be easily secured. An electric locomotive, with one larry, is shown in Fig. 11. At the furnace end of each bin the suspended track stringers are extended over the pit into which the skips are lowered, and the larries, having been properly filled, are pushed by the locomotive to a position over a chute guiding to the skip, and are there emptied. Between the end of the bin and the skip is a transfer table, operated by a special electric motor, by means of which, if any accident should happen to a locomotive or larry on one side, or if it should become necessary to repair a gate or its operating mechanism, the supplies could all be drawn from one side of the bin and transferred from one track to the other, so as to serve both skips. These bins are used only for the supplying of the various kinds of ore and limestone. The coke, which must be carried by the same skips, is brought in in cars on an elevated track, from which it is dumped into the coke bins, situated on each side of the skip pit, as shown on general plan No. 1. From these bins the coke is drawn off through gates into the side chutes leading to the skips. Two skips are used, running on an inclined double track, as shown in Fig. 2, from the bottom of the pit, in which they receive their loads, to the top of the furnace, where they are automatically dumped by means of a peculiar arrangement of tracks and wheels. The front wheels are of ordinary width, and follow the main track. The rear wheels are much wider, extending beyond the main track to such an extent that, at a point near the top of the furnace, where a second track is added outside the main track, these wheels will run on and follow the second track. This track continues in the same inclined plane in which lies that portion of the main track below the point referred to, insuring the continued upward motion of the rear end of the skip, while at that point the main track leaves this plane and follows a vertical curve, whose center is below the track, thereby leading the front wheels in toward the center of the furnace. The rear wheels having continued to rise, the skip is tipped toward the furnace and the contents are dumped into a large hopper. The hoisting mechanism being reversed, the skip descends while its mate rises, the weights of the skips counterbalancing each other, so that the power required is only that necessary to lift the load and overcome the friction.

At the bottom of the hopper is a cone, which distributes its contents with approximate equality, as the ore, limestone and coke pass through onto a small bell. When two skiploads have thus been deposited on the small bell, it is lowered and the distributed mass falls upon the large bell. Again two skiploads are deposited upon the small bell, and it is once more lowered. After the small bell has been raised again to its upper position, so as to form a seal for the gas, the large bell is lowered and the entire mass falls into the furnace, adding a well-distributed layer to those which have preceded it.





FIG. 11. ELECTRIC LOCOMOTIVE AND LARRY.

This presents in outline the course of the raw materials as they pass from the cars, in which they reach the yard, to the interior of the furnace, all operations, after the cars are left by the locomotive on the dumper floor, being performed by electricity and controlled by the minimum number of human hands, only eighteen men being required to perform all the operations described for the two furnaces. As suggested at the beginning, it is in the great reduction of manual labor, effected by these appliances, that the economy of installing them at considerable cost is found, but it is an easy matter to show that, with this plant efficiently operated to its maximum capacity, a saving in the cost of production can be secured equal to from 40 to 50 cents per ton of pig iron, which, at the

rated capacity of the two furnaces of 1400 tons per day, amounts to an annual saving of from \$200,000 to \$250,000.

It is not strictly within the scope of this paper, but it may be of interest to note that the elevated structure at the left of Figs. 2 and 3 is the approach to the Union Railroad Company's bridge across the Monongahela River, built and used solely for transporting the molten metal in large ladles from these furnaces to the steel furnaces of the Homestead Works, on the other side of the river.




PLAN NO. 1
SHOWING
STOCKYARD, BINS AND ORE HANDLING TRACKS
AT
CARRIE FURNACES, HOMESTEAD STEEL WORKS,
CARNEGIE STEEL CO.

ELEVATION OF TIPPLE

SCALE 1" = 8' FT.

= 1:96.




563'-1 1/2" OVERALL OF SHEAVES.

558'-0 1/2" OVERALL OF TRACK STRINGERS.

540'-1" TOTAL TROLLEY TRAVEL

250'-3" SPAN




10' 7 1/4" x 10' 7 1/4" 5' 4"

15' 0" x 15' 0" 4' 0"

40'-9"

MAXIMUM LOAD ON EACH WHEEL
INCLUDING WIND 45,000 LBS

MAXIMUM LOAD ON EACH WHEEL
INCLUDING WIND 35,000 LBS



CAPACITY OF
BUCKET
22,400 LBS.

CLEARANCE LINE OF DUMPED BUCKET

AREA OF CROSS SECTION
OF PILE 4000 SQ. FT.

CAPACITY
PER 100 FT
15.50
TONS

PLAN NO 2
SIDE ELEVATION

SCALE 1"=20 FT

= 1:240

AREA OF CROSS SECTION
OF PILE 10000 SQ. FT.

260'-0"

541'-6"



563'-12" OVERALL OF SHEAVES.

558'-0 1/2" OVERALL OF TRACK STRINGERS

540'-1" TOTAL TROLLEY TRAVEL

250'-3" SPAN

139'-9"



**THE BALTIMORE DRY DOCK OF THE WM. SKINNER
& SONS SHIPBUILDING AND DRY DOCK COMPANY.**

BY JAMES RITCHIE, MEMBER CIVIL ENGINEERS' CLUB OF CLEVELAND, OHIO.

[Read before the Club, October 8, 1901.*]

IN February, 1899, the writer was requested to prepare plans, specifications and estimates of cost for a timber dry dock for the Wm. Skinner & Sons Company, of Baltimore. After the plans had been prepared it was thought better to construct the dock of concrete and masonry, and plans were made on that basis. Proposals were received for a concrete dock, but the company decided to construct the dock of timber, with a concrete and masonry entrance. The plans and specifications were modified to conform to this decision, and on June 29, 1899, a contract was awarded to the Delaware Construction Company, of Wilmington, for the construction of the dock and approaches, and that contract will be completed by November 1 of this year.

The accompanying drawings show the general plan, midship and longitudinal sections, section through masonry entrance and the plans and sections of the power house.

The principal dimensions of the dock are as follows: Length over all, 626 feet; length on keel blocks, 576 feet; distance from inner face of gate, when placed in outer grooves, to head of dock on keel blocks, 600 feet; width of entrance at bottom in clear, 60 feet 2½ inches; width of entrance at top in clear, 80 feet 2½ inches; width of basin on top, 125 feet; depth of water on inner sill at low tide, 22½ feet.

Within the last three months, and after visiting the new dock at Newport News, it was decided to build at the head of the dock a pocket which will allow the bow of a vessel to extend 23 feet 4 inches beyond the original head of the dock, and will enable us to dock a vessel 600 feet long over all.

The location of the dock is such that it could not be wholly constructed within the limits of the existing shore line, as will be seen by examining the plan. In fact, the concrete and masonry of the entrance were constructed at a distance of about 208 feet from the shore, but still inside of the established harbor lines. This entrance had to be excavated to a depth of 36 feet below low water, and covered a space of 44 by 164 feet, requiring the above depth over the entire space. To accomplish this work and to provide a permanent protection for the same after the completion of the dock,


*Manuscript received October 21, 1901.—Secretary, Ass'n of Eng. Soes.

a bulkhead was constructed of 10 x 12-inch tongued and grooved sheet piling, from 34 to 48 feet in length, driven in two rows 16 feet apart, braced by guide piles, 12 x 12-inch timbers and $1\frac{3}{4}$ -inch iron rods every 10 feet, the inside walls of these bulkheads being from 132 to 145 feet apart. On the south side of the dock, opposite the south abutment, a third row of sheet piling was driven outside of the bulkhead, and between the two outer rows the concrete wall of the power house was constructed.

The entire area of the dock was then dredged to the depth required for the dock bottom, and the entrance closed by a cofferdam of the same form as the protection bulkheads. The 16-foot space between the walls of the bulkheads and cofferdam was filled with clay, and the water in the dredged portion was pumped out. During the process of pumping out, braces were put in from side to side of the basin, supporting them on temporary piling, which effectually prevented the bulkheads from yielding to the outside pressure. Also, there were two rows of 10 x 12-inch tongued and grooved sheet piling driven across the dock, one at each end of the proposed excavation for the entrance masonry, and these two rows were braced together by heavy timbers. The end cofferdam was also braced with timbers to the outer of these cross-rows, and the inner row was braced to a line of piling in the inner basin, afterward used as a part of the supports for the dock door.

After the water was pumped out the bottom of the entrance excavation was finished to the required depth, and the work of concreting was commenced. The foundation soil was a hard white clay, of such firmness that the sheet piling had broomed up on the ends as if they had struck rock. Above this clay there was fine white sand, of variable depth and occurring in pockets, and this material caused us considerable trouble by reason of its water-bearing character. Above the sand was a stratum of red gravel, very hard and compact, in which some of the sheet piles had brought up, so that in some cases we had to excavate below the ends of the piling to secure our depth. By careful handling of the concreting, we overcame the difficulties caused by the water, and concreted the whole area up to the level of the under side of the apron masonry without serious trouble. In order to prevent leakage from the outside when the dock should be in service we excavated a trench 3 feet deep in the white clay clear across the entrance, and filled the same with concrete, to act as a cut-off wall.

The south abutment was designed to contain the pumping plant, and a tunnel to convey the water from the dock to the pumps was formed in the concrete. The tunnel was 6 feet wide and 6



feet high, and its roof was formed of concrete $10\frac{1}{2}$ feet thick, the upper surface of which formed the floor of the engine room. Iron beams 12 inches deep were set on the walls of the tunnel and imbedded in the roof, and the suction pipes of the pumps and foundation bolts of the engines were also built into the concrete. The suction pipes had flanges cast on them at intervals, projecting into the concrete, to serve as supports and to cut off seepage of water. At the distance of 3 feet below the floor and the same distance back from the face of the engine room walls a layer of Portland cement mortar was put in for the purpose of overcoming the porous nature of concrete and preventing leakage. As the walls were built up this layer of mortar, which was 3 inches thick, was carried with them to a point above high water mark, the floor of engine room being 16 feet below low water line.


All of the concrete used on this work is made of one part of American Portland cement, two parts of sand and five parts of broken stone, and this mixture we found very satisfactory. The cement used was what is known as "Dragon," made in the Lehigh Valley, and each lot of one hundred barrels was tested for tensile strength after seven and after twenty-eight days' setting. Hot and cold pat tests were also made, both in air and water, and the results were such as to show a good quality of cement. We had considerable trouble in securing a good quality of sand, but, after repeated rejections, a very fair material was obtained. The broken stone was generally very good, being clean, uniform in size and of a good quality of granite.

The facing of the abutments and the floor of the aprons was of Port Deposit granite, and is a very fine piece of work. The sill stones are 6 feet thick, and weigh from 14 to 17 tons each. They rest upon the concrete base, which is from 8 to 10 feet in thickness. The apron floor is of granite, from 2 to 3 feet in thickness, according to location. The abutments are faced with granite in courses of 2 feet in thickness, the stretchers being not less than 6 x 4 feet and the headers 3 x 6 feet, which gives the walls a very massive appearance. All the stones are doweled together on the beds, and the outer sills are tied to the inner sills by steel bands bedded in the concrete base.

As soon as the concreting reached the floor level of the engine room, which is 10 feet above the floor of the dock, the Morris Machine Company, contractors for the pumps and engines, commenced to set the same in place and to put in the discharge pipes which go through the outer walls, and had to be concreted into place. There are three main pumps, each capable of discharging

35,000 gallons of water per minute, and one drainage pump, all being of the centrifugal type. The latter is for the purpose of taking care of the leakage of dock when same is in use. Each pump is operated by a vertical single high-pressure steam engine, and is furnished with gate valves in both the discharge and suction pipes. The pumps will discharge wholly below the level of the water in the harbor, and can thus be primed at any time by opening the valves in the discharge pipes.

The foundations of the boiler room consist of a bed of concrete 7 feet thick, supported upon a grillage floor which rests on piling.



HALF CROSS-SECTION OF DOCK MIDSHIPS.

The concrete extends down below low water line, and in it there is formed an air duct for the forced draft. The boiler plant consists of a battery of three Heine water tube boilers of 350 horse power each, or a total of 1050 horse power. In addition to this battery there is an auxiliary tubular boiler for furnishing steam for the drainage pump and the pumps in the gate, as well as the engine that drives the air fan.

As soon as the pumps and boilers were in place the contractors erected the power house superstructure, which is a brick building

with an iron roof, and which will have a platform 4 feet wide around the engine room, with stairs leading down to the engine platforms.

The dry dock basin is constructed of piling and timber, as shown on the plans and cross-section. There are thirteen longitudinal rows of piles, capped with 12 x 12-inch timbers, drift bolted to the piles. Upon these caps are placed the transverse sills, securely boted to the caps. These consist of 16 x 18-inch Oregon fir timbers, placed 4 feet apart on centers. Every alternate timber is 70 feet long, the intermediates being 14 feet long. On these timbers are placed the keel blocks every 4 feet, and the slide or bilge blocks every 8 feet, for supporting the vessels when in dock. The floor is of oak plank 4 inches thick, spiked to supports which rest upon and are bolted to the longitudinal caps. The floor slopes from the center of dock to the sides, and at each side there is a longitudinal drain which empties into a cross-drain leading to the tunnel under the engine room. The slopes are formed of five rows of piles on each side of dock, capped with 12 x 12-inch timbers longitudinally of dock, and braced by 12 x 12-inch braces from ends of transverse timbers to waling pieces bolted to the rows of piles. The slope timbers are 12 x 14 inches every 8 feet, resting on and bolted to the caps and framed into the upper side of the main cross-timbers of floor. Another slope timber, 8 x 14 inches, is placed midway between the main slope timbers, and framed into a filler which runs between the main cross-timbers of floor. There are four chutes on each side of the dock, extending from top to bottom of the slopes, for the delivery of material into the bottom. These are 8 feet wide, and are made of 6-inch oak plank laid on the slope timbers, and having a combing on each side consisting of an 8 x 14-inch timber. The remainder of the side slopes are covered by altars or steps, having a rise and tread of 10 inches, the top being finished by an oak coping made of two pieces of 12 x 12-inch edge, bolted together; all the altars being spiked to the slope timbers, and the coping being drift bolted to the upper cap. The head of the dock has an extension, previously mentioned, made by setting in 10 x 12-inch sheet piling and bolting same to heavy timbers framed into the caps and floor timbers, and braced in every possible manner.

As the east line of the street was only 16 feet from the top of the dock at its head and 12 feet above same, it was thought best to concrete the slopes at the head of the dock and also the sides for a distance of about 60 feet from the head end, to prevent any possibility of the settlement of the outside earth. Also at the end of the dock on the north side, just inside of the entrance masonry, where

the top of slope approached very nearly to the inside wall of the protection bulkhead, we placed a solid wall of concrete. In all other parts of the slope the earth excavated from the bottom was filled in back of the altars as they were placed in position.

On September 25, 1901, the contractors finished cleaning up the dock and removed all temporary pumps and engines from the same, allowing the water to gradually flow in until the dock was filled, and then commenced to remove the end cofferdam and dredge out the entrance. This will be completed about October 20, and the gate will then be placed in position and the dock pumped out for a final test.

The gate is a steel caisson, made to set in the grooves of the masonry entrance, and to be sunk into position by filling its compartments with water. It is provided with six Ludlow gate valves for letting water into the dock, each valve being 36 inches in diameter, and with valves for filling and emptying the caisson. There is also an engine and pump for emptying the caisson, they being placed on the main deck. Steam will be furnished through hose connections from the auxiliary boiler in the power house.

A retaining wall of rubble masonry, 158 feet long, has been built to protect the street at the head end of the dock, giving a drive 12 feet wide around the head of the dock. The side street is protected by the sheet pile bulkhead driven along the street line at the commencement of the work.

On each side of the dock, and extending its entire length, is a water pipe, with hose connections between every chute, for use in washing out the dock. This pipe is connected to the supply pipe from the city mains, and also to the pumps in the power house, so that in any case a full supply of water for washing out or for fire protection can be furnished.

The keel blocks are placed at intervals of 4 feet on the center line of dock. They are $3\frac{1}{2}$ feet high, being made of three pieces of 12 x 16-inch and one piece of 6 x 16-inch oak, bolted to the cross-timbers of floor. The slide or bilge blocks are placed every 8 feet, and arranged to be adjusted to the shape of the vessel, both by hinging the upper block and by sliding the entire block on the floor timber. Iron dogs, working in a rack on the floor timber, hold the blocks in place, and the dogs can be released by a pull of the chains used for moving the blocks back.

The work of construction was under the immediate charge of Mr. C. P. Ruple, resident engineer, who had a force of assistants on the work at all times, and the successful completion of the work without accident is largely due to their constant presence and care.



Editors reprinting articles from this journal are requested to credit not only the JOURNAL, but also the Society before which such articles were read.

ASSOCIATION OF ENGINEERING SOCIETIES.

Organized 1881.

VOL. XXVII.

NOVEMBER, 1901.

No. 5.

This Association is not responsible for the subject-matter contributed by any Society or for the statements or opinions of members of the Societies.

THE LOWER MISSISSIPPI RIVER: PHYSICAL CHARACTERISTICS, METHODS OF IMPROVEMENT, CHARACTER AND VOLUME OF TRAFFIC.*

By J. A. OCKERSON, MEMBER OF THE ENGINEERS' CLUB OF ST. LOUIS.


A STREAM carrying the drainage of an area of 1,256,000 square miles, having 15,000 miles of navigable tributaries and which is itself 2500 miles in length, justifies the appellation of "Father of Waters." The Mississippi River, rising in Northern Minnesota, where its waters are ice-bound for nearly half the year, flows southward, gathering strength and volume on its way to the sea until it finally enters the Gulf of Mexico, where it washes the shores of semi-tropical Louisiana.

The regulation and control of a river of such magnitude involves problems which greatly tax the ingenuity and skill of man to solve. In its lower half the river oscillates in volume from a minimum flow of 65,000 cubic feet per second to a maximum of 2,000,000 cubic feet per second, and the oscillations in stage between extreme high and low water amount to 53 feet. About 1250 miles above its mouth the Missouri River enters, with its sediment-laden waters that are prolific in hindrances to navigation. This sediment and that derived from the erosion of the alluvial banks form the

*A portion of this paper was read before the International Engineering Congress at Glasgow, Scotland, September 4, 1901. It was later revised by the author and enlarged so as to cover the question of river transportation, and in this shape was read before the Engineers' Club of St. Louis, September 18, 1901. It was profusely illustrated with lantern slide views, some of which are reproduced here.

sand bars which develop during the falling stages of the river, and become at low stages formidable obstructions to navigation.

It will thus be seen that there are two distinct problems,—one involving the improvement of low water navigation and the other the prevention and control of destructive floods. Incidentally, the works executed for the latter have a direct influence on the former, by preventing a dispersion of the waters, and thus inducing a scouring effect in the bed, which enlarges its capacity. The lower half of the stream flows in an alluvial bed of its own formation, the banks of which are very easily eroded. This erosion takes place for the most part on falling stages. The banks, being composed of alternate layers of sand and silt, or clay, are disintegrated by the layers




THE MISSISSIPPI RIVER WATERSHED.

of sand being washed out when the water in the saturated banks recedes toward the river as it falls. This leaves the clay unsupported and causes the banks to collapse in large masses, which slide into the river and then disintegrate from the force of the current. In the 885 miles of the river lying below the mouth of the Ohio River this erosion or caving amounts to an average of $9\frac{1}{2}$ acres in area for each mile of river in a year, or a volume of about 1,003,579 cubic yards for each mile of river per year. The total annual amount of erosion for this reach equals 10 square miles 86 feet in depth.

In its natural condition the river, below the mouth of the Ohio, overflowed its banks at flood stages, which generally occur in the spring months. The destructive floods invariably come from the Ohio River and its tributaries, chief among which are the Tennessee and Cumberland Rivers, which drain a region in which the rainfall is exceptionally heavy. The alluvial basin subject to overflow

covers an area of about 30,000 square miles. It has a soil of remarkable fertility, which yields enormous crops of cotton and sugar cane. It is thus capable of sustaining a large population, adding very materially to the wealth of the country. This brief description of the physical conditions of the stream is essential to



LOWER ALLUVIAL VALLEY OF THE MISSISSIPPI RIVER.
Showing area subject to overflow and lower limits of watershed.

an understanding of the problems relating to its improvement and the methods employed therein.


From St. Louis to Cairo, a distance of 180 miles, the work projected at present contemplates a channel 8 feet deep at low water and having a width of 2000 feet. The overflow stages are not of such frequent occurrences as to justify expensive embankments or levees to control the floods. The high stages occur in the months of May and June, while the low water season generally begins with

September, and often extends into the winter months. The system of improvement adopted for this reach consists in contracting the channel and closing the side chutes or channels by means of permeable dikes and hurdles. This requires that the banks must be held, which is done by means of revetment. Work is also done with hydraulic dredgers and temporary portable dikes, which are used to open channels through obstructing bars. On the completion of the contraction works now in progress, it is expected that a navigable channel of 8 feet in depth at low water will be readily maintained.

The Mississippi River Commission is charged with the survey and study of the physical conditions of the river from its source to the Gulf of Mexico. This survey consists of a chain of high-grade triangulation and a line of precise levels, which form the basis for a topographical survey covering a width of about a mile on either side of the river, and also for a hydrographic survey giving depths, slopes, volume of discharge, etc. Permanent marks or monuments are left at frequent intervals, and these serve as the initial points from which subsequent surveys are made for ascertaining changes occurring in the bed or banks of the river. The general survey, made in great detail, has been nearly completed; and about 2000 miles of the river have been mapped, and the maps have been published on a scale of 1 : 20,000.

The chief construction work of the commission has been confined to that portion of the Mississippi River lying between the mouth of the Ohio and New Orleans. The work has consisted of contracting the channel in wide places, revetment and dredging. A bill pending before the last Congress required that a thorough study shall be made with a view of ascertaining the feasibility and practicability of securing an ample waterway 14 feet in depth; the ultimate object being to secure a 14-foot channel from Lake Michigan to the Gulf of Mexico via the Illinois and Mississippi Rivers. The present law contemplates a channel not less than 9 feet in depth at the lowest stages of the river. Under natural conditions this depth prevails for an average period of about eight months in the year. The low water period generally ranges from the middle of August to December. This is, however, the period when the grain crops are moving and good navigation is most urgently needed. As the permanent improvement of a stream of such great length will necessarily require a long period of time, temporary expedients for the relief of navigation must be used, for which purpose hydraulic dredges of large capacity have been constructed. An experimental dredge was first constructed and worked for a period of over two

years, for the purpose of ascertaining whether dredging in a stream where such enormous quantities of material are continually moved along the bed by the current could give any beneficial results, and also to learn by experience how to maneuver and operate a dredge and discharge the material in strong currents. These experiments and work done since then have fully established the fact that a powerful hydraulic dredge can open an ample navigable channel through an obstructing sand bar and maintain it at a cost fully justifying the expense. There is now in the service of the commission a fleet of eight dredges, with a combined working capacity of over 10,000 cubic yards per hour.



U. S. DREDGE "IOTA."




A description of one of the later type of dredges now under construction will give a good general idea of what is considered essential to a good dredge for work in a stream where the material to be moved is river sand. This type of dredge is provided with propelling power operating two side wheels. The hull is of steel, and ample cabin accommodation for machinery and crew is provided. The general dimensions are as follows: Length, molded, 192 feet; width, molded, 44 feet; depth, molded, 7 feet; maximum width over wheels, 70 feet; suction well at bow, 25 x 33 feet; working draft, 4 feet; cabin, 44 x 130 feet; diameter of centrifugal pump, 75 inches; suction and discharge pipes, 32 inches diameter; length of discharge pipe, 500 feet; main engine (tandem compound), 16 and 26 x 20 inches; and seven boilers, with four 11-inch flues, 44

inches in diameter and 30 feet long. The capacity of the dredge is 1000 cubic yards of sand per hour, delivered through 1000 feet of discharge pipe at a pump speed of 160 revolutions per minute. (See illustration of sand pump dredge.)

The sand pump has a suction on each side of the pump casing, and the discharge leaves the casing from the lower side and follows along a pipe laid on the lower beams of the hull to the stern, where it is connected with a floating pipe line. This floating discharge pipe is carried on pontoons in lengths of 100 feet, coupled together with flexible joints of rubber, so as to discharge outside of the channel. The discharge pipe line can be deflected by means of shifting the pontoons, and also by the use of a baffle plate at the end of the line. The pump runner, 75 inches in diameter, has five blades, and is keyed upon a steel shaft. The blades are provided with removable wearing plates $1\frac{3}{4}$ inches thick. The casing is of cast iron. The intake of the suction is in two parts, each $11\frac{1}{2}$ feet long by $8\frac{1}{2}$ inches deep. These suction heads are brought down to a section 22 inches square, and enter the hull by means of radial joints, which admit of raising and lowering the suctions at will. This motion is effected by wire ropes passing over sheaves, and operated by suitable winding engines. The material at the suction intake is loosened by water jets from twelve 2-inch nozzles working under a pressure of 60 to 120 pounds per square inch by means of a horizontal duplex compound plunger pump. The main engines are horizontal condensing engines of the tandem compound type of the dimensions given above. The boilers are of the Mississippi River type, bituminous coal being used as fuel. The dredge is provided with an electric light plant, refrigerating plant and steam steering gear. Ample accommodation is provided for quarters and for maintaining a double crew. A well-equipped machine shop provides facilities for making ordinary repairs.

When in operation, the dredge is manipulated by two wire cables 1 inch in diameter and 1200 feet long, one end being attached to hauling drums 48 inches in diameter and the other to hollow iron piling or mushroom anchors securely placed in the bed of the river. With the cables all paid out, the dredge is at the lower side of the sand bar to be cut through, and it is pulled up-stream at a speed varying with the depth of the cut and character of material. For depths of 5 feet, the rate of movement ranges from about 90 to 150 feet per hour, or sometimes even as high as 200 feet of cut per hour. After one cut is finished, the hauling cables are shifted; the dredge is again dropped back to the lower edge of the bar, and another cut is made along the side of the first cut. This process is repeated until

SUCCESSIVE CONDITIONS - (a), (b), (c) - OF CHEROKEE CROSSING, SHOWING
RESULTS OF DRAINAGE.





sufficient width has been obtained. After the first cut has been opened, the current is an active agent in assisting the development of a channel, provided the cut has been properly located with reference to the natural direction of flow; otherwise the artificial cut may be filled as fast as it is opened by the material which is moved along by the current. Last year a 10-foot channel was maintained throughout the low water season.

Where the dredged cuts are properly located, a satisfactory channel can be readily opened; and experience shows that when



CENTRIFUGAL PUMP OF U. S. DREDGE "DELTA."

once opened the channel will maintain itself until there is considerable fluctuation in stage, such as to change the direction of flow of the thread of the current. Such a dredge is operated at a total cost of about \$100 per day of twenty-four hours.

REVTMENT AND CONTRACTION WORKS.

In a stream flowing through a bed of its own formation the banks are naturally very easily eroded, and a lateral movement in one direction or the other is continually in progress. Any permanent improvement of navigation requires the banks to be made stable to prevent the flanking of the channel works, and to stop the contribution of eroded material which builds up the obstructing

bars. Active bank erosion is confined to the concave sides of the bends in the river, where the thalweg lies close to the bank. These banks are sometimes 50 feet in height above low water, and extend down below for an equal depth. This gives a steep bank about 100 feet high, which must be protected in such a way as to prevent its erosion and disintegration, a very difficult and expensive work. There is no rock near at hand for use as ballast or paving, and it has to be brought from quarries several hundred miles away. The willows used for covering the bank below the low water line grow in profusion along the battures, but even the supply of willows would be severely taxed to meet the demands of a general system of bank revetment. The method now in vogue for holding the banks consists of a covering of fascine-willow mats ballasted with stone and usually 300 feet in width, extending from the low water line out into the stream. These mats are built and sunk in lengths of about 1000 feet. The only limit to the length is that fixed by the strength of the head lines which hold the floating mat in place during construction. With a strong current and large accumulations of drift, it is often difficult to hold a very long mat.

In the construction of a mat the first step is to secure the mooring barges end to end at right angles to the shore, and located at the up-stream end of the work. They are firmly fastened together, and cables reaching secure fastenings on shore hold them firmly in position. The heading for the mat is then made of a bundle of strong hardwood poles 5 to 8 inches in diameter, and is secured along the down-stream side of the mooring barges to which it is suspended. It is further secured by six or eight wire cables, an inch or more in diameter, passing under the mooring barges and leading to strong fastenings on shore. To obtain additional strength, a second heading is placed in the mat about 10 feet below the first one and securely fastened to it. Two mat barges, end to end, are dropped in below and parallel to the mooring barges, to which they are attached by three cables so arranged that the mat barges can be readily dropped down-stream as the mat is built. These barges are built with inclined ways on which the mat is constructed, and are provided with reels for holding the sewing cables and wire strands, all spaced at the proper intervals. Willow poles are next placed in position at the top of the incline and normal to the shore, and a fascine 12 inches thick and 300 feet long, or the full width of the mat, is constructed. The willows used range from 1 to 4 inches in diameter at the butts, and the entire length, including the bushy tops, is made use of. (See illustration.) Galvanized wire cables $\frac{5}{16}$ of an inch in diameter, spaced about 8 feet apart, are

attached to the heading, and run the whole length of the mat along its underside. The fascines are drawn close up to the heading, and are fastened together by a $\frac{1}{2}$ -inch galvanized wire strand, which passes around each fascine, and also the longitudinal cables which are the mainstays of the mat. The weaving strand and bottom cables are clamped together at frequent intervals by staples driven into the large willows. As the matways become filled and the mat develops, the mat barges are dropped away; and this process is repeated until sufficient length has been made. Rows of large willow poles are placed on top and lengthwise of the mat at intervals



MAT WEAVING.

Showing construction of mat and the mat barges.

of about 16 feet, and are securely fastened in place. These poles perform the double function of strengthening the mat and preventing the loose rock ballast from rolling off. The channel edge of the mat is further strengthened with a $\frac{1}{2}$ -inch galvanized steel wire cable having a breaking strength of 9 tons. This is clamped to the weaving cable on top of the mat at intervals of 10 feet, the upper end being secured to the heading. Where great strength is required, similar top cables are placed at intervals of 8 to 16 feet, according to the necessities of the case. A mat of the character described can be made at a rate of about 10 lineal feet per hour. When completed, the mat floats on the surface with one side resting against the river bank, the whole being held in place by the mooring lines. (See illustration.)

The next step is to sink the mat to the bottom. First a uniform distribution of stone is made all over the mat and of sufficient quan-

tity to barely allow the mat to float. Barges loaded with ballast stone are then brought to the head of the mat, and sufficient stone is placed thereon to sink it when the lines to the mooring barges are slackened off. The cables to the shore still hold it from moving down-stream. The head of the mat being on the bottom and the balance still afloat, the stone barges are dropped in below the mooring barges and parallel to them, and so connected that they can be floated down as the mat sinks. A large force of men then throw off the stone onto the mat, and as it sinks the barges float down over it, delivering the stone ballast uniformly until the whole rests securely on the bottom. The head cables, which are provided with special toggles for the purpose, are then removed and the subaqueous portion of the bank is secured by the ballasted mat. The final sinking of a mat 1000 feet long is accomplished in about an hour.

The form of mat described is found to serve the purpose very well, the weakest point being the wire fastenings, which in the course of time corrode and break. When once in place, the ballasted mat filled with sediment will remain under ordinary conditions even without fastenings. To obviate the defects incident to corrosion, experiments are being made with silicon bronze and other wires and different wire coatings.

The following materials are used per 100 square feet of mat: Willow brush, 1.639 cords; poles, 0.053 cord; steel wire, 4.861 pound; silicon bronze, etc., wire, 0.546 pound; wire strand, 10.965 pounds; clamps or staples, 1.500, and stone, 0.625 ton.

Another form of mat, called a crib mat, is used with good results where the plant is limited, and it also has the advantage of eliminating the use of wire and wire strand. These mats are constructed on temporary ways built on the bank near where the willows are cut. The dimensions are usually 100 x 150 feet and about 1 foot thick, but the mat may be of any suitable size or thickness. A bottom frame of sawed lumber is first laid on the ways, consisting of 2 x 4-inch pieces laid in pairs at intervals of 10 feet. Upright posts or binders are placed between the pairs of scantling at intervals of 5 feet, and are secured to them by wooden pins. The first layer of willows is next laid on and fastened with spikes across the frames, or at right angles to the river; a second layer is laid at right angles to the first, and a third layer parallel to the bottom layer. The whole is then firmly compressed by a special device, and a top frame similar to the lower one is put in place and securely pinned to the uprights. On top and across these top frames poles are fastened to stiffen the mat while being handled and to hold the ballast in

sinking. Each mat as completed is launched into the river, and when a sufficient number have been constructed they are bound together and towed by a tug or towboat to the point required. They can be bound together to form a long mat, or they can be sunk separately. The mat costs three cents per square foot afloat and six cents in place, and requires 12 pounds of stone per square foot to sink it.

After the sub-aqueous portion of the bank has been securely protected, the upper part of the bank is graded to a slope of 3 to 1 by a hydraulic grader, and the graded surface is paved with stone



POSITION OF MAT READY FOR SINKING.

Showing mooring barges and suspension lines holding mat up. Showing also the upper bank revetment or paving.

to a thickness of about 10 inches. This paving is carried up to within 10 feet of the top of the bank and sometimes is carried right up.

Where the ballast stone is very far from the work, artificial stone of cement and river gravel, which is usually near at hand in abundance, is made use of. German Portland cement is used in the proportion of 1 cement to 13 of sand and gravel. The mixer and its machinery is carried on a tramway laid on the gravel bar where the material is abundant, and a series of molds are placed on the ground along the tram. The blocks are made 7 inches thick, 12 inches deep and 6 feet long, and after hardening are broken into

sizes to suit. This artificial stone weighs about 140 pounds per cubic foot. A small plant will make about 160 tons per day at a cost of about \$1.40 per cubic yard, as against \$2 or more for the stone in some localities.

Experiments are being made with upper bank paving of concrete 4 inches thick laid *in situ*. Brick is also being tried for ballast and paving.

The average cost of a complete bank revetment, with a subaqueous mat 300 feet wide and upper bank graded and paved, is \$27 per running foot of bank.

In some cases spur dikes or buttresses, spaced 450 feet apart, have been used to hold high banks and check the erosion, constructed of willows and stone built up in layers on a broad foundation mat. In some places these have failed by scour taking place behind them, as the above-water bank is left unprotected. Such spurs properly spaced would doubtless be successful and perhaps more economical than the standard continuous revetment. The closure of chutes or side channels is effected by means of brush and stone dams and pile dikes built to a height somewhat above low water.

LEVEES.

The alluvial basins below the mouth of the Ohio, which are subject to overflow, cover an area of about 30,000 square miles. At high stages these lands, under natural conditions, are flooded to depths varving from a few inches to 15 feet, or even more. Originally they were densely wooded, but the extraordinary fertility of the soil attracted the agriculturist, who settled there and cleared up the lands at the risk of being overwhelmed by the floods. Under such conditions only the very highest of the lands, which always lie near the river banks, could be utilized, and most of the land was left in its wild state until the inhabitants undertook to build barriers to keep out the annual floods. In this way the levee system began, and so long as it was confined to isolated districts, leaving the major portion of the basins still open to the floods, the levees required were of small dimensions.

When the improvement of the river began, it soon became apparent that it was important to confine the waters as far as practicable to the same general channel lines at both low and high stages. This meant that the floods must be confined throughout the whole length of the alluvial valley. To restrain all the enormous volume of water necessarily required much higher and stronger levees than had been found sufficient to protect isolated patches of land. As was expected, the river in flood, confined between levees a mile or

two apart, reached a plane considerably higher than when it was allowed to spread unimpeded over the wide expanse of basins. While the cause seemed quite apparent, many people attributed the rise in the flood plane between the levees to a filling up of the bed of the stream. This led to an extended investigation by the author, extending over several hundred miles of river, the conclusion arrived at being that there had been no very decided change in the bed; but, on the whole, the evidence pointed to a lowering of the bed. This view was further substantiated by the fact that the low



CAVING BANK, CARUTHERSVILLE, MO.

water plane was very materially lower than it was prior to the completion of the levee system, although the depth and volume was equal to those of former years.

Prior to 1882 the construction of levees was confined to the several States and to private landowners. In that year there occurred one of the greatest floods known, and it became apparent that the aid of the general government was essential to adequate protection. Appropriations of funds were made, and since that time the Government has spent about \$16,000,000 in levee construction, while the several States have spent about double that sum. The total length of levee lines below the mouth of the Ohio is about

1450 miles, but they still lack much to bring them up to the dimensions and height deemed necessary for safety.

The ordinary standard levee is built with a crown of 8 feet and side slopes of 3 to 1. The crown and sides are sodded with a very tenacious grass, known as Bermuda grass. Where the levee exceeds a height of 11 feet it is reinforced on the land side with a banquette of earth, which reaches a height of 8 feet below the top of the levee. The crown of the banquette is 20 feet in width, and has a slope, for drainage purposes, of 10 to 1, the side slope being 4 to 1. These dimensions of both levee and banquette are increased if the foundation is bad or the material is not good. In some



WAVE WASH AT BASE OF LEVEE.

places the only material available is a very sandy soil, and in such cases a very large section is required. The use of levees as roadways is strictly prohibited.

On approaching the lower end of the levee system, the floods sometimes continue to stand far up on the levees for several months, which tries them very severely, as they become saturated and easily abraded by wave wash from wind or passing steamers. To prevent the wave wash, a plank revetment is fixed a short distance from the levee. After a levee becomes thoroughly saturated with water, a collapse, with its destructive effects, may occur. Such breaks in the levees are called crevasses. When once formed, they continue to increase in width, and the rushing flood plays havoc with every-

thing in its wake. Houses, fences and even the soil itself are torn up, and great damage is done. When a break occurs, but little can be done beyond holding the broken ends, so as to save as much of the levee as possible. So far efforts at closing a break have not been very successful, and are always attended with enormous expense. Bank erosion is one of the most active and formidable agents in the destruction of levees. A considerable length of completed line often caves into the river, necessitating the construction



WATER RUSHING THROUGH A CREVASSE OR BREAK IN THE LEVEE.

of a new line farther back and connecting with the stable ends of the old line.

The above brief general description of the chief works carried on for the improvement of the Mississippi River will give a fair idea of what is being done. Anything like a detailed account of works of such great magnitude would require volumes, and they have only been touched upon here and there in this paper. It is hoped, however, that it may be of some interest and value.

TRAFFIC ON THE MISSISSIPPI RIVER.

It is a well-established fact that waterways are the only satisfactory regulators of freight rates, and that they have brought about in a natural and effective way that control of rates which

has long been sought through legal enactments with indifferent success. A brief glance at the enormous cargoes carried will readily show why this must be so.

A single cargo of coal, amounting to between 40,000 and 50,000 tons, is carried from Louisville to New Orleans via the Ohio and Mississippi Rivers, a distance of 1400 miles, at a cost of about 10 cents per ton. Wheat in bulk is to-day carried from St. Louis to New Orleans, a distance of 1200 miles, and placed on shipboard at a rate of 4½ cents per bushel. Cargoes of 375,000 bushels, or 375 carloads, have been taken by a single towboat and its barges. A stern-wheel boat has carried at one time 9226 bales of cotton and a large amount of cottonseed. This load borne on a single hull would fill 369 ordinary freight cars.


Add to these the fact that the capacity of a great waterway is practically unlimited, and is open to all who choose to use it, and its great value to producers and consumers becomes at once apparent.

In this connection it will perhaps be of some interest to examine, as far as practicable, the condition of river traffic in the past. Efforts have been made from time to time to ascertain the volume of traffic on the Mississippi River for a period of years, and reaching back to the time when traffic by boat was said to be at its zenith. All such efforts have practically failed, owing to the fact that reports of receipts and shipments have not been exacted from steamboat owners or shippers. An accurate record covering the total volume of river traffic for a long period of years is essential to a satisfactory analysis of the changes which are commonly supposed to have taken place in both volume and character of that traffic. Fortunately, considerable scattering data can, by much tedious labor, be brought together for convenient use. Much of the data herein was obtained from the records of the St. Louis Merchants' Exchange.

No reliable record of the tonnage volume of river traffic at St. Louis prior to 1871 could be found. The record of boat arrivals is, however, complete. The total volume of grain shipments has been tabulated in connection with the shipments by river to show the percentage carried by the latter. The freight rates are given to show not only the great reduction in the rates from year to year, but the relation between rates on grain by river and by rail. This covers the rate from St. Louis to Liverpool via New York, and by the river route and New Orleans. All of these data are also shown graphically in a way that gives at a glance the salient points in each of the elements coming under this investigation.

During the Civil War, the traffic was diverted to the east-and-west lines by rail or by the Great Lakes to the seaboard, and the lower river was only utilized for the transportation of war materials and supplies. When the Mississippi River was again opened to traffic it was still handicapped by the shallow water at the mouth of the river, which prevented the standard seagoing craft from entering the river. Small craft of not over 15-foot draft were the rule.

While the freight on grain by the river to Liverpool via New Orleans was much less than via New York by rail or by the lake route, the shipments were comparatively small, owing to the shallow water at the passes and to the general belief that grain in



STEAMER "HENRY FRANK."

Loaded with 9229 bales of cotton; 369 carloads.

transit through the warm climate would be badly injured. Actual tests soon showed that no injury resulted in transit from climatic conditions. The obstructions at the mouth of the river were successfully eliminated, and the producers of the Mississippi Valley reaped very material benefits from the reduction in rates on export grain.

Prior to 1868 the river traffic was confined to individual steamboats carrying package freight and grain in sacks. In 1867 a barge line was organized having for its object the carrying of bulk grain and other heavy commodities on several barges propelled by a single towboat. This resulted in a large reduction in expense, and a consequent reduction in rates. Grain was loaded in barges at Peoria, on the Illinois River, at St. Paul and Rock Island, on the

upper Mississippi River, and taken direct to New Orleans, where it was transferred to ships for New York or foreign ports. These earlier barges had a capacity of about 300 tons each, and ten barges were taken by one towboat.

Owing to the small ships plying to New Orleans, much of the grain was taken to New York and there loaded into larger vessels. Even this was found to be cheaper than the routes by rail to New York.

The opening of the passes to vessels of 26-foot draft in 1879 gave a new impetus to the Southern grain route, which in 1880 carried one-third of the total shipments from St. Louis, and reached a total of over 15,500,000 bushels from that port alone. The development of the barge traffic on the Mississippi River established the fact, beyond a possibility of a doubt, that this is by far the cheapest form of transportation known to-day. By its proper development and use, there will result a movement of bulky freights in the raw material that will bring new products to a profitable market that would otherwise remain inert.

BOATS AND VOLUME OF BUSINESS.

The average annual number of arrivals of boats at St. Louis for five years, 1865 to 1869, inclusive, was 3790, while for the years 1896 to 1900, inclusive, the average annual number of arrivals was 2590. This shows a decrease of 31.6 per cent. in number; the difference in tonnage would doubtless be much less than this. The greatest number of boats arrived during a year was 4692, in the year 1880, and the least number was 2217, in 1900. The total number of ships passing through the jetties at the mouth of the river in 1900 was 3005.

The average volume of river business at St. Louis per annum, 1871 to 1875, inclusive, was 1,531,822 tons. The average for a corresponding number of years, 1896 to 1900, inclusive, is 924,756 tons, a decrease of 39 per cent. The largest volume of traffic occurred in 1880, and the smallest in 1899. The large volume of traffic followed closely the completion of the jetties at the mouth of the river.

An inspection of the stages and the traffic curves shows plainly that other causes than low water operate to influence the volume of river traffic. The general conditions of trade, the foreign demand, the crop conditions at home and abroad, all directly affect the volume of traffic both by river and rail, and account largely for the fluctuations that appear from year to year. In 1867 it was announced that "boating interests generally are dull and unprofitable."

The theory that there is a progressive deterioration in the navigability of the river, which is responsible for the decline in the volume of traffic, is not founded on fact. A search of the early records reveals many accounts of "4 feet and 5 feet scant to Cairo," and at least one of 3 feet. Such small depths are now unknown. There are also numerous records of less than 4 feet in the Missouri River and "2½ to 3 feet" in the Illinois River.

The volume of traffic in 1896 exceeded that of each of the five preceding years, and was greater than that of three other prior years, 1877, 1885 and 1888, so that, while the later years show less




DIAGRAM ILLUSTRATING VARIOUS PHASES OF MISSISSIPPI RIVER TRAFFIC AT ST. LOUIS FROM 1891 TO 1900.

traffic, the decline has not been a gradual or systematic one. The fluctuations were great, even during the earlier years, when steamboat traffic was regarded as flourishing.

On the whole the decline in volume of river traffic at the port of St. Louis has not been as great as commonly believed, and the traffic is still a very important factor in the problem of cheap transportation, which becomes more and more important as margins of profit in trade and manufacture grow smaller. The inevitable result must be an increasing use of the river as a commercial highway as the improvement of the stream continues, and finally estab-

lishes the fact that shipments can safely be made and their delivery assured without any delays due to deficient depth of channel.

GRAIN TRADE.

The volume of the grain trade of St. Louis since 1865 has varied with the development of the unsettled territory west of the Mississippi and with the foreign demand.

The former has resulted in a very large increase in the annual production. The amount exported depends on both the surplus at home and the demand abroad, and these may cause wide variations from year to year in the volume of export business. The volume of business of 1900 by river and rail combined has been exceeded by only two preceding years,—viz, 1889 and 1890, the total shipments during the latter year being 65,155,187 bushels of grain.


The average annual shipments of grain by river, 1871 to 1875, inclusive, were 1,025,742 bushels, while for a corresponding period, 1896 to 1900, inclusive, the annual average has been 5,668,596 bushels, or more than five times as large as the period often alluded to as the flourishing days of river traffic. The volume of river grain traffic varies widely with different years. In 1880, just after completion of the jetties, it reached 15,762,664 bushels, and in 1889 it reached 14,158,046 bushels, while it was less than one-half the latter amount in 1884. During the years 1871 to 1875, inclusive, 4.5 per cent. of the total grain shipments from St. Louis were carried by river. During the years 1896 to 1900, 12.0 per cent. of the total grain shipments were carried by river, reaching a maximum for the period under consideration of 25.5 per cent. in 1896. The highest percentage of total shipments was made in 1881, when the river shipments reached 37.9 per cent. of the total grain shipments. Over 30 per cent. of the grain was shipped by river in the years 1880, 1886 and 1887.

FREIGHT RATES PER BUSHEL OF WHEAT.

A great reduction in rates of freight has taken place since 1865, both by rail and river; but the river has always taken the lead in these reductions. From 1865 to 1881, there was a steady decline in river rates. From 1881 to 1891, the rates were quite steady, and then followed a gradual decline to the year 1900. In 1865 the average published rate on wheat was 30.6 cents per bushel by river from St. Louis to New Orleans. The average rate for the year 1900 was 4 $\frac{1}{4}$ cents, a decline of over 26 cents per bushel.

In 1865 the average published rate on wheat, St. Louis to New York by rail, was 70.2 cents per bushel; in the year 1900 the aver-

age rate was 11.6 cents per bushel. The average rate by river for the five years 1865 to 1869, inclusive, was 24.8 cents per bushel, while for the five years 1896 to 1900 the average was 4.62 cents per bushel, including transfer to ships for export. This is equal to \$1.54 per ton, and gives a ton-mile rate of 1.3 mills. The average rail rate, St. Louis to New York, during the same period has been 13.2 cents per bushel. This is \$4.40 per ton, or about 4.4 mills per ton-mile. This is more than three times the river rate per ton-mile. The later years have been used in these comparisons as giving the railways the benefit of all the latest traffic improvements, and the rates quoted are presumably as low as consistent with the



SIDE-WHEEL PACKET.

Loaded to the guards with miscellaneous package freight.

actual cost of transportation, and probably below the profitable limit.

On the other hand, methods of river traffic have made little or no progress since the advent of the barge lines, either in economy or efficiency, while the railways have made great strides in both.

The tabulation also shows the average annual rates per bushel of wheat from St. Louis to Liverpool by the Mississippi River via New Orleans, and by rail via New York, for the years 1883 to 1900, inclusive. The rates for the earlier years were not readily obtainable. The eighteen years show an average of 6.85 cents per bushel in favor of the river route. Some years it ran as high as $9\frac{1}{2}$ cents per bushel. Apply this to the output of grain in the territory tributary to the Mississippi River, and the aggregate is a sum

RIVER BUSINESS, PORT OF ST. LOUIS, Mo.

Year.	Total Boats Arrived.	Total Tons Freight Received.	Total Tons Freight Shipped.	Grand Total of Freight, Tons.	Total Grain Exports by Both Rail and River, Bushels.	Grain Exports by River, Bushels.	Percentage of River Traffic to Whole Grain Traffic.	Freight per Bushel of Wheat St. Louis to New Orleans, Cents.	Freight per Bushel of Wheat St. Louis to Liverpool via New York, and New Orleans, Cents.	Freight per Bushel of Wheat St. Louis to River Route, per Bushel, Cents.
1805	3,908				13,427,052			30.6	70.2	
1806	4,114				18,835,969			27.6	54.0	
1807	3,425				14,240,752			30.0	72.0	
1808	3,471				11,860,097			21.0	48.6	
1809	4,029				16,148,756			15.0	42.0	
1870	3,991				21,039,776	66,000	0.31	18.0	32.0	
1871	3,739	883,401	770,498	1,653,899	21,587,187	312,077	1.4	16.8	37.2	
1872	3,831	863,919	805,282	1,669,201	23,885,784	1,711,039	7.2	10.0	37.8	
1873	3,336	810,055	783,256	1,593,311	22,549,739	1,373,969	6.0	15.7	39.1	
1874	3,283	732,765	707,325	1,440,090	24,417,411	1,423,046	5.8	11.7	33.2	
1875	2,945	663,525	639,095	1,302,620	20,640,147	308,578	1.5	13.4	27.1	
1876	2,805	688,755	600,225	1,288,980	28,907,601	1,774,379	6.1	11.0	23.3	
1877	2,810	644,485	597,670	1,242,155	25,333,588	4,101,353	15.1	8.5	24.0	
1878	3,613	714,700	614,675	1,321,375	29,432,435	5,451,603	18.5	7.25	19.8	
1879	3,831	688,970	676,445	1,365,415	33,676,424	6,164,838	18.3	7.75	20.3	
1880	4,692	1,092,175	1,038,350	2,130,525	48,321,983	15,762,664	32.6	8.25	25.2	
1881	3,951	1,208,430	884,025	2,092,455	30,509,218	12,993,947	37.9	6.00	10.2	
1882	3,847	1,073,570	769,905	1,843,475	41,540,103	8,333,417	20.6	6.42	17.7	

RIVER BUSINESS, PORT OF ST. LOUIS, MO.—(Continued).

Year.	Total Boats Arrived.	Total Tons Freight Received.	Total Tons Freight Shipped.	Grand Total of Freight, Tons.	Total Grain Exports by Both Rail and River, Bushels.	Grain Exports by River, Bushels.	Percentage of River Traffic to Whole Grain Traffic.	Freight per Bushel of Wheat to St. Louis to New Orleans, Cents.	Freight per Bushel of Wheat to St. Louis to Liverpool via New York, Cents.	Freight per Bushel of Wheat to St. Louis to River Route, per Bushel, Cents.	Difference in favor of River Route, per Bushel, Cents.
1883	3,425	860,540	677,340	1,537,880	37,632,949	11,059,508	29.4	5.50	10.61	27.00	7.39
1884	3,047	760,685	514,910	1,275,595	41,227,380	6,647,558	16.1	6.62	14.61	21.25	6.64
1885	2,908	606,925	534,475	1,231,400	38,833,580	8,667,919	22.3	6.40	15.11	20.50	5.39
1886	3,356	779,000	561,895	1,332,885	27,690,878	8,834,924	31.8	6.50	16.16	24.00	7.84
1887	3,633	866,045	637,060	1,503,105	36,003,822	11,556,799	32.1	6.00	15.00	24.50	9.50
1888	3,323	728,808	510,115	1,239,023	38,402,167	7,252,578	18.9	6.50	15.16	22.95	7.79
1889	3,600	671,685	712,700	1,384,385	56,232,700	14,158,040	25.2	5.95	17.33	24.97	7.04
1890	3,201	663,730	617,985	1,281,715	65,155,187	10,217,244	15.7	6.58	14.33	21.48	7.15
1891	2,900	502,140	512,930	1,105,070	51,350,310	8,498,546	10.5	6.87	15.75	23.55	7.80
1892	3,143	687,200	502,215	1,189,415	53,545,976	8,444,940	15.7	6.50	14.00	21.00	7.00
1893	3,040	599,405	439,900	1,039,305	51,487,000	7,079,598	13.8	6.55	14.71	21.72	7.01
1894	3,300	583,530	363,680	946,610	35,170,487	2,345,503	6.6	5.80	11.00	18.71	7.02
1895	3,133	508,830	303,355	812,185	29,339,308	1,000,417	5.7	5.05	12.12	18.33	6.21
1896	3,400	671,705	572,410	1,244,115	41,200,512	10,527,208	25.5	5.00	13.50	16.07	6.17
1897	2,619	576,070	460,365	1,046,035	40,987,028	5,475,342	11.6	4.88	12.80	20.33	7.44
1898	2,372	506,585	399,583	906,168	52,722,079	6,600,707	12.5	4.50	14.24	20.32	6.08
1899	2,250	400,610	203,205	603,815	41,028,533	2,233,235	5.4	4.50	12.33	17.88	5.55
1900	2,217	512,010	245,580	757,590	54,006,499	3,500,491	6.4	4.25	14.04	18.41	3.77

of enormous proportions, which should have been largely divided between the producers and consumers rather than have it absorbed in high transportation charges.

Combining the known volume of freight carried by river during the years 1896 to 1900 from St. Louis, coal from the Ohio and the local traffic of Memphis and Vicksburg gives an average of about 2,785,550 tons per annum. This is doubtless far below the total amount of the traffic on the lower Mississippi River. The total traffic of the Mississippi River system must be many times this amount, reaching so great a volume as to become a highly important factor in the transportation problems of the country, and one which is of vital interest not only to the people of the Mississippi Valley, but to the entire country. The census report gives the volume of traffic for 1890 as 29,000,000 tons.

The main stem of this system has ample capacity for an enormous increase in the volume of traffic by making such practicable improvements as will insure a navigable depth at all stages that will fully satisfy the requirements of commerce.

Good use should be made of the river during our World's Fair by bringing exhibits from foreign countries to the port of New Orleans, and thence by river to St. Louis. This would result in considerable economy to shippers. As both delivery and return of shipments would be made at times when navigation is invariably good, there need be very little hesitation in encouraging transportation by this route.

While this great river has few if any parallels, the problems are most intricate and interesting; and their solution will doubtless keep the engineer busy for years to come. Little by little, step by step, the skill of the engineer will find means of overcoming the difficulties, until finally the great forces of nature pent up in the giant stream will yield to his bidding and become subservient to the requirements of man. Then will it indeed "flow unvexed to the sea," bearing in safety the products of the Mississippi Valley from the Great Lakes to the Gulf of Mexico, whence they will be distributed to the uttermost parts of the earth.

The very heart of our country will then be put in touch with the commerce of South America and, through the Isthmian Canal, with the great markets of the Orient.

THE ABOLITION OF GRADE CROSSINGS ON THE
PROVIDENCE DIVISION OF THE NEW YORK,
NEW HAVEN AND HARTFORD RAIL-
ROAD, BETWEEN BOSTON AND
DEDHAM.

By ARTHUR S. TUTTLE, PRINCIPAL ASSISTANT ENGINEER ON THE WORK.

[Read before the Boston Society of Civil Engineers, September 18, 1901.*]

BEFORE the abolition of its grade crossings between Boston and Dedham, the Providence division of the New York, New Haven and Hartford Railroad had its terminal at Park Square. Its main line from Park Square to Washington street, near Forest Hills, a distance of about $4\frac{1}{2}$ miles, was crossed at grade by eleven highways. Its West Roxbury branch, running from Forest Hills to Dedham, about $4\frac{1}{2}$ miles, was crossed at grade by four highways; and its Dedham branch, running from Readville to Dedham, about $2\frac{1}{4}$ miles, was crossed at grade by four highways. One of the latter, Milton street, at Readville, also crossed at grade the then New England Railroad, now the Midland division of the New York, New Haven and Hartford Railroad. There were no grade crossings on the main line between Washington street, near Forest Hills, and Readville. (See Fig. 1.)

A heavy train service was maintained on this division, about two hundred regular trains being handled daily at Park Square station.

The numbers of persons and teams using the eleven main line crossings in twenty-four hours, as determined by actual count, were 85,107 persons and 12,452 teams, amounting in one year to over 31,000,000 persons and over 4,500,000 teams. To protect this highway travel during the passage of the two hundred daily trains, the crossing gates were closed, during the same twenty-four hours, a total of forty-one hours and forty-seven minutes, which was nearly equivalent to the permanent closing of two crossings, provided the other nine were left open the whole time. Under these conditions, the maintenance of these crossings at grade constituted not only a grave menace to public safety, but also a great and annoying interruption to public convenience.

As far back as 1884 surveys were made for carrying all of these crossings over the tracks, the tracks to remain at the old grade, but the estimated cost of \$3,600,000 seemed so excessive that at that time nothing further was done.

*Manu-script received October 21, 1901.—Secretary, Ass'n of Eng. Soes.

In a report concerning the gradual abolition of the grade crossings in the State of Massachusetts, made to the legislature in 1889, by Augustus W. Locke, Wm. O. Webber and George A. Kimball, engineers, it was recommended that these main line crossings should be abolished by raising the tracks about 13 feet from Roxbury to Forest Hills, with a grade of 29 feet per mile north of Roxbury and one of about 15 feet per mile south of Forest Hills, connecting with the old grade; and by depressing the streets amounts varying from 1 to $5\frac{1}{2}$ feet; the total cost to be \$1,350,000.

In 1890 the Old Colony Railroad Company, which then controlled the railroad, acting under the grade crossing act of 1890, petitioned the Superior Court to appoint three commissioners to prescribe the manner in which the Tremont street grade crossing should be abolished. Fig. 2 shows this crossing before the change. In 1892 a special legislative act was passed enlarging the powers of this commission to include all the main line crossings in the city of Boston; the Old Colony Railroad Company to do all the work and to bear 55 per cent. of the cost; the Commonwealth of Massachusetts to bear $31\frac{1}{2}$ per cent. of the cost, and the city of Boston $13\frac{1}{2}$ per cent. The commissioners appointed were S. N. Aldrich, E. B. Bishop and H. C. Southworth. Necessary hearings were held and plans considered, and June 23, 1894, their final report was filed, confirmed and made a decree of the court.

The requirements of the decree were, in outline, as follows (see Fig. 3): The main line of the railroad was to be raised, beginning near Massachusetts avenue and rising to Roxbury station, where it should be about 20 feet above the old tracks; thence continuing about 20 feet above the old tracks to Washington street, thence descending for about 3000 feet to the old grade. The West Roxbury branch was to be raised about 20 feet at the main line and descend for about 1700 feet to the old grade.

Heavy retaining walls, ranging from 6 to 30 feet high, were to be built on either side of the railroad where the adjoining land was closely built upon, as shown by the heavy lines on the plan, and at other places land was to be taken and the earth embankment was to take its natural slope. A little over 3 miles in length of wall was required.

Four tracks on the main line and three on the West Roxbury branch were to be laid with 100-pound steel rails where the grades were changed. A new freight yard was to be built on the westerly side of the main line, between Center street and Mozart street. A siding was to be laid on the easterly side of the main tracks from Jamaica Plain to the Parkway at Forest Hills.

The old station on the easterly side of the tracks at Roxbury and the one on the westerly side at Boylston street were to be raised to the new grade of the tracks and stone basements built underneath, and new stations were to be built on the opposite sides. At Heath street, Jamaica Plain and Forest Hills new stations were to be constructed, one on each side of the tracks. A driveway 40 feet wide was to be carried under the railroad at the south end of Roxbury stations, and at the other stations subways 10 feet wide and 8 feet high were to connect the two station buildings.




FIG. 2. TREMONT STREET GRADE CROSSING.

Stony Brook, near Boylston street station, was to be changed, and a new channel constructed for it about 2600 feet long, 2300 feet of it being depressed in grade about 11 feet and carried in a brick conduit, and about 300 feet of it being carried at the old grade in an open walled channel. Near Forest Hills, a new channel was to be constructed for the brook, 10 feet wide at the bottom, with earth side slopes and with a double brick conduit connecting the new channel with the old double-arched stone culvert under Walk Hill street.

The brick arch over Stony Brook on the main line between Forest Hills and Mt. Hope and the Bussey farm arch on the West

Roxbury branch were each to be extended to carry one additional track.

A subway 10 feet wide and 8 feet high was to be built under the main tracks about 700 feet north of Ruggles street for convenient access to the railroad company's repair shops.

Under the tracks as raised, the highways were to be carried as follows: Ruggles street was to be depressed at the railroad $4\frac{1}{2}$ feet, Prentiss street 0.7 of a foot, Tremont street 1 foot and Boylston street $1\frac{1}{2}$ feet. Center street, which at that time was carried on a bridge over the railroad, was to be depressed $17\frac{1}{2}$ feet, and changed in grade for a length of nearly 1000 feet. West of Lamartine street, it was to be widened from 50 to 60 feet; between Lamartine street and Amory street it was to be 70 feet wide, and to cross the railroad more nearly at right angles than before, and east of Amory street it was to be from 80 to 140 feet wide. Walk Hill street, where it crossed the West Roxbury branch, was to be discontinued, and laid out 50 feet wide across the main line to Washington street. The remaining streets were to be unchanged, both in line and in grade. The railroad was to be carried over Morton street and the Parkway by stone arches, over Tremont street and Walk Hill street by steel arches and over the other streets by plate girder bridges. Two additional plate girder bridges were to be built for the future laying out of Mozart street and Williams street. The required headrooms under the bridges varied from 13 to $16\frac{1}{2}$ feet.

To carry out the provisions of the decree, it was necessary, first, to construct the new channels for Stony Brook, and October 25, 1894, a contract for this work was made by the New York, New Haven and Hartford Railroad Company, lessee of the Old Colony Railroad, with the Metropolitan Construction Company, and work was at once started. At Boylston street the excavation above the ground water level and above ledge was taken out by men shoveling directly into carts. The deeper excavation at the southerly end, where the material was hard pan, was handled with a Carson Trainor trench machine; the rock near the middle was handled with derricks, and at the north end, where the material was chiefly quicksand, a cableway about 700 feet long was used. As the old brook channel was only about 7 feet from the nearest line of the trench, the bottom of which was 12 feet below the bed of the brook, and as the main tracks of the railroad, on which trains were frequently passing, were close to the other side of the brook, very great care was required in placing and maintaining the sheet piling and bracing. The quicksand excavation was made in sections of

about 20 feet in length, sheet piling being driven across the trench, as well as on the sides, and thoroughly braced, the sand taken out and the invert foundation put in as rapidly as possible; then the next section was excavated to sub-grade before the sheeting between the two sections was removed. The trench was kept clear of water by an underdrain, which carried the water to a sump at the north end, whence it was raised by a steam pump and discharged into the brook below the work. The covered conduit (Fig. 4) as built consisted of a concrete invert foundation 6 inches thick, laid on from 6 to 12 inches of gravel, refilling where quicksand was encountered, but laid directly upon the natural earth where it was




FIG. 4. CROSS-SECTION OF STONY BROOK CONDUIT NEAR BOYLSTON STREET STATION.

firm and compact. Concrete sidewalls were carried a little above the springing line of the arch. The invert foundation and sidewalls were plastered with cement mortar and lined with 8 inches of hard-burned brick laid in cement mortar. Where the conduit was built in rock, only enough concrete was put into the foundations and sidewalls to fill the inequalities in the rock left in blasting and to bring the inner faces to the proper lines for the brick lining and arch. The arch was of hard-burned brick laid in cement mortar, 16 inches thick at the crown, and the extrados was plastered with cement mortar. The inside dimensions of the conduit were 17 feet wide and $15\frac{1}{2}$ feet high, large enough to allow of the passage of an ordinary railroad train. Upon the easterly haunch of the conduit, there was constructed the West Roxbury low-level

sewer, 2 x 3 feet 6 inches in size. Near Boylston street, there was also built upon this easterly haunch, and above the West Roxbury low-level sewer, about 560 feet of a 4 x 5-foot brick sewer to replace an elbow of the Stony Brook Valley sewer that was cut off by the new conduit, the sewerage being carried temporarily in a wooden flume fastened to the easterly side wall of the old brook channel. Two brick sewers and one pipe sewer were carried over, and overflows constructed into, the new conduit. The northerly end of the conduit was finished with a granite arch facing and squandrel wall, with sidewalls connecting with the old sidewalls, and a Portland cement concrete incline sloping from the low grade of the conduit up to the bed of the old brook. The southerly end of the conduit was finished with a similar arch facing and spandrel wall. The brick invert and sidewall lining, with heavy sidewalls built up to the surface of the ground, were carried about 20 feet south from the arch, and a dam wall built across and up to the level of the old bed of the brook. Southerly from this dam wall an open channel was constructed, with a concrete invert and granite sidewalls.

Connecting the upper end of this open channel, there was built a sand catcher, or settling basin, to stop and retain sand and other sediment brought down by the brook, and so constructed that sections of it could alternately be drained and cleaned while other sections carried the stream. An iron grating to catch driftwood, etc., and a footbridge over the basin were also placed here.

After the conduit at the northerly end had been completed the length of the cableway, the cableway was shifted to the south, a wooden bulkhead placed in the south end of the completed portion and the brook turned into the conduit through an opening left in the arch just below the bulkhead, and the old channel, where discontinued, used for a dump, an 18-inch drain pipe first being laid in the old channel.

After the completion of the whole channel, and at a time of low water in the brook, the stream was turned through this 18-inch pipe, the water in the conduit pumped out, the bulkhead removed, the hole in the arch repaired and the brook then turned through the completed channel.

The excavation for the new channel at Forest Hills was slight and simple. The covered connection with the culvert under Walk Hill street consisted mainly of a double conduit, with rubble sidewalls and a brick center pier, each 4 feet high, and semicircular arches of 8-foot span, 12 inches thick at the crown, the whole resting upon five longitudinal 6 x 6-inch spruce sills covered with 3-

inch plank. The total length of the conduit was 170 feet, and a little below the middle point in this length there was constructed a distributing chamber 17 feet 4 inches wide and 15 feet long, into which flowed the Bussey Park branch of Stony Brook, which was carried under the West Roxbury branch tracks in an 8-foot diameter circular brick conduit. The upper end of the new double conduit was finished with a stone arch facing and spandrel wall and necessary wing walls. The old double-arched stone culvert under Walk Hill street and the main line tracks was strengthened to sustain the additional 20 feet of filling and the retaining wall on the easterly line of the railroad by covering the arches with 18 inches of concrete.

The total cost of this Stony Brook work was about \$200,000. While this Stony Brook work was going on, plans for the main work were being prepared, buildings in the way were being torn down or moved out of the way and temporary tracks were being laid. Over 120 buildings of all kinds, from a shed to a large three-story brick factory, were either torn down or moved away. One large three-story brick machine shop, with long lines of shafting, was moved lengthwise about 300 feet and then back 50 feet, the machinery inside being kept constantly at work.

The work was divided into two sections, all north of and including Center street being on Section 1, and all south of Center street, Section 2. (See Fig. 3.)

The engineer corps, as organized to look out for the work, consisted of an assistant engineer of construction in personal control of the whole work, reporting to the chief engineer in New Haven, Conn.; a principal assistant engineer, two second assistant engineers, each with a party of one transitman and two rodmen, one party giving lines and grades on Section 1 and the other on Section 2; one cement tester, who tested on an average samples from one barrel in ten of those ordered for the work, and four inspectors; a total of sixteen men.

June 25, 1895, contracts were made with H. H. Brown for the work on Section 1, and with J. J. O'Brien for the work on Section 2.

At that time the railroad between Park Square and Reaiville was operated with a left hand running double track and a third track west of the double track, used by northbound trains in the early mornings and by southbound trains in the late afternoons, for the accommodation of the heavy suburban traffic. It was impracticable to maintain these three tracks for regular service and construct any part of the new work, especially on Section 1, which in

one place was only 53 feet wide, and regular traffic was therefore limited on Section 1 to the old double track, which was connected at Center street with a temporary double track on Section 2 laid east of the old double track on land taken or purchased. No track connection was permitted with this double track between Forest Hills and Chickering.

On Sunday, September 22, 1895, the regular traffic was transferred to these temporary tracks, and the interlocking tower at Forest Hills was disconnected from the old West Roxbury branch junction switches and signals and connected with the temporary junction switches and signals, there being only the one day when the tracks were not controlled from the tower.

This same day all double track of the Old Colony system of the New York, New Haven and Hartford Railroad was changed from left hand to right hand running. While this did not require many track changes on the grade crossing work, it did necessitate many precautions being taken to protect the men, who had become accustomed to left hand running and who, under the stress of the construction work going on, were liable to forget that trains were running right-handed. The old third track was used as a construction track, for the handling of stone and other construction material. A storage yard, for receiving construction freight, was constructed at Forest Hills.

The following printed rules were issued:

OFFICE OF ASST. ENGINEER OF CONSTRUCTION, N. Y., N. H.
AND H. R. R., OLD COLONY SYSTEM, JAMAICA PLAINS, MASS.

RULES FOR THE GOVERNMENT OF ENGINEERS AND INSPECTORS.

Main tracks must be kept clear for the safe passage of trains at all times. Contractors are not allowed to cross main tracks with materials, except in the usual way at street crossings that are protected by gates.

In case of an accident where one or more of the main tracks is obstructed the first thing to do is to send flags out in both directions, at the same time notifying, by telegraph, this office and also the office of the superintendent in Park Square station, Boston, of the nature of the accident, what tracks are blocked, and how long it will take to clear them. Take all the men in call on the work to clear the tracks.

Contractors must provide and keep along the work sets of emergency tools, such as axes, saws, tackle, etc., where they can be gotten at in case of accident.

Telegraph wires must not be interfered with. In case they are in the way, notify this office that a lineman is needed to look after them, and they are not to be touched without his consent.

All derricks that are set up so that the boom can reach over a main track must have boom fastened with guy rope, or posts must be set in the ground so as to prevent it swinging out over the main track at any time.

Foremen must inspect all guys every morning at each derrick.

In case it is necessary to take a guy line across tracks permission must first be asked of this office for necessary flagman (and lineman for wires if required), and the crossing of tracks with line must be done under direction of the section boss and under flags put out in both directions to protect trains.

Contractors' men are not allowed to fasten guys or the like to the tracks or to the false work carrying tracks.

Contractors must not unload from cars on construction track while regular trains are passing or approaching on main tracks.

Contractors will be allowed to work near the construction track, provided flags are put out in both directions at least 500 feet away on this track.

At no time must the construction track be blocked in such a manner that it cannot be at once freed. Trains must be expected on this track, in either direction, at any time.

All guys, where crossing tracks, must be at least 22 feet in the clear above the top of rail.

Contractors must have all excavations that are made near public travel, and all obstructions in public highways, properly protected by fences, and well lighted at night.

During heavy rainstorms, engineers and inspectors must be upon their work to guard against all possible accidents.

No excuse will be taken for disobedience of orders or carelessness, and inspectors will report any violation of rules or any carelessness on the part of contractors' men.

Per order,

C. M. INGERSOLL, JR.,

Asst. Engr. of Const.

Early in July, 1895, work was started by the contractors. On Section 1 derricks were erected every two or three hundred feet between the construction track and the westerly retaining walls from Old Heath street to Prentiss street, a distance of about three-quarters of a mile. North of Ruggles street, for about a third of a mile, they were placed on the westerly side of the wall.

On Section 2 the temporary main tracks were laid far enough to the east so that the retaining walls and westerly portions of the abutments could be built at the same time, and derricks were erected at the streets as well as along by the walls.

The lowering of the street grade at Ruggles street was such as to require the reconstruction of a portion of Stony Brook channel which ran through Ruggles street and Rogers avenue.

A double brick conduit was built, with a flatter section and at a lower grade than the old culvert, making a slight depression or siphon in the line of grade. The alignment was also changed to avoid the middle pier of the railroad bridge. Ruggles street was closed to highway travel during this work, the travel using Prentiss street, and the tracks were supported by temporary stringers and blocking.

At Center street the highway was closed to teams, but a foot-bridge was maintained over the tracks north of the old highway bridge while the southerly portion of the street was lowered to the new grade. A new sewer, new water pipes and gas pipes were laid, and the street railway company laid as much of their permanent track as could be put in. Walk Hill street was closed from the beginning to the end of the work. The other streets were kept open, except Tremont street, which was closed for a short time, as will be mentioned later.

Very large quantities of stone and cement were required, and in order to expedite the work it was essential that plenty of stone should be on hand to select from, and that it should be placed promptly.

A daily stone train was run between the Quincy quarries and the Forest Hills storage yard, constructed to receive this freight, as before mentioned, quite a surplus being kept in the yard. Stone came also from Fitchburg, Pascoag and even from Maine. At times there were as many as 250 cars of stone on hand. Each afternoon the contractors looked over the stone and made lists of the cars wanted placed the next day, stating at which derricks they were needed. The assistant roadmaster, in charge of the construction train service, rearranged these lists in the order in which the cars would be required placed on the construction track, and gave the revised list to the train crew, who made up the train in the required order and as early as possible the following morning backed the whole train to the north end of the work and on the way back dropped the designated cars at the appropriate derricks. Late in the afternoon this same crew took away the empty flat cars and placed at the derricks empty gondola cars, which were loaded during the night with material taken from the foundations by the excavation gangs working by electric light. Early in the morning, the loaded gondola cars were taken away, leaving the track clear for the morning stone train.

The inspectors submitted daily reports, on printed cards, of work done at each derrick, stating kind of work, location, whether done by company or contractor, number of men of each class of labor, time of starting and stopping, approximate amount of work done and what was required if delay was liable to ensue because of lack of men or materials.

After the westerly retaining wall on Section 1 was completed the construction track was taken up and the abutments for two tracks constructed, the stone being unloaded from the main tracks at night and piled up near the work, to be laid the following day.

Masonry was laid both summer and winter, brine being used in the mortar in very cold weather.

The temporary trestles were also erected as soon as the construction track was taken up. There was constructed a single track trestle north of Ruggles street, a double track trestle from Prentiss street to Center street, a double track trestle over the track leading into the Forest Hills freight yard and a double track trestle from Morton street to Washington street, passing over the West Roxbury branch temporary tracks.




FIG. 5. RETAINING WALL AT JAMAICA PLAIN AND GREEN STREET BRIDGE.

Where no trestles were built, the tracks were laid on the permanent embankments. The trestles were built all of hard pine, with 12 x 12-inch sills, posts and caps, thoroughly braced with 4 x 8-inch bracing. Bents were placed 12 feet apart on centers, with 4 x 8-inch longitudinal bracing in two of every three bays. Two 8 x 16-inch stringers, each 24 feet long and breaking joints at the bents, were placed under each rail. Ties were 6 x 8 inches, and guard timbers were of the same size and placed outside of each rail. On curves, the elevation of the outer rail was obtained by tapered shim blocks placed one on each tie.

The retaining walls and abutments were built of cut stone face masonry and rubble backing, laid solid in cement mortar. The wall under the dressed coping, which was 3 feet wide and 15 inches

deep, was 3 feet thick, plumb on the face, and battered down on the back 4 inches to a foot until the thickness equaled one-half the height, where the batter was increased to 6 inches to a foot. The two upper courses of the coping were chamfered, and in the vicinity of stations a neat and strong iron fence was set in the top of the coping. Fig. 5 shows the wall and iron fence and the bridge at Green street.

Tremont street crossed the railroad on quite a skew, and the abutments were built in a succession of jogs to support the ribs of the steel arch, which lapped by each other. Great care was required in the setting of the skew back stones.

South of Tremont street, Stony Brook flowed under the railroad and under a part of the westerly retaining wall in a brick




FIG. 7. COMPLETED PARKWAY AND MORTON STREET ARCH VIADUCT.

conduit of the same size as that hereinbefore described as built near Boylston street. To strengthen this conduit so as to safely carry the weight of the retaining wall, applied on one side only, and also the weight of the additional 20 feet of filling, the conduit arch was uncovered, and the space between the sides of the old rock trench in which it was constructed was filled level with concrete to a height of 18 inches above the crown of the old arch.

Between Forest Hills and Mt. Hope, the Stony Brook brick arch, carrying three tracks, was lengthened out to take the fourth track.

The Bussey farm arch was lengthened out to carry the new third track on the West Roxbury branch.

The five-stone arch viaduct at Forest Hills, four arches being over the Parkway and one over Morton street, is particularly

worthy of notice. Fig. 6 shows a right-angle section of the arches. The two end arches, the south one being for Morton street, had spans of 41 feet at right angles to their axes, the middle one a span of 45 feet and the two intermediate ones spans of 23 feet. The abutments were 17 feet thick at the bottom and 12 feet thick




FIG. 8. SECTION OF WALK HILL STREET STEEL ARCH ABUTMENT, FOREST HILLS.

at the spring. The piers were 16 feet thick at the bottom and 9 feet 4 inches thick at the spring. The angle of the faces with the axes was $63^{\circ} 03'$.

The abutments, piers and spandrel walls were built in courses, the top course just below the parapet being a variable course 1 foot 8 inches high over the middle arch and 4 inches high at the backs of the abutments. The parapet was quite ornamental, rising to a height

of about 6 feet above the level of the railroad tracks. The ends of the abutments and piers were finished in the form of buttresses, which were carried up to the top of the parapet. The ring stones were 2 feet 6 inches deep, except on the ends, where they were made deeper for architectural effect. The soffits were fine-pointed, the parapet either fine-pointed or fine-hammered and all other stone left with rock face. The upper surfaces of the arches were water-proofed with a layer of Portland cement mortar covered with ten layers of tarred paper, each thoroughly mopped with hot asphalt. The valleys between the arches were drained by 4-inch iron pipes extending down through the centers of the piers to about 4 feet underground, where they turned and connected with drain pipes, emptying into low ground northeast of the arches. A sufficient length of the westerly ends of these arches was constructed to carry the two westerly high tracks. Fig. 7 shows the completed structure.

The abutments for the Walk Hill street steel arch were built with inclined stones and Portland cement backing. Fig. 8 gives a comprehensive section of this masonry.

The station subways were built with abutments of rubble masonry, faced with white enameled brick, with a 2-inch air space between. Fig. 9 shows the subway at Forest Hills. The brick arches consisted of soffit courses of enameled brick and four other courses of hard-burned brick. The ends of the arches and abutments were finished with stone voussoirs and courses. At the stations the retaining walls were built to allow for wide platforms at the level of the tracks, with necessary stone steps giving convenient access to the streets.

The westerly stations were erected as soon as the retaining walls past their sites had been constructed. The basements were constructed with stone walls similar in color to the stone in the retaining walls, and lined inside with buff-colored brick. Stairs to the track floors and baggage rooms and the necessary heating apparatus were constructed in them. The upper stories were constructed with light-colored brick walls, sheathed up to the window sills inside in oak and lined with buff brick above the sheathing. The inside arrangements were convenient and commodious, with ticket offices and waiting, baggage and toilet rooms; suitable cover sheds were constructed over the track platforms.

At Forest Hills an approach was constructed, on the westerly side of the tracks, from the corner of Morton and Walk Hill streets up to the track platforms. At the other stations station grounds were constructed at the level of the adjoining streets.

While all this work was being done by the contractors, the road-master and his assistant were bringing in gravel filling, sometimes at the rate of from 60,000 to 70,000 cubic yards a month. At the beginning of the work the gravel was loaded at Readville pit by steam shovel and hauled in trains of dump cars, but after about 200,000 cubic yards had been taken from Readville pit the steam shovel was moved to Sharon pit, a large pit on the main line, about 13 miles from Forest Hills. Because of the long haul on the main line, the use of dump cars was discontinued and gondola cars substituted. These were large cars, holding 25 cubic yards each, equipped with air brakes and constructed with hinged sides, which




FIG. 9. FOREST HILLS SUBWAY.

when raised allowed about one-third of the load to fall out, the other two-thirds having to be shoveled out; 20 cars made up a train.

No filling could be deposited on Section 1 until after the wall was built, but on Section 2 there were long stretches where no walls were required and where the fill could be made at once. South of Washington street, considerable filling was put under the main tracks, the regular trains continuing to use the tracks, the tracks being raised over 8 feet in this way. As fast as the filling was brought up to the tops of the abutments on Section 2 the filling track was carried across the streets on temporary trestles and connected with the construction track on Section 1. The low construction track on Section 2 was then taken up and the embankment

widened out, and when regular traffic was transferred to the two westerly high tracks a filling track had been laid on the embankment east of the main tracks for the whole length of Section 2 north of Forest Hills. Tracks were laid on the trestles as soon as completed, and as much filling placed as could be put in without obstructing the low main tracks.

As fast as the bridges were received they were erected in place by the bridge contractor's men.

Most of the girder bridges were half-through bridges, and when in place the tops of the girders came but very little, if any, above the tops of the rails. Where station platforms were carried




FIG. 10. WALK HILL STREET STEEL ARCH, FOREST HILLS.

over the bridges, fence girders were placed on the outside of the platforms. All of the steel bridges had tight ballast floors. The entire bridge was painted with two coats of red lead; the upper floor surface was then swabbed with hot asphalt; screened gravel was placed around the drainage holes in both ends of the troughs and the rest of the troughs filled with mastic ballast, consisting of screened gravel and enough asphalt to make the stones stick together, but not to fill the voids between the stones. Small screened gravel ballast was then put on the floor and the ties bedded in it. Under the drainage holes were suspended copper gutters, leading either to pipes passing through the parapets into the drains to the sewers, or to down spouts emptying into the street gutter. The

bridges were finally painted one coat of the standard color for track bridges.

The Walk Hill street steel arch (Fig. 10) is a two-hinged arch built square. The Tremont street arch (Fig. 11) is a three-hinged arch on quite a skew. Fig. 11 shows also the Roxbury driveway plate girder bridge.

The two westerly tracks were laid with 100-pound steel rails, and the Forest Hills junction was controlled from a temporary interlocking tower.

Sunday, August 23, 1896, thirteen and one-half months after the beginning of the main work, all regular trains were transferred




FIG. 11. TREMONT STREET STEEL ARCH AND DRIVEWAY BRIDGE, ROXBURY.

to the two new high tracks. As soon as this transfer was made one of the old low main tracks was taken up and the other used as the new construction track. Derricks were erected and work at once begun on the easterly walls.

South of Tremont street, Stony Brook ran close to the railroad for a distance of about 600 feet, its westerly channel wall, about 10 feet high, sustaining the easterly side of the railroad. This wall was taken down and the new retaining wall started at the bed of the brook.

Center street was graded to its full width, the street car tracks laid and the surface of the street finished.

Lamartine street freight yard was completed and opened to the public.

After the retaining wall on Section 1 was completed, the construction track was taken up and the street abutments constructed, the stone being unloaded from the main tracks at night. On Section 2 the construction track was east of the retaining wall, and work on both the walls and abutments could go on at the same time.

At Roxbury the old station was raised and a stone basement constructed underneath. The other easterly stations were built similar to the ones on the westerly side, and station grounds graded and surfaced.

The Forest Hills freight yard was raised to connect with the main tracks. The filling was widened out from the main tracks, the low tracks being used for storage until the filling reached them, when they were taken up and relaid on the new fill. When the last low track was taken up, the track leading into the yard was also taken up and the gap under the main tracks filled in with gravel.

The filling on Section 2 was dumped from the filling track at the high grade in the day time. The filling on Section 1 was done largely from the main tracks at night. The greater part of this night filling was done in winter, and the cold was so great that the Italians who had been doing most of the grading work could not endure it, and a gang of Canadians was secured to finish this work.

South of Tremont street, filling was put in at night, until a siding could be laid from the main track running onto the new fill, down a steep grade to the old construction track and along to New Heath street. After this had been done gravel trains were backed onto this track and the filling then put in by day. The laying of the permanent easterly tracks followed closely the completion of the embankments.

The two westerly high tracks were carried on trestle over Tremont street and Roxbury driveway, the bridges not having been received at the time trains were transferred to these tracks. After the bridge masonry had been completed and the bridge material received, the bridge for the westerly tracks at Roxbury driveway was erected in the place for the easterly tracks and the ballast and ties put on, and one Sunday night, after the last train had passed, the two westerly tracks over the driveway were taken up, the trestle removed, the new bridge slid over into its proper position and the tracks connected up again before the first morning train was due. The bridge for the easterly tracks was then erected and the roadway underneath surfaced. Tremont street travel was then

diverted through the driveway and the easterly half of the Tremont street arch erected.

May 2, 1897, the regular traffic was transferred to the two easterly high tracks and the westerly half of Tremont street arch was erected. At the same time the two westerly tracks on the trestles were taken up, the trestle ties, stringers, guard timbers and caps taken out and removed to the supply yards, and the tracks relaid, ballasted and surfaced.

June 21, 1897, almost exactly two years after the main work was begun, the four tracks were put into permanent service and the abolition of the grade crossings on the main line in the city of Boston had been accomplished.

The following quantities of masonry and other work were constructed: 123,000 cubic yards stone masonry, 21,000 cubic yards concrete masonry, nearly 8000 cubic yards of brick masonry, eight new brick and stone stations and two old stations raised and enlarged, nearly a mile of temporary double-track trestle and a half mile of single-track trestle, 13 four-track and two five-track steel bridges, about 19 miles of main track, four miles of freight tracks and about eight miles of temporary or filling tracks, and 1,200,000 cubic yards of earth embankment. About 31 acres of land were taken or purchased in connection with the work. The total cost of the work was \$4,041,514.

Only one accident happened to a regular train during the whole work, and that was a very slight one, a pane of glass being broken in one of the local trains and one passenger cut slightly by the flying glass.

The plans accompanying the commissioners' reports were prepared under the direction of Mr. S. L. Minot and Mr. J. W. Rollins, Jr., but the execution of the work, from the beginning nearly to its close, was under the personal supervision and charge of Mr. C. M. Ingersoll, Jr., assistant engineer of construction. January 1, 1897, when the work was nearing completion, Mr. J. W. Rollins, Jr., took charge and completed it, Mr. Ingersoll leaving to assume the duties of assistant to the president of the railroad and later to become chief engineer, which position he now holds. All the filling and train work was done under the direction of the roadmaster, Mr. R. P. Collins, and his assistant, Mr. Hugh Steele.

FOURTH TRACK CONSTRUCTION, MT. HOPE TO READVILLE.

During the progress of the abolition of these main line crossings, an additional track was laid from Mt. Hope to Readville, thereby making the four-track service continuous from Boston to

Readville. A new station was built at Mt. Hope; the stations at Clarendon Hills, Hazelwood and Hyde Park were moved back and new station platforms constructed; the Stony Branch culvert, south of Clarendon Hills, extended to carry the fourth track, and a new bridge erected at Canterbury street spanning the four tracks.

In 1896 acts of the legislature were passed providing for the abolition of all grade crossings, both public and private, on the West Roxbury and Dedham branches, and of the grade crossings of Milton street and the New England Railroad at Readville; also providing for the construction of a new highway over the Providence division between Hyde Park and Readville stations; the crossings to be abolished and the new street constructed in the manner prescribed by commissioners to be appointed by the Superior Court. S. N. Aldrich, E. B. Bishop and H. C. Southworth, the same commissioners who prescribed the manner of abolishing the main line crossings in Boston, were appointed. Their report covering the crossings on the West Roxbury branch was confirmed by the court April 24, 1897, and their report covering the crossings on the Dedham branch and at Readville was confirmed May 7, 1897.

Before the work was begun the New England Railroad was leased to the New York, New Haven and Hartford Railroad Company, becoming the Midland division of the latter road.

December 27, 1897, contracts were made with Dwight & Daly for the work on the Dedham and West Roxbury branches, except the Milton street crossing, and with J. J. O'Brien & Co. for the work at Readville, and work was at once started.

WORK ON THE WEST ROXBURY BRANCH.

The three highway grade crossings abolished on the West Roxbury branch were South street at Roslindale, La Grange street at West Roxbury and Spring street at Spring street station. Several private crossings were also abolished.

South street was discontinued where it crossed the railroad and a new street, 60 feet wide, laid out from Brandon street to a point on South street a little south of South Walter street, crossing under the railroad tracks about 430 feet south of the old South street crossing. The railroad was raised at the new street 5 feet and carried over it by a plate girder bridge supported upon abutments and steel columns at the curb lines of the sidewalks. North from

the bridge the railroad ran on a descending grade of 1 per cent. for about 4000 feet, and south from the bridge on an ascending grade of 0.4 per cent. At the old South street crossing a subway for foot travel was constructed. The railroad was carried over this subway by a steel solid-trough flooring, resting upon abutments of rubble masonry faced with white enameled brick.

The old Roslindale station was raised to the new grade of the tracks and a new station constructed on the opposite side, and station grounds on each side were graded and surfaced.

La Grange street, at West Roxbury, was widened 10 feet on the north side to 60 feet, and depressed at the railroad about 14 feet. Spring street was widened 20 feet on the north side to 60 feet by the decree, and before much grading had been done the street was again widened by the city to 80 feet. The street was constructed at the latter width. It was depressed at the railroad about 15 feet. La Grange and Spring streets had maximum grades on the approaches of 4 per cent. The railroad was raised at La Grange street 4 feet, and at Spring street 3 feet, and carried over these streets by two span plate girder bridges, supported upon abutments and middle stone piers. The bridge carrying the railroad over the private way called Cass street was replaced by a new plate girder bridge, resting upon new abutments spaced 33 feet apart. The abutments at Spring street were built upon broad foundations of concrete, resting directly upon quicksand. At Cass street a pile foundation was put in.

The new street at Roslindale, La Grange street and Spring street, and the connecting streets, changed to meet the new grade of these streets, were surfaced with granite block gutters and macadam roadways. Considerable difficulty was experienced in macadamizing Spring street, fully double the contemplated amount of broken stone being put upon the subgrade, which was quicksand, in order to make a satisfactory pavement.

A new station was built on the westerly side at West Roxbury and the old easterly station raised up to the new grade. At Spring street the two main tracks were spread apart and an island station, so-called, was constructed between them, with a long platform connecting by stone steps with Spring street and Cass street. A freight yard was constructed on the westerly side of the railroad south of Cass street. The railroad, where changed in grade, was laid with two new 100-pound steel rail tracks.

As a substitute for all the private crossings on the West Roxbury branch between Spring street and Dedham a 30-foot street was constructed on the westerly side of the railroad, extending

from Belle avenue to Washington street in Dedham. This street was carried over Mother Brook by a wooden truss bridge resting on piles.

WORK ON THE DEDHAM BRANCH.

The Dedham branch, which was a double-track branch, was lowered at Walnut street 5 feet, and at Mt. Vernon street about 6 feet. At East street it was raised about 2 feet. The total length of change of grade on the branch was 6300 feet. Between Walnut street and Mt. Vernon street the railroad was in quite a deep rock cut, and in lowering the tracks about 6 feet it was necessary not only to take out the rock under the tracks, but also to widen out the slopes. One track was lowered at a time, the other track being used as a single track between Dedham and Readville. The excavated material was hauled away in small dump cars by a small narrow-gauge locomotive, the average haul to the dump being about three-quarters of a mile. Walnut street freight yard was lowered to meet the new grade of the branch and the tracks relaid. Where changed in grade, the branch was constructed with two new 100-pound steel rail tracks.

A heavy retaining wall, about 700 feet long, was built on the southerly side of the branch between Walnut Hill and Stone Haven stations.

Walnut street was raised 15 feet, and Mt. Vernon street 14 feet, and they were carried over the branch by plate girder bridges with plank floors. The abutments were built plumb, with cut face stone and rubble backing laid solid in cement mortar, and the wings, where carried out to retain the embankment slopes, were battered $\frac{1}{2}$ inch to 1 foot, the faces at the heights of the abutment bridge seats being in line with the faces of the parapets, and the lines of the wings making angles of about 17° with the lines of the abutments.

East street was depressed at the railroad 14 feet, and the railroad was carried over it by a four-track plate girder bridge spanning the whole width of the street. The abutments and wings were built plumb on the face.

The street approaches to all the bridges were surfaced with cobblestone gutters, macadam roadways and tar concrete sidewalks, the maximum grade on them being 5 per cent.

New wooden island stations were built between the two main tracks at Walnut Hill and Stone Haven, the tracks being spread to permit it, and a wooden stairway was constructed at Walnut Hill connecting with the Walnut street bridge, and one at Stone Haven connecting with Mt. Vernon street bridge.

THE WORK AT READVILLE IN HYDE PARK.

Fig. 12 is a general plan of the work at Readville. Near Readville station, in the town of Hyde Park, Milton street crossed at grade the Midland division (formerly the New England Railroad); about 60 feet further west it crossed above the Providence division main line, and about 360 feet west of this latter place it



FIG. 13. HYDE PARK AVENUE GROINED ARCH, READVILLE.

crossed at grade the Dedham branch. About 500 feet east of the Midland division crossing, Milton street was crossed at right angles by Hyde Park avenue, which ran northerly about 700 feet, then curved to the west and passed under the Midland division, then curved to the north and ran northerly toward Hyde Park station. Sprague street joined Milton street about midway between the

bridge over the Providence division and the Dedham branch grade crossing, and ran southerly, passing under the Midland division. Regent street left Milton street just west of the Dedham branch grade crossing and ran northerly nearly parallel with the Providence division main line. The Midland division passed over the Providence division about 80 feet south of Milton street.

This combination of grade crossings, under crossings and over crossings made it a very expensive matter to abolish the two grade crossings of Milton street. Hyde Park avenue was discontinued where it crossed the Midland division and relocated, beginning at its junction with Milton street and running northwesterly 60 feet wide, passing under the Midland division and curving to the right and then running northeasterly, passing over the electric track connection bridge to the old location of Hyde Park avenue.

Milton street was discontinued from Prescott street to Regent street and relocated, beginning at the new location of Hyde Park avenue about 350 feet north of where it passed under the Midland division and running westerly 60 feet wide, passing over the Providence division main line, the Midland division connection tracks and the Dedham branch tracks, then turning and running southwesterly 50 feet wide to the old junction of Milton and Regent streets.

Sprague street was relocated, beginning at the old junction of Milton and Regent streets and running southwesterly 50 feet wide, passing above the Dedham branch and the Midland division to its old location.

The Midland division was carried over Hyde Park avenue by a stone arch of 78 feet span and 165 feet length and a clear head room at the center of 15 feet. Nine tracks were carried over the arch. The foundation was of piles, driven in quicksand and cut off about $11\frac{1}{2}$ feet below the street grade. The spring of the arch was 8 inches above the street grade and 9 feet back from the street line, thus giving an economical distribution of masonry with a maximum resistance of foundation. The ring stones were 2 feet 6 inches deep, except on the face, where they were made deeper for better architectural effect.

The upper surface of the arch and backing was water-proofed with four thicknesses of tarred paper thoroughly mopped with tar and covered with 3 inches of tar concrete. Passing on a skew through the southerly haunch of the arch, there were constructed two arched stairway openings, 8 feet wide, leading up to platforms between the Midland division passenger tracks. Particular care was required in designing the groined arch stones for these stair-

way openings. Fig. 13 shows the groined key at one of the openings being set, and Fig. 14 gives a more general view of the opening and of the partially-constructed arch. The westerly face of the arch was constructed at an angle of $77^{\circ} 52'$, and the easterly face at an angle of 61° with the axis of the arch, with necessary spandrel face walls capped with a dressed coping.

Milton street was carried over the Providence division by a two-span plate girder bridge, supported upon abutments and an intermediate stone pier. The easterly span was 96 feet and the westerly one 104 feet. The easterly and part of the westerly spans




FIG. 14. HYDE PARK AVENUE ARCH, UNDER CONSTRUCTION, READVILLE.

were on a grade of 5 per cent., the rest of the westerly span being level, and there were vertical angles in the girders about 12 feet west of the pier, a somewhat unusual construction. The abutments were plumb on the face, the wings battered $\frac{1}{2}$ inch to a foot and constructed at an angle of $26^{\circ} 34'$ with the line of the abutments. The pier was battered on all sides. The bridge was at right angles, and the masonry was typical of the masonry for overhead bridges.

Sprague street was carried over the Dedham branch and the Midland division by two spans of a through pin-connected steel truss bridge, each span being 223 feet long, supported upon abutments and a middle pier similar to the masonry at Milton street,

but on a skew and considerably higher, especially the pier, which was 50 feet high from the bottom of the foundation to the top of the bridge seat. The southerly span was constructed on a grade of $2\frac{1}{4}$ per cent., and the northerly span on a grade of 5 per cent.

A plate girder bridge of short span carried Hyde Park avenue over the proposed electric track connection between the two divisions.

The street approaches to these overhead bridges were on high earth embankments, the earth being brought from Sharon on cars, dumped near the work and hauled into place in carts; and they were all finished with granite block gutters and macadam roadways. The total length of streets resurfaced at Readville was 5500 feet, a little over one mile.

The Midland division was carried over the Providence division by a new five-track through pin-connected steel truss bridge of 129 feet span, with necessary masonry abutments.

A new large two-story brick station, with necessary covered platforms, was built near the crossing of the Midland and Providence divisions, the lower story being at the level of the Providence division main tracks and the upper story at the level of the Midland division tracks. A long subway, passing under nine tracks on the Providence division, was constructed with abutments of rubble masonry faced with enamel brick, with necessary stone stairways leading to covered platforms between the passenger tracks, and with a covering of solid steel troughs. Most of its length, the subway was built on a grade of 4.3 per cent., and at the lowest place the floor was about $5\frac{1}{4}$ feet below the ground water level. To make this water-tight, a water-proofing of ten thicknesses of thoroughly mopped tar paper, protected by a sufficient thickness of concrete on each side, was carried under the whole subway and brought up on the sides and ends to meet the water-proofing put on top to shed rain water, etc. To make doubly sure of keeping this subway dry, a drain was laid from the subway to an 18-inch drain pipe which was laid down to the Neponset River.

Large and convenient station grounds on both sides of the Providence division were graded and surfaced.

The Midland division was raised at Hyde Park avenue 3 feet, and depressed at Sprague street about $1\frac{1}{2}$ feet, it being changed in grade for a length of 5000 feet. Five steel tracks were laid where the grade was thus changed. On the Providence division main line, two additional tracks were laid, making four in all, from a point about 800 feet north of the Readville station, where the four tracks at that time terminated, to a point about a mile south of it,







FIG. 1.
NEW YORK NEW HAVEN & HARTFORD RAILROAD. 490
MAP OF THE BOSTON READVILLE
AND DEDHAM CIRCUIT.

FIG 3.
PLAN AND PROFILE OF THE
ELIMINATION OF GRADE CROSSINGS
ON THE
N.Y.N.H.&H.R.R. PROVIDENCE DIVISION
IN THE
CITY OF BOSTON










FIG 12.

RAILROAD & R.R. PROJ'D

TRACKS AND CROSSINGS
AT READVILLE AND VICINITY

SECTION FOR 50'

the line and grade remaining unchanged. Two new passenger connection tracks were laid from a point on the Providence division about 1800 feet north of the Readville station to a point on the Midland division under Sprague street bridge. The Dedham branch was changed in alignment, and two new tracks laid so as to pass under the new Milton street and Sprague street bridges. The old freight yard on the Providence division was abandoned to make way for the new passenger tracks, and a new freight yard constructed north of Regent street. Large interlocking towers, one on each division, were constructed for the safe handling of switches, signals, etc. A freight connection and transfer yard between the two divisions were constructed south of the new station.

About half-way between Readville and Hyde Park stations, the new street, 40 feet wide, was constructed, passing over the Providence division and the new freight yard by a two-span plate girder bridge, spanning fourteen tracks. One span was 114 feet, and the other 94 feet. The masonry was similar to that at Milton street. Approaches to this bridge, 600 feet long on the easterly side and 1100 feet long on the westerly side, were constructed with cobblestone gutters and macadam roadways. A brick arch of 20-foot span, with stone abutments, was constructed under the westerly approach to allow access from the railroad to Mother Brook. The exposed ends of this arch were finished with granite ring stone and spandrel face walls. This westerly street approach was carried over Mother Brook by a plate girder bridge supported upon masonry abutments.

About 24 acres of land were taken or purchased in connection with the abolition of the grade crossings on the Dedham and West Roxbury branches and at Readville.

The final estimates of work done by the contractors on this work were submitted in February and April of 1899, about fifteen months after the beginning of the work. The cost of this work was \$2,020,894, making a total cost for abolishing all the grade crossings on the Providence division between Boston and Dedham \$6,062,408.

All the work on the West Roxbury and Dedham branches and at Readville was done under the personal supervision of Mr. George R. Hardy, assistant engineer of construction.

The chief engineer, during the entire construction of the work from Boston to Dedham, was Mr. F. S. Curtis, who is now the fourth vice-president of the railroad company.

THE SEWERAGE OF NEW ORLEANS.

BY W. T. CROTTS, MEMBER LOUISIANA ENGINEERING SOCIETY.

[Read before the Society, ——*]

THAT a city having attained the proportions of a metropolis should be entirely without one of the most necessary accompaniments of sanitation and municipal progress in this progressive age must be a source of surprise to other communities. That New Orleans has been sadly derelict in this respect is, however, only too true, and the causes thereof are perhaps not hard to find. Much is doubtless due to the character and influence of its earlier citizens, reflecting the conservative spirit displayed toward many municipal improvements, and some to the cosmopolitan character of our population; but the main and controlling factor was the deep-rooted conviction, so fondly cherished by many and not yet thoroughly eradicated from the minds of all, that the successful construction of any underground structure, extending to any depth, was an impossibility and foredoomed to failure. The soil was so much worse and the conditions so entirely different from those of any other community that this belief came to be with many a matter of local pride, and could not be relinquished without a tinge of regret and doubt.

The first recorded progressive step toward sanitary improvement came in the form of a suggestion of underground sewers from Dr. Barton, in 1850. His appeal, however, seemed to have awakened no response. The horrors of the epidemics of 1853 aroused the citizens apparently to the absolute necessity of effective measures to protect them from a recurrence of such calamities as had visited them in the past, finding their culmination in the year just closed. A sanitary commission was appointed to consider the adaptability of a sewerage system to the conditions existing in New Orleans, and the inauguration of a system of quarantine. Quarantine was established, but sewerage was again relegated to oblivion until the breath of pestilence once more swept over the city and left its inhabitants prostrate and discouraged, but still undaunted.

After the yellow fever epidemic of 1878 the desire for proper sanitary measures became stronger. There appeared, however, the great obstacle of the financial inability to meet the obligations necessary to secure the desired improvements, and the question of undertaking and operating sewerage and drainage by private capital was agitated. The Legislature passed an act giving to municipalities

*Manuscript received October 23, 1901.—Secretary, Ass'n of Eng. Socs.

the authority to grant the necessary franchises and rights to corporations or individuals to undertake these functions. Under the authority of this act, the City Council, in April, 1881, after much discussion and many protests, entered into a contract with the New Orleans Drainage and Sewerage Company for the performance of certain drainage work and the establishment of a sewerage system, the compensation for the latter to be laid upon the property owners or tenants connected therewith. Under the terms of this franchise, the territory from Louisiana avenue to Enghein street and between the river and Rampart street from Enghein street and Washington avenue, and the river and Carondelet street from Washington to Louisiana avenue, was to be sewered within five years, and the system thereafter extended into other portions of the city.

Under this grant a plan was drawn up embracing a circular sewer 6 feet in diameter, lying along Rampart street from Esplanade to Washington avenues, at an average depth of about 13 feet below the surface, and having so slight a fall as to be practically flat. Into this main sewer were to enter sewers draining the territory prescribed in the contract. At or near the corner of Esplanade avenue and Rampart street a pumping station with a capacity of 30,000,000 gallons in twenty-four hours was to be located, discharging the sewage into the river near the foot of Esplanade avenue and at a safe distance from the shore. Owing to dissensions in the company, this important work was never undertaken, and the opportunity for its early construction was lost.

Again, in 1892, private enterprise sought the privilege of sewerage the city, and on March 22 of that year the City Council passed an ordinance granting such a franchise, which was transferred to a corporation organized under the name of the New Orleans Sewerage Company. This was practically a renewal of the franchise of 1881, excepting that the limits were extended in the rear to Claiborne street between Lafayette avenue and the New Navigation Canal. As usual with enterprises of this magnitude and importance, many plans and ideas were suggested for the proper solution of the problem confronting the company, and a brief reference to a few of these may not be without interest.

First, by request, there was submitted a design for the sewerage of this area by what is commonly designated the Shone system. As is doubtless well known to all, this involves no departure from ordinary practice in sewerage design, so far as local collection of sewage is concerned. The territory is divided into smaller local drainage areas, each with a central well or ejector station, in which the sewage collects, and from which it is automatically discharged

through force mains into its outlet by compressed air. This plan, while presenting considerable economy of first cost as applied to the five-year limit, when extended throughout the entire city failed to maintain this advantage. This fact, taken in connection with the great amount of perishable material and the increased cost of operation, resulted in the ultimate rejection of the plan.

What may be termed the siphon scheme was also presented and seriously urged for adoption. This plan involved the collection of the sewage in local wells, and its transportation from them to a central pumping station through iron siphons of suitable size, laid upon a hydraulic grade of 1 : 500, the final receiving well being some 40 feet in depth. The numerous obstacles to its safe and certain operation, in connection with the many complications that would arise in the extension of this plan beyond the five-year limit, were insuperable obstacles to its consideration.

A modification of the siphon plan consisted in the laying of a steel pipe of suitable size below the bottom of the lowest sewer. The sewage was to be collected into local wells and delivered into this steel pipe through air-tight gates or valves. This main was equivalent to a large and lengthy suction pipe, with numerous branches extending to the various local wells, and presented the same serious objections as the siphon project.

Nor must we omit, in passing, the scheme whereby the sewage, after collection, was to be discharged into the Mississippi River at a velocity of 1500 feet a second. No plan, however, was presented for the protection of the shipping in the harbor in the event that any vessel should be so unfortunate as to get within range of this discharge.

In the plan finally adopted the sewage was gathered into a main sewer in the rear and delivered to a pumping station located on the site of the old Parish Prison, at the corner of Marais and Orleans streets, with an outlet into the river at the foot of Esplanade avenue. This main sewer, while designed sufficiently large to handle all the sewage up to and including Carrollton, would still, for many years to come, have but a small proportion of its ultimate flow to care for, and was therefore made oval in shape. The system was to have been mainly flushed from a surrounding flushing main, and from such flush tanks as were necessary where the flush main was not available. Under this plan, after much delay and many discouragements, work was finally started. Thirty-six hundred feet of main sewer and several miles of pipe sewers were constructed before financial disaster overtook the enterprise, and the prospect of immediate sewerage again vanished. But the

leaven was working, and, with the growing sentiment in favor of sewerage, the demand that this and other public improvements should be under municipal control also increased. Then began that magnificent popular movement, which is recent history, and which resulted in the means being devised whereby the city could construct and operate its own public works. Under the legislation resulting from this movement, sewerage plans have been formulated, and it is of these that this paper treats to-night.

Lake Pontchartrain



FIG. 1.

In the design of the sewerage system for this city no startling or novel departures have been employed or attempted. Well-known and accepted principles, such as have stood the test of years of practical use and operation, have been the basis, the interests at issue and the amounts involved being too large to trust to untried methods, however correct and adaptable in theory.

AREA COVERED.

The act creating the Sewerage and Water Board provides that contracts for construction should be so let as to cover the whole city at the same time, further defining the whole city to mean that

inhabited portion now divided into squares and lots, where the streets are open and in use as such, or whenever hereafter opened and in use. The plans as drawn, therefore, had in view the immediate sewerage of the built-up portions of the city, with extensions of the system to meet future growth. They embrace all the territory from the upper Protection levee to the Barracks, and from the river back to Metarie road, Gentilly road, Marigny avenue and Florida walk, and also Algiers, an area of 22.9 square miles. These plans embrace some 900 miles of sewers, of which about 400 miles are for immediate construction. In Fig. 1 the

TABLE I.
POPULATION PER ACRE IN AREAS OF GREATEST DENSITY IN
VARIOUS WARDS.

Ward.	Area Acres.	No. of Premises.	Premises per Acre.	5 PERSONS PER PREMISE.		AS SHOWN BY CENSUS.		
				Total Populat'n at 5 per Premise.	Populat'n per Acre	Populat'n per Prem- ise, whole Ward.	Total Populat'n.	Populat'n per Acre.
1	51.0	622	12.2	3110	61.0	4.72	2930	57.5
2	112.0	1050	9.4	5295	47.3	5.40	5718	51.0
3	63.0	802	14.2	4400	70.0	4.46	3978	63.1
4	63.0	757	12.0	3785	60.0	3.96	2968	47.6
5	93.0	1258	13.5	6200	67.6	5.52	6044	74.6
6	84.0	961	11.4	4805	57.2	5.20	5084	60.5
7	63.0	881	14.0	4495	70.0	5.13	4519	71.7
8	50.5	896	15.0	4480	75.3	4.71	4220	71.0
9	22.5	309	13.7	1545	68.7	6.14	1897	84.1
10	131.5	1044	12.5	8220	62.5	4.64	7628	58.0
11	116.0	1400	12.1	7000	60.3	4.71	6594	56.9
12	193.5	1556	8.0	7780	40.2	5.13	7982	41.9
13	68.0	628	9.2	3140	46.2	5.39	3384	49.8
14	45.0	201	4.5	1005	22.3	6.51	1368	20.2
15	48.0	368	7.7	1840	38.3	6.67	2454	51.1
16	20.0	102	5.1	510	25.5	5.66	577	28.8
17	42.5	234	5.5	1170	27.5	5.55	1200	30.5

area between the hatched line and the river represents the present inhabited area, which is to be sewerred immediately, and which covers 13.8 square miles; while that portion in the rear is not yet built up, but must be provided for in the general plan.

POPULATION.

After fixing the territory to be covered in the plan the next most necessary and essential factor was the determination of the population, both that existing at present and that to be provided for in the future; also the disposition and varying densities of such population in different portions of the city. A decade having elapsed since the last government census, it became necessary to turn to other sources of information. A count of all the premises

within the inhabited area was made from the insurance maps, showing a total of 56,423 within this territory. Assigning five persons to each, this gave an existing population of 282,115. The government census, taken the following month and promulgated some time thereafter, gave to the entire city a population of 287,104, or 5000 in excess of that which we estimated. The government census, however, covered the entire parish, including West End, Milneburg, etc., and the scattered houses outside the limits computed by us, and which would easily cover this difference. This estimate of 282,113 gave an average of 31.9 persons to each

TABLE II.
REDUCTION OF FLOW TO CUBIC FEET PER SECOND PER ACRE. TO
APPLY ONLY TO AREAS UNDER 200 ACRES.

Area.	Total Acres in Area.	Estimated Population per Acre.	HOUSE DRAINAGE PER ACRE.			Ground Water Cubic Feet per Second per Acre.	Total Cubic Feet per Second per Acre.
			Gallons in 12 Hours.	Cubic Feet in 12 Hours.	Cubic Feet per Second.		
A	642	50	4000	533.3	.012	.003	.015
B	1018	55	4400	586.7	.014	.003	.017
C	866	60	4800	640.0	.015	.003	.018
D	500	80	6400	853.3	.020	.003	.023
DI	501	115	9200	1226.7	.028	.003	.031
E	515	80	6400	853.3	.020	.003	.023
F	432	70	5600	746.7	.017	.003	.020
G	479	70	5600	746.7	.017	.003	.020
H	323	70	5600	747.7	.017	.003	.020
I	437	70	5600	746.7	.017	.003	.020
J	532	70	5600	746.7	.017	.003	.020
K	834	50	4000	533.3	.012	.003	.015
L	519	50	4000	533.3	.012	.003	.015
M	200	50	4000	533.3	.012	.003	.015
N	378	50	4000	533.3	.012	.003	.015
	8839						
O	5744	50	4000	533.3	.012	.003	.015

acre in the inhabited portions of the city, varying from 8.9 per acre in the sparsely built sections to 58.3 per acre in the older portions of the city immediately below Canal street. Taking the number of premises in each ward by actual count and the population as given by the census, it was found that the number of persons to each premise varied from 3.96 each in the Fourth Ward to 6.67 each in the Fifteenth Ward. With these figures upon which to base an estimate, the greatest density of population in each ward over a limited area was found to vary from 28.8 per acre in the Sixteenth Ward to 84.1 per acre in the Ninth Ward, as shown in Table I.

Having ascertained the present population, and taking into consideration the probable direction and density of future growth, the next problem was the determination of the future population

TABLE IV.

ACRES AND FLOW TRIBUTARY TO FRONT MAIN AND TRUNK SEWER AT VARIOUS POINTS; ALSO PROPORTION OF FLOW TO MAIN AND SIZE OF MAIN.

TRIBUTARY AT		Total Acres Tributary to Main.	Total Flow Due to Full Discharge, Cube Feet.	Percentage of Full Discharge Due to Enlarged Area	Cube Feet Reaching Main.	Size of Circular Sewer Running Half Full.		Size of Circular Sewer Running Full.	
Plum and Broadway	Acres Drained by Sub-Main.					Feet	Diameter	Feet	Diameter
State and Willow	1030	1030	15.45	00.83	12.82	3'	6"	3'	0"
Peters Ave. and Clara	425	1455	22.67	00.73	16.55	3	0	3	3
Valence and Clara	518	1973	31.48	02.50	19.07	4	3	5	6
Berlin and Clara, S. S.	484	2457	30.43	02.50	24.04	4	0	3	0
Marengo and Clara	275	2732	43.55	02.50	27.21	4	0	4	0
Louisiana Ave. and Clara	427	3150	50.81	02.50	31.75	5	0	4	3
Washington and Clara	382	3541	57.52	02.50	35.05	5	3	4	0
Jackson Ave. and Clara	371	3012	64.41	02.50	40.25	5	0	4	0
Felicity and Clara, S. S.	553	4405	74.57	02.50	46.60	5	0	5	0
Melchome and Clara	401	4860	83.41	02.50	52.13	6	0	5	3
Erato and Clara	333	5100	88.40	02.50	55.25	6	3	5	0
Callopie and Clara	302	5501	95.50	02.50	59.68	6	3	6	0
Lafayette and Clara	221	5532	96.12	02.50	60.77	6	3	6	0
Poydias and Clara, S. S.	52	5753	102.15	02.50	63.84	6	0	6	0
Petidine and Clara	45	5805	103.10	02.50	64.19	6	0	6	0
Gravier and Derbigny, S. S.	40	5850	104.00	02.50	65.05	6	0	6	0
Cleveland Ave. and Derbigny, S. S.	30	5920	105.49	02.50	65.55	6	0	6	0
Canal, U. S., and Derbigny	178	6068	110.55	02.50	68.06	6	0	6	0
Canal, L. S., and Derbigny	181	6270	114.51	02.50	71.70	7	0	6	0
Blenville and Derbigny, S. S.	24	6303	114.00	02.50	71.80	7	0	6	0
Toulouse and Derbigny	18	6321	115.35	02.50	72.00	7	0	6	0
St. Peter and Derbigny, S. S.	14	6302	116.22	02.50	72.05	7	0	6	0
St. Ann and Derbigny, R. S.	135	6497	119.32	02.50	74.57	7	0	6	0

strate the fact that this estimated flow was very close to that actually obtained, being the more valuable in that it extended through several rains.

Having then determined the population per acre, the sewage per capita and the amount of ground water, there remained to combine and tabulate these factors and reduce them to a convenient form for the rapid determination of the size of sewer required for different areas. Table II shows the manner in which the run-off per second per acre from each area was reached, and Table III shows the number of acres in each of the various sections of the city that are served by different-sized sewers.

This maximum run-off per acre, as given in Table II, is intended to apply only to areas under 200 acres. As the area increases the tendency to a more uniform flow becomes more marked. It is evident also that, from sections contiguous to the point of final disposal, the sewage will have been discharged before that from the more remote portions of the system reaches this territory. For all areas over 2000 acres it was decided to proportion the sewers for a daily discharge equivalent to a per capita consumption of 100 gallons, including ground water; and that for mains and sub-mains between these limits (200 and 2000 acres) they were to be proportioned for a gradually decreasing run-off as the area increased. Fig. 2 is a set of curves showing the estimated run-off in the various sections of the city between these limits. Table IV shows the method of determining the flow and size of main sewers.

SIZE, SHAPE, ETC.

The unit of the system is a pipe of 8 inches internal diameter, and constitutes about 87 per cent. of the total mileage of the system as designed. Increasing in size as the flow increases, the largest main finally attains a diameter of 6 feet for some distance before it reaches the pumping station. Sewers up to and including 24 inches are to be of vitrified stoneware pipe, and those above that size are to be of brick. All sewers are circular, the brick sewers having a rectangular base resting upon a plank foundation. As the sewers to be built at once serve practically the whole territory for which they are designed, and, while not receiving their ultimate amount of sewage, will still have a good initial flow, it was decided to make them circular from the point of view of both strength and economy. The standard design of brick sewers is shown in Fig. 3.

All sewers up to and including 18 inches are designed to run half full. Above 18 inches, they are designed to run 0.7 full, the

larger area served insuring a more nearly constant and uniform discharge.

DEPTHS OF SEWERS.

Before entering upon the design of the sewerage system, several factors had to be considered and determined. Foremost among these was the question of limiting depths of sewers. A certain initial depth was necessary, not only to enable house connections to be laid with proper grade and alignment, but to avoid obstructions where the struggle has been with all underground




FIG. 2




FIG. 3.

structures to keep as near the surface as possible. On the other hand, the peculiar character of the soil, saturated and plastic, where the deeper excavations threatened damage to streets, curbs and buildings, where every foot of depth meant a rapidly increasing cost, and yet a too shallow depth meant a too rapidly increasing number of dead ends and the consequent first cost and annual expense of innumerable flush tanks, the question of maximum depth assumed a position of prime importance. After carefully weighing the matter it was decided to adopt a minimum depth of 5 feet and a maximum depth for laterals of 6 feet and of sub-mains of 16 feet. For reasons of economy and efficiency, these limiting depths were not applied to main sewers.

GRADES AND VELOCITIES.

Where natural conditions contribute so little to grades, and where fall must be created by increased depths and expense, the question of minimum grades becomes of the utmost importance, and when a system of grades has been once established it must be rigorously adhered to. Economy of construction through economy of depth requires that the sewers be laid at the smallest possible inclination that will insure their efficiency and operation. Assuming the value of n , in the Kutter formula, as 0.011 for pipe sewers and 0.013 for brick sewers (because it is believed that these values can be secured by proper and careful construction), and the initial velocity of 2 feet per second, the conclusion was reached that a slope of 1 in 300 could be safely adopted for an 8-inch sewer, and the bulk of the system is designed to that grade.

Along with the disadvantages under which we labor, there are, however, some compensating features. In sewer design the usual experience is to have the steep grades and high velocities in the higher and smaller portions of the system, and the flat grades and slow velocities in the lower and larger portions, a condition leading to the formation of eddies and deposits from the sudden checking of the flow. Here, where grades and velocities are to be determined and established,—not by topography, but by calculation,—there is presented the possibility of ideal conditions in this respect. Starting with the initial velocity of 2 feet per second in the laterals, the velocity is gradually accelerated, increasing with the size of the sewer until it reaches 3.66 feet per second in the largest main. This point has been kept carefully in view throughout the entire design, and few if any instances will be found where there is any departure from it. Any material, therefore, which is capable of transportation in the smaller sewers will be pushed steadily along until it reaches the sand pit at the pumping station without being permitted to stop and form obstructions along its course.

In this connection it may not be uninteresting to trace the route and the time required for the transportation of sewage from the more remote portions of the city to the outfall. The longest distance to be traversed is from the corner of St. Charles and Carrollton avenues. Starting at this point, the sewage enters the sub-main at Hampson and Dante, travels along Dante to Cohn, Cohn to Lowerline, where it encounters the first pumping station and is lifted 7 feet; continuing thence along Cohn to Broadway, Broadway to Plum, across to Clara and it passes down Clara to Marengo, where it is once more picked up 7 feet by a second pumping station;

and continues along Clara to Gravier, Gravier to Derbigny and Derbigny to the main pumping station, having occupied in its subterranean journey three hours and ten minutes and traveled 6.4 miles at an average speed of 2.96 feet per second. It is not allowed to tarry here, however, but is immediately picked up by powerful pumps and forced into an iron main, from which it emerges twenty-one minutes later into the Mississippi River, three hours and thirty-one minutes after starting on its trip of 7.81 miles.

FLUSHING.

Recognizing the importance and necessity of flushing, provision has been made to flush every block of sewer. For daily flushing, reliance is placed in automatic flush tanks, located at the head of each sewer and discharging about 300 gallons in each twenty-four hours. This, however, must be supplemented by such hand flushing as may be necessary to keep the system in good order. This will be accomplished, first, by introducing, into each flush tank and at intervals into manholes along the laterals, a 2-inch pipe, which is connected directly with the water main and which can be opened full and allowed to run as long as desired. In the manholes on the larger pipe at intervals will be built simple devices which, when closed, will retain the sewage until a sufficient amount has collected to form an effective flush, when it will be released. In the main sewer flushing gates will be built at suitable distances apart, and a connection will also be made with the Navigation Canal, furnishing abundance of water for that purpose.

COLLECTION OF SEWAGE.

The alignment of the sewers and the topography of the city are so closely related that both will be considered under one head. From Esplanade avenue to the upper Protection levee, the city is practically built on radial lines, diverging toward the river with the hub far in the rear. Below Esplanade avenue there is a straight reach of river to the lower city line, the streets being laid off parallel and at right angles. The highest portion of the city is next to the river, sloping back, with a fall of as much as 15 feet in some cases to the rear, where a vast flat and level area stretches out.

In studying general methods of alignment for the collection of sewage, consideration was necessarily given to the several factors which would affect the final decision on this point. Due weight must be given to maintaining proper depths of sewers; the number of flush tanks must be kept down to a minimum, and full benefit received from those constructed; consideration has to be paid to

all existing structures, both above and below ground, to avoid conflict with them, and economy of construction and operation were quantities not to be disregarded. The fundamental basis upon




FIG. 4.

which the method for the lateral collection of sewage is based, and the dominant feature of the whole design, may be termed the rapid concentration of flow. Contrary to usual practice, the designing of the system starts at the head and works down, the use of minimum grades dictating this procedure. Selecting, at the head of the

sewer, two points as widely separated as is possible without ultimately exceeding the specified depth or making too long a distance for flush, each sewer is run alternately one block parallel with the river and one at right angles thereto, or zigzag, until a junction is effected with a sub main or main. In this design much attention is




FIG. 5

given to provision for enabling the flushing water to traverse the entire length of sewer, from the tank at its head, without the use of an excessive number of such structures. In the method of alignment adopted this is accomplished by constructing the manholes for the maintenance of distinct flow. Figs. 4 and 5 show two designs, in the first of which the sewers change their direction in

passing through the manhole, and in the second of which they pass through on a straight line. By this method the discharge from the flush tank remains in its individual line of sewer until it is emptied into the sub-main.

In the upper ends of the system, especially in that portion near the river front, all possible advantage is taken of such natural fall as exists to rapidly concentrate the sewage into sub-mains, when the smaller inclination of the large sewer serves to keep it more nearly parallel with the surface. In some cases two or more of these sub-mains unite into a still larger one before reaching the main sewer. By thus taking advantage of such slight surface slope as nature has kindly granted us, and this rapid concentration of the flow, the sewage is delivered to the main at a depth of from 10 to 13 feet, through a distance in some cases of as much as 9000 feet, without an intervening lift or pumping station. Different sections of the city naturally require different arrangements of the sub-mains without any departure from the general method of alignment and collection as outlined.

LATERAL TRANSPORTATION OF SEWAGE.

After the sewage has been collected into the sub-mains comes the question of its transportation to the main pumping stations or point of final disposal.

The peculiar contour of the city, extending for a great distance parallel with the river and of comparatively shallow depth, combined with the necessity for the discharge of the sewage below the central portion of the city and the distance it has to be transported from the upper sections, made this problem one of great importance, and the one that has given rise to the various projects which have been advanced. After a thorough and exhaustive consideration of the question in all its phases, the gravity main in the rear was selected as the most durable, efficient, certain and economical of operation. From the upper Protection levee to the Barracks stretches a line of sewers, distant in some cases 9000 feet from the river, containing in its course two main and two smaller pumping stations. Into this sewer discharges by gravity all the sewage between it and the river, and for some distance in the rear. Reaching from this main into the rear are other mains for the transportation of the sewage from those sections to the front main or pumping station direct. Through this main sewer, with never-ceasing flow, will run the sewage of the city to the point of final disposal, unhindered by the breakage of complicated machinery or the failure of perishable material.

The front main was located as far in the rear as entering sub-mains would permit, because of the greater area tributary to it by gravity. In the large uptown main also the farther in the rear the shorter will be the length to be built, the less the depth of sewer due to the lower elevation of the ground and the less disturbance to traffic and damage to streets, curbs and property in the unbuilt sections.

POINT OF DISPOSAL.

The sewage having been collected and transported to the pumping station, the point of its disposal must next be considered. A point must be selected where the sewage will not be caught up by returning eddies and carried upstream along the city's front. It must not lodge upon the shore below, or be of such quantity as to be offensive or dangerous in any way.

Taking up the latter point first, we find that few cities are so fortunately situated in this respect as New Orleans. With the waters of almost a continent sweeping by its front toward the Gulf, and no cities below dependent upon this stream for their water supply, the river presents itself at once as the safest, surest and speediest point of disposal. Assuming that a flow of 4 cubic feet per second for each 1000 of the population is necessary to sufficiently dilute the sewage as to render it inoffensive, the low water flow of the Mississippi River, based upon a discharge of 200,000 cubic feet per second, would suffice for the disposal of the sewage of a population of 50,000,000 without becoming offensive if uniformly mixed. At low water there passes each minute of the day a volume of water equal to twice the amount of sewage that will be discharged into the river at present in twenty-four hours. Looking at it still further, when the population has reached the 1,000,000 mark, with a daily discharge of 150,000,000 gallons of sewage, supposing the sewage to be 1 part solid and 99 parts water, there would be 1 part solid to 86,000 parts water, a not very alarming proportion.

Taking for granted, therefore, that the sewage will be so amply diluted as to be neither dangerous nor offensive, attention is next directed to the other points,—namely, a discharge at a point where it will be borne downstream and away from the city. To study this question satisfactorily and avoid the danger of any error, float observations were made in order to determine the lower end of the eddy and select a point whence the current does not impinge upon the bank, the proposed discharge being well out into the stream and at considerable depth below low water. Floats were started at various distances from the shore, and their course was

followed to the lower limits of the city. These observations indicated the foot of Spain street as the highest point where the sewage would be neither carried upstream nor into the bank and under the wharves below. We can assure ourselves that, when the sewage has entered the river, no further trace of it will be discoverable.


VENTILATION.



The lungs of a sewer are a very important part of its construction, for without ventilation a sewer cannot be maintained in a proper and sanitary condition. It is usual to supplement other means of ventilation by openings in the manhole covers. We cannot, however, avail ourselves of this method in the system under consideration. The large extent of unpaved streets would admit large quantities of dirt, requiring constant attention to keep the receptacles cleaned and the dirt from entering the sewers. The controlling reason, however, is the flooding of streets, which occurs with each hard shower. Each flooding over manholes would pour into the sewers, through these perforations, such quantities of water as to overload them perhaps for hours, beside bringing in large amounts of detritus to find lodgment in the sewer or manhole. To limit the operation of the sewers to the legitimate function of removing sewage only, it is evident that perforated covers must be omitted and reliance for ventilation placed upon house drains. As admission of air is necessary for the operation of the flush tank, both to insure its discharge and to prevent siphonage, special devices will be used, consisting of a pipe extending to the curb and terminating in an ornamental stand pipe.

UNDERGROUND OBSTRUCTIONS.

New Orleans apparently is no exception in the matter of underground structures and obstructions. Many of these have been laid entirely regardless of any city supervision or regulation, and where the constructing companies have so willed, and upon no well-defined plan except that of expediency. The aim of all has been apparently to seize the most available location and get as near the surface as possible, regardless of either alignment or grade, and to keep no records. While other cities have more and larger underground structures, few present more complications than New Orleans, where narrow streets cause crowding and lack of specific information renders location difficult. Much time was devoted to ascertaining the underground conditions existing in the conduit area.








SIPHONS.

Where there are so many and such large drainage canals, both existing and prospective, conflict in grades is inevitable, except by going to such a depth with sewers as would involve enormously increased cost and complications. Under such conditions, many siphons are rendered necessary, occurring mainly upon the pipe sewers near the head of the system. Owing to its great depth, one only occurs upon the uptown main sewer, and this only partially so, where the main sewer on Clara street crosses the Third street drainage canal, calling for a construction somewhat different from that of the ordinary siphons. In this case the invert of the sewer is about 21 inches below the bottom of the drainage canal. Two 18-inch pipes are to be laid on a straight line under the drainage canal, and these are of sufficient capacity to carry the minimum flow of the sewer. When the amount of sewage so increases as to overcharge these two pipes, it will overflow into two 21-inch pipes laid as a siphon immediately under the 18-inch pipe, the flow through these 21-inch pipes ceasing as the amount of sewage approaches the minimum. Suitable arrangements are provided for flushing the 21-inch pipes, the 18-inch pipe being self-cleansing. Advantage is also taken of the opportunity of overflowing into the drainage canal in the event of an accident or stoppage in the main sewer, the 36-inch connection shown being designed to accomplish this purpose. Figs. 6, 7 and 8 show the various details of this crossing.

Figs. 9, 10 and 11, representing the crossing of the St. Bernard sewer under the Broad street canal, show the general plan which will be employed on all siphons. The sewer is divided into two sewers having the same capacity as itself. During ordinary flow, the sewage will run through one of these only until it runs full, when it overflows into the second sewer. The sewage is thus confined to a smaller channel, with beneficial results, during light flow, and with a relief in case either should become obstructed. Automatic flush tanks will give each sewer a thorough flush daily.

PUMPING STATIONS.

But little has been or can be said in connection with the pumping stations, as the plans are not sufficiently advanced to justify a full description of them at this time. It may be said briefly, however, that the complete plan calls for a total of three main pumping stations and thirteen small pumping or lift stations, of which the three main and six small pumping stations will be included in present construction. The greater number of the latter, however,



should hardly be dignified by the appellation of pumping stations, as the quantity handled there is very small, varying from 400 to 800 gallons per minute at present to an ultimate capacity of from 1000




FIG. 10.

to 4500 gallons per minute. The pumps will be automatic in their action.

Of the three main pumping stations, one serves the whole of Algiers, ranging from a present capacity of 1500 gallons per minute to an ultimate discharge of 5000 gallons per minute. Another,

located at Jourdan avenue and Urquhart street, will serve all the territory between Lafayette avenue and the lower city line, the river and Florida walk with an estimated present capacity of 2,500 gallons and an ultimate capacity of 13,000 gallons per minute. The third and main pumping station serves all the territory above




FIG. 11.

Lafayette avenue, designed for a present discharge of 26,000 gallons per minute, or 37,400,000 gallons in twenty-four hours, while it will be called upon ultimately to care for a flow of 57,200 gallons per minute, or 82,000,000 gallons in twenty-four hours.

It is hardly necessary to go further into a description of this design. While we have waited long for sewerage, the wait has not

been without some compensating advantages. When sewerage starts with the early life of a municipality, and the direction and extent of growth are undetermined factors, the engineer must depend upon his judgment to determine these, and yet is stopped from proportioning and designing his system for a period too far advanced, not only from financial considerations, but from inability to determine what the future demands may be. The result is necessarily more or less of a patchwork, requiring correction here, relief mains elsewhere, as the necessity arises.

Here, where the city has already grown to metropolitan proportions, and its future limits and conditions can be defined with almost mathematical accuracy, it has been possible to outline a system of sewerage as a completed whole, the most widely separated sections in perfect harmony and proportion to a completed structure; where the construction for present needs is in conformity with a well-defined and perfected plan, to be filled out and completed as the growing needs of the city demands. On the vast importance of this great work to the health of the community, recognized by all, it is useless to enlarge; we can only hope for its early consummation, when our city will have completed one great stride in the march of progress.

Editors reprinting articles from this journal are requested to credit not only the JOURNAL, but also the Society before which such articles were read.

ASSOCIATION OF ENGINEERING SOCIETIES.

Organized 1881.

VOL. XXVII.

DECEMBER, 1901.

No. 6.

This Association is not responsible for the subject-matter contributed by any Society or for the statements or opinions of members of the Societies.

SMOKE ABATEMENT IN ST. LOUIS.

BY WILLIAM H. BRYAN, MEMBER OF THE ENGINEERS' CLUB OF ST. LOUIS.

[Read before the Club, October 2, 1901.*]

OF all the cities of America burning soft coal, none feels the blight of the omnipresent smoke cloud more than does this city of St. Louis. It has made our name a by-word and a reproach. The comment of the Chinese minister was only the last straw needed to fix our degradation upon us. Now that we are in a fair way to realize our ambitions for good streets and pure, clear water, we venture to indulge the hope that the "new St. Louis" may be smokeless.

The problem of smoke abatement is an old one, and has often been discussed before this Club. I can hope, therefore, to give you but little if anything interesting or novel. In view, however, of the recent passage of a new smoke ordinance, and the more recent appointment of inspectors looking to its enforcement, it would seem that the time is propitious to briefly review the history of the movement in this city, to recapitulate the methods which have been successful and to indicate what we may reasonably hope to accomplish.

This discussion is limited to St. Louis, where the conditions surrounding the problem are as unfavorable as they could possibly be. Remedies effective here, therefore, may be accepted as equally so elsewhere.

St. Louis is naturally a smoky city. It is a busy city. Its industries cover a large volume and a wide variety of product. In no small degree does St. Louis owe its growth and its prosperity

*Manuscript received November 11, 1901.—Secretary, Ass'n of Eng. Soc's.

to its manufactures, and all good citizens are heartily in favor of encouraging them in every legitimate way.

St. Louis has come to be an important manufacturing center largely because of its proximity to the soft coal beds of Southern Illinois, scarcely a dozen miles to the east. These are apparently inexhaustible and are easily mined, making it possible to deliver this fuel to the consumer in St. Louis at exceedingly low cost. These coals leave much to be desired in many respects. They run high in volatile matter, moisture and ash, and comparatively low in calorific value, which characteristics, particularly the first-named, are highly favorable to the making of smoke when burned in the ordinary manner. It is the duty of the engineer to point out how the smoke nuisance may be abated while continuing the use of the fuel which Providence has sent us in such abundance. We must be prepared to meet the argument that a smoky city means a busy and a prosperous city, and to show that the prevention of smoke by modern methods imposes no hardships on our industries.

The Engineers' Club of St. Louis has long taken the lead in this movement. A review of its proceedings shows that many papers and discussions have been presented. We have long had a standing Committee on Smoke, which has at intervals made reports to the Club. These reports, it is true, have not always been as encouraging as might have been desired. There was not, in the early days, as thorough an understanding of the problem, nor had inventions been so far perfected as to give us the wide choice of remedy we have to-day. Nevertheless, there was always some progress to report.

There has always been a strong sentiment that the emission of smoke should be controlled by ordinance, but it was felt that, for the time being at least, our energies could best be directed toward the education of the public and the development of improved furnaces. In 1888 Mr. Charles E. Jones and Mr. Charles F. White—both pioneers in the movement in this city, and both then members of this Club, the former of whom is still with us—made a report to the president of the City Council which indicated that the forms of smoke-abating apparatus then available for steam boilers cut down their capacity an average of 28 per cent., and that their use involved a slightly increased expenditure of fuel. There were then, as now, a number of boiler plants which were regularly worked beyond their normal or rated capacities, and for them there seemed to be no satisfactory way of controlling the smoke.

In the same year, 1888, Mr. Robert Moore read a paper before this Club on "Smoke Prevention," which was a most able presenta-

tion of the status of the art at that time. It was a complete *résumé* of the local situation, and will well repay study even at this day. It is interesting to note that the optimistic views then held by Mr. Moore were destined to be fully realized.

Substantial progress had been made in 1891, when Mayor Noonan appointed a committee of citizens to investigate local conditions and to report upon the entire situation, with a view of pointing out what could be done toward the reduction of the smoke nuisance, complaint against which had become widespread and persistent. This committee, composed of Col. E. D. Meier, Prof. W. B. Potter, Mr. Robt. E. McMath and Mr. Charles E. Jones, all members of this Club, and familiar with the problem, at once accepted the task, and set systematically to work on the collection of data. On March 8, 1892, the committee made to a meeting of citizens, held at the Mercantile Club, a report which was studious and exhaustive, and which stands to-day as our highest authority. It is indeed the source and fount of wisdom for those who would study this problem thoroughly as it relates to St. Louis.

This report was shortly afterward repeated before this Club, and discussed at some length, after which it was published for general distribution. The committee recommended the passage of two ordinances by the Municipal Assembly, drafts of which were attached to the report. The first of these declared smoke to be a nuisance, and provided for its suppression. The other established an expert commission, which was to canvass the city and determine what could be done. This commission was also to make tests of smoke-preventing devices and smokeless fuels.

These ordinances were promptly introduced into the Municipal Assembly and were passed, and approved by the Mayor in February, 1893. President Burnet, of the Board of Public Improvements, with the approval of Mayor Noonan, appointed on this commission Prof. W. B. Potter, Capt. Wm. McClellan and the author.

At about that time the Citizens' Smoke Abatement Association was formed, with the object of educating public sentiment and of providing lawyers and inspectors to co-operate with the city officials. There were also appointed about this time two city inspectors, whose duty it was to report violations of the ordinance to the president of the Board of Public Improvements, who then took the necessary steps toward prosecution in the courts when that step seemed necessary.

This expert commission immediately entered upon its work, beginning with a canvass of the smoke-making plants, with a view

of determining the conditions, if any, under which smoke could not be entirely prevented, such conditions being a valid defense against complaint. It was also to report whether or not there were practical methods of abating the smoke.

These reports were duly submitted, together with a code of rules governing tests to be made on alleged smokeless furnaces. In due course exhaustive tests and reports were made on the Boileau furnace, the Hawley down-draft furnace, the Standard furnace or automatic stoker, the Keene Economizer and the Haxton base burner. All these reports were approved by the Board of Public Improvements and published. The commission also took up smokeless fuels, and made a series of trials and investigations upon coke, which report, however, has never been published. Another investigation into smokeless fuels of the character of Pocahontas was begun, but was not completed, owing to lack of funds.

During this time much other effective work was being done, both by the Citizens' Association and by the commission, the latter appearing before many bodies and meetings with a view of awakening a favorable sentiment. The members of the commission worked in close harmony with the Citizens' Association, and gave their advice free of charge to all inquirers looking for the best means of abating the smoke.

In the consideration of the smoke problem we should not forget the very excellent paper by Mr. R. J. McCarty, of Kansas City, Mo., read before this Club in December, 1895.

In the meantime the Citizens' Association and the city inspectors were pushing their part of the work actively, the most serious offenders being taken in hand to begin with. Both before and after the expiration of the six months period before the ordinance went into effect the owners of smoke-making plants took up the question of abating the smoke, and large numbers of them put in effective appliances. The willingness and desire to comply with the ordinance were almost universal. Every effort was made to induce compliance by friendly means, and it was not until moral suasion had failed that prosecutions were undertaken in the courts.

As is always the case, however, there were a few obstructionists who fought the ordinance, with the result that the now famous Heitzberg case was carried to the Supreme Court of the State, where, in 1896, very much to our surprise, the ordinance was declared invalid on the ground that the municipal legislature had exceeded its authority in declaring smoke a nuisance *per se*. This made it necessary to prove in each case that the particular smoke complained of had caused special and individual damage. This

decision, while not in harmony with the views of many eminent legal authorities, as well as the decisions of many high courts, was nevertheless conclusive, and ended our efforts under the ordinance. In the revision of the municipal code in 1899 the smoke ordinance was rewritten to conform to the Supreme Court decision, but nothing has been done under it on account of the practical impossibility of proving damage in each case.

In spite, however, of the many difficulties encountered, and the final overthrow of the ordinance, great good had been accomplished. Disinterested and competent outside observers said that St. Louis had done more than any other city in this country, and that our smoke cloud had been reduced fully 75 per cent. The city records show also that at that time about 75 per cent. of the steam boilers in this city had been equipped with smoke-preventing devices. Many of these have been kept in operation, so that our condition is not so bad now as it was before the original ordinance went into effect, although there has, of course, been some increase in the number of plants. Is it not reasonable to expect that even better results may be secured under the new ordinance?

Early this year the Executive Committee of the Citizens' Smoke Abatement Association, in conference with many leading citizens, prepared the draft of an act, to be introduced into the State Legislature, giving to cities of over 100,000 inhabitants the right to declare smoke a nuisance and to provide for its regulation. Such a law was duly passed and approved. (See appendix A.) In accordance with its provisions the Municipal Assembly of this city has passed a new ordinance, which was approved by the Mayor on August 21 last. (Appendix B.) He has now appointed a chief inspector and four deputies to enforce the ordinance.

Having now brought the situation up to date, let us get an exact idea, if possible, as to what smoke is.

The constituents of all fuels may be classified as volatile matter, fixed carbon and ash. The ash is inert as regards smoke, except that when present in large quantities it greatly impedes the proper handling of the fires. The fixed carbon, with which we are familiar in the form of coke, is smokeless. The remaining constituent, the volatile matter, occurs in large percentages in our fuels, and is the one which causes the smoke.

When a fuel rich in volatile matter is charged into a furnace, the result is that the volatile matter is first set free as a gas, principally in the shape of hydrocarbons. Part of these are of what is known as the olefiant series. These are dissociated at a red heat, and part of the carbon is set free, which, if unconsumed,

passes off, forming the visible smoke. It is possible to burn this free carbon, but to do so there must be sufficient oxygen present and the temperature must be high. Failing of either of these conditions, the furnace will smoke. All successful smoke-abating devices work in the direction of meeting these two important requirements.

It was shown long ago, by careful experiments, that the amount of carbon in the densest smoke is very small,—from one-sixth to one-half of 1 per cent. by weight. It has, however, an immense coloring power. You may, therefore, stamp as false all those claims of furnaces which offer to save fuel by consuming the smoke. It has, however, been shown repeatedly that the best forms of smokeless furnaces have made marked savings in fuel, not because they burn the smoke, but because of the improved construction and better engineering details, which bring about more favorable furnace conditions and result in more nearly perfect combustion. The best furnaces make a fuel saving more than sufficient to pay the interest on their cost, as well as repairs and maintenance.

Broadly speaking, there are three methods for stopping the smoke: First, the shutting down of smoke-making plants; second, the use of smokeless fuels; third, the burning of our ordinary fuels smokelessly.

Heroic as it may seem, much good has already been accomplished by the actual shutting down of plants. A few years ago the city was dotted with small factories, each with its smoke-making boiler. To-day most of these are operated by electric motors, supplied from central stations located at a distance and provided with smoke-preventing apparatus. Many buildings get their entire service of light and power from the street mains, operating their boilers only for heating during the cold months. This practice may be expected to grow as electricity becomes cheaper and is distributed over wider areas. It does not take the eye of a prophet to look into the not distant future when our generating plants will be located across the river, or at the coal mines themselves.

Much has been done in smokeless fuels, and they are already in extensive use in this city, particularly for heating, in the residence districts and for many special operations. Indeed, it is not too much to ask of the average good citizen that he will go to some little extra expense if necessary to aid in beautifying the city. This, however, could not be expected under steam boilers, which are our largest smoke producers. I had hoped that the oil from the newly opened Texas fields could be introduced here at something like reasonable cost, but present rates appear to be prohibitive.

Oil has many advantages, however, which would warrant some increase in cost over coal. In addition to solving the smoke problem it greatly reduces the labor charge, can be handled and controlled much more easily and usually permits an increase in the working capacity of the plant. On the other hand, however, the elements of danger and of odor should not be overlooked.

As indicating in a general way what may be done under boilers with the various fuels coming to this market I have prepared the following table. No claim is made for the absolute accuracy of the figures, but they are believed to be fairly reliable, relatively at least. A glance is sufficient to show that the smokeless fuels are out of reach in cost, except as the use of powdered coal may be developed.

FUEL.	Cost, Dollars.	Calorific Value, Heat Units.	Efficiency, per Cent.	Equivalent Evaporation in Lbs. of Water.	Cost of Evaporating 1000 Lbs. of Water.
	Per 1000 Cubic Feet.	Per 1000 Cubic Feet.		Per 1000 Cubic Feet.	Cents.
Fuel Gas.....	0.10	240,000	80	198.8	50.30
	Per Ton of 2000 Lbs.	Per Lb.		Per Lb.	
Anthracite.....	6.75	14,000	75	10.87	31.05
Texas Oil	8.08	15,950	80	13.22	30.56
Coke.....	4.50	12,500	70	9.05	24.87
Pocahontas.....	4.75	13,300	72	9.90	24.00
Big Muddy.....	2.50	12,200	68	8.57	14.60
Mt. Olive, Lump...	1.60	11,200	65	7.53	10.62
Powdered Coal.....	1.25	10,000	80	8.28	7.55
Common Slack.....	0.90	10,000	60	6.20	7.25

The deliveries in this table are assumed to be on cars at consumer's switch. The oil weighs 7.43 pounds per gallon, and costs 3 cents per gallon, $2\frac{1}{2}$ cents of which is freight.

The oil companies hope to reduce the price in the near future to \$1 per barrel of 42 gallons, but even at that figure it would still fall short of competing with coal in the St. Louis market, even after an addition of 10 to 50 cents per ton for coal and ash handling is made.

The outlook for oil is much better if, instead of burning it under boilers, it be used in oil engines of the Diesel or other modern type, which consume about $\frac{3}{4}$ pound of oil per I. H. P. hour, at a cost of 0.30 of a cent. The ordinary Corliss engine uses about 4 pounds of Mount Olive coal per I. H. P. hour, costing 0.32 of a cent.

In the table above it is assumed that the powdered coal is made from ordinary slack, at an additional cost of 35 cents per ton for powdering. As a matter of fact, this charge would be offset by the saving in labor for coal and ash handling.

After all, however, our greatest hope for immediate relief must come from the successful burning of our ordinary fuels smokelessly. As the largest offenders are the steam boilers, they only will be discussed.

Devices without number have been invented for this purpose, but, unfortunately, most of them have failed to meet the exacting requirements of regular service. These failures have led some good citizens, who have spent money fruitlessly, to believe that the problem is beyond solution.

It should be remembered that the ordinary furnace, without a special device, can be so handled as to greatly reduce the smoke, providing, of course, it is not overworked. It is not absolutely necessary, therefore, to buy a patent furnace in order to control the smoke, nor, as will be shown later, will the purchase of improved apparatus of itself control the smoke or insure the owner against prosecution. A deep furnace, high bridge wall, ample grate surface and good draft are essential to a good smoke record. Such a furnace, if skillfully fired, will make no serious smoke when working up to, say, two-thirds of its rated capacity. By skillful firing is meant the charging of alternate doors with small and uniform quantities of fuel, particularly if the coking system of firing is used. The firing of consecutive doors, at long intervals, with large quantities of fuel and by the sprinkling method is responsible for a very large proportion of the present smoke nuisance.

If the furnace, however, is not well designed, or is overworked, no amount of skill or care will keep the smoke within bounds. In such cases resort must be had to special apparatus. Successful devices and processes may be divided into five general classes:

First. Steam jets. These are the simplest devices in use, and they can be put together by any engineer at small expense. Sometimes they are placed under the grates, discharging into the ash pit, but more usually they are above the grate, immediately over the fire doors, or in the side walls, discharging backward or across and slightly downward. The steam jet draws in air and discharges it at high velocity immediately above the fuel, where it meets the gases being given off by the disintegrating fuel.

Devices of this character have come into extensive use. They are reasonably effective in reducing smoke, but are not usually economical in fuel. The jets are often allowed to blow continuously, but it is better to turn them on at the time of firing and then shut them off in two or three minutes, after the fresh fuel has become ignited. In some devices this is done automatically, the act of opening the fire door turning on the jet, and clockwork or

dash-pot mechanism gradually closing it. The objections to such devices are their first cost, their complicated character and the necessity for some attention and adjustment for fluctuating service.

In Fig. 1 is shown a simple device of this type, using air preheated in ducts in the side and end walls of the furnace.




FIG. 1. STEAM JET DEVICE USING PREHEATED AIR.

Second. Cooking furnaces or firebrick arches. These come next in first cost, and are capable of giving almost perfect results in smoke abatement if properly designed and intelligently operated. The firebox is kept well away from the cooling effect of the heating surface, and can therefore be maintained at high temperature. Contracted checker work, or throat areas, insure a thorough mixture of air, which is often preheated. These are built in many

forms, many of which are capable of burning very **inferior** fuels. They are excellently adapted to plants where the service is reasonably uniform. The objections are that some forms require an increase of space, and the brickwork, if not properly constructed, may not be durable and repairs may be large. These objections, however, have been very largely remedied in the best types. There will usually be a material saving of fuel over the common setting if properly constructed and operated. Figs. 2 and 3 show successful forms of this type, the former representing the Reynolds and the latter the Kent furnace.

Third. Down-draft furnaces. These have proved very successful in many instances, and they have come into extensive use,




FIG. 2. FIREBRICK ARCH.

particularly where excessive demands for overwork are frequently made.

In the Hawley, one of the best-known forms (Fig. 4), there are two grates, one above the other. The upper grate is a row of water tubes, single or staggered, so connected as to form a part of the circulation system of the boiler. Grates of the ordinary pattern would not withstand the high temperatures. The tubes are inclined upward to the rear to insure rapid circulation. The space above the rear drum is closed off, and the gases must make their exit downward through the bed of fuel. Considerable partly burned fuel falls to the lower grate, where its combustion is completed under very favorable conditions. The two flames unite at the rear of the grates, forming a throat through which it is almost impossible for the particles of free carbon to pass unconsumed. Somewhat greater draft is usually required for this furnace than

for the common setting. Most of the air required for combustion enters through the doors above the upper grate only, a small amount being admitted under the lower grate. This furnace is independent of the skill or ignorance of the fireman to a greater degree than many others. The objections are its first cost and the fact that it is a part of the pressure system of the boiler. With bad water or careless or inefficient handling, there is great liability to tube and drum repairs. It usually effects a considerable saving in fuel.

Fourth. Automatic stokers, with which may be classed underfeed devices and chain grates. These have come into extensive




FIG. 3. WING WALL FURNACE.

use, particularly in large modern plants. While they are built in many forms, they all operate on the same principle,—that of feeding the coal automatically to the grates in continuous and regular amounts. Most of them are designed for the use of the finer grades of coal, such as nut, pea or slack. In many localities there is a surplus of this fuel, and its cost is low, but the increasing demand is raising the price and reducing the supply. Many recent stoker plants are provided with crushers to permit the use of the larger sizes of coal when necessary. When accompanied by coal handling and storage plants, the automatic stoker reduces the labor required in the fireroom, and this arrangement has been adopted in many large modern plants. The ability of the stoker to maintain practically uniform steam pressure and the fact that the air supply

is nearer the theoretical requirements are features which have contributed largely to its success.

The objections to automatic stokers are: First, their cost; second, the complication of parts and the necessity of repairs; third, the steam required to operate them. Under proper conditions there is a material saving both in fuel and labor. That the objections named are not serious is shown by the fact that their use is constantly increasing. The fuel to be burned should have expert study, however, before a device of this kind is selected, as they are not equally well adapted to all fuels. Some do not respond to fluctuating loads and to overwork as well as other types of furnaces.




FIG. 4. HAWLEY DOWN-DRAFT FURNACE.

Well-known and successful forms of stokers are shown in Figs. 5 and 6; the former represents the Roney stoker, and the latter the Green traveling link or chain grate.

Fifth. Powdered fuels. These have recently attracted much attention, having been employed successfully in rotary cement kilns, and more recently under boilers to a limited extent. Experiments along this line have been going on for some time in European countries with considerable success. In the most satisfactory devices the coal is reduced to an almost impalpable powder, and is then forced into the furnace under pressure, exactly as would be done with oil or gas. Among the greatest advantages of this fuel is the fact that it may be made of slack or mine waste, which can be had at very low cost. While the apparatus for burning the fuel is simple and inexpensive, the plant necessary for preparing the fuel is somewhat elaborate. As the fuel is liable to spontaneous combustion, it cannot be stored or handled in large quantities, but

should be used as fast as made. This would seem to call for a powdering plant at each point of use. I am of the opinion, nevertheless, that good results may be looked for in this direction in the not distant future.

Time will not permit a discussion of all the methods which have been proposed, but the foregoing covers in a general way the devices which have been more or less successful. The list would not be complete, however, without mentioning double-combustion furnaces, smoke-washing apparatus, complete combustion devices, mechanical draft, etc. Some of these have come into limited use with encouraging results, both alone and in combination with others of the above-named types.

The classes enumerated above are not always clear and distinct, as the types named are often found in combination. The fire-




FIG. 5. RONEY STOKER.

brick arch, for instance, is nearly always found in combination with the stoker, and often with the steam jet.

The fireboxes of locomotives and of steamboats require special treatment, but brick arches or steam and air jets have given good results. The best work is done when the two are combined. The arrangement is, of course, not economical in fuel, although it is not particularly wasteful. Some experiments have also been made with down-draft furnaces, with promise of success. Oil is admirably adapted for locomotives, and is already in extensive use where the cost will permit. It is urgently recommended that larger grate and heating surfaces be provided wherever possible.

I am unhesitatingly of the opinion that some one or more of these devices is applicable to every smoke-making boiler in St. Louis, and that, too, without hardship. The greatest care, however, must be exercised, first, in selecting the apparatus to be sure that it is adapted to the service; second, in seeing that it is care-

fully applied so as to be reliable and durable, and, third, that it is intelligently operated and maintained. The last is perhaps the most important of the three. No apparatus, however efficient, can be expected to run itself. Give it a chance; see that it is taken care of and kept in repair, and not abused.

It is to be hoped that the city of St. Louis will itself set a good example in this matter. Under the old ordinance work was handicapped by the fact that the water works plants, public build-




FIG. 6. THE GREEN TRAVELING LINK OR CHAIN GRATE.

ings and schoolhouses were very slow in stopping their smoke. It was hard to answer the argument offered in defense that the city itself was one of the greatest offenders.

I am in hopes that the World's Fair authorities will handle this problem in an effective manner. What could be more interesting and valuable than to show an immense power plant developing thousands upon thousands of horse power burning our own smoky fuels with perfectly clear stacks?

We can do this successfully, and with a wide choice of apparatus. In so doing we would give an object lesson to the world.

APPENDIX A.

An act to prohibit the discharge into the open air of dense smoke within the corporate limits of cities which now have or may have hereafter a population of one hundred thousand inhabitants; to declare the discharge into the open air of dense smoke within the corporate limits of such cities a public nuisance, and to provide penalties for the violation and enforcement hereof.

Be it enacted by the General Assembly of the State of Missouri, as follows:

SECTION 1. The emission or discharge into the open air of dense smoke within the corporate limits of cities of this State which now have or may hereafter have a population of one hundred thousand inhabitants is hereby declared to be a public nuisance. The owners, lessees, occupants, managers or agents of any building, establishment or premises from which dense smoke is so emitted or discharged shall be deemed guilty of a misdemeanor, and upon conviction thereof, in any court of competent jurisdiction, shall pay a fine of not less than twenty-five dollars nor more than one hundred dollars. And each and every day whereon such smoke shall be emitted or discharged shall constitute a separate offense; *Provided, however*, that in any suit or proceeding under this act, it shall be a good defense if the person charged with a violation thereof shall show to the satisfaction of the jury or court trying the facts that there is no known practicable device, appliance, means or method by application of which to his building, establishment or premises the emission or discharge of the dense smoke complained of in that proceeding could have been prevented.

SEC. 2. All cities to which the provisions of this act are applicable are hereby empowered to enact all necessary or desirable ordinances not inconsistent with the provisions herein, nor the constitution, nor any general law of this State, in order to carry out the provisions of this act.

SEC. 3. All acts or parts of acts inconsistent with this act, or any part hereof, are hereby repealed.

Approved March 21, 1901.

APPENDIX B—ORDINANCE NO. 20,455.

An ordinance to prohibit the discharge into the open air of dense smoke within the corporate limits of the city; to declare the discharge into the open air of dense smoke within the corporate limits of the city a public nuisance; to provide penalties for the violation and enforcement hereof; to create the positions of Chief Smoke Inspector, and Deputy Smoke Inspectors, prescribe their duties and salaries and the manner in which their work shall be controlled and supervised; and to repeal Sections One Thousand Five Hundred and One, One Thousand Five Hundred and Two, One Thousand Five Hundred and Three and One Thousand Five Hundred and Four of "The Municipal Code of St. Louis" (said sections being Ordinance Number Nineteen Thousand Seven Hundred and Seventy-two, approved April sixth, Eighteen Hundred and Ninety-nine).

Be it ordained by the Municipal Assembly of the City of St. Louis, as follows, to wit:

SECTION 1. Sections One Thousand Five Hundred and One, One Thousand Five Hundred and Two, One Thousand Five Hundred and Three and

One Thousand Five Hundred and Four of "The Municipal Code of St. Louis" (said sections being Ordinance Number Nineteen Thousand Seven Hundred and Seventy-two, approved April sixth, Eighteen Hundred and Ninety-nine) are hereby repealed, and they are hereby enacted in lieu thereof the following new sections:

SEC. 1501. The emission or discharge into the open air of dense smoke within the corporate limits of the city of St. Louis is hereby declared to be a public nuisance. The owners, lessees, occupants, managers or agents of any building, establishment or premises from which dense smoke is so emitted or discharged shall be deemed guilty of a misdemeanor, and, upon conviction thereof, in any court of competent jurisdiction, shall pay a fine of not less than twenty-five dollars nor more than one hundred dollars. And each and every day whereon such smoke shall be emitted or discharged shall constitute a separate offense; *Provided, however*, that in any suit or proceeding under this ordinance, it shall be a good defense if the person charged with the violation thereof shall show to the satisfaction of the jury or court trying the facts that there is no known practicable device, appliance, means or method by application of which to his building, establishment or premises, the emission or discharge of the dense smoke complained of in that proceeding could have been prevented.

SEC. 1502. The Mayor is hereby authorized to appoint a Chief Smoke Inspector and such Deputy Smoke Inspectors, not to exceed five in number, as may be, in his judgment, necessary to aid in carrying out the provisions hereof, and the provisions of the Act of the General Assembly of the State of Missouri relating to smoke abatement in cities of one hundred thousand inhabitants, approved March 21, 1901, and all such appointments shall be confirmed by the Council.

SEC. 1503. Said Chief Smoke Inspector and Deputy Smoke Inspectors shall hold their respective positions during the pleasure of the Mayor.

SEC. 1504. For all services contemplated by the provisions hereof the Chief Smoke Inspector shall receive from the city compensation at the rate of one hundred and twenty-five dollars per month, and each of said Deputy Smoke Inspectors shall receive compensation at the rate of eighty-three and one-third dollars per month, all payable monthly at the expiration of each month.

SEC. 1504 A. Said Chief Smoke Inspector and said Deputy Smoke Inspectors are hereby authorized, in the performance of their duties, to enter, at all reasonable hours, upon and into any and all buildings, establishments, premises and inclosures, in or from which they may believe that this ordinance, or the said Act of the General Assembly of Missouri, has been or is being violated; and to inspect and examine such building, establishment, premises or inclosure in order to ascertain whether or not there is any known practicable device, appliance, means or method by the application of which to said building, establishment or premises the emission or discharge of dense smoke therefrom into the open air could have been or can be prevented. Said Chief and Deputy Smoke Inspectors shall collect and preserve evidence of all facts touching violations of this ordinance, or of said Act of the General Assembly, and said Deputy Smoke Inspectors shall make reports of their examination and investigation to the Chief Smoke Inspector at such times and in such manner as he may direct. Said Chief Smoke Inspector shall report all cases of violation of this ordinance to the proper officers, or

prosecuting officer, for the prosecution of the offender, and he and said deputies shall aid in all such prosecutions by furnishing whatever evidence they may have procured. They shall devote on each day to the discharge of their duties at least the number of hours provided by Section 11 of Article IV, of the City Charter, and for failure to do so, or for any other reason satisfactory to the Mayor, they may be removed by him at any time. The Chief Smoke Inspector shall furnish the Mayor with reports and information whenever he shall be required to do so.

SEC. 1504 B. The appointments and the removals of Smoke Inspectors, under this ordinance shall be made matters of official record. Each Smoke Inspector when appointed shall be furnished with a certificate or written evidence of his appointment, signed by the Mayor, which certificate or written evidence such Smoke Inspector shall exhibit if required by any person upon whose premises he proposes to enter for purposes of inspection. All Smoke Inspectors shall be guided in the performance of their duties by such orders and directions as the Mayor may see fit from time to time to give them.

SEC. 1504 C. It is hereby made the duty of all patrolmen and officers of the police force of the city to assist said Smoke Inspectors in the performance of their duties, and to report to the Chief of Police all violations of this ordinance coming to their knowledge.

SEC. 1504 D. Any person who shall interfere with any of the Smoke Inspectors hereinbefore provided for, in the discharge of their duties, or shall hinder or prevent any of said inspectors from entering into or upon, or from inspecting any buildings, establishments, inclosures or premises in the discharge of their duties, shall be deemed guilty of a misdemeanor and on conviction thereof shall be subject to a fine of not less than twenty-five dollars nor more than one hundred dollars for each offense.

Approved August 21, 1901.

THE EFFICIENCY OF COMPOUND CENTRIFUGAL PUMPS.

BY PROF. F. G. HESSE, MEMBER OF THE TECHNICAL SOCIETY OF THE
PACIFIC COAST.

[Read before the Society, November 1, 1901.*]

IN 1869 I volunteered to design a centrifugal pump for the Stanislaus Water Company, of which Mr. N. W. Spaulding was president. It was a two-stage compound pump; that is, a combination of two pumps, exactly alike, having the shaft in common, arranged so that the first pump discharged into the other, and each provided with a free vortex for the purpose of converting into pressure the kinetic energy of the absolute velocity of discharge from the runners.

The important question now presented itself, How does the efficiency of such a combination of two or more pumps compare with that of a single pump doing the same duty?

The power lost in a centrifugal pump may be separated into three separate losses, viz:

1. Friction of shaft in bearings, independent of quantity discharged.
2. Friction of water as it passes through suction pipe along the vanes of runner into the discharge pipe, proportional to square of quantity discharged.
3. Friction of runner rotating in water, independent of quantity discharged.

Unfortunately, no tests heretofore made, so far as I know, have recognized the loss of power due to the wheel discs; that is (3), above, and in consequence those losses have been charged to the "hydraulic" resistance, thereby producing coefficients of resistance too large and otherwise giving rise to formulas which are misleading and standing in the way of a true interpretation of the phenomena presented by the action of the pump under different conditions and elements of construction. The theory of the centrifugal pump, as usually given, will not explain the experimentally demonstrated higher efficiency of a compound pump over a single pump, as will be shown later.


In 1869 no experiments on the friction loss of discs rotating in water had been made, as far as I could ascertain, and I was obliged to use a formula which I developed on a purely theoretical basis. Its application proved conclusively that the compounding

*Manuscript received December 5, 1901.—Secretary, Ass'n of Eng. Socs.

of pumps increased the efficiency over that of the single pump doing the same duty.

Much to my regret, the pump referred to was never built, owing to the dissolution of the Stanislaus Water Company, and the drawings, which had been kept at the company's office, disappeared. Mr. Spaulding informed me later that some one of the company had secured a patent, or caused a patent to be obtained by a manufacturing company in New Jersey.

Matters remained *in statu quo* until the year 1887, at which time I published University Bulletin No. 2, on a "Hydraulic Step,"



which contained the results of experiments on the resistance offered to discs rotating in water.

I found the energy lost in foot-pounds per second to be

$$W = 0.105 \lambda n^3 d^5 \quad (1)$$

in which

n = number of revolutions per minute.

d = outer diameter of disc in feet.

λ = a coefficient.

This coefficient λ is a function of d and n . The variation of n is mainly felt for small velocities, and can be neglected, since the use of the formula deals with large values of n . λ , as a function of d , approaches an asymptote for d greater than unity.

Expressing W , the energy lost per second, in terms of the peripheral speed of the disc, we find

$$W = 0.00205 \, d^2 \, v^3 \quad (2)$$

which formula shall be applied to the theory of the centrifugal pump.

We shall use the following notation in connection with the diagram representing a pump with a diffuser:

d = diameter of runner in feet.

v = peripheral speed of runner.

Q = quantity of discharge in cubic feet per second.

h = height to which Q is to be raised.

h_r = hydraulic head lost.

w_o = velocity of discharged water.

g = acceleration of gravity.

d_o = diameter of inlet pipe equal to inner diameter of runner.

$$c = \frac{d}{d_o}$$

σ = density of water in pounds per cubic foot.

c_i = velocity of water in inlet pipe.

$h_1 = \xi \, h$.

δ and γ = angles as shown in the figure.

Also since $Q = \frac{\pi \, d_o^2 \, c_o}{4}$

it is $d^2 = \frac{4 \, c^2 \, Q}{\pi \, c_o}$

The total head against which the pump works is

$$H = h + h_1 + \frac{w_o^2}{2g} \quad (3)$$

in which $\frac{w_o^2}{2g}$ is the head corresponding to the velocity of discharge.

Accordingly the work per second is $H \, Q \, \sigma$.

The theory of the pump indicates that

$$v^2 = g \, H \left\{ 1 + \frac{\tan \gamma}{\tan \delta} \right\} = g \, H \, B \quad (4)$$

where B is a constant depending upon the construction of the pump.

The introduction of γ as a characteristic is due to Prof. G. Hermann, Technical University, Aachen.

Equations (2) and (4) are sufficient to determine the formula for efficiency of any pump, simple or compound.

Expressing d in terms of Q , and substituting for v from (4), it is

$$W = .475 \, c^2 \, h^{\frac{3}{2}} \, (1 + \xi)^{\frac{3}{2}} \, B^{\frac{3}{2}} \, \frac{Q}{c_o} \quad (5)$$

neglecting $\frac{w_o^2}{2g}$ as very small compared with h and h_1 in any actual

case. The hydraulic efficiency $\eta = \frac{\text{Useful work done}}{\text{Useful work done} + \text{hydraulic losses}}$

$$\eta = \frac{Q \sigma h}{(1 + \varepsilon) h Q \sigma + .475 \frac{Q \sigma h^3}{c} (1 + \varepsilon) B} \quad (6)$$

and the efficiency with m pumps in series working under the same head h is

$$\eta = \frac{m Q \sigma}{m (1 + \varepsilon) \frac{h}{m} Q \sigma + .475 \frac{m Q \sigma^2}{c} \left(\frac{h}{m}\right)^3 (1 + \varepsilon) B} \quad (7)$$

which, divided through by $Q \sigma h$, becomes

$$\eta = \frac{1}{1 + \varepsilon + .0075 \frac{c^2}{h^3} \left(\frac{h}{m}\right)^3 (1 + \varepsilon)^2 B} \quad (8)$$

This is the final formula for the efficiency of a compound pump, and it indicates that, for a given head h , the efficiency will increase with the number of stages or pumps in series.

If we had assumed the disc friction loss proportional to the square of the velocity, with the same coefficients, the efficiency

$$\eta = \frac{1}{1 + \varepsilon + c^2 B (1 + \varepsilon)^2 .0075}$$

which formula will not account for the observed higher efficiency of a compound pump over a single pump doing the same work. This greater efficiency is due to the decrease of the disc friction loss by diminishing the peripheral speed of the runner, as indicated in the formula (7). It should be mentioned here that I have not yet had an opportunity to determine the coefficient ε for different styles of runners and constructions, but the equipment of the new hydraulic laboratory at the University of California will render this possible in the very near future. In the following table, showing how a change in B of formula (4) and m affects the efficiency, I have taken $\varepsilon = 0.3$:

ε	c	h	m	$(1 + \varepsilon)^2$	c	$\frac{c^2}{h^3}$	B	η	hydraulic efficiency	
0.3	4	900	1	1.48	4	15	25	4.57	320	.35
0.3	4	900	1	1.48	4	90	1.00	170		.62
0.3	4	900	9	1.48	4	15	25	4.57	107	.56
0.3	4	900	9	1.48	4	90	1.00	57		.71

*When $\frac{c^2}{h^3} = 0$, B becomes unity irrespective of the value of ε .

SUMMER STREET VIADUCT, SOUTH BOSTON.

BY HERMAN K. HIGGINS, MEMBER BOSTON SOCIETY OF CIVIL ENGINEERS.

[Read before the Society, June 19, 1901.*]

THE Summer street viaduct, South Boston, is essentially a part of the general expansive movement, observable for a few years past, on the part of the business of Boston, using the term in the broad sense and including therein not only the buying and selling of goods, but as well the transportation, storage and shipment of much material that passes through Boston's railway terminals to foreign countries without involving any financial transactions in Boston proper.

As our city's importance as a commercial center increases, it becomes increasingly difficult to transport merchandise through crowded streets to wharves in the city proper, and the difficulty may be expected to increase even more rapidly in the future.

Within the past few years, owing partly to the inevitable consolidation of land transportation companies, but principally to the geographical peculiarities of our city, the condition has arisen that there is but one principal artery of travel between the railway terminals and the wharves of the city proper, that is, Atlantic avenue. Already, at certain times of day, the capacity of the street is severely taxed, and the increased local traffic, incident to the business which will doubtless be fostered by the improved means of transit provided by the elevated railway, has of course yet to be felt and should be liberally allowed for. It is not financially practicable to widen such a street, nor is it practicable to so administer it as to keep it always reasonably safe and clear of blockades.

It will be seen, therefore, that available dock frontage in localities more accessible, particularly from railway terminals, is a prime necessity if Boston is to continue to increase in commercial importance. Moreover, the older docks and wharves are already tolerably well occupied by traffic in lines which have been for some time in possession of certain territory, and could be removed only at considerable loss. For example, the fisheries near T wharf, various coal wharves and power plants, the excursion steamer lines, ferries, etc., all small items in themselves, but aggregating enough to occupy a very appreciable share of the available water frontage of the city proper. Under these conditions trade must naturally turn to districts more remote from the older center of business.

*Manuscript received December 20, 1901.—Figs. 1 to 4, inclusive, reprinted, by permission, from "Engineering Record" of December 21, 1901.—Secretary, Ass'n of Eng. Soes.

Another reason, not less important perhaps, is found in the fact that the older part of the water front is owned in comparatively small parcels by a considerable number of persons. This effectually prevents any large system of improved facilities such as other ports have found essential to their growth and continued prosperity.

Fortunately, the larger Boston is so situated that commercial expansion can be carried to an almost indefinite extent, and we find that for some time the bulk of the heavier traffic has taken itself to Charlestown, East Boston and South Boston.

Charlestown's docking facilities are comparatively well developed, and the new Charlestown Bridge on the one hand and the railway facilities offered by the Boston and Maine Railroad leave little to be desired in the way of transportation possibilities to assure the ultimate perfect utilization of its comparatively limited water frontage.

East Boston is unfortunately not so happily situated, as it is handicapped in handling local traffic by the natural barrier set by the harbor imposing the use of ferries to secure access to the business center of the city. Notwithstanding the excellent management and equipment of our ferries the limitations imposed by fog, weather and a crowded harbor form a condition which must have considerable effect upon any business requiring their use. Its rail connection, also, leaves much to be desired, as the many and dangerous grade crossings will ultimately have to be eliminated and the cost of so doing will constitute a charge upon traffic which, although not readily visible to casual observation, is nevertheless a real handicap to its future growth and prosperity. Its natural advantages, however, are so great that it has already a very large share of the trans-Atlantic trade of Boston, and its opportunities for expansion are nearly unlimited.

South Boston, unlike its two sister localities, has had so far comparatively little development, notwithstanding its natural advantages are of the best. Its rail approaches are direct, and have only one grade crossing, and that not very serious, as the bulk of its street traffic is heavy trucking, and its ultimate abolition should not prove exceptionally expensive. Its room for future growth is nearly as unlimited as East Boston, and long before its full development the business of ocean transportation may have undergone such transformations that all our docks may require complete reconstruction. The movement just begun of consolidation of steamer lines seems destined to effect great changes in a few years. Its means of access from the city proper have, however, been in the

past not so satisfactory, Congress street, the only direct thoroughfare, being narrow and crowded by local freight traffic to and from the railway yards. The State docks and future extensions will shortly call for largely increased facilities for access to the business center. The water frontage of South Boston proper must also sometime be included in the general harbor system, and a great and still growing population is clamorously demanding better means of access to the city.

To accommodate all these interests, a wide, commodious avenue across the South Boston Flats, as they were formerly called, became a necessity, and postponement of its construction could only result in a greatly increased cost, as the appreciation of values in this district is rapid and continuous.

A number of studies were made at various times with the object of determining whether a change in level of Congress street would not upon the whole best serve the interests of all concerned, as it is apparent that Congress street is very close to the most desirable location for such an avenue. Such studies seem to show conclusively that this would not finally solve the problem, and that the legitimate function of Congress street is to provide for the already large and growing warehouse business located between the railway and Summer street and the local freight service of the New York, New Haven and Hartford Railroad, leaving the new thoroughfare, Summer street, to form a means of access to the lands east of the railway terminal, including the State's docks, the shipbuilding interests, present and prospective, and whatever through traffic may in time be developed.

The planning of this street or viaduct was in itself something of an undertaking and would be more highly appreciated were it not for the dwarfing effect of the greater problems presented by the construction of the passenger terminal so nearly adjacent.


The effect of gradient on such a street, carrying as it must a very heavy traffic, is seen to be most serious, and heavy expenditure is warranted in the effort to reduce it to a minimum. The viaduct over the railway, on the contrary, calls for as much room as possible over the tracks, not only to reduce risk to brakemen, but of nearly equal importance to reduce the deterioration due to corrosion. This element of clear room over the stack of a locomotive is not yet properly appreciated, even by the engineering profession, and those who have occasion to maintain metal structures exposed to such conditions know that mere painting, even when frequent and accompanied by thorough cleaning, forms at best a very unsatisfactory means of protection. The life of iron over

locomotives varies according to the distance from the stack to the surface exposed, probably somewhere nearly as the square of said distance.

A viaduct over a railway freight terminal must also leave ample room for handling bulky machinery and other freight, and in this case it was needful to provide room enough to construct tight roofs over the freight houses, one of which had already been built and two others were under way.

The final determination of grades was therefore in the nature of a compromise and called for the exercise of considerable judgment to properly evaluate the conflicting interests.


The width of the street, 100 feet, is fixed by general local practice rather than by any formally logical process. There is, however, already sufficient occasion to believe that long before the complete development of the territory tributary to this street there will



be no lack of crowding on even this 100-foot thoroughfare. It should be remembered in this connection that Atlantic avenue is essentially a distributing street; most of its traffic following it for only a few blocks, then turning up some of the radial streets toward the center of business, whereas Summer street will ultimately be more of a thoroughfare.

The character of the expected traffic on this street fixed the surface finish, it being early apparent that nothing short of granite block pavement would be at all permanently satisfactory. This materially increases the weight to be carried, but is of less importance than frequent blocking of traffic to permit repairs to a less durable pavement.

This pavement weighs about 120 pounds per square foot, with its pitch joints and sand cushion, and rests on a layer of waterproofing material consisting of about one inch of tarred sand on a four-ply layer of tar-paper, thoroughly mopped with hot tar, similar in general to an ordinary tar and gravel roof. (See Fig. 1.)



THE FOUR REAL

To safely carry this heavy pavement and the expected heavy live load, even after a considerable amount of decay, the drive-ways were planked with 6-inch hard pine and the sidewalks with 3-inch hard pine. Stringers were made 8" x 16" under the drive-ways and 3" x 12" under the sidewalks, and will safely carry a steam roller or a steam motor carriage of the European type, which will no doubt in a few years become as common here for heavy freighting as the electric cabs now are for passenger traffic.




FIG. 3. TYPICAL TRUSS AND COLUMN.

As all this timber would in time decay and the interruption to traffic for repairs will in a few years become a serious matter, and as the rapidly progressing destruction of our forests will have materially increased the cost of lumber by the time such renewals will have to be made, it was determined to subject all the lumber to some preservative process, and the creosoting process, so-called, was selected as having the preponderance of evidence in its favor.

The wooden stringers rest on shelf angles on the steel floor beams, with their tops nearly flush with the floor beam flanges. This enables the use of a deep and stiff floor. (See Fig. 2.)




FIG. 4. DETAIL OF SIDE COLUMNS.

In order to reduce the span and consequent weight of the floor beams as much as practicable and also to keep the truss sections down to reasonable limits, three trusses were determined upon, spaced forty feet apart on centers. The sub-Pratt type was chosen as the most economical and generally satisfactory. They are notable only for their great weight. The trusses rest on steel seg-

mental rollers 12" in diameter; these on steel columns, and the columns on the masonry piers. (See Fig. 3.)²

The use of steel columns in place of the more usual stone piers enables much room to be saved under the bridge, as the necessary spread of base can be carried below the floors of the freight houses. The columns are also more rigid against overturning, being anchored deep into the masonry, and cost, if anything, a little less than masonry piers. Their weight being much less, the foundation may be smaller, and the ultimate cost is materially reduced without any sacrifice of efficiency. (See Fig. 4.)

The lengths of spans were fixed by the necessity for reducing to a minimum the obstruction to the future development of the terminal below. To this end the piers were placed in the centers



FIG. 5. RAILROAD BRIDGE FOUNDATIONS.


of the freight houses to permit trucking freely between and around them and in the center of one of the driveways devoted to teaming bulk freight. (See Fig. 5.) The piers adjacent to B street, Fig. 6, were designed to form part of the wall of a future extension of the freight house to cover the entire B street frontage of the property, which will logically form a feature of its ultimate development. As doors will be needed, the space between truss bearings was left unencumbered by needless masonry.

The foundations of such a structure, while logically the final consideration, are constructively the first to be put under way, and

²For a more detailed description of superstructure see "Engineering Record" of December 21, 1901.

in this case are of the first importance. The geological formation is similar to much of the low-lying portion of Boston, being of clay covered with miscellaneous filling. Being made land, the clay was rather wet, and consequently soft. Piles were driven two feet apart on centers each way. The number of piles in each foundation was fixed by the load on the pier, which varied somewhat, and the piles were allowed to carry some twelve tons each. As the soil is certainly good for one ton per square foot, the actual load transmitted by the pile to the strata below cannot much exceed eight tons.

This work offered a notable example of the consolidating effect of piles upon the adjacent soil. The first piles in each group drove easily, and the resistance increased with reasonable uniformity. As the group approached completion, however, the resistance increased markedly, and the last few piles were driven with



considerable difficulty. The bottoms of the pits were forced up and the sides were forced in, and additional excavation was necessary to make room for the masonry.

The piles being driven and cut off, concrete was placed about their heads for a depth of one foot. The concrete was of Portland cement, sand and screened gravel, in the proportions of one, two and four, mixed unusually wet, and thoroughly compacted about the piles. This concrete extended two feet above the piles and formed the lower course of the masonry. On it was laid the body of the pier in two-foot courses of split granite of superior quality in rectangular blocks, very thoroughly bonded, each stone being shown on detail drawings of each course, with all dimensions and positions of joints specified.

These piers are designed to fully utilize the strength of the granite and spread out the foundations to the requisite extent as rapidly as possible, thus saving excavation and pumping. The ground water level in this vicinity is very close to the surface, and piles cut off at grade 13 would be safe so far as drying out is concerned. A shallow foundation is consequently as good here as one deeper. As will be seen from the plans, the required spread of foundation necessitated extending the concrete down to a point well below high water. (See Fig. 7.)

In considering the loads on piles and underlying strata, the eccentricity of loading was considered and the northwest piers were set over nine inches in order to bring the centers of columns in the axis of the freight house. In the other piers the greatest eccentricity is only 2 inch. In the northwest abutment, Fig. 8, the thrust of the filling carries the line of pressure well forward toward the limit of the middle third. In the original design the piles were




FIG. 7. MIDDLE PIERS.

spaced enough closer toward the front to bring the resultant of reactions coincident with the line of pressure. For constructive reasons this was changed before awarding the contract, and the piles were spaced two feet on centers, as in the other foundations, the result being that the piles near the toe of the abutment really carry about fifteen tons each instead of the twelve tons originally intended. Of course, they are capable of carrying much more than this.

In order to build the middle piers it became necessary to remove part of a freight house already built, and after the completion of the bridge to restore it to a condition of usefulness. The problem of water-proofing the roof was solved by constructing a nearly flat roof, with extensive flashing about the columns, the roof coming well below the rollers and movable parts of the bearing, and was covered with the usual tar and gravel.

The falsework was comparatively simple in plan and consisted of I beams and wooden stringers, carried on ordinary framed bents between tracks, in some cases spanning two tracks. Tracks were moved a few inches to equalize the clearance and lessen the chance of any collision between cars and bents. The traveler used was a substantial structure of wood and iron of sufficient span to cover two trusses. It was carried for the first half of the work on rails resting directly on the falsework. After the north and middle trusses had been swung, one leg was shortened to run on the top chord of the middle truss and cover the other half of the bridge. (See Figs. 9 and 10.)

The erection of the ironwork was carried on much the same as in similar work elsewhere, being notable principally for the great




FIG. 8. NORTHWEST ABUTMENT.

weight of some of the top chord sections, some of which contained over two hundred square inches of metal in section. Some of the permanent stringers were placed and used to carry service tracks for distributing material to its place in the structure, but the floor was not permanently laid until the completion of the ironwork.

The provision and treatment of the lumber deserves some passing mention, illustrating as it does a radical change which is or has been taking place in the lumber business. This lumber was cut not far from Norfolk, Va., and treated at the Old Dominion Creosoting Works at that city. We are accustomed in this part of the world to think that the heaviest and most difficult work is done by the most modern establishments, as in case of steel bridges and




FIG. 9. TRAVELER AND FALSEWORK.




FIG. 10. TYPICAL TRUSS AND COLUMNS.

heavy machinery. In the later lumber mills, however, this rule does not hold, the reason being that modern mills are generally run on comparatively short logs, and long sticks have to be sawed on more ancient machines. The later mills have the carriage operated by a direct steam cylinder, the piston being attached directly thereto.

There are several such mills in the vicinity of Norfolk, in which band saws are used, and the celerity with which logs in the water are transformed into lumber, sorted and piled ready for shipment, forms a marked contrast to older methods. Very little manual labor is employed. It is undoubtedly owing to the limited demand for long timber that these mills confine themselves to the shorter lengths.

As nearly half the lumber in the Summer street bridge is in 6" x 12" x 36' sticks, it was necessary to obtain it from country mills, most of which, in that region at least, are run with the usual Southern disregard of hurry, so the delays in delivery at the creosoting works were both continuous and vexatious. This lumber being furnished under the main contract for the steel bridge, most of the vexation fell upon the local sub-contractor, who was no doubt accustomed to it.

The process of creosoting, while simple enough to one who has made a study of the subject, is not, however, at all well understood, as is attested by the commercial success of various washes and so-called paints, which can at best only temporarily retard decay.

There is plenty of information in print bearing on the subject, but so effectively scattered through various issues of many periodicals that one must be exceptionally well read to even know of its existence, much more to know where to look for it.

In brief, the process used in this case was as follows: First, the lumber was inclosed in a retort and steamed, first with saturated steam, to open the pores of the wood and dissolve most of the putrescible and soluble materials which nourish the bacteria, to whose presence decay is largely due; later by superheated steam, which removes the turpentine and other volatile substances from the wood, at the same time destroying any bacteria already present.

Second, the air, steam, water, turpentine, etc., are removed by air pumps, the temperature being meanwhile maintained by steam pipes in the retort, the exhausting process being continued several hours until the exhaust from the pump shows no trace of turpentine.

Third, the retort is filled with the dead oil from the storage tanks, and enough more is forced in to fill the requirements of the




FIG. 11. GENERAL VIEW SUMMER STREET BRIDGE OVER NEW YORK, NEW HAVEN AND HARTFORD RAILROAD.

EVERY MEMBER OF THE

Association of Engineering Societies

should have and use

THE ENGINEERING INDEX.

Originally started by Prof. J. B. Johnson in the Journal of the Association of Engineering Societies, this great work has been continued since 1895 solely by

THE ENGINEERING MAGAZINE.

Prof. Johnson says :—" The work has been far better performed by The Engineering Magazine, both in scope and thoroughness, than I was ever able to do."

The Engineering Index is published as a part of each number of The Engineering Magazine and also as a separate publication. In the latter form it is printed on only one side of the paper for the use of those who wish to cut it up for card index purposes. The subscription price of either publication alone is \$3.00 a year; but both publications will be sent to one address for \$4.00 a year. Send for sample copies.

THE ENGINEERING MAGAZINE,

120-122 LIBERTY STREET,

LONDON OFFICE:
222-225 STRAND, W. C.

NEW YORK.

ASSOCIATION OF ENGINEERING SOCIETIES.

VOL. XXVII.

AUGUST, 1901.

No. 2.

PROCEEDINGS.

Engineers' Club of Minneapolis.

THE 144th regular meeting of the Club was held at 8 P.M. on May 20, 1901, at its permanent quarters in the County Commissioners' rooms, in the County Court House. Seven active members and one honorary member, Col. J. T. Fanning, present.

Reading of minutes was dispensed with. Mr. Fanning's paper on "Canals and Canal Devices" was discussed. Mr. D. C. Washburn was elected to active membership, and the name of H. D. Lackore, electrician with the Minneapolis General Electric Company, was proposed. The new constitution and by-laws of the Club, as amended, were then read and adopted. Mr. Sublette was appointed as a committee of one to induce engineers at Duluth, Minn., to form an engineering association.

Adjourned.

EDWARD P. BURCH, *Secretary.*

CONSTITUTION AND BY-LAWS OF THE ENGINEERS' CLUB OF MINNEAPOLIS.*

ARTICLE I.

NAME, ETC.

The name, style and title by which this Society shall be known will be the "Engineers' Club of Minneapolis" (that is to say, Minneapolis, Minnesota). This Constitution and By-Laws appended to same are hereby enacted for the government of the Club.

ARTICLE II.

OBJECTS AND PURPOSES.

The object of the Club will be to discuss the various subjects embraced in the term engineering; to further the more perfect understanding of the dif-

*This Constitution and By-Laws was read and adopted at the regular meeting of the Engineers' Club of Minneapolis, held May 20, 1901, that being the 144th meeting of the Club. Read by the President, Wm. W. Redfield, who was also chairman of committee, appointed by the previous President to draft a new Constitution and By-Laws.

ferent methods, appliances and materials in current use; to examine into any or all achievements and failures in engineering work, and thus aid in the professional improvement of members; in promoting the general benefit of the public; and also in facilitating social intercourse among engineers.

ARTICLE III.

ELIGIBILITY.

Civil, mechanical, electrical and other engineers, and any interested in the advancement of engineering, who shall have attained the age of twenty-one years, and who are known to be in good standing, shall be eligible as members of either class, as hereinafter defined.

ARTICLE IV.

GOVERNMENT.

The government of the Club shall consist of a President, Vice-President, Secretary, Treasurer and Librarian, who shall be elected by ballot by a majority of the voters present at the Annual Meeting of the Club, and who shall hold their offices until others are elected in their stead. Any vacancy occasioned by resignation, death or otherwise, may be filled (by a special election held in the same manner as the above election) at the next regular meeting, after due notice to all voters of such vacancy.

The duties of the government shall be to have a general oversight of the affairs of the Club; to provide for literary exercises or programs of the meetings, and to arrange for any special function that may occur; in all of the above, they may be assisted by, or their powers delegated to the Committee on Entertainment. Furthermore, if found advisable, the offices of Secretary and Treasurer may be filled by the same person. As such combination would cause the government to consist of only four (4) active members, it would be necessary that a fifth member of the government be chosen at the same time and in the same manner as that of the election of the other officers; this extra office only holds valid as long as the offices of Secretary and Treasurer are so combined.

ARTICLE V.

FINANCE COMMITTEE.

The Finance Committee shall be composed of the five members of the government, together with two (2) other active members of the Club, each chosen by a majority of the votes cast by ballot at the Annual Meeting of the Club, or at any regular meeting, as soon as practicable after the adoption of this Constitution. They shall hold office until others are elected in their stead. The duties of this committee shall be to recommend to the Club any special assessments or appropriations for specific purposes; and to attend to any special financial business of the Club.

ARTICLE VI.

DUTIES OF OFFICERS.

SECTION 1. *President.* The duty of the President shall be to attend and preside at all meetings of the Club; to appoint all committees (except that of Finance), as follows: At each Annual Meeting, immediately after the termination of the election of all officers, the Finance Committee, and all Representatives to the Association of Engineering Societies, the incoming

President shall appoint the Standing Committees on Membership and Entertainment, and also such other additional standing committees as may be deemed necessary, the same shall also be done at any regular meeting after the adoption of this Constitution. Each of these standing committees to consist of three (3) active members (not officers nor those serving on Finance Committee). The members of standing committees serve for one year, or until their successors are appointed. Other special committees may at any time be appointed, such special committees only serving long enough to accomplish the purposes for which they were appointed.

The President shall also countersign all the bills against the Club before they are paid; he shall make an advisory message and report upon the general condition of the Club at the Annual Meeting after each presidential term; he shall also make a brief inaugural on assuming the chair when not his own successor; he shall notify the Vice-President of any intended absence of himself from any meeting of the Club; and also notify the Secretary of any special meeting to be called.

SEC. 2. *Vice-President.* The duty of the Vice-President shall be to preside at all the meetings at which the President is unable to be present; and to be President *pro tem*, whenever the President is absent from the city.

SEC. 3. *Secretary.* The duty of the Secretary shall be to be present at all the meetings of the Club; to record the proceedings of each meeting in a minute book, and to read the minutes of any meeting at the next regular meeting held. He shall see that copies of such instructions as are recorded in the minutes, and that refer to any officer, committee, or member are sent to the proper parties. He shall read the names of such candidates as may be proposed, in correct form, for membership, as early as one (1) regular meeting previous to the one on which the election of said candidates is to occur. He shall notify each and every member at least three (3) days in advance of the date set for any regular meeting; but notice of the date set for the Annual Meeting shall be sent to each and every member at least one week in advance of the date set for said Annual Meeting. At this Annual Meeting he shall make a report of the preceding year. Notifications of special meetings are to be sent to active members only; unless some special reason requires the presence of any or all corresponding and honorary members, in which case the members concerned are also to receive notifications. It will also be the duty of the Secretary to promptly forward a properly condensed copy of the proceedings of every regular and important special meeting to the Association of Engineering Societies for publication in their journal; this means also a copy of any paper or communication read by any member at any meeting, and recommended by the Club for publication in said journal; also to notify the city papers of the date of any intended meeting. In consideration of the personal time necessarily devoted by him to the affairs of the Club, the Secretary is exempt from all dues while holding said office. If the duties of the Secretary should at any time become so great as to make it necessary, he may, with the approval of a majority of active members present at any regular meeting, appoint any active member (not a member of the Finance Committee) to be Assistant Secretary, said Assistant Secretary to act as Secretary during the absence of that officer, but shall neither be considered as an officer, nor as a member of the Government nor Finance Committee. His term shall always expire at the Annual Meeting following his appointment and confirmation. In case the offices of Secretary and Treasurer

ASSOCIATION OF ENGINEERING SOCIETIES.

are combined, according to Article IV of this Constitution, the Assistant Secretary shall also be Assistant Treasurer.

SEC. 4. *Treasurer.* The duty of the Treasurer shall be to keep a ledger account of all financial transactions of the Club with every member, and others indebted or credited; to cause the Secretary to send to each newly elected member a receipt for his initiation fee, and to cause the Secretary to send receipts for other dues from all members on payment of same, and to cause the Secretary to notify each member at least two weeks in advance of the date on which any dues are payable.

He is himself to notify each member who fails to pay his dues on the date called for, and failing to receive said delinquent dues within thirty (30) days after such notice has been sent, he is to hand their names to the Finance Committee. He is to deposit any surplus funds of the Club in such bank or banks as the Finance Committee shall direct, and to make such investments as the Finance Committee, on ratification by the Club, may determine. He is to pay all bills against the Club that are countersigned by the President, and to give receipts for all moneys paid to him, to whomsoever said receipts are due. He is to keep an accurate account of all his transactions for the Club, and must submit an annual financial report. If found expedient, at any time, either temporarily or permanently, the offices of Secretary and Treasurer may be filled by the same person, in accordance with Article IV of this Constitution.

SEC. 5. *Librarian.* The duty of the Librarian shall be to take entire charge of the library of the Club, and to see that all books and pamphlets and maps and other library property are marked with the name of the Club, and numbered and recorded in a catalogue. In respect to the management of the library, he shall conform to such regulations as may be prescribed by the Club.

ARTICLE VII.

AUDITOR.

At each Annual Meeting of the Club the incoming President shall appoint an Auditor whose duty shall be to audit the accounts of the Treasurer for previous fiscal year up to the date said Auditor is appointed, and then certify as to the accuracy of the accounts.

ARTICLE VIII.

REPRESENTATION IN THE ASSOCIATION OF ENGINEERING SOCIETIES.

In order that the Club may have an organ to represent it in the matter of publishing its proceedings or any communications furnished by members of the Club, the Club has affiliated itself with what is called the "Association of Engineering Societies." This Association publishes a journal in which appear the proceedings of and papers or other communications furnished by the members of the component societies. Each Society is entitled (according to the number of members composing the same), to send one or more of their active members as Representatives to said Association. Accordingly, at each Annual Meeting of this Club, after the election of the sixth and seventh members of the Finance Committee, any active member or members as required (other than those on Finance Committee) may be elected by ballot (in the same manner as are the officers) for Representative or Representatives to the Association of Engineering Societies.

ARTICLE IX.

ADMISSION, ELECTION AND DUTIES OF MEMBERS

SECTION 1. *Active Members.* The name of every candidate for active membership shall be proposed by two (2) active members of the Club, and the signatures of the applicant and those of his two proposers shall be written upon the proper blank application furnished by the Secretary. This application, properly filled out and signed, shall be filed with the Secretary, and accompanied with the initiation fee. The Secretary, as soon thereafter as practicable will deliver to applicant a receipt for initiation fee, obtaining the receipt from the Treasurer on deposit of initiation fee with him. In case applicant fails of being elected into the Club, this receipt on indorsement by the Secretary, will become an order on the Treasurer for a refunding of the initiation fee.

At the next regular meeting of the Club, after receipt by Secretary of the application properly drawn up and completed, with accompanying fee, the Secretary will read the names of the applicants and their proposers, and blank ballots (with names of candidates and proposers placed thereon, and a place to cross off "Yes" or "No" printed opposite each candidate's name), must be sent to all active members not later than the day after the meeting. The ballots when properly marked and filled out, will be inclosed in ballot envelopes, sealed, and then promptly sent back to the Secretary before the following regular meeting. At the latter meeting the ballots will be opened before the Club, and a two-thirds vote of the entire ballots received (a quorum voting) will elect a candidate. At the close of said meeting the Secretary will furnish to each newly elected member a card or certificate of membership, signed by the President and Secretary of the Club. Every duly elected active member has full privileges of voting and holding office, and shall be liable for all his dues and special assessments, and shall be considered an active member, and so liable until his resignation has been sent to the Secretary and accepted by the Club; *provided, however*, that no resignation can be accepted until all dues in arrears be paid.

SEC. 2. *Corresponding Members.* Any person qualified for eligibility as mentioned in Article III, of the Constitution, and who does not desire to be an active member, may become a corresponding member in the same manner as provided for active members. They shall be voted for by active members only. Corresponding members have all the privileges of active members, except voting and holding office. They may, however, serve on any committee (except that of Finance), at the discretion of the President. If the Club so desires, corresponding members may vote occasionally on matters concerning particularly their class of membership; or on questions where expediency may call for their vote, but such vote shall only be given (on special assent of active members) to corresponding members present at any meeting at which such assent be given. They shall be subject to no dues except the initiation fee, and a nominal annual assessment, the amount of same to be determined upon by the Club.

SEC. 3. *Honorary Members.* Any engineer who has achieved marked distinction by reason of his professional attainments may be proposed in writing by two active members as an honorary member; said proposal having been read by the Secretary at any regular meeting. Notice must then be sent by Secretary to all active members absent from that meeting. At the following regular meeting the candidate proposed for honorary membership

may be elected by a unanimous *viva voce* vote of the active members present. Honorary members shall be exempt from all dues and assessments; shall not pay an initiation fee; may attend and participate in literary exercises at all regular meetings; join in all excursions or functions, but may not vote nor hold office, and shall not serve on any committee, except at the discretion of the President should expediency warrant it. The Club, if it sees fit, may establish a limit to the number of honorary members permitted to be in the Club; or to prescribe a limit to the number elected during any one year.

ARTICLE X.

QUORUM.

At any regular meeting of the Club five (5) active members shall constitute a quorum for the transaction of business.

ARTICLE XI.

ALTERATIONS TO THIS CONSTITUTION.

Any alteration to this or any preceding article of this Constitution, whether it be addition, subtraction, revision or amendment, may be made by a two-thirds vote of all the active members who vote upon the same; *provided* that a copy of each and every proposed alteration, together with a notice (stating the time set for said proposed alteration to be voted upon) shall have been sent to each active member at least one month before the time set for voting thereon. Each and every alteration as then proposed must be read by the Secretary before the Club at two consecutive regular meetings. Ballots may be opened after the discussion at the second reading.

By-Laws.

ARTICLE I.

REGULAR MEETINGS.

The regular meetings of the Club shall be held on the third Monday of each month in the year at 8 o'clock P.M. If, however, reasons of expediency occur for changing the day, week or hour, either or all may be so changed.

ARTICLE II.

ORDER OF BUSINESS.

The following Order of Business shall be observed at all regular meetings, unless set aside by a four-fifths vote of active members present; except the reading of the minutes, which is not to be omitted, except by a unanimous vote of those present.

1. The reading of the minutes of the previous meeting.
2. Reading proposals for new members; balloting for new members, previously proposed.
3. Unfinished business.
4. New business; reports of committees.
5. Literary exercises.

ARTICLE III.

SPECIAL MEETINGS.

The President may call a special meeting of the Club, when he deems it expedient, and shall be bound to do so at the written request of three (3) active members, stating the purposes of such meeting.

ARTICLE IV.

DONATIONS AND RECORD THEREOF.

A record of all donations to the Club, whether in money, books, maps, models or other articles of value, with the names of the donors shall be entered by the Secretary in a book provided for that purpose, and to be kept in the rooms of the Club; the articles themselves being turned over to the custody of the proper officers, and the Secretary shall acknowledge to the donors the receipt of the donations, with the thanks of the Club.

ARTICLE V.

VISITORS.

Any person, not a member, may be introduced to the rooms of the Club, or be invited to any of the regular meetings of the Club, by any member, and all visitors are requested to register their names in a book provided for that purpose.

ARTICLE VI.

CARE OF PROPERTY.

No property of the Club shall be removed from the custody of those to whom any such property is intrusted, until the trust is relieved by action of the Club.

ARTICLE VII.

RULES FOR LIBRARY.

The Librarian may make necessary rules for the use of the library, subject to the approval of the Club.

ARTICLE VIII.

ADDITIONS TO OR DUPLICATIONS OF BOOKS IN LIBRARY.

A book shall be kept by the Librarian in which members may enter the titles of any book or books they may wish to be added to the library or duplicated, and the Librarian is to report thereon for action of the Club at each regular meeting should occasion arise.

ARTICLE IX.

ACCESSIBILITY OF RECORDS.

The records of the Club shall at all times be accessible to any or all members, at seasonable hours.

ARTICLE X.

MANUSCRIPTS FOR PUBLICATION.

A copy of any communication from a member, if ordered to be printed by the Club shall be furnished to the Secretary by the author thereof on due notice to him by the Secretary.

ARTICLE XI.

LETTERS OF MEMBERSHIP.

Letters of membership shall be issued to any member of good standing who may wish to visit other similar Clubs or Societies in other cities.

ARTICLE XII.

DUES AND ASSESSMENTS.

The initiation fee shall be three (3) dollars, and *must* accompany every application for active or corresponding membership filed with the Secretary

No annual dues are called for until the Annual Meeting following the payment of initiation fee. The initiation fee covers the cost to all active members of a subscription to the JOURNAL of the ASSOCIATION of ENGINEERING SOCIETIES for the balance of the current year in which the initiation fee is paid. To active members the subscription is continued as long as annual dues are paid promptly.

Corresponding members, if they desire the JOURNAL are entitled to the same on payment of the subscription price of \$3 per annum. To honorary members it is sent free, commencing at the time of their reception into the Club.

The annual dues for active and also for corresponding members will be as approved of by the Club, on recommendations made from time to time by the Finance Committee.

Special assessments are made to active members only; and then only after a two-thirds vote of the active members present at any regular meeting; *provided* that notice of recommendation of same by Finance Committee shall have been sent to *all* active members one month previous to the regular meeting set for vote upon said special assessment.

ARTICLE XIII.

MEMBERS DELINQUENT AS TO THEIR DUES.

Active or corresponding members who are delinquent in their dues for over six months, may, if the Club think expedient, be dropped from the rolls.

ARTICLE XIV.

EXPULSION.

A member may be expelled from the Club by a two-thirds vote of the active members present at any regular meeting, a quorum voting; a notice stating causes of such proposed expulsion having been sent by the Secretary, at least one month previous, to all active members, including the members proposed to be expelled; *provided always* that on written application to the Secretary said member will be given a hearing, before action is taken by the Club; and *provided also*, that no movement toward expulsion take place until after a formal resolution of censure has been passed by the Club upon the member proposed for expulsion.

ARTICLE XV.

BLANKS AND FORMS.

The Secretary shall provide for all necessary blanks and forms to be used by the Club, but the forms of application for membership and certificates of membership shall be approved of by a majority of votes of all the active members present at any regular meeting; *provided* that in sending notice of such meeting, the Secretary will state thereon the fact that such forms will be presented for approval.

ARTICLE XVI.

AMENDMENTS.

These By-Laws may be amended by a two-thirds vote of the active members present at any regular meeting, a quorum voting; *provided* that the amendments were proposed at the previous regular meeting, and that the proposed amendment or amendments be stated on the notices sent by the Secretary announcing the date of the regular meeting at which action upon such amendment or amendments is to take place.

PAST OFFICERS OF THE CLUB

ENGINEERS' CLUB OF MINNESOTA.

DATE OF ELECTION.	PRESIDENT.	VICE-PRESIDENT.	SECRETARY AND TREASURER.	LIBRARIAN.
May 18, 1883.	Andrew Rinker.....	Wm. de la Barre.....	Wm. A. Pike.....	Geo. O. Foss.....
Jan. 25, 1884.	Wm. de la Barre.....	Geo. W. Cooley.....	Wm. A. Pike.....	Geo. O. Foss.....
Jan. 16, 1885.	Geo. W. Cooley.....	E. T. Abbott.....	Wm. A. Pike.....	W. W. Redfield.....
Jan. 8, 1886.	D. P. Waters.....	E. T. Abbott.....	W. S. Pardee.....	W. W. Redfield.....
Jan. 14, 1887.	Geo. W. Sublette.....	John H. Butt.....	W. S. Pardee.....	

THE MINNEAPOLIS SOCIETY OF CIVIL ENGINEERS.

DATE OF ELECTION.	PRESIDENT.	VICE-PRESIDENTS.	SECRETARY.	ASST. SEC. AND TREAS.	LIBRARIAN.
Feb. 1, 1888.	W. A. Pike.....	{ 1st, G. W. Sublette } { 2d, E. T. Abbott. }	W. S. Pardee.....	C. O. Huntress.....	W. W. Redfield.....
Jan. 2, 1889.	W. A. Pike.....	{ 1st, G. W. Sublette } { 2d, E. C. Deterly. }	W. R. Hoag.....	C. O. Huntress.....	W. W. Redfield.....

ENGINEERS' CLUB OF MINNEAPOLIS, MINN.

DATE OF ELECTION.	PRESIDENT.	VICE-PRESIDENT.	SECRETARY AND TREASURER.	LIBRARIAN.
May 7, 1890.	W. A. Pike.....	Wm. de la Barre.....	F. W. Cappelen.....	W. W. Redfield.....
Jan. 15, 1891.	W. A. Pike.....	T. P. A. Howe.....	F. W. Cappelen.....	A. B. Coe.....
Jan. 7, 1892.	W. A. Pike.....	W. W. Redfield.....	F. W. Cappelen.....	A. B. Coe.....
Jan. 12, 1893.	F. W. Cappelen.....	J. M. Hazen.....	Elbert Nexsen.....	A. B. Coe.....
Jan. 15, 1894.	F. W. Cappelen.....	J. M. Hazen.....	Elbert Nexsen.....	A. B. Coe.....
Mar. 18, 1895.	F. W. Cappelen.....	I. E. Howe.....	Elbert Nexsen.....	A. B. Coe.....
Mar. 2, 1896.	F. W. Cappelen.....	I. E. Howe.....	Elbert Nexsen.....	A. B. Coe.....
Jan. 27, 1897.	F. J. Llewellyn.....	I. E. Howe.....	Elbert Nexsen.....	A. B. Coe.....
Feb. 14, 1898.	F. W. Cappelen.....	I. E. Howe.....	Harry E. Smith.....	W. W. Redfield.....
Apr. 10, 1899.	F. W. Cappelen.....	E. H. Loe.....	Harry E. Smith.....	W. W. Redfield.....
Jan. 22, 1900.	G. W. Sublette.....	C. L. Pillsbury.....	Harry E. Smith.....	W. W. Redfield.....
Jan. 15, 1901.	W. W. Redfield.....	C. L. Pillsbury.....	Edward P. Burch.....	Jas. L. Carroll.....

May 9, 1884, Club voted to join the Association of Engineering Societies.

MEMBERS OF THE BOARD OF MANAGERS, ASSOCIATION OF ENGINEERING SOCIETIES, WITH DATE OF ELECTION.

July 18, 1884, Geo. W. Cooley.
 January 8, 1886, Geo. W. Cooley.
 January 14, 1887, Geo. W. Cooley.
 February 1, 1888, Andrew Rinker.
 January 2, 1889, Wm. de la Barre.
 May 7, 1890, Andrew Rinker.
 January 15, 1891, Andrew Rinker.
 January 7, 1892, Elbert Nexsen.
 January 12, 1893, Wm. A. Pike.
 January 15, 1894, Wm. A. Pike.
 March 15, 1895, Wm. A. Pike.
 February 3, 1896, Geo. D. Shepardson.
 January 26, 1897, Geo. D. Shepardson.
 February 14, 1898, Geo. D. Shepardson.
 April 10, 1899, Geo. D. Shepardson.
 January 22, 1900, W. R. Hoag.
 January 15, 1901, W. R. Hoag.

ORIGINAL CHARTER MEMBERS.

ANDREW RINKER, Great Falls, Mont.

WM. DE LA BARRE, Supt. St. Anthony Water Power Co., Minneapolis, Minn.

†WM. A. PIKE, State University, Minneapolis, Minn.

†JAS. WATERS, Chief Engineer Board of Water Commissioners, Minneapolis, Minn.

WM. W. REDFIELD, Engineer Water Department, Minneapolis, Minn.

GEO. O. FOSS, Civil Engineer and Contractor, Minneapolis, Minn.

I. C. PATTERSON, Civil Engineer.

H. M. WAITT, Civil Engineer.

E. T. ABBOTT, Civil Engineer, Minneapolis, Minn.

W. E. WESTON.

G. W. STURTEVANT.

S. H. BAKER.

GEO. H. WHITE.

C. E. SPRAGUE.

W. D. VAN DUZEE.

GEO. W. COOLEY, Civil Engineer and Surveyor, Minneapolis, Minn.

M. D. RHAME, Civil Engineer C. M. and St. Paul Ry.

†Now deceased.

ASSOCIATION OF ENGINEERING SOCIETIES.

VOL. XXVII.

SEPTEMBER, 1901.

No. 3.

PROCEEDINGS.

Boston Society of Civil Engineers.

BOSTON, MASS., SEPTEMBER 18, 1901.—A regular meeting of the Boston Society of Civil Engineers was held at Chipman Hall, Tremont Temple, at 7.50 o'clock P.M. President Bidwell in the chair; forty-five members and visitors present.

The record of the last meeting was read and approved.

Messrs. Charles H. Dodd, Hardy S. Ferguson, Walter B. Foster and Harry A. Storrs were elected members of the Society.

On motion of Mr. Higgins, the thanks of the Society were voted as follows: To Messrs. Winston Brothers and Locher, contractors at the Wachusett Dam, Clinton, for courtesies shown at the excursion on July 24; to Mr. E. B. Winslow, of the Portland Stoneware Co., for courtesies and generous entertainment during the excursion to Portland on August 17, and to the Fore River Ship and Engine Co., for courtesies extended this afternoon during the visit to the plant of that company.

In connection with the vote of thanks to Mr. Winslow, the President thought a concise statement of what we engineers learned on our visit to Portland, Me., of August 17, 1901, about the Portland Drain and Sewer Pipe, would be of interest to all engineers, as in almost all construction the matter of drainage must be taken into account, and he therefore submitted the following notes:

First, we found that about three-quarters of the clay used came from New Jersey, at a far greater cost than the remaining one-quarter, which came from ground within easy reach of the works; and that the New Jersey clay made a body that would, in stacking and burning, keep its shape, but pipe made wholly from the home clay would melt down; and that a mixture of the two gave the best results, as explained. From this it would appear that if the pipes were, when burned, in proper form, too much of the cheaper clay had not been used. Of course, the manufacturer would use as much of the cheaper clay as possible and make a perfect pipe; and, as this clay causes, when baked, the vitrification, the purchaser would, if he had no other guarantee, be quite sure that, if the pipe was in good shape and well baked, requiring only a simple inspection, he would get a strong and durable pipe. We also found that those pipes which were placed next the walls of the kiln, although when baked in windy or bad weather, would show a little lighter in color, the vitrification was even

deeper than on those of a darker color, which is an indication that they might be even more durable when light in color.

Further, we found that where formerly a large part of the work was piecework, now very nearly all is daywork; and that to obtain the most perfect product a very much less number of pieces were required for a good day's work from a workman than were formerly turned out under the piece system, notably in one case that of fitting and placing the branches, about 125 being expected where the same workman had under the piece system finished about 275 in a day, the object being to have each pipe as perfect as possible when it left the manufactory.

We also found that a die was partly made for producing a thirty-six-inch pipe, three feet in length and three and one-quarter inches in thickness. The use of vitrified pipe is constantly increasing, and we were told by the City Engineer of Portland that, notwithstanding the largely increased plant and output, he could not get a promise of delivery of twelve-inch pipe in less than three weeks. One of the reasons for this increased use over brick for sewers or drains is the smoother surface making less danger of clogging, and the fact that they can be placed by an intelligent man who could not command more than one-half a brick mason's wages.

As to the paving brick, we found them quite strong and apparently made and baked with great care, and made a very neat pavement. Some of our party seemed to think it doubtful whether they would stand under our Boston trucking, which is said to be heavier than in almost any other city. They have, however, been in use under heavy traffic at some place in Portland for three years and with slight wear; but this paving we did not see. Although more readily laid than granite, it is yet to be determined whether they will replace granite where it can readily be obtained, although the cost is less per square yard. In such places where the granite could not be readily had, certainly it would seem that they will be used, and they would work in well and make very neat approaches to buildings and drives across sidewalks, etc.

Mr. R. S. Hale offered the following resolution, which was adopted:

WHEREAS, It is probable that the American Society of Mechanical Engineers will hold its semi-annual meeting of 1902 at Boston,

Resolved, That the Boston Society of Civil Engineers will cordially welcome the American Society of Mechanical Engineers to this city.

Resolved, That the Board of Government be authorized to appoint a committee of five which committee shall have power to fill vacancies and add to its numbers, to co-operate with the local members of the American Society of Mechanical Engineers.

The paper of the evening was read by Mr. Arthur S. Tuttle, entitled "The Abolition of Grade Crossings on the Providence Division of the New York, New Haven and Hartford Railroad between Boston and Dedham."

The paper was illustrated by numerous lantern slides. In the discussion which followed the reading of the paper, Messrs. Rollins, Fitzgerald and Tuttle took part.

On motion of Mr. Kimball, the thanks of the Society were voted to Mr. Tuttle for his very interesting paper.

Adjourned.

S. E. TINKHAM, *Secretary*.

Engineers' Club of St. Louis.

529TH MEETING, SEPTEMBER 18, 1901.--Held at 1000 Locust street, President Spencer presiding. Attendance, twenty-four members and fourteen visitors. Minutes of the 528th meeting were read and approved. Minutes of the 312th and 313th meetings of the Executive Committee were read.

The applications for membership of Roderick H. Tait, Alexander S. Langsdorf, Benjamin Charles Milner, Jr., and Tyron Ervin Beebe were read and referred to the Executive Committee.

On ballot, John Innerarity Boggs was elected to membership.

A letter was read from a committee of the Missouri Historical Society with reference to securing among the buildings of the Louisiana Purchase Exposition a fireproof building to be used for housing the collections and libraries of the Missouri Historical Society, Academy of Science of St. Louis, and other scientific societies.

On motion of Mr. Ockerson, the following resolutions were adopted:

WHEREAS, It is understood that an effort is being made to secure, among the buildings needed for the Louisiana Purchase Exposition, one of fireproof materials, suitably located, and to be used after the Exposition for the housing in an accessible and instructive manner of the libraries and collections of the Missouri Historical Society, the Academy of Science of St. Louis, and other organizations devoted to history, archaeology, natural history, and other pure and applied sciences, and for meeting places for such organizations.

Resolved, That the Engineers' Club of St. Louis is heartily in favor of such effort and indorses the proposed ends, which, it is believed, are in the best interests of the community at large.

Resolved, further, That a committee of three be appointed by the chair without delay, authorized to represent this body, in connection with similar committees appointed by other organizations, in such action as may be necessary to secure the desired end.

Mr. J. A. Ockerson then read a paper entitled "The Mississippi River: Physical Characteristics and Methods of Improvements."

He gave a general description of the river and of the methods used to improve navigation and prevent overflow.

He gave statistics showing the traffic and tonnage on the river, and showed that while the traffic is now a much smaller percentage of the total of adjacent territory, it is still nearly as large as it was at its prime. The paper was accompanied by a large number of lantern slides, showing objects of interest along the river and illustrating methods used in its improvement.

On invitation of the president, Mr. A. V. A. Brueggeman, president of the Architectural Club, addressed the club with reference to obtaining downtown quarters in conjunction with the Architectural Club and the St. Louis Chapter of the American Institute of Architects.

Adjourned.

A light lunch was provided in the library room by the entertainment committee.

GEORGE I. BOUTON, *Secretary pro tem.*

Montana Society of Engineers.

A REGULAR meeting of the Montana Society of Engineers was held in Rooms 16 and 17, Tuttle Block, Butte, Mont., on September 14, 1901. The following members were present: Messrs. Harper, Patterson, Blackford, Putnam, Blossom, McArthur, Strasburger and R. R. Vail. Visitors, Messrs. Summers and Brotherton. Mr. F. W. Blackford was elected chairman *pro tem*.

The minutes of the last meeting were read and approved.

Mr. Eugene Sickles then gave a very interesting talk on the subject of "Electrical Current Transmission."

Moved and seconded that the Society adjourn until 8 P.M., September 21, 1901. Carried.

On September 21, the Society met at their headquarters with the following present: Messrs. Blackford, Christian, Harper, Moulthrop, Leonard, Patterson, McArthur, Flood, Koberle, Dunshee and R. R. Vail. Mr. Christian, First Vice-President, in the chair.

A committee of three was appointed to nominate officers for the ensuing year as follows: Messrs. F. W. Blackford, C. W. Goodale and Samuel Barker, Jr.

A short discussion of the financial condition of the Society followed. Moved by Mr. Blackford and seconded by Mr. Harper, that the Secretary be instructed to prepare statement of accounts with an estimate of expenses and present to the trustees for their consideration. Carried.

Society adjourned.

RICHARD R. VAIL, *Secretary*.

ASSOCIATION OF ENGINEERING SOCIETIES.

VOL. XXVII.

OCTOBER, 1901.

No. 4

PROCEEDINGS.

Technical Society of the Pacific Coast.

REGULAR MEETING, AUGUST 2, 1901.—Called to order at 8.30 P.M. by Past-President C. E. Grunsky. The minutes of the last regular meeting were read and approved.

Dr. C. S. G. Nagel thereupon delivered a lecture on the mechanical structure of the eye, treating its anatomical and optical features, and explaining in detail the modern methods of eye operations. This subject was discussed by members present.

The President thanked Dr. Nagel in the name of the Society for his interesting and instructive lecture.

Adjourned.

OTTO VON GELDERS, *Secretary*.

REGULAR MEETING, AUGUST 15, 1901.—The Technical Society invited its members to visit the destruction of Arch Rock, in the harbor of San Francisco, which took place at 12.10 P.M. The members and their guests were conveyed in a steamboat to a point in the bay where the most advantageous view of the explosion could be had.

After the blast, the party was taken to the locality of the one-time formidable rock, upon which the steamboat returned to the wharf.

OTTO VON GELDERS, *Secretary*.

REGULAR MEETING, SEPTEMBER 6, 1901. Called to order at 8.30 P.M. by Thos. Morrin. The news having been received, just prior to the meeting, of the attempted assassination of President McKinley, the desire was expressed that business only be transacted, and that all technical discussion be postponed.

Mr. Morrin called attention to the matter of the Technical Society transferring its rooms to the Mechanics' Institute Building and becoming a part of the institute, without losing its identity as a society or its membership in the Association of Engineering Societies. Every member of the Technical Society would become a member of the institute, and have the benefit of the very extensive technical literature of the Mechanics' Library without any increase in dues, and without the loss of a single one of those advantages to which his membership in the Technical Society entitled him.

Mr. Irving, President of the Mechanics' Institute, explained at length the present condition of the institute, financially and socially, and indicated that the members of the Technical Society might become a very important element in the transactions of the institute, which, by reason of its great wealth, could offer them many advantages that the Society could not now afford.

There being but a small number present at this meeting, it was thought advisable to take no definite action, but to appoint an investigating committee of three or four members to meet a similar committee from the institute and submit to the Technical Society some formulated project by which an affiliation of the nature suggested this evening might be consummated. Three members were appointed on this committee,—Stetson G. Hindes, J. G. H. Wolff and Hermann Kower, to which Mr. Luther Wagoner was added subsequently.

This committee is to report upon the probable result of such change, so vital to the interests of the Society, and to make a full statement to the Board of Directors, who will present the matter to the members of the Society if it be thought desirable to entertain the proposition.

Meeting adjourned.

OTTO VON GELDERN, *Secretary*.

REGULAR MEETING, OCTOBER 4, 1901.—Called to order at 8.30 P.M. by Vice-President Henry.

The minutes of the last regular meeting were read and approved.

The following applications were received and referred to ballot, having been approved by the Board of Directors:

Charles E. Wetherell, surveyor, of San Francisco, proposed by C. E. Grunsky, H. D. Connick and F. C. Herrmann.

Dr. C. S. G. Nagel, scientist, of San Francisco, proposed by Otto von Geldern, D. C. Henny and J. H. G. Wolf.

The Chairman stated that this meeting had been set aside for the purpose of discussing the important proposition of affiliating with the Mechanics' Institute, and that the committee having investigated the proposition upon its advantages and disadvantages, would report at once to bring the matter intelligently before the meeting for earnest discussion.

The committee thereupon reported as follows:

"SAN FRANCISCO, CAL., October 4, 1901.

"To the President and Members of the Technical Society, San Francisco, Cal.

"GENTLEMEN: Your committee appointed at the regular September meeting for the purpose of investigating the conditions and desirability of affiliating with the Mechanics' Institute has the honor to report as follows:

"Two meetings have been held, the first on September 11 in these rooms, at which the essential points to be observed in considering the proposition were carefully gone over and noted. One week later our committee met the Library Committee at the Mechanics' Institute rooms and discussed minutely the conditions and requirements pertaining to the proposition of affiliation.

"We found that the new policy of the Institute favored the fostering of all scientific and engineering societies of the city. The Institute expects in the near future to put up a new building in which adequate provision will be made for any such societies.

"The absolute identity of the Technical Society, which is of supreme importance, would be preserved, and our relation to the Institute would be that of a tenant. The proposition as outlined would be to give up these quarters and move to the Institute, thus avoiding paying rent. All regular

active members and the resident associate members would be entitled to all the privileges of Institute membership, and in fact would be regular members, for which the Technical Society would pay 50 cents per month for each of these members. They would have a vote in the affairs of the Institute and would be entitled to take books from the library.

"It is found that the amount saved in rent, etc., would just about equal the amount to be paid the Institute in membership dues, so that the Society would be at no greater expense than at present and would be able to give its members additional privileges and benefits.

"This Society would manage its own affairs exactly as at present, collect its dues, and continue to furnish its members with copies of the JOURNAL OF THE ASSOCIATION OF ENGINEERING SOCIETIES, and it would still remain a member thereof.

"The assembly hall in the Library Building is a large-sized room, and well adapted to our purposes, and could always be had on the regular meeting night,—viz, the first Friday of each month, as well as at other times if desirable. There is also a room available as an office where the records of the Society could be kept, and its business transacted.

"The Institute desires to keep up its technical and scientific side, as there is a great tendency for the fiction portion to be always in the supremacy. And it is believed that by taking in our Society, our members will be encouraged to take an active part in the affairs of the Institute, and will be able to add to its success as one of the prominent institutions of San Francisco.

"It would also appear that a number of new members might be acquired who are already Institute members, and who would willingly pay the 50 cents additional dues required by the Technical Society. This would apply especially to the younger men, who might not feel like maintaining membership in both organizations as at present at an expense of \$1.50 per month.

"As about one-half of the Technical Society members are already members of the Mechanics' Institute, these would save their present Institute dues, amounting to 50 cents per month. Non-resident members and non-resident associate members who now pay dues of 50 cents per month into this Society would not be full members of the Institute, and could not take out books; but they would have the JOURNAL and the privilege of attending all meetings and voting in the Technical Society just as at present.

"The Society would have to pay an admission fee of \$1 for each member not already a member of the Institute. This would amount to about \$35, and could be paid out of the funds now in the treasury.

"Our books, while always remaining our property, could be put upon the shelves of the library for circulation, and any of our periodicals not already possessed by the Institute would be bound at their expense.

The committee has carefully considered the various phases and believes the advantages to be much greater than any disadvantages, and would recommend the affiliation of the Technical Society with the Mechanics' Institute.

"STETSON G. HYNDES,

"J. H. G. WOLF,

"HERMANN KOWER,

"LUTHER WAGONER,

"Committee."

A discussion was then started, which was opened by Mr. S. C. Irving, President of the Mechanics' Institute, who held out the advantages that would be gained by the Society in affiliating with the Institute, whose policy is to foster mechanical art and engineering science, and who had ample funds for the purpose of inaugurating serious work along lines of technical importance. Other members followed, the general opinion being expressed that the proposition had its merits, and that there were many mutual advantages and possibilities.

President Marx expressed in writing to the Secretary his entire sympathy with the project, taking it for granted that the base of the affiliation would be that outlined in the circular letter to members dated September 26, 1901.

It was finally moved by Mr. Grunsky, and duly seconded, that it be the sense of this meeting that the Technical Society affiliate with the Mechanics' Institute on the lines indicated by the committee in its report, and that a copy of this report, together with a statement of the proceedings of this meeting be mailed to every member of the Technical Society, with a request for an individual vote in favor of or against the proposition. Motion was carried.

It was then moved by Mr. Wagoner, and duly seconded, that if the vote upon this question be favorable, the Board of Directors be instructed to carry out the work of the proposed affiliation in the manner outlined by the special committee, which is to have further time and continue its work until the rendering of the final decision. Carried.

Meeting thereupon adjourned.

OTTO VON GELDERN, *Secretary*.

Engineers' Club of St. Louis.

530TH MEETING, OCTOBER 2, 1901.—Held at 1600 Locust Street at 8 P.M.: President Spencer presiding. Attendance, thirty-three members and twenty-five visitors. Minutes of the 529th meeting were read and approved. Minutes of the 314th meeting of the Executive Committee were read.

The applications for membership of Charles Wm. Roehrig, George Eugene Wells and C. D. Purdon were read and referred to the Executive Committee.

On invitation of the President, Mr. A. V. A. Brueggeman, President of the Architectural Club, addressed the Club, giving further information with reference to obtaining down-town quarters in conjunction with the Architectural Club and the St. Louis Chapter of the American Institute of Architects.

On motion of Mr. Bryan, which was duly seconded, the Executive Committee of the Engineers' Club was authorized to confer with the St. Louis Architectural Club and with the St. Louis Chapter of the American Institute of Architects regarding arrangements for down-town quarters, and requested to report at the next meeting. The motion was carried.

Mr. William H. Bryan then read the paper of the evening, entitled "Smoke Abatement in St. Louis." Mr. Bryan gave a brief history of the movement in St. Louis, and of the prominent part taken in it by the Engineers' Club. He stated clearly the difficulties which have been encountered and the results which have been accomplished to the present time.

Regarding fuels it was shown that the cost of smokeless fuels was beyond the reach of the ordinary consumers and that the problem resolved itself into burning the ordinary fuels smokelessly.

Smoke-preventing devices were discussed and classified as follows: Steam jets, coking furnaces or fire brick arches, down-draft furnaces, automatic stokers and powdered fuels. Each in turn was described and illustrated by numerous lantern slides. It was stated that while no one device was applicable to all furnaces, some one or more would be found for each furnace which would work successfully, providing it was intelligently operated and maintained.

The hope was expressed that the problem would be so effectively handled by the World's Fair authorities as to give an object lesson to the world.

Discussion was participated in by Messrs. C. E. Jones, Joseph A. Wangler and Mr. Dan. C. Nugent and Eugene McQuillin, of the Citizens' Smoke Abatement Association.

Adjourned to the library room, where lunch was served.

E. B. FAY, *Secretary pro tem.*

531ST MEETING, OCTOBER 16, 1901. - Held at 1606 Locust Street at 8 P.M.; President Spencer presiding. Attendance, thirty-four members and seven visitors. Minutes of the 530th meeting were read and approved.

Applications for membership of Ben F. Adleck and James C. Travilla were read and referred to the Executive Committee.

On ballot the following were elected to membership: Charles W. Roehrig, George E. Wells, Charles D. Purdon, Tyron Ervin Beebe, Roderick H. Tait, Benjamin C. Milner, Jr., Alexander S. Langsdorf.

Mr. J. H. Kinealy, for the Executive Committee, made a report regarding securing downtown quarters in conjunction with the St. Louis Architectural Club and the St. Louis Chapter of American Institute of Architects. He stated that suitable quarters could be obtained in the Howard Building, and submitted a proposed plan of new quarters, together with information regarding the sizes of rooms as compared with the present quarters, probable cost, etc. He stated that the members of the Executive Committee were unanimously in favor of making the move and of making arrangements with the Clubs mentioned. After considerable discussion motion was made and carried to defer final action until the next meeting and make the question a special order of business at the next meeting, all members of the Club being notified.

The subject of the evening was a paper by Mr. George I. Bouton on "Stair Lifts." A detailed description of the various lifts which are manufactured and used in the United States was given. The paper was illustrated by numerous lantern slides, showing the various kinds of lifts in operation in department stores and elevated railroad stations. A statement was given regarding the power required for operating and the cost of installation. Discussion was participated in by Messrs. Ockerson, Borden and Bouton.

On conclusion of the paper letters were read from the Public Welfare Commission, addressed to the President, as the Club's representative on the commission, requesting such service as could be rendered in aid of the proposed charter amendments, and requesting the signature of as many voters as could be reached to the appeal which accompanied the letter. President Spencer stated that copies of the appeal would be found on the Secretary's table in the library room, and he hoped that all members of the Club would sign it.

Adjourned to the library room, where lunch was served.

E. B. FAY, *Secretary pro tem.*

Boston Society of Civil Engineers.

BOSTON, MASS., OCTOBER 16, 1901.—A regular meeting of the Boston Society of Civil Engineers was held at Chipman Hall, Tremont Temple, at 8 o'clock P.M.; President L. B. Bidwell in the chair; forty-eight members and visitors present.

The record of the last meeting was read and approved.

Messrs. E. Roland Simpson and John B. Wright were elected members of the Society.

A communication was read from the Secretary of the American Park and Outdoor Art Association in relation to its proposed annual convention to be held in Boston in August, 1902, and suggested that some uniform action might be taken by the several kindred organizations in this neighborhood in the way of entertainment during the convention. On motion of Mr. French, the whole subject was referred to the Board of Government.

On motion of Mr. Higgins, the thanks of the Society were voted to the civil engineers located at the Navy Yard for courtesies shown the members of the Society during the visit to the Navy Yard this afternoon.

Prof. William Carey Poland, of Brown University, was then introduced and gave a very entertaining and instructive talk, illustrated by numerous lantern slides, entitled "The Development of Artistic Forms in Architecture from Elements of Construction."

At the conclusion of the talk, on motion of Mr. Rice, the thanks of the Society were voted to Professor Poland for his interesting lecture.

Adjourned.

S. E. TINKHAM, *Secretary*.

ASSOCIATION OF ENGINEERING SOCIETIES.

VOL. XXVII.

NOVEMBER, 1901.

No. 5

PROCEEDINGS.

Engineers' Club of St. Louis.

532D MEETING, NOVEMBER 6, 1901.—Held at 1600 Locust Street at 8.15 P.M.; President Spencer presiding. Attendance, thirty-seven members and six visitors. Minutes of the 531st meeting were read and approved. Minutes of the 315th meeting of the Executive Committee were read.

Mr. Ockerson, chairman of the committee appointed to confer with the committees of the Missouri Historical and other societies regarding obtaining a permanent fire-proof building from the Louisiana Purchase Exposition Company for housing libraries, etc., reported that a meeting of the committees which had been called for some days before had been postponed indefinitely, and from what he could ascertain they had no building in mind, and if such a building was obtained it would be located in Forest Park.

Mr. Kinealy, for the Executive Committee, made a report regarding securing downtown quarters, repeating the report made at the last meeting and also giving additional information regarding the cost of furnishing the new quarters. After considerable discussion a motion was made by Mr. Bryan, which was amended by Mr. Flad; the amended motion was as follows: "That the recommendation of the Executive Committee in the matter of securing downtown quarters in association with the St. Louis Chapter of the American Institute of Architects and the St. Louis Architectural Club be approved, and that the Executive Committee be authorized to arrange all necessary details." This motion was seconded, but before it was put to a vote there was further discussion by Messrs. Wheeler, Ockerson and Bryan, after which the motion was voted upon and carried.

The application for membership of Myin D. Reed was read and referred to the Executive Committee. On ballot Messrs. Ben F. Affleck and Jas. C. Travilla were elected to membership.

Owing to the unavoidable absence from the city of Mr. H. H. Humphrey, who was to have read a paper on "Uses of Beaumont Oil," Mr. Alex. S. Langsdorf kindly addressed the Club on the subject of "Iron in Alternating Current Circuits." He discussed the curves of magnetization, loops due to hysteresis, and described a simple method of obtaining the co-efficient of self-induction. Discussion was participated in by Messrs. Kinealy, Klauder and Langsdorf.

Adjourned to the library room, where lunch was served.

E. B. Fay, *Secretary pro tem*

Technical Society of the Pacific Coast.

REGULAR MEETING, NOVEMBER 1, 1901.—Called to order at 8.30 P.M. by President Marx.

The minutes of the last regular meeting were read and approved.

The tellers appointed opened the ballots, and counted the vote cast on the proposition to affiliate with the Mechanics' Institute, on the lines indicated in the Special Committee's report, circulated to members, under date October 25, 1901, with the following result: Total vote, 77; for, 75; against, 2.

The President thereupon declared the proposition carried, and instructed the committee to make all arrangements to enter upon this agreement by December 1, 1901.

The following were elected to membership upon a count of ballots: Thos. E. Wetherell, surveyor, of San Francisco; Dr. C. S. G. Nagel, scientist, of San Francisco.

Prof. F. G. Hesse delivered an address, demonstrating mathematically the "Efficiency of the Compound Centrifugal Pump."

A discussion followed, which was reported by the stenographer.

Meeting thereupon adjourned.

OTTO VON GELDERN, *Secretary*

ASSOCIATION OF ENGINEERING SOCIETIES.

VOL. XXVII.

DECEMBER, 1901.

No. 6.

PROCEEDINGS.

Engineers' Club of Cincinnati.

125TH REGULAR MEETING, CINCINNATI, OHIO, JUNE 20, 1901.—Dinner was served at 6.30 P.M.

The regular meeting was called to order at 8.00 P.M.; President Jewett in the chair, and fourteen members present.

Minutes of the meeting of May 23 were read and approved.

Resolutions on the death of Alfred Petry were presented by the committee as follows:

Death having removed one more name from the rolls of this Society, be it

Resolved, That we, the friends and fellow-members of Alfred Petry, place on record our sincere regret and feeling of deep loss sustained by his untimely death; further be it

Resolved, That we extend our heart-felt sympathy to his sisters; and, further, be it

Resolved, That these words be entered upon the minutes of this Society, and that a copy hereof be sent to his sisters;

which, on motion, was ordered received and spread upon the minutes of the meeting, and a copy forwarded to his relatives, as provided.

Mr. C. A. Keller, representative of the Scherzer Rolling-Lift Bridge Company, of Chicago, read a paper on "The Rolling-Lift Bridges at Cleveland, Ohio."

Mr. Keller described, with the aid of the stereopticon, the two railroad bridges, one a single leaf and the other a double leaf structure, recently constructed by his company over the Cuyahoga River at Cleveland, on the line of the C., C., C. and St. L. Ry. under the direction of Mr. G. W. Kittredge, chief engineer of that road. These bridges replace the old wooden swing bridges that had been in use for a number of years, and needing renewing, the rolling-lift bridge was selected as the best type filling all the requirements.

After a vote of thanks to Mr. Keller for his paper, and a discussion of the same, the Club adjourned.

J. E. WILSON, *Secretary*.

126TH REGULAR MEETING, CINCINNATI, OHIO, SEPTEMBER 26, 1901.—Postponed from the 10th on account of and out of respect to the death of President McKinley, whose funeral occurred on that date.

Supper was served at 6.20 P.M.

The regular meeting was called to order at 7.30 P.M. with President Jewett in the chair and nine members present.

Minutes of the meeting of June 20 were read and approved.

The following papers were read:

(a) Elevators. By O. F. Shepard, Jr., being an extempore talk on the subject of the construction and operation of elevators, principally electric, as practiced by the Warner Elevator Manufacturing Company.

(b) Operating Machinery by Electricity. By Louis E. Bogen, in which he showed the application of electric motors in the operation of machinery and machine tools.

After a short discussion of the subjects, as the hour was getting late, and a vote of thanks to the speakers, the meeting adjourned.

J. F. WILSON, *Secretary*.

127TH REGULAR MEETING, CINCINNATI, OHIO, OCTOBER 19, 1901.—Supper was served at 6.30 P.M.

The regular meeting was called to order at 7.20 P.M. with President Jewett in the chair, and ten members present.

Minutes of the meeting of September 26 were read and approved.

Mr. C. W. Johnson, chief draftsman of the engineering department of the Bullock Electric Manufacturing Company, favored the Club with a talk on the subject of "Indexing of Drawings," which comprised a thorough and interesting account of the very complete system of filing and indexing the large number of plans covering the great variety of work turned out by that company, and which contained much of interest to those present.

After a discussion of the subject and a vote of thanks to Mr. Johnson the meeting adjourned.

J. F. WILSON, *Secretary*.

128TH REGULAR MEETING, CINCINNATI, OHIO, NOVEMBER 21, 1901.—Dinner was served at 6.15 P.M. The regular meeting was called to order at 7.30 P.M., with President Jewett in the chair and eighteen members present.

Minutes of the meeting of October 19th were read and approved.

The minutes of the meeting of the Executive Board, held November 16th, were read, in which recommendations were made providing for the withdrawal of the Club from the Association of Engineering Societies, the reduction of the amount of the annual dues, and changing the hour of meeting. These questions were discussed at some length, and to indicate the preference of those present, a vote was taken, resulting as follows: Continue membership in the Association, yes, 4; no, 14. Reduce annual dues, yes, 14; no, 4. Change meeting hour, yes, 8; no, 8.

It was finally decided proper to submit these matters to a vote of the entire membership, amendments to the By-laws being involved, which the Secretary was directed to do, with a circular explanatory of the situation, embodying in it the result of the vote above noted, the amount of the dues and the hour of meeting recommended being those in vogue before the changes made at the annual meeting in December, 1898.

The question of instituting a "Junior" class of membership, which was also suggested at the Executive Board meeting, was taken up and discussed,

Mr. Bogen presenting the following: "Amendment to the Constitution is proposed, as follows: That the grade of 'Junior' member be established and that the dues be one half that for full membership."

As amendments to the Constitution can only be made at an annual meeting, the matter is in order for the December meeting.

The paper for the evening was read by Mr. James A. Lilly. It had been announced under the title of "Paint and Painting," but as an introduction, Mr. Lilly stated that in its preparation he had found the paper grow to such an extent that he had concluded to divide the subject and confine himself to the first word of the title "Paint."

This he did in a very exhaustive and entertaining manner, going thoroughly into the merits of paints of various kinds, and the analysis and composition of the component parts of paints, pigments, oils, etc., and their manufacture.

After a discussion of the subject, participated in by Messrs. Gordon, Bogen, Morris, Jewett, Wulff, Warrington, Lilly and others, and a vote of thanks to Mr. Lilly, the meeting adjourned.

J. F. Wilson, *Secretary*.

14TH ANNUAL MEETING, CINCINNATI, OHIO, DECEMBER 19, 1901. Dinner was served at 6.30 P.M. The regular meeting was called to order at 8.10 P.M., with President Jewett in the chair and seventeen members present.

Minutes of the meeting of November 21 were read and approved.

On motion the Chair appointed Messrs. Miller and Warrington a committee to canvass the votes received on the matters presented at the November meeting, and which had been submitted to letter ballot. The committee reported the result of the ballot, as follows: Continue membership in the Association of Engineering Societies, yes, 11; no, 24; total 35. Amend By-laws to provide for reducing amount of annual dues, yes, 26; no, 7; nil, 2; total, 35. Amend By-laws to provide for changing hour of meeting, yes, 17; no, 14; nil, 4; total, 35. Not counted, 3 votes unsigned. Upon which it was announced that it had been elected that the Club withdraw from the Association of Engineering Societies; that the annual dues and the time of meeting be restored to those prevailing before the change made at the annual meeting on December 15, 1898.

The question of proper amendments to the Constitution and By-laws to cover the proposed creation of a "junior" class of membership, presented at the November meeting, and also the changes as to annual dues and time of meeting, was discussed at some length, resulting in the appointment of Messrs. Bogen and Nicholson as a committee to prepare the same.

A proper resolution embodying the necessary amendments was submitted by the committee and adopted.

On motion to that effect it was resolved that the old custom of providing a light lunch after the meeting be observed in the future.

The Secretary and Treasurer presented his reports for the year 1901, which were accepted and ordered printed for distribution to the members. The report of the Secretary shows a reduction in average attendance from 16.3 in 1900 to 14.6 in 1901, the addition of five new members during the year, and a decrease in membership of 1 by death, 7 by resignations and 2 members dropped for non-payment of dues, leaving the total membership at the end of the year 82 as against 92 at the end of the previous year.

The Treasurer's report shows receipts of \$605 and disbursements of \$621.48, and a balance of \$327.12 at the end of the year.

Officers for the year 1902 were elected as follows:

President—Louis E. Bogen.

Vice-President—A. O. Elzner.

Directors—H. E. Warrington, C. H. Meeds, Jas. A. Lilly.

Secretary and Treasurer—J. F. Wilson.

The retiring President, Mr. Wm. C. Jewett, read an address, taking for his topic a discussion of the affairs of the Club.

ADDRESS OF RETIRING PRESIDENT.

Gentlemen, of the Engineers' Club of Cincinnati.—First let us congratulate ourselves upon the selection of our President for the coming year. The choice is a wise one, and he will no doubt be the means of putting new life into the Club, an element of which we are sadly in need.

It has often occurred to us during the year that our members were losing interest in the Club, and in our discouragement we have examined the Secretary's reports, and to our pleasure find that our attendance is really above the average. It is true that we have lost in membership, but the proportion of actual members who have attended the meetings during the year has equaled that of similar societies. This proves that those who have remained with us have retained their interest in the welfare of the Club, and have performed their share of the work necessary to keep the Society alive.

The close of the year 1895 gave us the largest membership. The average attendance for that year was 20 per cent. of the members. Last year, with a membership of eighty-eight, we had an attendance of 19 per cent., from which it may readily be seen that the interest is maintained. The attendance of the November and December meetings show such an increase in the number present and such an activity among the members that it gives us every reason to believe we are to have a real revival. Let us continue this good work and see if we cannot have, not only a technical club, but a scientific one of value to the profession.

Section 2, Article II, of the Constitution, says that "an active member shall be a civil, military, mining, mechanical, electrical or hydraulic engineer." This covers the entire profession of engineering, making all engineers eligible to membership.

Let us glance at our list of members and see of what our society is composed. We have civil engineers, 59; mining engineers, 1; mechanical engineers, 10; electrical engineers, 3; architects, 1; associate members, 10. A total membership of 84. The civil engineers are largely in the majority, but we consider the number entirely too small when we see how many are engaged in the profession in this city, and how many young men should be associated with us who have taken up engineering as a profession. The small number of mining engineers is easily accounted for, as this is an agricultural region only. But in our midst are many factories, and these must employ many mechanical engineers and we certainly should have more than ten in our list of members. In fact I do not hesitate to say that our Club should have equally as many mechanical as civil engineers. In a city of this size we certainly should have a better representation in our Club of electrical engineers. Those we have are very active and interesting members, and a larger number would benefit all of us. We have but one architect with us, and he is one of our most active members. Now if he could only persuade a

few of his brethren to join us, we would have some valuable material added to our Society. The modern building requires not only the services of the architect, but those of the civil engineer as well. They are often interested in the same work, and if they were associated in the same technical society an interchange of ideas would be of benefit to both.

Our associate members have in many cases been active and regular attendants of the meetings. Would it not be well to bring more of them into our Society?

There is little doubt but that the creation of the "junior" grade in the Club will result in great benefit, not only to the juniors themselves, but to the Society at large. There are many young engineers and draftsmen that would unite with the Society in the proposed new grade that would not and could not enter as full members. This may be the means of adding many of the young engineering students from the university. They would be interested, add new life to the Society, and undoubtedly derive much information from the discussions of the older and practicing engineers.

Let us see if we cannot induce the coming engineers to spend a few evenings with us each year, for it will be only a short time until they will fill our places.

There appears to be a great dearth of papers in the Club, and when we note the number that have been furnished by friends during the past two years, it would seem that our Club is not capable of producing ten papers per year. But this is not true; a glance at the list of members tells us that there is not one who could not only write and read an interesting paper, but he could at the same time impart valuable information on the subject that is his especial work. Each engineer has his particular work, which differs materially from that of any other engineer. On this he devotes his entire time, thinking and investigating, spending many hours reading and studying, until he gathers ideas of other engineers; out of this mass of information he evolves new ideas and methods to suit his individual work. Now if the result of his labors was written in a short paper, and presented to the Club, there would be a record of his work which might otherwise be lost. Let as many members as possible prepare a paper this year, no matter how short. If we have more than can be read this year, we can have them next. Our custom has been to write long papers. During our present prosperous times, we are all so busy that few can devote the time necessary to write a formal paper that would require three-quarters of an hour to read. But most of us can write a five-minute paper, which would prove very interesting; and instead of one long paper two or three short ones could be read. Very often the shortest paper promotes the longest discussion. Let each member assume that he has a duty to perform, and if he performs that duty our Club will grow and flourish. We become interested in that for which we work. In these short papers we would learn much of each other's methods.

Our mechanical and electrical members could each tell us of some machine he had designed or constructed. The latter have given us some very interesting and instructive papers during the year, which we all appreciate. Each engineer could tell us of some structure he had built. He often spends weeks upon the design of a structure; while so doing has carefully studied into the methods of others and entirely new thoughts have occurred to him that would be most interesting to his brother engineers.

In choosing subjects let us not fail to consider the simple ones. They are the ones which often trouble us the most. Take what appears to be a very simple subject,—the mixing of concrete.

An entire evening could be spent upon the discussion of this subject with profit to all. There are many ways of doing this and each engineer has his own method and his reasons for considering his method the best. Unequal foundations for large structures. Every engineer has had this problem to solve, and he has in many cases found it a very difficult one. Having solved his problem satisfactorily, he has built his structure, which has settled equally, as all structures should, without cracking. He congratulates himself upon his success. Why should he not tell us how this was done and describe the method of preparing the foundation, that other members may profit by his experience? While on this subject, let us say to the members present that it is of the utmost importance that an engineer give his personal attention to the preparing of the foundations for important structures and that they should use every precaution for its stability. If this were done, we would have fewer failures of structures, accounts of which we read every week in our technical journals. Important matters of this kind cannot be left to the younger engineer, as he lacks the necessary experience which he must acquire with age. As an example, one structure that failed from lack of proper attention by the engineer in charge; although he may have used his best judgment, he failed in making a thorough examination. This was the pivot pier of a bridge in a small river. The pier was sunk to within three or four feet of rock, where it was stopped, resting on a bed of gravel. The pier, acting as an obstruction, caused the current to undermine the foundation, resulting in the pier settling on one side and standing at such an angle that it was necessary to take down the entire structure and reconstruct it on a rock foundation, as should have been done at first.

Earth dams; how should they be constructed? This is becoming a very important subject in this country, and up to a reasonable height this method of impounding water is largely used on account of the small cost. Nearly every engineer of experience has built earth dams, each using slightly different methods. Why not have a short paper on the subject and a lengthy discussion? It is true we can find numerous professional papers on earth dams, but at the same time a discussion may bring out thoughts that cannot be found elsewhere.

The best method of laying sewer pipe and inspection of the same. This is apparently a very simple problem, but to have sewer pipe properly laid is one of the most difficult tasks that an engineer has to perform, and the back filling of the trench takes all of his patience; and then very often after the first rain he will see the surface settle. This requires the very best inspection and supervision, and even then there is a constant fight to secure perfect results.

How to run a straight line. Every engineer has had this problem to solve, and all of us could profit by the experience of others. Easy? Not so easy either, rich in thought and one of the most difficult problems in railway location. Many a man has spent the evening and night studying how to hit a point five miles off, and after he has hit the point he has the problem of finding out if the line is a straight one. Usually it is not, and he must work on it until he has the proof that it is straight. The long tangents of many of the older railways are full of kinks, generally one at every summit and sag. This may be seen on many of the older railways in northern

Ohio. Engineers now spend more time on their tangents, and I believe usually have them reasonably straight.

Only a few of the subjects with which we are all so familiar have been mentioned to present to you; how simple a matter it would be for us to make our Club a most interesting one, if each of us would contribute a short paper during the year. Many societies require that a paper must be prepared and read by each member in his turn.

Most Clubs prepare a program at the beginning of each year, a committee being appointed to attend to the preparation. This is published in the annual volume. In this way the subject of each meeting is known far in advance. There is no doubt that this knowledge of the subject gives the members time to gather their information and come prepared for spirited discussions. I have in mind a woman's club of only twenty members that meets monthly. Their program is made up at the beginning of each year; it is an elaborate one and is carried out to the letter at each meeting, with a majority of the members present, all of whom take an active part in the literary discussions. I would suggest that the preparation of a program in advance, by a committee, be given a trial in this Club. The committee could communicate with the members who are willing to contribute papers, and the subjects could be published in the annual report and list of members.

Since we have decided to withdraw from the Association of Engineering Societies, it might be suggested that to take the place of that publication in our Society that we publish an annual volume, in which should be given a list of members, annual report, proceedings of the meetings and such papers as the members may furnish for publication. With a reduction of the dues this may not be possible, but we might consider the matter and meet the cost by other means.

We have a small library which in its present inaccessible condition is of little value to the members. A bookcase at a cost of thirty dollars and a few dollars each year for binding of periodicals would place the books where they would benefit the members. Some member who is interested in such matters might be persuaded to classify and index the library. A system of putting the books in circulation among the members should be devised and a librarian appointed to look after this particular work. The Secretary already has his hands full and should not be expected to take charge of the library.

An excellent feature of many technical societies is that of visiting, in a body, shops and public works under construction. Many Saturday afternoons could be profitably spent in this manner, and would result in greater sociability among the members. If it became known that our Club was in the habit of making these visits, many large shops and factories would possibly extend invitations to us. In fact many of our members are connected with these plants and would no doubt take pleasure in showing us through their works.

We may read of the methods used in the manufacture of a twelve-inch pipe, but we may never thoroughly understand the process and comprehend the details until we see the work actually performed. This may be said of nearly every piece of work. We have here one of the largest pipe foundries in the country, which might be visited with profit. There are large electrical plants and factories for the manufacture of electrical machinery, extensive machine shops; in fact nearly all branches of manufacturing are largely represented in Cincinnati.

One of our mechanical members has a model shop in the west end, for the manufacture of machine tools, that might be visited with profit to all. We have large railway plants, and extensive municipal improvements are under construction, all of which would be of interest, no doubt, to the members.

The time has now come for me to resign the chair to my successor. My great desire is to see him in every way successful, and that the Club may thrive under him as it has never done before.

Gentlemen, I thank you for your assistance during the year and your kind attention this evening.

J. F. WILSON, *Secretary*.

Boston Society of Civil Engineers.

BOSTON, MASS., NOVEMBER 20, 1901.—A regular meeting of the Boston Society of Civil Engineers was held in the Society's library at 8 o'clock P.M.; 8 o'clock P.M.; President L. B. Bidwell in the chair; forty-five members and visitors present.

The record of the last meeting was read and approved.

Mr. Leonard P. Wood was elected a member of the Society.

Mr. George T. Sampson read the paper of the evening, entitled "Railroad Organization," illustrating it with a number of lantern slides.

The discussion, which followed the paper, was participated in by Mr. James H. French, late superintendent of the Plymouth Division of the N. Y., N. H. and H. R. R., and by Messrs. C. F. Allen and J. P. Snow.

Adjourned.

S. E. TINKHAM, *Secretary*.

BOSTON, MASS., DECEMBER 11, 1901.—A special meeting of the Boston Society of Civil Engineers was held in the Society's library at 8 o'clock P.M.; Vice-President F. W. Hodgdon in the chair; eighteen members and visitors present.

Prof. L. J. Johnson read the paper of the evening, entitled "The Determination of Unit Stresses in the General Case of Flexure."

Adjourned.

S. E. TINKHAM, *Secretary*.

BOSTON, MASS., DECEMBER 18, 1901.—A regular meeting of the Boston Society of Civil Engineers was held at Chipman Hall, Tremont Temple, at 7.50 P.M.; President L. B. Bidwell in the chair. Fifty-six members and visitors present.

The records of the last regular meeting and of the special meeting of December 11 were read and approved.

Messrs. Langdon Pearse and James W. Tower were elected members of the Society.

On motion of Mr. Burke, the thanks of the Society were voted to the National Construction Company for courtesies extended this afternoon on the occasion of the trip to the tunnels of the Metropolitan Sewerage Works at Jamaica Plain; also to the Buff & Buff Manufacturing Company for courtesies extended during the inspection of its new shops at Jamaica Plain this afternoon.

The paper of the evening was presented by Mr. Frank W. Hodgdon, entitled "Notes in Relation to Docks and other Engineering Structures in Great Britain, France and Belgium."

The paper was very fully illustrated by lantern slides.

Adjourned.

S. E. TINKHAM, *Secretary*.

Technical Society of the Pacific Coast.

REGULAR MEETING, DECEMBER 9, 1901. Held in the meeting hall of the Mechanics' Institute, 31 Post Street, for the first time. Called to order at 8.30 P.M. by Past-President George W. Dickie.

The minutes of the last regular meeting were read and approved.

The following propositions for membership were read and referred to the directors for regular ballot:

For members—Geo. H. Wallis, mechanical engineer, proposed by C. E. Grunsky, Luther Wagoner and Otto von Geldern; Geo. E. Day, mechanical engineer, proposed by Luther Wagoner, Adolf Lietz and Otto von Geldern.

Mr. Alphens Bull, of San Francisco, was reinstated to membership from January 1, 1902, upon recommendation of the Board of Directors.

A communication was read from the Trustees of the Mechanics' Institute, indicating to the Society that the proposition of an affiliation as outlined in the agreement had been accepted, and that the Society is welcomed to the Institute as a member thereof. It is proposed by the Institute to hold a reception, to be given for the purpose of bringing together the members of the various affiliated societies, and those of the Mechanics' Institute, on Thursday evening, December 12, 1901, at the Library Building.

All members of the Technical Society of the Pacific Coast, the California Association, No. 3, National Association of Stationary Engineers and the Pacific Philatelic Society will be invited by individual cards.

Mr. Marsden Manson then read a paper entitled "The Distribution of Rainfall on the West Coasts of North and South America." The paper was illustrated by an elaborate map, showing the relative areas of precipitation in California, and the comparative distribution of forest growth.

The paper, containing some valuable records, was discussed at length by Past-President Grunsky.

In accordance with the Constitution and By-Laws, a Nominating Committee was appointed by selection of the members present, and duly confirmed by the casting vote of the Secretary, consisting of C. E. Grunsky, A. d'Erlach, James D. Mortimer, Hermann Barth and Hubert Vischer.

This committee is to select a ticket of officers for the ensuing year, and will meet for discussion of the subject on Monday, December 9, in the business office of the Society, 31 Post Street.

Mr. Frederick J. Toggart, Librarian of the Mechanics' Institute, appeared before the Society, and welcomed its members in the name of the library. He stated that it is his aim to create a first-class technical library, and that if members would indicate to him the names of desirable technical books and current engineering literature, every effort would be made on his part to obtain them, in order to make the library one of value and utility to the technical professions. He realized that this lack of technical literature had been long felt in San Francisco, and that the Institute will overcome the difficulty, and, in time, create a Mechanics' Library in the true sense of the word.

The meeting adjourned.

OTTO VON GELDERN, *Secretary*.

Engineers' Club of St. Louis.

534TH MEETING, DECEMBER 4, 1901.—Held at the Mercantile Club at 8.30 P.M.: Vice-President Kinealy presiding. Attendance, thirty-one members. Minutes of the 533d meeting were read and approved. Minutes of the 317th meeting of the Executive Committee were read.

The application for membership of Thomas K. Peters was read and referred to the Executive Committee. On ballot Mr. Fritz Lubberger was elected to membership.

Mr. Layman brought up for further discussion the propositions on which the members of the Board of Managers were requested to vote, regarding the Secretary's salary, indexing the JOURNAL, etc. There was some discussion.

A letter was read from the St. Louis Railway Club, inviting the members of the Engineers' Club to attend, on Friday, December 13, 1901, at the Southern Hotel, both their afternoon meeting and annual Christmas tree smoker, which is to be held in the evening. Motion was made and carried to tender a vote of thanks to the Railway Club and accept the invitation.

The next order of business was the reading of the annual reports of the officers and various committees of the Club. Owing to the absence of the President, no report of the Executive Committee was made. The Secretary's report was read and on motion made and carried it was accepted and filed. The Treasurer's report was read and referred to the Executive Committee. Reports of the Librarian, members of the Board of Managers, and Entertainment Committee were read and motion was carried that they be accepted and filed. The report of the Committee on Prizes was read. The Chair announced that the recommendations of the committee had been approved by the Executive Committee at their meeting of November 6, and in accordance with their recommendations he was pleased to award the prize to Mr. J. S. Branne for his paper, entitled "The Steel Skeleton Construction of a Tall Office Building," which was read before the Club at the meeting held November 7, 1900.

The Nominating Committee made its report on nominations for officers for the ensuing year, as follows:

For President—J. M. Kinealy, F. B. Maltby.

For Vice-President—E. A. Hermann, J. L. Van Ornum.

For Secretary—D. W. Roper, A. H. Zeller.

For Treasurer—Geo. I. Bouton, N. W. Perkins, Jr.

For Librarian—E. B. Fay, W. H. Henby.

For Directors—Carl Gayler, A. L. Johnson, E. J. Spencer, Wm. Wise.

For Members Board of Managers of Engineering Societies—E. R. Fish, J. A. Laird, W. A. Layman, P. N. Moore.

Additional nominations were made as follows:

For President—E. A. Hermann.

For Vice-President—A. H. Blaisdell.

For Secretary—W. H. Bryan.

For Librarian—Walter Brown.

For Directors—W. A. Layman, H. L. Reber.

For Members Board of Managers—E. E. Wall, E. B. Fay.

Motion was made and carried that an annual banquet be held on Wednesday evening, December 18, 1901, the price per plate not to exceed \$3.50. The Executive Committee was authorized to make the necessary arrangements.

The meeting then adjourned and members remained seated while a lunch, provided by the Entertainment Committee, was served, during which every member present was required to make a speech or tell a story. A very enjoyable evening was spent.

E. B. FAY, *Secretary pro tem*

535TH MEETING, DECEMBER 18, 1901.—The annual dinner of the Club was held at the Mercantile Club at 8 p.m.; President Spencer presiding. There were thirty-seven members and five guests present.

After dinner had been served the Club was called to order and announcement made of the Executive Committee's report of the letter ballot for officers for the ensuing year, with the following result:

For President—J. H. Kinealy was elected.

For Treasurer—Geo. I. Bouton was elected.

For Librarian—Edw. B. Fay was elected.

For Member Board of Managers—F. R. Fish was elected.

For Vice-President, Secretary, two Directors and one member of Board of Managers there was no election, none of the candidates having received a majority of the votes cast.

As the newly-elected President, Mr. Kinealy, was not present Mr. Spencer retained the chair and ruled it in order to fill the above-mentioned vacancies.

After the ballots were taken the following results were announced, viz:

Vice-President—J. L. Van Ornum.

Secretary—D. W. Roper.

Directors—A. L. Johnson and E. J. Spencer.

Member Board of Managers—J. A. Laird.

The first toast on the program was "Remarks by the Retiring President," in which Mr. Spencer gave a short talk appropriate to the occasion and thanked the Club for the cordial support given him during the past year.

Mr. S. Bent Russell then responded with an interesting address on "When is Engineering Profitable as an Investment?"

Col. E. D. Meier, one of the Club's oldest members, then gave an interesting talk in which he discussed the spirit of "Commercialism" of the present age, and predicted that the present century would be one of "engineering" in which the work of the engineer would predominate. The subject assigned to him was Helios, "The Sun do Move."

The next subject on the program was "International Expositions and Engineering Practice," by Henry Rustin, electrical engineer of the Louisiana Purchase Exposition. Mr. Rustin, however, was absent, and Dr. David Day, chief of the Department of Mines and Metallurgy, Louisiana Purchase Exposition, kindly responded with a very entertaining and instructive talk on the work already done and that which his department expected to do toward making the exposition a great success. He urged all to give their hearty support to the project.

Mr. J. A. Laird followed by responding to the toast, "Community of Interests Among Engineers," in which he urged a thorough organization of engineers.

The Chair then called upon Mr. Philip N. Moore, who responded in a very happy vein in behalf of the many disappointed candidates.

Adjourned.

W. G. BRENEKE, *Secretary*.

MEMBERS ARE ADVISED . .
THAT THEY CAN OBTAIN

Reprints or Extra Copies of their Papers

AT THE FOLLOWING RATES:

			4 pages or less	5 to 8 pages	9 to 16 pages	17 to 24 pages	Covers extra.
100 Copies	.	.	\$2.25	\$4.00	\$5.50	\$9.25	\$2.25
250 "	.	.	2.75	5.00	6.50	11.25	2.75
500 "	.	.	3.50	6.50	8.75	15.00	3.50
1000 "	.	.	4.50	8.75	12.50	21.00	4.50

An extra charge will be made for printing and inserting such illustrations as are not printed on the same pages as the text, and for enameled paper, when this is used, but it is of course impossible to name rates for this in advance.

When reprints are wanted, notice of the fact, stating how many are desired and whether they are to be furnished with covers, should accompany the paper when it is sent to the Secretary of the Association.

If the paper has been discussed, please state whether it is desired that the reprint shall contain the discussion.

JOHN C. TRAUTWINE, Jr., Secretary,
257 SOUTH FOURTH STREET,
PHILADELPHIA.

10

NORTHEASTERN UNIVERSITY LIBRARIES



3 9358 00829168 1

NORTHEASTERN UNIVERSITY LIBRARIES



3 9358 00829168 1